

This volume was digitized through a
collaborative effort by/ este fondo fue
digitalizado a través de un acuerdo
entre:

Ayuntamiento de Cádiz

www.cadiz.es

and/y

Joseph P. Healey Library at the
University of Massachusetts Boston

www.umb.edu



Ayuntamiento de Cádiz



THE NAVAL ANNUAL



FIFTEENTH YEAR OF PUBLICATION


J. GRIFFIN & Co. PORTSMOUTH


LIBRERIA RELIGIOSA

DE V. LEAÑEZ

Ancha, frente á S. Pablo

CADIZ





H.M.S. "CRESSY."
FIRST-CLASS ARMoured CRUISER.

12
4
2

THE
NAVAL ANNUAL,
1901.

EDITED BY
JOHN LEYLAND.

PART I.—Lord BRASSEY; Admiral Sir J. O. HOPKINS, G.C.B.;
Vice-Admiral Sir CYPRIAN A. G. BRIDGE, K.C.B.;
Captain R. H. S. BACON, R.N., D.S.O.; Commander
C. N. ROBINSON, R.N.; Messrs. J. R. THURSFIELD,
G. R. DUNELL, and A. S. HURD; and the EDITOR.

PART II.—Lists of Ships: Commander C. N. ROBINSON, R.N.,
and the EDITOR; Plates: S. W. BARNABY, M.I.N.A.

PART III.—Armour; Belleisle Experiments; Ordnance and
Ordnance Tables.

PART IV.—FIRST LORD'S MEMORANDUM: NAVY ESTIMATES, BRITISH
AND FOREIGN.

1901.

PORTSMOUTH:


J. GRIFFIN AND CO., 2, THE HARD.

(BOOKSELLERS TO HER LATE MAJESTY QUEEN VICTORIA.)

London Agents: SIMPKIN, MARSHALL & CO.

Foreign Agents:

PARIS: BOYVEAU & CHEVILLET, 22, RUE DE LA BANQUE.
NEW YORK: D. VAN NOSTRAND COMPANY. BERLIN: W. H. RUM.
HONG KONG, SHANGHAI AND YOKOHAMA: KELLY, WALSH & CO.
TOKIO: Z. P. MARUYA & CO.



H.M.S. "CRESSY."
FIRST-CLASS ARMoured CRUISER.

12
4
7

THE
NAVAL ANNUAL,
1901.

EDITED BY
JOHN LEYLAND.

PART I.—Lord BRASSEY; Admiral Sir J. O. HOPKINS, G.C.B.;
Vice-Admiral Sir CYPRIAN A. G. BRIDGE, K.C.B.;
Captain R. H. S. BACON, R.N., D.S.O.; Commander
C. N. ROBINSON, R.N.; Messrs. J. R. THURSFIELD,
G. R. DUNELL, and A. S. HURD; and the EDITOR.

PART II.—Lists of Ships: Commander C. N. ROBINSON, R.N.,
and the EDITOR; Plates: S. W. BARNABY, M.I.N.A.

PART III.—Armour; Belleisle Experiments; Ordnance and
Ordnance Tables.

PART IV.—FIRST LORD'S MEMORANDUM; NAVY ESTIMATES, BRITISH
AND FOREIGN.

1901.

PORTSMOUTH:

J. GRIFFIN AND CO., 2, THE HARD.

(BOOKSELLERS TO HER LATE MAJESTY QUEEN VICTORIA.)

London Agents: SIMPKIN, MARSHALL & CO.

Foreign Agents:

PARIS: BOYVEAU & CHEVILLET, 22, RUE DE LA BANQUE.
NEW YORK: D. VAN NOSTRAND COMPANY. BERLIN: W. H. KÜHL.
HONG KONG, SHANGHAI, AND YOKOHAMA: KELLY, WALSH & CO.
TOKIO: Z. P. MARUYA & CO.

LONDON:
PRINTED BY WILLIAM CLOWES AND SONS, LIMITED,
STAMFORD STREET AND CHARING CROSS.

PREFACE.

THE *Naval Annual* of 1901 appears as the record of a very important year in the history of the British Empire, and at a period of significance also in the opening of a new century. For the second time the honour of editing its pages has fallen to me, for engrossment in political concerns has precluded the Hon. T. A. Brassey from taking his accustomed part in the preparation of the volume. I could place before myself no better object than to invest the work with the character of completeness and accuracy which have given it world-wide authority.

I have been fortunate in receiving the ready help of many writers, who have contributed to these pages, and to Lord Brassey himself, the founder of the *Annual*, a very great deal is due. Returning from his responsible duties as Governor of Victoria, his lordship has been able, after an interval of six years, to contribute to the *Annual* a general survey of the naval situation, as well as an important discussion on the subject of Manning, to which he has devoted life-long attention. What may be described as the "permanent" features of the *Annual* retain their familiar form. Commander C. N. Robinson, R.N., describes the progress of the British Navy, while the chapters devoted to foreign navies and comparative strength have been in my hands. Mr. Thursfield again contributes a critical estimate of the naval manœuvres, while Mr. Dunell reviews the progress of naval engineering, and deals with the interim report of the Admiralty Boiler Committee and the weighty questions to which it has given rise. An important chapter, which may be said to belong to the same category, since it deals with the development of the navy, is Admiral Sir John Hopkins's conclusive plea for auxiliary ships.

The great importance of the war in South Africa has led to the inclusion of two chapters of current interest. In one I have endeavoured to present a picture of the vast work of transporting the forces over sea. It has been my aim to describe the conditions and estimate the success, and in doing so I have been able to vindicate the Admiralty from certain charges made against it in the early part of the war. A record of the operations of the naval forces ashore was essential in this volume, and it is from the experienced pen of Commander Robinson, who has included an account of the work of the naval forces in China.

A chapter of the highest value, being reflections at the opening of the new century, is from the pen of Vice-Admiral Sir Cyprian

Bridge. It is a warning that should be taken to heart by all who recognise—and all Englishmen should recognise—the importance of efficiency to the Navy: a warning against the spirit of formalism and professional self-sufficiency, which becomes as a fetter to check individuality, and has led to many a sharp disillusionment in the history of nations. A chapter to be linked with this is that of Captain Bacon on Naval Strategy, which presents some very far-reaching considerations.

A contributor new to the *Annual* is Mr. A. S. Hurd, who reviews the naval construction of the past five years, explains the delays that have occurred, and presents the view of those who are disposed to lay the blame upon the Admiralty.

The tables of British and foreign ships have been brought up to date, as have also the diagrams. Owing to the absence abroad last year of Mr. S. W. Barnaby, Mr. F. K. Barnes, that old and valued contributor to the *Annual*, consented to supervise the preparation of the diagrams in the volume for 1900; but now Mr. Barnaby has resumed the work and added much that is new, and it will be found that sketches of many of the latest British and foreign ships are included. A section of the new American submarine boats is among the additions.

The death of Captain Orde Browne was a serious loss to the *Naval Annual*. That well-known authority, with impartial judgment and ripe experience that were rare, had written the section on armour and ordnance for many years, with a competence and discrimination that gave to Part III. very exceptional value. To find a successor was no easy task, and, after mature deliberation, it was decided that in the new volume the chapters should, appropriately, assume the form of a review and estimate of recent progress, from which sound lessons might be drawn. The present editor claims no credit for what appears in this section of the work. He has passed it for press with a full recognition of its great value, and believes the readers of the *Annual* will recognise that its author possesses a profound knowledge of his subject—the fruit of long and intimate acquaintance with it—and a penetrating judgment which have enabled him to seize the significance of recent changes in the production of armour and ordnance. In the chapter on armour will, indeed, be found some considerations which are of great importance. Finally, it is a pleasure to acknowledge help that has been received from many competent authorities.

Forest Hill,
April, 1901.

JOHN LEYLAND.

CONTENTS.

PART I.

| | PAGE |
|--|------|
| CHAPTER I. | |
| INTRODUCTORY | 1 |
| CHAPTER II. | |
| PROGRESS OF THE BRITISH NAVY | 15 |
| CHAPTER III. | |
| THE PROGRESS OF FOREIGN NAVIES | 33 |
| CHAPTER IV. | |
| COMPARATIVE STRENGTH | 71 |
| COMPARATIVE TABLES | 80 |
| CHAPTER V. | |
| BRITISH NAVAL MANŒUVRES | 90 |
| CHAPTER VI. | |
| MARINE ENGINEERING | 119 |
| CHAPTER VII. | |
| THE MANNING OF THE NAVY AND MERCANTILE MARINE .. | 153 |
| CHAPTER VIII. | |
| FLEET AUXILIARIES | 161 |
| CHAPTER IX. | |
| THE TRANSPORT OPERATIONS TO SOUTH AFRICA .. | 167 |
| CHAPTER X. | |
| THE OPERATIONS OF OUR NAVAL FORCES ON SHORE, 1899-1901 | |
| Commander C. N. Robinson, R.N. | 187 |
| CHAPTER XI. | |
| WAR AND ITS CHIEF LESSON | |
| Vice-Admiral Sir Cyprian A. G. Bridge, K.C.B. | 218 |
| CHAPTER XII. | |
| SOME NOTES ON NAVAL STRATEGY | 233 |
| CHAPTER XIII. | |
| THE PAST FIVE YEARS' WAR-SHIPBUILDING | 253 |

PART II.

TABLES OF BRITISH AND FOREIGN SHIPS.

TORPEDO-BOAT TABLES.

Commander C. N. ROBINSON, R.N., and JOHN LEYLAND.

PLANS OF BRITISH AND FOREIGN SHIPS.

S. W. BARNABY, M.I.N.A.

PART III.

| | PAGE |
|--|------|
| I. ARMOUR | 391 |
| II. SHELL FIRE.—THE BELLEISLE EXPERIMENTS | 412 |
| III. GUN MOUNTINGS.—ACCURACY AND RAPIDITY OF FIRE .. | 424 |
| TABLES OF BRITISH AND FOREIGN ORDNANCE | 436 |

PART IV.


| | |
|--------------------------------------|-----|
| FIRST LORD'S MEMORANDUM | 461 |
| BRITISH NAVY ESTIMATES | 482 |
| PROGRAMME OF SHIPBUILDING | 490 |
| FRENCH NAVY ESTIMATES | 494 |
| GERMAN NAVY ESTIMATES | 499 |
| ITALIAN NAVY ESTIMATES | 501 |
| RUSSIAN NAVY ESTIMATES | 503 |
| UNITED STATES NAVY ESTIMATES | 504 |

LIST OF ILLUSTRATIONS.

| | | | | | |
|---|---|---|---|---|-----------------------|
| H.M.S. Cressy (first-class armoured cruiser) | . | . | . | . | <i>Frontispiece</i> |
| Hatsuse (Japanese first-class battleship) | . | . | . | . | <i>facing page</i> 33 |
| Gromoboi (Russian first-class armoured cruiser) | . | . | . | „ | 51 |
| Alabama (United States first-class battleship) | . | . | . | „ | 57 |
| Mikasa (Japanese first-class battleship) | . | . | . | „ | 63 |
| Norge (Norwegian coast-defence ship) | . | . | . | „ | 70 |
| Idzumo (Japanese first-class armoured cruiser) | . | . | . | „ | 119 |

DIAGRAM.

| | | | | | | | | | | |
|--|---|---|---|---|---|---|---|---|---|-----|
| Diagram showing the Expenditure on the Construction of New Ships (British) in the financial years 1872-73 to 1900-1901 | . | . | . | . | . | . | . | „ | „ | 492 |
|--|---|---|---|---|---|---|---|---|---|-----|



PART I.

CHAPTER I.

INTRODUCTORY.

I.

2 As the founder of the *Naval Annual* I must always take an interest in its production. During my absence in Australia I ceased to be a contributor, and in taking up the pen after a long interval, I may appropriately refer to the enormous advance in Naval Expenditure under all the leading Administrations. In round figures France is spending £13,500,000 upon her Navy; Russia, £9,000,000. The Navy Estimates now before the British Parliament in this present Session provide a net total of £30,875,500, being an increase of £2,083,600 beyond the amount voted for the year 1900-01. The Estimates with which we are now dealing show an increase of nearly £12,000,000 upon those of the year 1894-95.

The justification for the policy we have followed was well put in the following passage:—"The Fleet is England's right arm. But for her Fleet England would be a cypher in the Councils of Europe, might be denuded of her Colonies, and could not hold the Indian Empire a year. But for the Fleet the English working man might any day find his daily occupation gone, and the price of his children's bread risen to half-a-crown a loaf. The greater the Fleet, and the wider the area of its operation, the more effective this mighty right arm of the nation must become. Every shilling that is devoted to it, if expended with economy and judgment, is well bestowed, for it is England's insurance against those great accidental calamities which destroy the happiness and prosperity, and sometimes the lives, of nations." In a recent number the *Spectator* has truly said: "On the Navy hang our Empire and our commercial prosperity. Our island position made it needful to begin with, and our scattered Colonies increase the necessity. It is the one fighting arm in which by the nature of things we have the chance of surpassing all other peoples. It is the form of war most suited to the genius of our race, and bound up with the most stirring traditions of our history. Bare tables of statistics may help to prove its importance, but the reasons at the back of them all must be plain to every man in the nation."

Naval
policy.

The Fleet is not only necessary for defence; it is the surest guarantee for the maintenance of peace. In his memorandum on the well-known paper drawn up by the Duke of Wellington in 1847 Lord John Russell wrote as follows:—"France is the country nearest to us as a neighbour, most formidable as a rival, and with whom we have at once the most frequent opportunities of friendly concert and the greatest probability of irreconcilable quarrel. . . . If both are prepared both will be unwilling to rush into war at the hazard of severe and instant retaliation, or at least of successful repulse. But if one is prepared and the other is not, the State which is prepared becomes eager to take advantage of its superiority."

French
official
views.

The Report of the Committee of the French Chamber of Deputies on the Navy Estimates for the year 1901 is opened by M. Fleury-Ravarin with some observations on Naval Policy: "Every nation desirous to play a part in the world must possess the means of using an adequate force in support of its policy. A Navy cannot be improvised; a policy must be consistently pursued. Modern France has inherited a position among the family of nations which was long commanding, and is still of no mean importance. It is the bounden duty of all who have faith in their country to sustain that position, and, as far as possible, to strengthen it. It cannot be abandoned without loss of self-esteem, nor without taking from every citizen that confidence without which enterprises in distant lands cannot be undertaken.

"In all the campaigns of the last seventy years the naval forces have materially influenced, and have often decided, the result. The conquest of Algiers, the Crimean War, the war in Italy, would have been impossible without the support of the French Navy. Naval forces played a great part in the Civil War in America, in the struggle between Chili and Peru, in the war between Russia and Turkey, and between Italy and Austria, and, more recently, the Spanish-American War. The difficult questions connected with the opening up of China will not be decided on the Continent of Europe, but upon the sea, and probably in the Far East on the Pacific Ocean.

"Naval power is an essential instrument in diplomacy. The standard of strength at which our Fleet should be maintained must depend on the line it is proposed to follow in relation to foreign affairs. If our policy is expansion, whether colonial or simply commercial, we must have an adequate Navy to support it. Without such a Navy we must abandon the field to other nations. It has been often contended that France cannot maintain a strong Navy as well as a powerful Army. The truth is that the Navy, so far from

imposing a heavy charge on the country, is the main source of wealth through the protection it affords to commerce. Without the Navy created by Colbert, Louis XIV. would have been unable to undertake the Continental wars in which he was engaged. The neglect of the Navy was quickly followed by reverses on land."

Accepting as our standard equality to any two Powers, British expenditure cannot be considered inadequate. There are some who insist that our Fleet should be superior to a combination of France, Russia, and Germany. The maintenance of such a force would impose a heavy burden. It cannot be necessary while prudent counsels prevail in the direction of the policy of the Empire.

Standard
of
strength.

II.

If we turn from the expenditure to the manning of the Fleet, the Estimates for 1901-2 provide for an increase of 3745 men, including 287 officers, 1150 seamen, 1000 marines, 500 stokers, and 100 electricians. Our permanent force for the year 1901-2 will aggregate 119,000 men, as against 43,000 for France and 45,000 for Russia.

Manning
of the
Fleet.

The Fleet Reserve should be a valuable addition to our strength. The reserves which we should endeavour to create in the Mercantile Marine are not as strong or as efficient as we should wish. The numbers voted for the British Reserve are 23,000, as against 114,000 in the French Inscription Maritime. The Fisheries and the Mercantile Marine of France supply annually some 4000 men for deck duties. For the engine-room complements it is necessary to have recourse to voluntary enlistment, some 3000 men being annually entered and specially trained.

For the manning of the British Navy we are relying unduly on a permanent force. It is an extravagant method. It must be difficult to give sufficient sea time to the growing numbers. A permanent force not supported by Reserves cannot adequately supply the means of reinforcement in time of war. As a reserve, standing behind the permanent force of marines and marine artillery, a volunteer force, recruited from the classes which were enrolled in the Royal Naval Artillery Volunteers, disbanded by the Admiralty over which Lord George Hamilton presided, seems desirable. An original error was committed in treating the Royal Naval Artillery Volunteers as a bluejacket force; they had no claim to that character, although a considerable number were well acquainted with a sea life. The Royal Naval Artillery Volunteers were well fitted to act as marines. They were highly intelligent in picking up their gun drill, they were able to pull a strong oar, they could have been instructed in signalling, and might have been most useful in association with a few old seamen

A
volunteer
reserve.

in relieving the coastguard in time of war. As seamen, it was impossible to assign to the Royal Naval Artillery Volunteers any definite place or sphere of action in a scheme of naval defence ; as a reserve of marines the difficulties would have disappeared.

III.

Ships.

Passing from the men to the ships, it is unnecessary in this place to deal at length with the strength and distribution of the Fleet. In the following chapter Commander C. N. Robinson has described the progress made since the *Annual* last appeared ; while in another chapter Mr. John Leyland estimates the comparative strength, indicates the naval strength on the foreign stations, and has brought up to date the comparative lists of ships of the Powers.

While our strength is fully up to the standard of equality to any two Powers, a deduction must be made in the case of a fleet which will be expected to act on the offensive. Blockade, under modern conditions, must be an arduous service. Steam has made it possible to put to sea in all weathers. There are risks of attack by torpedo vessels such as were unknown in the days of Nelson. The crews of ships keeping watch and ward outside an enemy's port soon become exhausted. Bunkers are rapidly emptied.

In cruisers we have a decided numerical superiority. For the protection of our vast commerce it is desirable to make further provision by auxiliary vessels. Such a policy will render it possible to concentrate our efforts upon those powerful fighting ships which it is impossible to obtain from the Mercantile Marine. In future Estimates the appropriation for battleships should be increased, looking to the mercantile auxiliaries as the scouting ships of our squadrons and the defenders of our commerce.

In regard to ships in commission, it may be said that we maintain considerable squadrons on every station. The main strength of the Russian Navy is concentrated in the Far East, that of France in the Mediterranean. On both stations we are well able to hold our own.

IV.

*Naval
training.*

In the past year the training of the Navy has been the subject of frequent discussion. Dealing first with the officers, a naval friend, at the date of writing on half-pay, but now Commander-in-Chief on a foreign station, writes as follows : " I wish that the training of the officers and men were such as it should be. The age of entry for officers was raised that they might enter with a fair grounding in knowledge, and with a reasonable hope that they would continue to

Officers.

instruct themselves, but no sooner do they arrive at an age when every faculty should be employed in acquiring practical knowledge than they are carried off to the College at Greenwich for a most protracted course which is of little use in a practical profession, and which is dropped from the day they leave the College.

"Before the Greenwich course was introduced there were always a select few who took up special branches for themselves. In the present day the young officer on entry is driven from pillar to post, from one subject to another. When he has got through what is called his seamanship examination, he is sent off to college to be run through a groove of the higher mathematics, the use of which is rarely seen in his after life. In the meantime practical work afloat is an unknown quantity."

A knowledge of trigonometry is essential in the study of the theory, but not in the practice, of navigation. Few indeed are the masters and mates of the Mercantile Marine in whom any competent knowledge of mathematics would be found. On the other hand, ignorance of a foreign language, and more particularly of French, is a most serious deficiency in a naval officer, who may at any time be called upon to deal with a difficulty abroad. The expectation that all junior officers of the Navy will acquire a colloquial knowledge of French will be vain unless adequate facilities and encouragements are given. In the home ports and at important stations abroad, such as Malta and Sydney, instruction should be given to naval officers by teachers specially qualified. The study of languages should be encouraged by the Admiralty, by giving more prizes for proficiency in the subject. In the examination for the rank of lieutenant, French counts for not more than 150 marks out of a total possible number of 2000. Every naval officer should be a good seaman and a competent navigator. It would be for the advantage of the Service to accept, in a certain number, a lower standard of mathematical knowledge in order to secure higher attainments as linguists.

The training of seamen was the theme of an animated debate Seamen. initiated last summer in the theatre of the United Service Institution by Mr. Thursfield, who was able to tell his audience that he had seen more of the naval service afloat during the past twelve years than any civilian had ever seen before. His claim to be heard was fully recognised by naval men. Opening with an observation which affords subject for reflection, Mr. Thursfield said: "The country has created a new Navy of unexampled strength and excellence in *matériel*; for its *personnel*, on the other hand, it has given no commensurate training." Among many speakers it is difficult to make a selection. Sir Edmund Commerell believed that "masts and

sails were not done with," that "it would be much to the detriment of our men as practical sailors if that were so; when the country understood that the training of men in sailing-ships was the only way to make good seamen, we might be sure there would be no difficulty as to expenditure." Sir Frederick Richards "hoped that it was not true that masts and sails were doomed. If they did away with the training they afforded what did their opponents propose to substitute for it? This training taught the boys the qualities of nerve and courage which were so necessary. To train the men who were now coming forward no very great increase in the Training Squadron would be required—eight ships would be sufficient. He hoped that those entrusted with the administration of the Navy would pause and consider before they incurred the grave responsibility of making a change which might have very far-reaching and momentous consequences." Sir Anthony Hoskins, the predecessor of Sir Frederick Richards in his high post at the Admiralty, expressed his full concurrence: he warmly advocated a sailing squadron. Nor should the opinion of the younger officers be put out of view. Commander Lowthian Nicholson "entirely disagreed with the idea that the day of masts and sails had gone; he believed that training in a sailing-ship gave seamen self-reliance and resource, quickness of eye, steadiness of nerve, coolness in all difficulties, and a sense of comradeship, all going to keep up the efficiency of the British seaman." Commander Napier held "that the seaman who had undergone mast and sail training was undoubtedly a superior man to one who had not."

The discussion was continued in the *Times*. Sir Cyprian Bridge, in a practical and instructive letter, referred to an inquiry instituted a few years ago into the physical characteristics of the ships' companies of a squadron comprising ships with sails and ships without sails. The inquiry showed that the able seamen and petty officers of ships with sails surpassed in every particular of weight and physical power their equals in rating serving in the sailless ships. He urged the difficulty of finding a substitute for the work aloft.

The balance of argument and authority in the recent discussion seems to lie with the advocates of masted training ships. A squadron of eight ships of the C class, or of a class specially designed for the service, should be kept in commission, cruising singly and in squadrons. There is no better cruising ground in the winter than the south coast of Spain.

In addition to the re-establishment of the Training Squadron, sailing tenders should be attached to all our port-guard ships and reserve ships in home waters. Sea habits, pilotage, the rule of the

road and experience of bad weather, may be perhaps best acquired in small vessels.

The growth of establishments on shore requires most careful watching on the part of the Admiralty. If the men who take our ships to sea are far in advance of the men of any possible enemy, it is because the ship of the British Navy is more at sea than that of any foreign power. The sea is the only place where the seaman can learn the duties of his trying and arduous profession.

The tendency to diminish the sea-training of officers and men may prove very prejudicial to efficiency of the Navy. A correspondent of the *Times*, under the assumed name of "Navalis," has recently shown that the proportion of lieutenants serving in harbour and ashore has increased from 4 per cent. in 1880 to 9 per cent. in 1900. In the case of sub-lieutenants, the numbers in harbour and ashore have increased from 27 per cent. to no less than 41 per cent. The training in gunnery in the Navy seems worthy of our great national Service: the standard of proficiency is steadily advancing. Let us not lose the seamanship for which our Navy has long been famous.

The training in the torpedo flotilla lately introduced by the Admiralty cannot fail to give excellent results.

V.

The necessity of battleships as the main instruments for maintain- Battle-
ing command of the seas shall not be insisted upon here. The modern ships.
battleship is greatly superior in sea-keeping qualities to the earlier types, in which the preponderating value was given to smallness of target. In smooth water a low freeboard is an obvious advantage. In a seaway the want of freeboard involves loss of speed and inability to fight the guns. The recent ships designed by Sir William White have ample freeboard, and carry their guns at a commanding elevation above the water. The advance in speed in modern ships is a notable feature.

The gain in sea-worthiness, speed, and coal endurance has rendered necessary a rapid growth in dimensions. In the list of British battleships we have the Royal Sovereign class of 14,150 tons, Majestic class of 14,900 tons, Canopus class of 12,950 tons, eight Formidable class of 15,000 tons, and six Duncan class of 14,000 tons. In former years the present writer bestowed much labour in collating arguments for restricting dimensions, with a view to a proportionate increase of numbers. The conditions have changed. At the present time our British ships of 15,000 tons cost less than French and Russian ships of far inferior dimensions. It

may confidently be claimed that the requirements, often conflicting, of a perfect man-of-war are skilfully combined in the designs produced at the Admiralty. The able men on whom the responsibility rests of directing the naval construction of the leading maritime Powers are intimately acquainted with professional work elsewhere. In point of ability the presumption is that they do not differ widely. Ton for ton in ships of even date there is no appreciable difference between the fighting vessels of the Russian, the German, the Italian, the United States, the French, or our own Navies. It is a reasonable presumption that the biggest ships are the best, and ours are the biggest.

Criticisms of British battleships are seldom heard. It does not require the technical knowledge of an expert to appreciate that our ships, more especially those of the later designs, are truly noble types. In ability to hold the sea they are immeasurably superior to the low freeboard ships, of which the *Devastation* and the *Thunderer* were characteristic examples. The *Monitor* was a perfect type for inshore warfare, or for the bombardment of fortresses from a sheltered channel or anchorage. The designer of ships for the British service must produce a type capable of keeping the sea and carrying the national flag to the furthest limits of the world. The British Navy has a decided advantage in possessing groups of ships of uniform type.

The French are steadily increasing the dimensions of their battleships: the new Suffren type will have a displacement of 14,865 tons. In the French Navy it is now recognised that too much importance has been attached to the armoured belt.

The recent construction for the United States has been exhaustively described in a valuable paper read by Professor Biles at the recent session of the Institute of Naval Architects. It deals fully with the productions of constructors who belong to a country supreme in ingenuity, and acting under a body of naval officers who have had the latest experience in the actual operations of war. In the recent designs for battleships in the United States more importance is assigned to superiority of armament than to an extra knot of speed. In the new battleships it has been possible to add eight 8-inch guns to the armament by the adoption of the super-imposed turrets. The American constructors object to the system: it finds favour with the Ordnance Department and the naval officers. The United States naval authorities have gone up to dimensions of 15,000 tons for their most recent designs.

VI.

Machinery will be dealt with in a special chapter by a competent hand. The sudden introduction on a vast scale into the British Navy of water-tube boilers rendered it necessary to put them into the charge of engine-room complements with no experience of their use. Many accidents and breakdowns having occurred, an inquiry was ordered by Lord Goschen, and a preliminary report of the committee has been laid before Parliament. The Committee do not consider the Belleville boiler to be the best type, and recommend the trial of four types of large straight-tube boilers now being extensively adopted in foreign navies. The water-tube boiler was adopted in deference to arguments of great force. No country could afford to relinquish a decided advantage in speed for a given weight or the greater advantage of getting up steam and increasing speed rapidly, unless there were strong grounds for supposing that the defects in details which now render the machinery less reliable than the older and well-tried types were likely to be permanent. All foreign navies have adopted water-tube boilers.

Machinery
and engine
room
personnel.

The training of our engine-room complements has become a question of urgency. While every bluejacket spends two years in a training-ship, is exercised in brigs, and has until lately served in the sea-going Training Squadron, there is no corresponding provision for the training of stokers and artificers. As the result of the insufficient training, it has been alleged that one-third of the engine-room branch are inefficient during the first year or more of every commission, and that for the first two years no ship is possessed of a fully trained engine-room staff. It is pointed out that the difficulty is accentuated by the insufficiency in the number of engineer officers. When ships are under steam the engineers are too fully occupied with urgent duties to be able to bestow attention on untrained men. It would seem necessary to employ ships for the special training of the engine-room complements, and the Powerful and the Terrible might be suitable for this purpose. They should make frequent passages between the home ports and Gibraltar.

In the introduction of the Belleville boiler we made too great a rush. In principle we were right, but we had not, and we cannot for some time provide, a fully trained *personnel* for the engine-room complements. In this respect foreign navies, and notably the Italian and the Japanese, seem to have done better than ourselves in the avoidance of mistakes of management. Our experience of failure with the Belleville boiler seems to point with emphatic force to the necessity for more careful training of our engine-room complements.

VII.

Cruisers.

Passing from the types of battleships to the cruisers, the effect of the laying down of the Russian ship *Rurik* was quickly seen in the construction of our *Powerful* and *Terrible*. These ships were unprecedented in their dimensions. They have been followed by the eight ships of the *Diadem* class of 11,000 tons, the six ships of the *Cressy* class of 12,000 tons, the four ships of the *Drake* class of 14,100 tons, and the ten ships of the *County* class of 9800 tons. High speeds, under ocean-going conditions and large coal endurance, have rendered the advance in dimensions inevitable. The cruisers recently constructed for the British Navy have been sometimes criticised as being inferior in speed or armament. There are other essential details as to which a limited comparison gives no information. Tables supply no particulars as to structural strength or freeboard, both being features essential to seaworthiness. When the radius of action can be restricted, the coal supply, the stores, and even the ammunition may be cut down and the disposable weight applied to the increase of armour protection or of armament.

Several armoured cruisers of the largest dimensions are being constructed for the French Navy. The French have always been famed for the production of models admirably adapted for speed. In their latest ships they have well sustained their ancient fame. As with us, so in the French Navy, tubular boilers have presented difficulties.

In the Russian Navy three first-class vessels have recently been laid down with a displacement of 13,600 tons. Six protected cruisers of 6500 tons are also in hand. In vessels of comparatively restricted dimensions the coal supply is too limited for ocean cruising.

In the United States the construction of first-class cruisers has been commenced with vigour. The list of ships building or ordered includes six vessels approximately 13,700 tons, and three others of 9700 tons, which will be up to the highest standard of fighting efficiency. Defects which were criticised by some American authorities in designs of earlier date and inferior dimensions will no longer appear.

VIII.

Recon-
struction
of ships.

Expenditure on re-armaments, and on the fitting of new machinery to the older types of battleships, is not viewed with favour by constructors, to whom it must always be a more grateful task to build from designs of their own rather than to modernise ships which are becoming obsolete. Within prudent limits, no expenditure would yield more immediate results in reinforcing the Navy than that

incurred in fitting the sound and not badly protected hulls of the earlier ironclads with effective engines and guns. In war with a first-class Power the sphere of action of our converted ships would be found in distant waters, in the capture of coaling stations, and in defending our trade with the East by convoy and patrol.

As a member of Lord Northbrook's Administration the present writer naturally looks to the ships of that period. The "Admiral" class are too low in the bows; the central batteries are unarmoured. By suppressing the forward turret, and the two heavy guns which it contains, a large disposable weight could be utilised in raising the bow, and in giving protection to the battery. The armament forward might consist of powerful quick-firing guns protected by armour. The disposition might be similar to that adopted for the latest types of first-class armoured cruisers. Such ships as those of the "Admiral" class, with the improvements which might be made, would be a good match for many ships which will long be retained on the effective lists of foreign Powers. Reinforced by fast cruisers for services demanding extreme speed they would form efficient squadrons for the protection of the lines of communication by the Cape route to India and the Far East.

The belted cruisers of the same period might be brought up to such a standard of fighting efficiency as would keep them on the list of effectives for many years. The belted cruisers are powerfully armed and engined. The ocean speeds at sea fall short of the results which would certainly be obtained with more length and more free-board forward. They should be lengthened amidships.

Lieutenant Dawson, R.N., in the able paper recently read at the Society of Arts, recommends that ships of a still older date than those laid down by Lord Northbrook should be taken in hand. He compares the fighting power of the *Inflexible*, armed with her muzzle-loading guns, with those of a French cruiser of the *Cassard* class armed with breechloaders. The following paragraph may be quoted:—

"At a range of 8000 yards, or beyond, the French ship would be in safety against the fire of the *Inflexible*'s guns, whereas at this range the French cruiser, with the aid of her modern guns and of modern telescopic sights, would be able to make good practice against the British ship, and, in my opinion, would put her quickly out of action by firing large capacity high explosive and other modern shells. Let us, from this particular illustration, consider further the cost to the country. Each man employed on board ship costs us about £100 per annum, and thus the wages bill for 485 men is at the rate of £48,500 per annum. The up-keep during war of a ship of the *Inflexible* class in the expenditure of coal alone, since it would be at famine prices, would be enormous, and the cost of repairs, etc., greatly disproportionate to the services rendered. But apart from these monetary items there is the far more important question of the ineffective employment of the 485 men, whose training represents a large national asset. And, what would be still more deplorable from more views than one, if these obsolete ships, of which there are very many in the Service, are sunk or taken, a very large and very unpleasant gap would be made in our *personnel*. Other

similar illustrations might be given, but this one surely affords strong reason for either selling the old obsolete ships and expending no more money on them even in peace times or for arming them with modern artillery. The latter course seems to me more advisable, as armaments of a kind can be provided much more quickly than new ships to replace the old vessels, and history has shown the value of reserve ships to fill up gaps in naval warfare, even if they be not quite up to the mark from a ship construction point of view. The nation which can more expeditiously challenge the enemy anew after a hard-fought battle is the more likely to succeed ultimately."

The French Administration has decided to cut down the heavy superstructures with which their ships have been encumbered, and at the same time to modernise the machinery and to arm the ships with guns of the most recent pattern, of smaller calibre, and lighter in weight, but with a more commanding range. As the result of an exhaustive examination of the subject, schemes were approved in 1896 for the reconstruction of certain coast-defence vessels, and in 1897 for a similar reconstruction of certain battleships. In all, fifteen ships have been, or will be, taken in hand. The list includes ten battleships, namely, *Formidable*, *Amiral Baudin*, *Courbet*, *Redoutable*, *Dévastation*, *Hoche*, *Amiral Duperré*, *Marceau*, *Neptune*, and *Magenta*, and five coast-defenders—*Terrible*, *Caïman*, *Indomptable*, *Requin*, and *Furieux*. The total expenditure authorised is, in round figures, one million sterling.

IX.

Torpedo
craft.

The torpedo flotilla is becoming a most important feature in the navies of the Continental Powers. The types produced by the Schichau firm are now largely represented in the Russian, German and Italian navies. Their displacements range from 350 tons upwards; they carry ninety-five tons of coal; speed, 26 knots and upwards; armament, three or more 2-inch guns and three torpedo-tubes. Their sea-keeping powers are of a superior order. The passage is made without difficulty to the Farthest East even during the height of the monsoon. Some sixteen torpedo-boat destroyers exceeding 400 tons displacement are being constructed for the United States Navy.

The efficiency of submarine boats is limited to the defence of harbours. The French and Americans are building several vessels for that purpose. We are following them in this new type.

X.

Mercan-
tile
auxiliaries

Fewer cruisers will be required, specially built for fighting purposes, if we make our mercantile auxiliaries more effective. A lecture of much interest has recently been delivered at Liverpool by Mr. Peskett, of the Cunard Company. The writer is a strong

advocate for subsidies to mercantile auxiliaries, conditional upon the adaptation of the ships to the requirement of naval warfare. The paragraphs which follow are quoted from a *précis* of his lecture:—

Merchant ships of the *Campania* or *Saxonia* class could actually be built lighter than they are under the present system if they were built with one very strong deck, such as a protective deck with sloping sides, or with a deck of cellular form. The disposition of material in some of our large steamers is not perhaps in strict accordance with the best designs our naval architects could produce, but entirely due to the requirements of owners and the various registration societies. I should say that a cruiser's hull with protective deck is lighter in proportion to her displacement than that of many of our first-class passenger steamers.

Taking into consideration the fact that our supremacy depends on the efficiency of our naval and mercantile marine, a committee of Admiralty officials, shipowners and shipbuilders should be formed to discuss the best method of constructing a combined naval and mercantile marine, and to consider whether ships could be built as merchant cruisers, with protective decks, ram stems, machinery and steering gear below the waterline, and still be able to carry enough passengers and mails which with a reasonable subsidy would make the ships remunerative to owners.

These ships would have to be permanently mounted with light guns, racer-plates for heavier armaments being built in the ships during construction, the heavier guns and mountings being kept at ports of call, and made to suit the various ships of any particular fleet.

The policy recommended by Mr. Peskett was many years ago strongly advocated by Sir Nathaniel Barnaby. It has been consistently supported in the *Naval Annual*. If we turn to foreign writers, Admiral Fournier in *La Flotte Nécessaire* gives his opinion as follows: "As types of fast cruisers for the destruction of commerce, I know of nothing which more fully meets the requirements than those magnificent trans-Atlantic steamships, the *Lucania* and *Campania*, capable of maintaining a speed of 22 knots an hour with extraordinary uniformity. The *New York*, *Paris*, *St. Louis*, and *St. Paul*, and the English ships *Majestic* and *Teutonic*, possess the same qualities, though in a somewhat lesser degree of perfection. Such ships will, in my view, be the destroyers of commerce in the future."

XI.

The delays in the completion of ships call for some observations. In five years the expenditure has been four and a half millions below the sum voted by Parliament. We are assured by the First Lord that the difficulties in the manufacture of armour, which have been the main cause of delay, have been overcome. The most serious delays having occurred in the case of dockyard built ships, it would seem desirable to put out construction to contract more largely. It is much to be regretted that firms which have been extensively employed have been involved in financial difficulties as the result, presumably, of excessive competition for Admiralty work. Undue cutting of rates cannot be for the public advantage if it leads to the closing of great establishments on which we have relied for the maintenance and

Retarded
construc-
tion.

reinforcement of the Navy. Contracts should be given at prices sufficient to yield a fair profit. The penalties for delay should be enforced.

XII.

British
naval
adminis-
tration.

Any attempt to review the naval administration on the vast scale which the defence of the British Empire demands must be imperfect and unsatisfactory. There is much more to say if space and time permitted.

It is a very agreeable duty to pay a well-merited tribute of praise to the great departments of the Admiralty. They achieve their enormous task with as large a measure of success as it is reasonable to look for in all the circumstances of unceasing change and progress with which they have to deal. Certainly no foreign administration does better. Under none is there so little wasteful expenditure. No Service produces a finer body of officers and men; none possesses more powerful ships. No Administration is supported with a liberality so large as that which the British Parliament has in late years bestowed on the Navy. It has not been thought necessary to press for additional expenditure on the Navy. A forward movement is certain to be general, leaving the relative position unchanged, while the taxpayer is burdened. In this connection it should not be put out of view that the strength of the British Navy rests on a broad foundation.

Our Empire comprises one-fourth of the population of the globe. The combined trade and revenues are fully proportionate to the numbers of the people. As an evidence of our maritime resources we may compare the 1,502,000 tons of shipping built in 1900 for the British Empire with the combined construction of all other countries.

In closing this contribution to the *Naval Annual* it is a pleasing duty to pay the tribute he so abundantly deserves to Viscount Goschen for his long and most able and valuable service in the administration of the Navy. To Lord Selborne the Navy and Parliament are ready to give their full confidence. He bears a heavy responsibility, which it is the duty of all patriotic men who interest themselves in naval affairs in some sense to share by suggestions, offered in no party spirit, and with a single desire to promote the efficiency of the Service.

BRASSEY.

CHAPTER II.

PROGRESS OF THE BRITISH NAVY.

It was pointed out in the *Annual* last year that of the programme of 1896-97 three battleships—the Canopus, Goliath, and Ocean—had been completed and commissioned. The remaining battleships of the same programme and type are the Glory, Albion, and Vengeance. With regard to these three vessels, the Glory was floated out of dock at Birkenhead on March 11, 1899, and her trials are reported in last year's *Annual*. She was commissioned on November 1, 1900, and is now in China waters. The Albion, having been launched at Blackwall on June 21, 1898, was delivered by the contractors during the past year, and began her trials on March 14, 1901. The results of these are taken from the report in the *Times*:—The vessel left the Nore on Thursday (March 14) morning, the trial beginning at 9.45 A.M. A course was steered down the English Channel to the Start Point, which was reached at midnight, when the vessel was turned towards the east, arriving at the Nore about 4.30 on Friday afternoon. The machinery and boilers worked smoothly during the whole of the trial, there being no incident of any kind. The boilers provided a continuous and sufficient supply of steam under natural draught conditions, no fans, air-blowers, or other means being used for the purpose of assisting combustion. The contract power under these conditions was 10,250 I.H.P. The actual mean results of the thirty hours' steaming were ascertained at the end of the trial to be 10,809 I.H.P. The speed of the vessel was 16.8 knots. The mean results for thirty hours were as follows:—Steam pressure at boilers, 244 lbs. per square inch; steam pressure at engines, 199 lbs. per square inch; revolutions per minute, starboard, 102.6; revolutions per minute, port, 101.8; vacuum in condensers, starboard, 27.7; vacuum in condensers, port, 27; I.H.P., starboard, 5294; I.H.P., port, 5515; mean total for thirty hours, 10,809; consumption of coal for all purposes, 1.8 lbs. per I.H.P. per hour. The engines are of the usual vertical triple expansion type, steam being supplied by twenty Belleville boilers, arranged in three stokeholds. The results of the eight-hours' trial were as follows:—

Pro-
gramme of
1896-97.

full-power trial carried out on March 28 were also satisfactory, the power obtained being 13,885, and the speed 17·8 knots.

The last ship of this group is the *Vengeance*, which was launched from Messrs. Vickers, Son, and Maxim's yard on July 25, 1899. She is still at Barrow, where she is, it is reported, to be completed. A full description of this vessel was given in last year's *Annual*.

Pro-
gramme of
1897-98.

The battleships of the 1897-98 programme are the *Formidable*, *Irresistible*, and *Implacable*, and the type was described in the *Annual* for 1899. The *Formidable* is at Portsmouth, the *Irresistible* at Chatham, and the *Implacable* at Devonport. The *Formidable* has begun her trials, the *Irresistible* is nearly ready to begin hers, and the *Implacable's* have been completed with success. The thirty-hours' trial of the last-named vessel at one-fifth the full power took place on January 18. The mean results were as follows:—Steam in boilers, 220 lbs.; vacuum, 28 in.; revolutions, 66; I.H.P., 3265; speed, 11·10 knots. The eight-hours' full-speed trial was carried out on March 15 and 16, with the following mean results:—Steam at boilers, starboard, 270 lbs.; port, 270 lbs.; steam at engine, starboard, 243 lbs.; port, 242 lbs.; vacuum, starboard, 27 in.; port, 27 in.; revolutions, starboard, 109·1; port, 108; pressure at cylinders, high-pressure cylinders, starboard, 101·8; port, 104·8; intermediate, starboard, 43·7; port, 39·5; low, starboard, 18·7; port, 19·4; I.H.P., high-pressure cylinder, starboard, 2230; port, 2273; intermediate, starboard, 2552; port, 2289; low, starboard, 2914; port, 2986; total, starboard, 7696; port, 7548; gross total, 15,244. The coal consumption was 1·88 lb. per I.H.P. per hour, and speed, 18·22 knots.

Pro-
gramme of
1898-99.

The battleships of the 1898-99 programme, which were described in the *Annual* of last year, are the *Venerable*, *London*, and *Bulwark*. The *London* is at Portsmouth, the *Bulwark* at Devonport, and the *Venerable* at Chatham. These three vessels are still completing; they were all launched in 1899.

Four other battleships appeared in the Supplemental Programme of 1898-99, these vessels being the *Duncan* and *Cornwallis*, laid down at the Thames Ironworks on July 19, 1899; the *Exmouth*, laid down at Messrs. Laird's at Birkenhead, and the *Russell*, at the Palmer Shipbuilding Company's yard at Jarrow, in the same year. The last-named vessel was launched on February 19, 1901, and the following description of her was given in the *Times* of that date:—

The principal dimensions are: length between perpendiculars, 405 ft.; breadth, 75 ft. 6 in.; draught, 26 ft. 6 in.; displacement, 14,000 tons; indicated horse-power, 18,000; speed, 19 knots. She is of steel throughout, and is built on the longitudinal system; the stem, sternpost, propeller shaft brackets, and ram of massive strength are formed of steel castings. The hull is divided into 320 water-tight compartments, and

there is a double bottom, extending four-fifths of her total length, under the engine and boiler rooms, magazines, and shell-room spaces. The port and starboard engine-rooms are divided by a middle line water-tight bulkhead extending from the keel to main deck 10 ft. above the load water-line. There are three boiler rooms, each being a separate water-tight compartment, and containing in all twenty-four Belleville water-tube boilers. There are longitudinal water-tight bulkheads at the sides extending throughout the machinery and boiler spaces, and subdivided off by athwartship water-tight bulkheads, forming in all fifty-two coal bunkers which act as an additional protection to the engines and boilers. On the platform and lower decks is placed the auxiliary machinery for the working of the ship, including electric engines, hydraulic pumping engines, capstan engines, air compressors, &c., as well as a fully equipped engineers' workshop and numerous store-rooms.

The officers and crew are accommodated on the middle and main decks, the admiral and captain having day-cabins on the upper deck. The officers' accommodation consists of cabins situated aft, those for the superior officers being on the main deck. The admiral's accommodation is at the extreme aft end of the main deck, with access to a handsome stern walk fitted with a light steel canopy. The upper deck extends from stem to stern without a break, and above it are the forward and after shelter decks, on which are placed the conning towers, the latter being of 12-in. Harvey steel, and the former of 3-in. nickel steel; these are surmounted by flying bridges, and connected on each side by a fore and aft bridge. The boats, of which there are eighteen, including two 56-ft. steam pinnaces, are stowed amidships on skid beams. A strong steel derrick, worked by hydraulic power, tested to 36 tons lift, is fitted to the mainmast for lifting them, and the foremast is also fitted with two steel derricks of 10 tons test each, for working those of a lighter description. The fore and main lower masts are built of steel, and fitted with military fighting tops and searchlight platforms, with wood topmasts and upper and lower signalling yards. There are two funnels in fore and aft line between the masts.

The barbettes, one forward and one aft, rise from the middle deck and project a few feet above the upper deck, protected by 10-in. and 11-in. Harvey armour, and inside are powerful hydraulic turning engines, and all the gear necessary for controlling the ponderous turn-table, carrying two 12-in. b.l. guns in a specially protected shield in each barbette. The main deck, which forms the top of the armoured citadel, is a protective deck 2 in. thick, enclosing the barbettes, and reduced to 1 in. thick at the stem. The middle deck, which is a protective deck of 1 in. steel, is horizontal in the centre, 2 ft. 6 in. above the load-line, and sloped down at an angle of about 40 degrees at the sides to 5 ft. below the load-line, which forms the shelf on which the side armour rests, this protective deck running in this form from after to forward barbettes, of which it is the foundation; it then dips down at the centre, gradually losing the angles at each side, and eventually forming the lower deck, still retaining its protective thickness right to the stem casting, to which it is strongly secured. Before and abaft of the barbettes the line of this deck is continued as an ordinary deck. The lower deck is a sloping protective deck of 1 in. thickness before the forward barbette, and 2 in. thick aft of the after barbette, and protecting the steering gear, &c. The sides of the vessel are protected from stem to transverse armoured bulkhead with two thicknesses of $\frac{1}{2}$ -in. nickel steel on $\frac{1}{4}$ -in. ordinary steel plating, and from armoured bulkhead to a distance of 286 ft. by 7-in. Harvey armour about 14 ft. wide in wake of barbettes, reducing gradually to 2-in. nickel which finishes in the rabbit on stem, giving great rigidity to the powerful ram. Behind this belt of armour coal bunkers are arranged whereby a large amount of additional protection is secured. With a view to preventing water from finding its way below the protective deck, means are provided for closing the several openings by water-tight shutters and covers, while in the case of those which must necessarily remain open in action coffer-dams have been fitted with the same object.

The main armament consists of four 50-ton breechloading guns of 12-in. calibre, with a training of 120 degrees each side of the middle line. The auxiliary armament consists of twelve 6-in. quick-firing guns, each placed in a casemate of Harvey armour 6-in. thick. Four of these are on the upper deck, the two forward ones training over the bow and 30 degrees abaft the beam, and the two after ones training over the stern and 30 degrees before the beam. The other eight are situated on the main deck, the four forward and aft trained the same as the guns on the upper deck, and the four in the midships are trained 60 degrees before and abaft the beam. Twelve 12-pounders, two in the bows and two in the after-quarter on the main deck, and six in waist of ship on upper deck, and two on forward shelter deck, the latter being field and boat guns, eight Maxims on shelters and bridges, and six 3-pounders, three in each military fighting top. Four submerged 18-in. torpedo tubes, two forward and two aft.

The ship will be lighted throughout by electricity, with an installation of about 900 electric lamps, and will also be equipped with six searchlights of 25,000 candle-power each, the dynamos being under protection. Means are so arranged that when in action she can be fought from either of the two conning towers. The main propelling engines

are twin screw, and are also constructed by Palmer's Company, each set consisting of four cylinders—*i.e.*, one high pressure $33\frac{1}{2}$ in. diameter, one intermediate pressure $54\frac{1}{2}$ in. diameter, and two low pressure each 68 in. diameter, the stroke of all being 4 ft. The engines will be run at 120 revolutions per minute. Steam is supplied by twenty-four boilers of the Belleville type, the total tube surface being nearly 45,000 square feet. The working pressure of the boilers is 300 lb. per square inch, reduced at the engines to 250 lb. per square inch. In addition to the main propelling engines, there are steering engines, electric light engines and dynamos, air-compressing engines, distilling machinery, coal-hoisting machinery, hydraulic boat hoists, capstans, workshop engines, and about seventy other auxiliary engines, such as feed pumps, fire and bilge pumps, fans and engines, air-blowing engines, ash hoists, centrifugal pumping engines, &c.

The weight of the Russell, when she was launched, was 5950 tons, and her contract delivery date is February, 1902. It is anticipated, however, that she will be delivered somewhat earlier, as good progress has been made on her. The Exmouth is rapidly approaching a state fit for floating out of dock, having now nearly 5000 tons of material worked into her hull, exclusive of armour, and about a third of the heavy citadel armour in place. Her machinery has been erected, and is well advanced. The Duncan was launched on March 21, and the Cornwallis will be launched on June 18 of the current year.

Pro-
gramme of
1899-1900.

The battleships of the 1899-1900 programme are the Montagu, laid down at Devonport on November 23, 1899, and the Albemarle, laid down at Chatham on January 1, 1900. These two vessels were launched on March 5, 1901. They are of the same class as the Russell, described above. The launching weight of the Albemarle was 5100 tons, and that of the Montagu 4987 tons.

Pro-
gramme of
1900-1901.

The battleships of the 1900-01 programme, the Queen, at Devonport, and the Prince of Wales, at Chatham, have taken the places on the stocks of the vessels last named, but will be heavier than these and somewhat differently armed. Their dimensions are as follows: Length, 400 ft.; breadth, 75 ft.; mean load draught, 26 ft. 9 in.; displacement, 15,000 tons. The armour will include a steel belt, commencing about 30 ft. from the bow and running a distance of 220 ft. towards the after part of the ship. This belt will be 15 ft. deep and of 9-in. armour plates. There will be a curved, transverse bulkhead, near the after barbette, made of 12-in. armour plates, while the barbettes themselves will be built of plates varying from 6 in. to 12 in. thick. A protective deck covering the vital parts has been provided for, this being of the turtle-back shape, having a thickness of 1 in. on the flat and 2 in. on the slopes. The barbette hoods will be of 8-in. and 10-in. armour, and the casemates for the 7-in. and 6-in. guns will consist of 6-in. plates. The armament will comprise four 12-in. 50-ton wire-wound, breechloading guns, mounted in pairs in two barbettes—one forward and the other aft; eight 7.5-in. modified Q.F. guns of a new type; eight or ten 6-in. Q.F.

guns; sixteen 12-pounders (12 cwt.), and two 12-pounders (8 cwt.); six 3-pounder Hotchkiss, eight .45-in. Maxim machine guns, and four submerged Whitehead torpedo-tubes. The engines are to develop about 20,000 I.H.P., giving a speed of 19 knots.

In this year's programme three battleships are mentioned, two of which are to be built at Portsmouth and Devonport respectively, and the third by contract. In the estimates it is stated that the design of these ships is not complete, and the sums which it is proposed will be spent on their construction during the current financial year are (1) £40,186; (2) £32,770; (3) £12,192.

An estimate of the relative rate of progress made on the battleships of the later programmes may be formed from the following tables. The six ships of the Formidable class have been considerably advanced. The Implacable is to be ready for the pennant during June, the Formidable and Irresistible should be finished in the summer of 1901, and the Bulwark in December. The London and Venerable are to be completed by May, 1902.

DOCKYARD BUILT.

| Ship. | Dimensions, &c. | | | | Laid Down. | Date of Launch. | Total probable Expenditure on Hull, &c. to Mar. 31, 1901 (exclusive of Armour). | Proportion of Total Estimated Cost of Hull, &c. (exclusive of Armour). |
|---------------|-----------------|----------|----------|----------|---------------|-----------------|---|--|
| | Length. | Breadth. | Draught. | Tonnage. | | | | |
| | ft. | ft. in. | ft. in. | tons. | | | £ | |
| DUNCAN CLASS: | | | | | | | | |
| Albemarle | 405 | 75 6 | 26 6 | 14,000 | Jan. 8, 1900 | Mar. 5, 1901 | 179,378 | ·464 |
| Montagu | | | | | Nov. 23, 1899 | Mar. 5, 1901 | 169,746 | ·438 |

CONTRACT BUILT.

| | | | | | | | | |
|---------------|-----|------|------|--------|---------------|----------------|---------|------|
| DUNCAN CLASS: | | | | | | | | |
| Duncan | 405 | 75 6 | 26 6 | 14,000 | July 10, 1899 | Mar. 21, 1901 | 229,080 | ·517 |
| Cornwallis | | | | | July 13, 1899 | *June 18, 1901 | 196,477 | ·443 |
| Exmouth | | | | | Aug. 10, 1899 | Not fixed | 188,663 | ·421 |
| Russell | | | | | Mar. 11, 1899 | Feb. 19, 1901 | 234,696 | ·513 |

* Probable date.

The armoured cruisers in hand are of three classes, of 14,100 tons displacement, 12,000 tons, and 9800 tons respectively, and are known as the Drake, Cressy, and Kent (or County) classes. Of the Cressy class six ships are under construction. The Sutlej was launched at Clydebank on November 18, 1899, and the Cressy at the Fairfield Company's works at Govan on December 4, 1899. During the past

Armoured
cruisers.

year three other vessels of this class have taken the water—the Aboukir at Govan on May 16, the Hogue at Barrow on August 13, and the Bacchante at Clydebank on February 21. The remaining vessel of this class on the stocks is the Euryalus, building at Barrow. This vessel was to be ready for launching in April, 1901, but the actual date on which she would take the water depended on the completion of the Ramsden Dock sill. The vessels of this class were briefly described in the *Naval Annual* for 1899. The following additional details are taken from official particulars, others furnished by the builders of the Hogue, and information from other sources:—

The Hogue is of the Cressy type, and in some respects resembles the Powerful, embodying features of that ship, with the addition of an armoured belt of considerable area. The displacement is 12,000 tons. The hull is sheathed with teak and coppered. The armament comprises two 9·2-in. (22-ton) guns, each mounted in an armoured barrette, the mountings being of special design, by which the guns can be loaded at any angle of elevation or training. There are also eight 6-in. guns, twelve 12-pr. Q.F. guns, and a number of machine guns. The four boiler compartments of the Hogue take up 130 ft. of the length of the ship; the coal bunkers being arranged on either side of the boiler rooms and over the protective deck, and an ammunition passage is situated immediately under the protective deck. There is also an athwartships bunker right forward. Thirty boilers are carried, all of the Belleville type. The Hogue is about 5 ft. longer than the Diadem class, and has a few inches more beam and draught. She is, however, built on finer lines forward, and, though this gives her a more lively pitch in a seaway, her speed and stability are improved. The special characteristic of the Hogue is her armour, which weighs 1100 tons, and some small economies have had to be effected to give her only 1000 tons more displacement than the Diadem. For instance, in the Hogue, in the wake of the citadel, the deck consists of only two $\frac{1}{2}$ -in. plates, while the protective deck is not so thick as in the Diadem. The belt, which is coterminous with the citadel, has a length of 230 ft. and a depth of 11 ft. 6 in.—that is to say, beginning at the main deck, it goes to a depth of 5 ft. below the water-line, where it joins the protective deck, thus completely enclosing in armour the vital parts of the ship. Throughout the armour is of Harveyized steel, of a thickness of 6 in. at the belt and of 5 in. at the thwartship bulkheads at either end of the citadel. Forward of the citadel the structure is stiffened by 2 in. of nickel steel to support the ram and to keep out small projectiles. The conning tower is of the thickness of 12 in. Above the belt are the 12 6-in. Q.F. guns, and these are carried in 6-in. casemates, but with no other armoured protection.

The Cressy was delivered at Portsmouth in October, 1900, from the works of the Fairfield Company, and subsequently went through the whole of her contractor's trials with remarkable success. As reported in the *Times* of December 17—

“During her eight hours' full-power trial, when the wind and sea materially reduced her speed, she averaged 20·7 knots, while her engines worked so uniformly that the I.H.P. was 10,473 starboard and 10,767 port, but the difference between the power of the two engines at the preceding thirty hours' trial at four-fifths power was only 12, the I.H.P. starboard being 8141 and port 8129, while the revolutions on both sides were identical, being 1·146 starboard and port. During this trial the vessel made five runs over the deep-sea course at a mean speed of 20·596, or only a fraction less than that recorded at the full-power trial. It is not customary to record the coal consumption at a

full-power run, but it was taken in the case of the Cressy, and worked out at 1·93 per unit of power per hour, but at the four-fifths power run it was only 1·79."

The four armoured cruisers of the Drake class are building at Pembroke, the Good Hope (late Africa) at Govan, the Leviathan at Clydebank, and the King Alfred at Barrow. Of these four ships the Good Hope was launched on February 21 and the Drake on March 5. The other two are yet on the slips; but the King Alfred will be ready for launching in August.

The
Drake
Class.

The design of the vessels of the Drake class is practically identical in principle with that of the cruisers of the Cressy and Monmouth classes; that is to say, it is a combination of two thick armoured decks, with vertical side plating. The principal dimensions are:—Length between perpendiculars, 500 ft.; extreme breadth, 71 ft. 4 in.; mean load draught, 26 ft.; displacement at load draught, 14,150 tons. The boiler and engine-rooms occupy the middle portion of the ship below, and magazines, shell-rooms, and stores of one kind and another, the lower parts at the ends. Above the lower deck for a considerable distance, on the fore side of the armour bulkhead, the space between it and the main deck forms coal bunkers which, when full of coal, will greatly increase the protection afforded to the vital parts below them. Underneath the lower deck, on each side, are ammunition passages, which enable the ammunition to be conveyed under protection to armour tubes, which communicate between it and the casemates. The space between the lower and main decks, at the fore end, is occupied by store-rooms, and at the after end warrant-officers' cabins, pantries, &c., will be constructed. On the main deck aft, the officers' cabins will be built, while forward, and between the casemates, which are situated at intervals along the side, four in number on each side, the crew will be accommodated. The casemates are in every case double storied. They are to be formed of 6-in. Krupp armour-plates in front, and 2-in. plates at the sides and rear. At the fore and after ends of the ship are the barbettes for mounting the two 9·2 B.L. guns, protected by 6-in. armour. Sixteen 6-in. B.L. guns will be mounted, one in each casemate, twelve 12-pounder Q.F. guns on the upper deck, and the minor armament will consist of two boat and field 12-pounders, and three 3-pounder Q.F. guns. They will also carry nine ·75 Maxims, with two submerged torpedo-tubes, each capable of discharging 18-in. torpedoes. The propelling or driving machinery consists of twin screws driven by independent sets of vertical triple-expansion engines, with inverted cylinders, the diameters of which are: high pressure, 43½ in.; intermediate, 71 in.; and low pressure (two in number), 81½ in. The main condensers will have a cooling surface of 32,000 square feet, and the auxiliary condensers, 3,450 square feet. Steam will be supplied by forty-three Belleville boilers, which will be fitted with economisers. The boilers comprise a total of 5348 tubes, with 47,520 square feet of surface, and the economisers 5328 tubes, with 24,450 square feet of surface. There will be forty-three fire-grates, with a total heating surface of 2310 square feet. The engines are expected to indicate 30,000 horse-power, giving the ship a speed of 23 knots. They will be required to maintain their full power for eight hours continuously on the official trial. In smooth water at sea 21 knots is to be the steady speed. Electricity for lighting purposes will be supplied from four dynamos.

Of the vessels of the Monmouth class two belong to the programme of '98-99; the Kent, laid down at Portsmouth February 12, 1900, and launched March 6, 1901; and the Essex, laid down at Pembroke January 1, 1900, and expected to be ready for launching in August or September next. Two are of the programme of '99-1900, the Monmouth and Bedford, both building by the Fairfield Company at Govan. These vessels should be ready for launching in May and June respectively. The remaining six are of last year's programme. They have been, or are to be, laid down as follows:—The Cornwall at Pembroke, on the slips from which the Drake was launched; the Suffolk at Portsmouth, in the place of the Kent; the Berwick by

The Mon-
mouth or
"County"
Class.

Messrs. Beardmore and Co., Limited; the Cumberland by the London and Glasgow Shipbuilding Company, Limited; the Donegal by the Fairfield Company; and the Lancaster at Elswick.

With regard to this class, the following comments on their design are taken from an article on the subject in the *Engineer* of October 12, 1900.

The principal particulars of the type are as follows:—

| | | | |
|------------------|-----|-----|--|
| Displacement ... | ... | ... | 9800 tons. |
| Length ... | ... | ... | 440 ft. |
| Beam ... | ... | ... | 60 ft. |
| Draught—mean ... | ... | ... | 24½ ft. |
| Armament ... | ... | ... | fourteen 6-in., 45 calibre; ten 12-pounders; three 3-pounders; and an indefinite number of Maxims, probably eight. |
| Torpedo-tubes... | ... | ... | Two 18-in. submerged. |

In the arrangement of her guns the Essex closely resembles the Renown, and bears much the same ratio to the big armoured cruisers of the Drake and Cressy classes that the Renown bears to the Majestic class; the only striking difference is that the Essex has the high fore-castle common to all our cruisers nowadays, and that the 12-pounder battery amidships is open as in the Duncan. As for these differences, the high fore-castle is absolutely indispensable to a swift cruiser. Earlier cruisers, like the Blake and Edgar classes, suffer a good deal in bad weather from the sea they take in forward; the effect of which is noticeable in two vessels of the class—Crescent and Royal Arthur, which had their fore-castles built up to improve their steaming qualities in bad weather. The more or less open upper deck is, we believe, the result of a report sent in by Captain H. J. May, R.N., who pointed out that the high bulwarks in the Majestic, and later types up to the Duncan, would simply burst shells in the worst possible place—*i.e.*, just in front of men at the guns. The compromise in the Essex design falls a good deal short of Captain May's ideal, which was to have the 12-pounders absolutely unencumbered by boats, davits, stanchions, or anything else—still it is a vast improvement upon the older idea of high bulwarks. All fourteen 6-in. guns are protected in the Essex, being mounted in armoured casemates. The armour of the Essex is thin and extensive. There is a belt about 250 ft. long amidships of 4-in. Krupp cemented armour, and this belt extends right up to the main deck. It is continued to the bow at a thickness of 2 in. Aft it is terminated by a 5-in. bulkhead. A curved protective deck runs throughout the length of the ship and reinforces the water-line protection. The space above and below is filled, as usual, with coal bunkers. The casemates are 4 in. thick, the turrets 5 in., but for these nickel armour, not Krupp, is employed. It has less resisting power, but is more easily worked. There is said to be great difficulty in using Krupp armour for circular or nearly circular turrets. These turrets have short armoured bases of 5 in. thickness, with armoured hoists going down the main deck. The turrets are distinctive and, so far, peculiar to the Essex class. To begin with, the guns in each can be trained together and fired as one piece or else used independently. There is a single hoist to the pair of guns, worked by an electric motor. It serves with very great rapidity, and when in full working order delivers every alternate charge to the port gun, which has a special small motor to catch it as it comes up the endless chain. This arrangement can be easily disconnected—the hoist is then made to serve one gun only. It remains to be added that three layers of projectiles are carried in the turret underneath the guns, which can be loaded in any position or elevation. Double hoists, adapted from the same system, will, it is said, be fitted to the two-storey casemates.

A similar table to that prepared for the later battleships is placed below in order that the present state of the three classes of cruisers may be seen. Of the twenty under construction the Cressy only has carried out her steam trials. Preliminary trials have been made with the new mounting for her 9·2-in. guns, and her gunnery trials are to take place early in April. The Sutej has been delivered at

Chatham, and is preparing for steam trials. The Aboukir is to be delivered almost immediately.

DOCKYARD BUILT.

| Ship. | Dimensions, &c. | | | | Laid Down. | Date of Launch. | Total probable Expenditure on Hull, &c., to Mar. 31, 1901, (exclusive of Armour). | Proportion of Total Estimated Cost of Hull, &c. (exclusive of Armour). |
|-----------------|-----------------|----------|----------|----------|---------------|-----------------|---|--|
| | Length. | Breadth. | Draught. | Tonnage. | | | | |
| | ft. | ft. in. | ft. in. | tons. | | | £ | |
| DRAKE CLASS: | | | | | | | | |
| Drake | 500 | 71 0 | 26 0 | 14,100 | Apr. 24, 1899 | Mar. 5, 1901 | 255,653 | ·644 |
| MONMOUTH CLASS: | | | | | | | | |
| Kent | 440 | 66 0 | 24 6 | 9,800 | Feb. 12, 1900 | Mar. 6, 1901 | 150,943 | ·516 |
| Essex | | | | | Jan. 1, 1900 | Aug., 1901 | 135,718 | ·464 |
| Cornwall | | | | | Mar. 11, 1901 | — | 40,690 | ·139 |
| Suffolk | | | | | — | — | 41,340 | ·141 |

CONTRACT BUILT.

| | | | | | | | | |
|-----------------|-----|------|------|--------|----------------|---------------|---------|------|
| DRAKE CLASS: | | | | | | | | |
| Levia- than | 500 | 71 0 | 26 0 | 14,100 | Nov. 30, 1899 | Uncertain | 130,484 | ·303 |
| Good Hope | | | | | Sept. 11, 1899 | Feb. 21, 1901 | 203,425 | ·481 |
| King Alfred | | | | | Aug. 11, 1899 | *Aug., 1901 | 139,690 | ·325 |
| MONMOUTH CLASS: | | | | | | | | |
| Mon- mouth | 440 | 66 0 | 24 6 | 9,800 | Aug. 20, 1899 | *May, 1901 | 110,538 | ·364 |
| Bedford | | | | | Feb. 19, 1900 | *June, 1901 | 150,632 | ·467 |
| Berwick | | | | | — | — | 10,375 | ·034 |
| Cumber- land | | | | | Feb. 19, 1901 | — | 10,930 | ·034 |
| Donegal | | | | | Feb. 14, 1901 | *Feb., 1902 | 10,870 | ·034 |
| Lan- caster | | | | | — | — | 11,125 | ·034 |
| CRESSY CLASS: | | | | | | | | |
| Aboukir | 440 | 69 6 | 26 3 | 12,000 | Nov. 9, 1898 | May 16, 1900 | 308,105 | ·880 |
| Cressy | | | | | Oct. 12, 1898 | Dec. 4, 1899 | 339,029 | ·986 |
| Hogue | | | | | July 14, 1898 | Aug. 13, 1900 | 272,049 | ·747 |
| Sutlej | | | | | Aug. 15, 1898 | Nov. 18, 1899 | 333,826 | ·919 |
| Eury- alus | | | | | July 18, 1899 | *May, 1901 | 181,439 | ·471 |
| Bac- chante | | | | | Feb. 15, 1899 | Feb. 21, 1901 | 214,209 | ·602 |

* Probable dates.

Six armoured cruisers are in this year's programme, of which number one is to be built at Chatham, the others by contract.

Protected
cruisers.

Of first-class protected cruisers the only vessel which remained uncompleted last year was the *Spartiate*, laid down at Pembroke on May 10, 1897, and launched October 27, 1898. This vessel has been delivered at Portsmouth, where, in November last, she began her trials, with the following results. She first made a satisfactory official trial at one-fifth her full power, and, on that occasion, she drew 24 ft. 6 in. forward and 26 ft. 5 in. aft, and had 215 lbs. of steam to the square inch in her boilers. The total I.H.P. was 3834, and the mean speed 12.3 knots. The coal consumption worked out at 1.83 lbs. per unit of power per hour. She used only ten out of her thirty Belleville boilers, which gave no trouble of any kind. A few days afterwards she left Portsmouth for a thirty-hours' trial at four-fifths her power, but had to return, as four hours after the run began, one after another, in quick succession, the bearings became overheated. The trial was at once stopped, and the vessel was placed in the Dockyard hands before resuming her trials. A condemned crank shaft has to be replaced.

Second-
class
cruiser.

The new second-class cruiser of an improved *Hermes* type, referred to on page 17 in last year's *Annual*, is building at Chatham, and will be named the *Challenger*. She was laid down on December 1, 1900. The new vessel will be much larger than any of the second-class cruisers now afloat, and will deviate from those recently constructed. She will be 355 ft. long, 56 ft. wide, and have a displacement of about 5880 tons. It is intended that she shall be fitted with Babcock and Wilcox boilers, and engines of 12,500 I.H.P. The draught forward is to be 19 ft. 3 in., and aft 21 ft. 3 in. It will be noted that she is only five feet shorter than the *Crescent* and *Edgar* classes. A similar ship of the same programme was laid down at Devonport on January 28, 1901, and will be named the *Encounter*. The engines and boilers of this vessel are to be made at Keyham. Good progress has been made in the construction of both these vessels. The *Encounter* was proposed to be fitted with Belleville boilers.

Special attention has been directed to an earlier type of second-class cruiser by the mishaps which have befallen the *Hermes*. This vessel was commissioned for the North America and West Indies Station in October 1899, and soon after she arrived on the station her boilers gave considerable trouble. While on passage from Bermuda to Halifax she became completely disabled, and had to be towed into harbour. After repairs the defects in her boilers became again manifest, and she was eventually ordered to return home, and it is understood that she will have to be provided with new boilers. The

Highflyer, a sister ship, was commissioned on December 7, 1899, as flagship in the East Indies. On a two hours' full power trial of the ship, the following mean results were obtained:—Steam in boilers 295 lbs., at engines 241 lbs.; vacuum, starboard 24·5 in., port 25·1 in.; revolutions, starboard 180·4, port 178·9; I.H.P., starboard 5180, port 5005—total, 10,185; air pressure, ·22 in.; speed, 19 knots. The Hyacinth, the third vessel of this type, was commissioned on September 3, 1900, and has been employed in making a series of trials under the supervision of the special Boiler Committee.

The Pandora, mentioned in last year's *Annual*, which was built and engined at Portsmouth, went through her trials in December with the following results: On the thirty hours' half-power, with a mean of 195 revolutions, she made 3638 mean I.H.P., and a mean speed of 16·7 knots. Her coal consumption was 2·11 lbs. per horse-power. She is the last of the "P" class, the corresponding trials of which were as follows:—

Third-class
cruisers.

| NAME. | HOURS. | I.H.P. | KNOTS. |
|--------------------------|--------|--------|--------|
| Pelorus | 60 | 4277 | 17·3 |
| Proserpine | 60 | 3615 | 17 |
| Pactolus | 30 | 3631 | 16·6 |
| Pegasus | 30 | 3698 | 17·3 |
| Pomone | 30 | 3604 | 16·5 |
| Prometheus | 30 | 3556 | 17·5 |
| Pyramus | — | 3605 | 17·5 |
| Pioneer | — | 3665 | 16·3 |
| Psyche | — | 3647 | 16·8 |
| Pandora | — | 3638 | 16·7 |
| Perseus (not available). | | | |

Two third-class cruisers, to be built by contract, are in the new programme of shipbuilding.

In addition to the vessels named under the head of sloops in last year's *Annual*, the two which appeared in the programme for 1900–1, were laid down at Sheerness on February 11, 1901. They are to be called the Merlin and Odin. There are now, altogether, ten vessels of this type, of which the two earliest, the Condor and Rosario, are in commission—the one in the Pacific, the other in China. The Shearwater and the Vestal underwent their trials during the latter part of 1900; these vessels were laid down February 1, 1899, and were floated on February 10, 1900. The following are the results of their trials:—

Sloops.

EIGHT HOURS' NATURAL DRAUGHT TRIALS.

| NAME. | COAL PER I.H.P. PER HOUR. | TOTAL I.H.P. | MEAN REVOLUTIONS. | SPEED. |
|-------------------|------------------------------|--------------|----------------------|------------|
| Shearwater | 1·57 lbs. | 1432·3 | 194·2 | 13·5 knots |
| Vestal | 1·55 lbs. | 1484·7 | 204·8 | 13·56 „ |

Both ships afterwards underwent a series of trials to ascertain the consumption of coal and water, the results being highly satisfactory in each case. The Vestal's engines and boilers were manufactured at Keyham, while those for the Shearwater were supplied by the Thames Ironworks and Shipbuilding Co. The coal consumption of the Vestal for the thirty-hours' run at 300 horse-power was 1·57 lbs. per horse-power per hour compared with 1·88 lbs. for the Shearwater. At the thirty-hours trial at five-sevenths horse power the Vestal's I.H.P. was 1014·6, with a coal consumption of 1·42 lbs. per I.H.P. per hour; on the other hand, the Shearwater's I.H.P. was 1024·5 and her coal consumption 1·73 lbs. per I.H.P. per hour. These two vessels have been completed and passed into the Reserve.

Of the other vessels of the same type, the Mutine and Rinaldo, building at Laird's, have been launched, and the former has been delivered. The Espiègle and Fantôme have also been launched at Sheerness, and their places occupied by the Odin and Merlin. The boilers of the Espiègle are of the Babcock and Wilcox water-tube type, and her engines have been supplied by the Wallsend Slipway and Engineering Co. The Fantôme will be fitted with Niclausse boilers.

The trials of the Mutine have been concluded, and were most satisfactory. The following are particulars of the eight hours' full-power natural draught trial:—Draught of water—forward, 9 ft. 10½ in.; aft, 12 ft. 11 in.; pressure of steam in boilers, 225·2 lbs.; ditto in engine-room, 215·6 lbs.; air pressure, ·17 in.; vacuum, 26·4 in.; revolutions, 206·5 per minute; I.H.P.—high, 483·9; intermediate, 428·8; low, 577·9—total, 1490·6 I.H.P.; speed by the patent log, 14·55 knots; speed on the measured mile, 13·74 knots. The machinery and Belleville boilers worked satisfactorily throughout.

Gunboats.

Two gunboats of light draught, the Teal and Moorhen, have been begun in the past year, and are now well advanced.

De-
stroyers.

The table on the opposite page, published in *Engineering* of December 28, gives particulars of the trials of torpedo-boat destroyers in 1900.

The most important boat of those mentioned in this table is the Albatross, which is not only heavier than the others but has higher power and speed. Comparisons were drawn between the coal consumption of this boat and that of the Viper fitted with Parsons's steam turbine, and these elicited an interesting correspondence in the *Times*. Of the five destroyers with speeds of over 30 knots the two above mentioned have completed their trials. The Cobra has been tried, and for three hours exceeded the 30 knot speed. Two others are to be delivered shortly. Altogether, at the close of the financial year,

ten destroyers remained to be delivered, but five additional vessels have been purchased and are to be delivered this year. There are ten new destroyers in this year's programme. During the year the Lively, torpedo-boat destroyer, was launched from the yard of Messrs. Laird Bros., at Birkenhead, making the eighteenth vessel of this class built by the firm for the Navy.

TRIALS OF TORPEDO-BOAT DESTROYERS DURING THE YEAR 1900.

| Name of Firm and Engineer. | Name of Vessel. | Approximate Displacement. | Type of Boilers. | Grate Area. | Tube Surface. | I.H.P. | Speed in Knots. | Pounds of Coal per I.H.P. per Hour. |
|---|-----------------|---------------------------|-------------------|-------------|---------------|------------------|-----------------|-------------------------------------|
| | | tons. | | sq. ft. | sq. ft. | | | |
| John Brown and Co., Limited .. | Brazen | 318 | Clydebank Normand | 224 | 12,000 | 6539 | 29.565 | 2.5 |
| | | | | | | 6734 | 29.418 | — |
| | | | | | | 466 | 12.963 | 1.61 |
| | Electra | 319 | " | 224 | 12,000 | 6567 | 29.557 | 2.32 |
| | | | | | | 6751 | 29.583 | — |
| | Recruit | 324 | " | 224 | 12,000 | 6581 | 29.319 | 2.33 |
| | | | | | | 6521 | 29.268 | — |
| J. I. Thornycroft and Co. .. | Thorn | 342 | " | 224 | 12,652 | 6540 | 30.174 | 2.34 |
| | | | | | | 6455 | 30.063 | — |
| | Tiger | 339 | " | 224 | 12,6.2 | 6840 | 29.921 | 2.34 |
| | | | | | | 6409 | 30.056 | — |
| | Vigilant | 338 | " | 224 | 12,652 | 6218 | 30.094 | 2.38 |
| | | | | | | 6507 | 30.147 | — |
| | Albatross | 360 | Thornycroft | 252 | 16,020 | 718 | 14.330 | 1.97 |
| Earle's Shipbuilding and Engineering Company, Limited | | | | | | 7722 | 31.552 | 2.26 |
| | | | | | | 7678 | 31.500 | — |
| | Stag | 306 | " | 193 | 12,072 | 406 | 13.081 | 2.25 |
| Fairfield Shipbuilding and Engineering Company | | | | | | 5204 | 30.156 | 2.307 |
| | | | | | | 5561 | 30.345 | — |
| | Bullfinch | 318 | " | 236 | 13,400 | 6022 | 29.460 | 2.37 |
| Palmer's Shipbuilding Company | | | | | | 5802 | 29.250 | 2.75 |
| | | | | | | 6012 | 29.363 | — |
| | Dove | 322 | " | 236 | 13,400 | 6299 | 30.135 | 2.22 |
| Doxford | | | | | | 6318 | 30.099 | — |
| | | | | | | 437 | 13.040 | 1.549 |
| | Falcon | 333 | " | 245 | 13,000 | 6311 | 30.112 | 2.206 |
| Hanna, Donald, and Wilson .. | | | | | | 6172 | 30.161 | — |
| | | | | | | 6444 | 30.097 | 2.300 |
| | Ostrich | 331 | " | 245 | 13,000 | 9320 | 30.054 | — |
| Hawthorn, Leslie, and Co. | | | | | | 6558 | 30.110 | 2.635 |
| | | | | | | 6265 | 30.078 | — |
| | Peterel | 340 | Reed | 258 | 13,784 | 3885 | 27.171 | — |
| Lee | | | | | | 419 | — | — |
| | | | | | | Power trial only | 12.971 | 2.56 |
| | Lee | 322 | Thornycroft | 237 | 13,520 | 3713 | — | — |
| Zephyr | | | | | | | | |
| | | | | | | | | |
| | Zephyr | 326 | Reed | 238 | 9,936 | | | |
| Havock (trial after reboiler-ing) .. | | | | | | | | |
| | | | | | | | | |
| | Havock | .. | Modified Yarrow | 150 | 8,512 | | | |

In addition to the above vessels, the Viper and Cobra, fitted with turbine engines by the Parsons Marine Turbine Company, have run their official trials. These two vessels, built by Messrs. Hawthorn, Leslie, and Co. and Messrs. Armstrong, Whitworth, and Co. respectively, have boilers of the modified Yarrow type, made by Messrs. Hawthorn, Leslie, and Co., with a grate area of about 276 square feet, and a tube surface of about 15,044 square feet per vessel.

An improved type of torpedo-boat, known as No. 98, being the first of the four mentioned on page 20 of the *Annual* last year, was launched from the yard of Messrs. Thornycroft and Co., of Chiswick, on January 22. The dimensions of this vessel are 160 ft. long by 17 ft. beam, 8 ft. 4 in. draught, 128 tons displacement. She has a heavier armament than any boat yet built, and, with 2850 indicated horse-power, is to develop the high speed of 25 knots with a full load of 42 tons on board. The engines are of the Thornycroft patent balance type, and the boilers are of their water-tube type, which have

Torpedo-boats.

worked successfully in the destroyers built by this firm for the British and other Governments. It is anticipated that the large size necessary for the increased speed and heavy load compared with the earlier boats will enable this type of vessel to maintain full speed even in rough weather better than its predecessors did in smooth. No. 98 was launched complete and ready to begin her trials; No. 99 has since been launched; the remaining boats will be numbered 107 and 108. All four boats are to be delivered and tried by September next. Five boats are in the new programme.

The
Royal
Yacht.

Reference was made in last year's *Annual* to the accident which occurred while undocking the new royal yacht at Pembroke, and to her having been sent to Portsmouth to undergo alteration. She underwent her trials in September with highly satisfactory results: not only did the machinery work smoothly, but the speed reached the maximum of expectation, the coal consumption was moderate, and the sea-keeping qualities of the vessel proved to be all that could be wished. In a heavy sea and three-fourths of a gale the stability of the ship under trying conditions was fully tested. In running before the wind she was perfectly steady; against the wind she pitched, but her movement synchronised with the action of the sea; with the wind abeam she rolled, but, even in turning, the heel did not exceed ten degrees, and the time taken in rolling from one side to the other was about the average of a well-found warship. The mean results of the forty-eight hours' run were as follows:—I.H.P. 5142; coal consumption per hour, 10,241·3 lbs.; consumption per unit of power per hour, 1·94 lbs.; speed, 16·3 knots. At a second trial with 7625 I.H.P., the coal consumption worked out at 1·94 lbs. per unit of power per hour, the mean speed being 18·3 knots. A third run of forty-eight hours at 7649 I.H.P. gave a coal consumption of 1·87 lbs. per I.H.P. per hour, and a speed of 18·47 knots. The final trial of eight hours, with full speed, was made in the Channel, with the following results: The yacht drew 18 ft. 2 in. forward, and 20 ft. 1 in. aft. She had 306 lbs. of steam in her boilers. The vacuum was 25·2 in. starboard and 25·3 in. port, the revolutions being 147·2 starboard and 147·6 port. The I.H.P. was 5620 starboard, and 5678 port; the collective I.H.P. being 11,298. The mean air pressure was ·6 in., and the mean of four runs over the measured course gave a speed of 20·53 knots. These trials have been of special interest, as, after the unfortunate mishap at Pembroke, doubts arose as to the stability of the yacht. Such doubts have been entirely dispelled by the behaviour of the vessel in two gales. The engines and boilers have given as much satisfaction as the hull, and the trials have been a complete success.

The most interesting item in the new programme is five submarine boats, which were ordered from Messrs. Vickers, Son, and Maxim in 1900, when work was at once commenced upon them. The secret of their construction was kept for some time, and when it did leak out did not obtain universal credence. In the First Lord's memorandum, 1901-1902, it is stated that the first of them will be delivered next autumn, and the following explanatory paragraph is added:—"What the future value of these boats may be in naval warfare can only be a matter of conjecture. The experiments with these boats will assist the Admiralty in assessing their true value. The question of their employment must be studied, and all developments in their mechanism carefully watched by this country."

Submarine
boats.

The dimensions of the boats are 63 ft. 4 in. length over all, 11 ft. 9 in. beam, and 120 tons displacement submerged. They will be provided with means of expelling torpedoes either with the boat stationary, during the run on the surface, or submerged at full speed. The armament consists of one torpedo expulsion tube situated at the extreme forward end of the vessel, opening outward 2 ft. below the light water-line. Interlocking safety devices are employed to prevent accident while operating valves &c. on the expulsion of the torpedo. The general construction of the vessels is such that all portions of the exterior of the hull are free from projections of a nature to be entangled by ropes or other obstacles when submerged, and the lines of the vessel are specially designed to minimize resistance for surface cruising. The propulsion of the vessel on the surface is effected by a gasoline type of main engine, which is supplied with a sufficient amount of fuel for a run of about 400 knots with a maximum speed of about 9 knots. An electric main motor is provided for giving the vessel a speed of 7 knots when submerged. It is worked by storage batteries having a capacity which will admit of a speed of 7 knots for a four hours' submerged run. Gearing is provided to allow for the charging of the battery, driving the propeller from the main engine, or moving the engine from the main motor, these combinations being effected through clutches which are operated as desired. The lighting of the vessel is effected by portable incandescent electric lamps. The ballasting system consists of apparatus and means for quickly changing the vessel from light to a diving condition and for keeping her displacement constant in different waters. Also for keeping the longitudinal trim under the control of the navigator, and for compensating for the variable weights installed or expended from time to time, such as discharging torpedoes, &c. The air supply and ventilation are secured by compressed air stored on board the vessel, the gasoline vapours

from the engines being carefully excluded by suitable arrangements. Safety valves are arranged to relieve any excess of pressure in the vessel over that of the atmosphere. The steering and diving engines are provided with automatic means of moving the rudders to the desired positions to prevent the vessel from inclining to excessive angles during diving or rising, and to keep the depth of submergence constant, as well also as to bring the vessel to a horizontal position at the required depth, and to prevent diving to excessive depths. Steering and diving can be executed by hand gear if desired. The compasses are compensated and adjusted so that the boat can be steered with equal accuracy submerged as on the surface. The type is that which has been invented by Mr. Holland, and has been tried in America.

“Appendages” of the Fleet.

The provision of fleet auxiliaries or “appendages” has excited considerable discussion during the past year and has been under the consideration of the Admiralty. These auxiliaries are of six classes. Repair ships, one of which is now being fitted up. Torpedo depôt ships, of which we have two in existence, the *Vulcan* and *Hecla*. For this purpose it is believed to be more economical and more conducive to efficiency to purchase ships of the mercantile marine than to build them. Fleet colliers: There are three of these vessels now under trial, and in regard to them it is also thought that, on the whole, using private enterprise will give a better result than Government building. Distilling ships: One of these vessels has been purchased and another is to be obtained, but the trial made with two which were hired for the purpose during last year’s manœuvres was not very satisfactory. Telegraph ships: The official view on this class was reported in last year’s *Annual*. Hospital ships: It is expected that the *Maine* will be secured for service as a hospital ship in the Mediterranean during the ensuing summer.

Removals from the Navy List.

A number of old and obsolete vessels which have long encumbered the list of the Navy have now been removed. The list includes the following ironclads:—*Triumph*, *Invincible*, *Audacious*, *Northumberland*, *Agincourt*, *Achilles*, *Minotaur*, *Black Prince*, *Warrior*, *Belleisle*, *Hydra*, *Neptune*, *Swiftsure*, *Iron Duke*, *Nelson*, and *Northampton*; and the following unarmoured ships:—*Pelican*, sloop; *Raleigh*, second-class cruiser; *Rapid*, third-class cruiser; *Satellite*, third-class cruiser; and *Volage*, second-class cruiser. Two ships also have been wrecked during 1890–91, but in each case only one life was lost. The river gunboat *Sandpiper* was sunk at Hong Kong in a typhoon on November 10 last. She has since been raised and may be made serviceable. The *Sybill*, second-class cruiser, went ashore at Lambert’s Bay in Cape Colony on January 16 last

and became a total wreck. The *Hind*, a small coastguard cruiser, was also lost on the East Coast of England during the year.

The total number of officers, seamen, and boys, coastguard and Royal Marines proposed for the year 1901-1902 is 118,635, being an increase of 3745. The additions proposed are made up of 287 officers, 1150 seamen, 500 stokers, 398 miscellaneous ratings, 310 artisans, including 100 electricians, 1000 Marines, and 100 apprentices (shipwrights and coopers). The rating of electrician is a new one, and it is hoped to raise a hundred this year, and a hundred more subsequently. The increase in electrical departments has necessitated this step; they will be rated as chief petty officers, assistants to the torpedo lieutenants in connection with the large amount of electrical gear those officers have to superintend in the ships. Mr. Arnold-Forster, referring to the proposed increase in the *personnel*, made the following statement in his speech as Secretary of the Admiralty on March 18 of the total available resources which it was hoped to have ready for manning the fleet in case of war:—Upon the active list, 118,625; in the Royal Naval Reserve, 28,650; and in the Royal Fleet Reserve, 7300—giving a total of 154,575.

Personnel
numbers.

The Royal Fleet Reserve is a new force, to consist partly of men who have served in the Navy or in the Royal Marines, but who have left without taking pensions; this is called Class B; and partly of men who have been pensioned—this is Class A. The seamen pensioner reserve will be superseded eventually by the new Royal Fleet Reserve, but the present Royal Naval Reserve is not affected. The first entries in the Fleet Reserve were made on March 1, 1901, and it is hoped to eventually raise the numbers in Class B to 15,000. The men in this new reserve will undergo periodical drill—for a week every year, or a fortnight every second year, at their option. A scale of pay and victualling is fixed, and clothing will be provided free. The men in Class B receive a retaining fee of sixpence a day from the date of enrolment, so long as they abide by the conditions of their engagement. They can be called out for service by Royal Proclamation up to the age of fifty-five, receiving a war retainer when called up. Additional pensions are granted to men in Class A at the age of fifty, and a pension of £12 a year to men in Class B at fifty-five years of age.

The Royal
Fleet
Reserve.

Owing to a falling off in the numbers of seamen in the Royal Naval Reserve and in those embarking for training, it has been decided to readjust the pay and to reduce the period of training from six to three months and the total sea service from fifteen months to nine months. A readjustment of the system of instruction is to be made in order, as far as possible, to neutralize the loss of time under training. In

Royal
Naval
Reserve.

order further to facilitate mobilization an Act of Parliament has been passed enabling the Admiralty, when the Royal Naval Reserve is called up for service, to limit the numbers called out to such as may from time to time appear desirable.

Colonial
Reserve.

A branch of the Royal Naval Reserve has been established in the North American Colonies, and fifty seamen from Newfoundland have been embarked in ships on that station for six months' training.

Royal
Marines.


It is proposed to create a reserve of officers of the Royal Marines, and all officers who voluntarily retire will be liable to serve in this reserve, those already on the retired list or who may be retired compulsorily having the option of joining if under fifty years of age. During the year 1900 the number of recruits raised for the Marine Artillery was 616 and for the Marine Infantry 2014—a total of 2630. During the twelve months there was a wastage of 2165, but more than half of this number were men whose time had expired or who were pensioned, purchased out, or had been invalided. Most of these will be eligible for entry in the new Fleet Reserve, and, it is anticipated, will join it.

Naval
training.

The recommendations of a committee on the training and examination of junior officers have been embodied in the King's regulations. Special encouragement is given to the better study of foreign languages; the seamanship examination has been revised; promotion to the rank of lieutenant will not in future depend only upon success in examinations, but a certificate will be required to be obtained by every sub-lieutenant from his commanding officer after six months' service in a ship of war at sea, as to his fitness to take charge of a watch at sea, and to perform efficiently his other duties as a lieutenant. A naval strategy course has been begun at Greenwich for the benefit of the senior officers, and is being conducted by the captain of the college. The Council of Naval Education has been directed to examine the Greenwich course in order to ascertain whether the matter and period of study of the gunnery and torpedo lieutenants is that most adapted to the efficiency of the service. Several changes have been made in the training of the seamen and stokers with a view to increased efficiency, and in the First Lord's memorandum it is stated, "There is no doubt but that the standard of proficiency in gunnery is steadily rising in the Navy."

CHAS. N. ROBINSON.

[The information in this chapter is brought up to the end of March, 1901, and where "the present time" is mentioned, that month is referred to.]



"HATSUSE,"

JAPANESE FIRST-CLASS BATTLESHIP.

CHAPTER III.

THE PROGRESS OF FOREIGN NAVIES.

THE adoption by certain Continental Powers of extensive shipbuilding programmes, covering periods of years, which was referred to in the *Annual* last year, is still the most considerable feature to be recorded here. The French and German programmes, which were described in detail, and are alluded to below, have now received the sanction of the legislatures of the respective countries. It has to be noted also that shipbuilding work in Russia is active at all the yards, in prosecution of the programme of expansion. In the United States, again, the new policy adopted has inevitably entailed a rapid increase of the fleet, and the outlay upon new construction has never been so great as at the present time. In the Far East the Japanese have now completed, or have in hand, nearly all the ships included in their extensive shipbuilding programme, but their further intentions have not been disclosed. No ruling features in shipbuilding during the past year seem to call for special note in this place, but it may be said that, while at one end of the scale foreign Powers seem to be tending towards larger displacements in battle-ships, there is, at the other, everywhere a special interest in the development of submarine or submersible boats, due in part to the success which is reported to have attended recent French trials of these engines of war, and partly to the enterprise shown by the United States in undertaking the building of a flotilla. The decision of the British Admiralty to build certain vessels of this class has caused some attention to be devoted to foreign progress in submarine navigation in what follows.

FRANCE.

The principal work of the year 1900 was the elaboration of that programme for the augmentation of the Fleet, which provides for the building, before January 1, 1907, of six battleships of 14,865 tons, five armoured cruisers of 12,416 tons, twenty-eight destroyers of 305 tons, and a number, not yet decided upon, of sea-going and submarine torpedo boats. It is stated, however, that there will be about 112 of the former and about twenty-six of the latter. The Bill embodying the programme was presented to the Chamber in

The ship
building
pro-
gramme.

February, 1900, and was reported upon favourably by M. Godin. It was then laid before the Senate, and a report was presented in November by M. Fleury-Ravarin, some of whose remarks in support of the Ministerial programme for the building of large battleships deserve to be cited. He pointed out that the naval expenditure had been heavy, and had led many to ask if there did not exist a more economical means of making war than that which consists in opposing to certain ships others of like character. Hence the *guerre de course* had exercised a fascination for many minds. But M. Fleury-Ravarin told the French Parliament that it has never brought an enemy to submission, and that in the existing conditions of naval warfare it is costly, while speed, its essential element, is, of all elements of strength at sea, the most elusive. Moreover, the organization of the *guerre de course* requires many naval bases, so that, not only is it more costly in the beginning, but it demands greater charges for maintenance. For these reasons, he said, this system of warfare cannot be raised to a method; it must remain an accessory. "If we are now asked what the fighting navy should really be, we must say that it should be capable of fighting upon the high seas with the navies of rival nations, and that it is the business of the technical boards of the Navy to indicate the nature and composition of the fleet required for the purpose. It is for the Parliament to decide if we shall be content with a modest defensive navy, which would be unable, as we cannot repeat too often, to do more than delay defeat in case of war, and which would be of little weight in the balance in time of peace, or whether, on the other hand, France is resolved to enforce her position as a Great Power, and to make the heavy but remunerative sacrifices necessary to give weight to her voice in the councils of Europe, thus attracting to herself commerce and riches, and spreading throughout the world her influence and her traditional ideal of justice and generosity."

The Chamber had adopted the programme, and had augmented the vote by fifty million francs, to be devoted to the building of torpedo craft, and the plan thus modified was voted by the Senate on December 7, 1900. Considerable opposition had been raised to the building of the large battleships, but M. de Lanessan, Minister of Marine, in the course of the discussion, explained the grounds of the Government policy in a manner that was generally thought conclusive. He spoke of the short range of the torpedo and the long range of the gun, and deduced from the conditions the necessity for two classes of vessels—torpedo craft and battleships and armoured cruisers. He then explained that, in order that the gun should be given its full value, it was essential that the platform

should be stable, a vessel of considerable dimensions thus being called for. It was possible upon such a platform to place many powerful guns, but a necessary consequence was that these should be protected, and hence came the need for heavy armouring. In short, the two qualities of offence and defence were indissoluble, but they were not the only qualities called for; speed and range of action were also necessary, and these again led inevitably to the heavy battleship. These views, though diametrically opposed to those which have latterly exercised a considerable hold upon French naval opinion, were finally adopted by the Legislature.

The following are the vessels which were added to the French Navy during the year 1900: the battleship Saint Louis; the cruisers Guichen, D'Estrées, and Infernet; the gunboats Décidée, Zélée, Argus, and Vigilante (the last two built by Messrs. Thornycroft, at Chiswick); the destroyers Fauconneau, Espingole, Yatagan, and the unfortunate Framée (the disaster to which is described below); several sea-going torpedo boats, and the submarine boats Morse and Narval.

The vessels under trial have not been numerous. The battleship Iéna was commissioned towards the end of 1900 for her trials, which are still in progress. Many difficulties have occurred. Early in February, 1901, the engines worked up to 12,500 I.H.P. during four hours, and with 15,000 I.H.P. and 120 revolutions the speed was over 17 knots, but there was some heating, and the vibration was described as unbearable. The maximum I.H.P. at the trials should be 15,500 and the revolutions 125.

The battleship Hoche, one of the vessels that have been undergoing transformation, was under trial in August, when satisfactory results were attained. With 10,800 I.H.P., and 86 revolutions, the speed was 16 knots. The coal consumption has been reduced, for whereas at the date of the former trial, with the normal coal supply of 610 tons, the ship's range of action was 803 miles, it has now been raised to 1,292 miles. She has received Belleville boilers, and the trim of the vessel has been slightly changed. Much weight has also been taken out of her by reducing the superstructure and making changes in the secondary armament, so that she now floats at the intended water-line and her side armour is not submerged. Some particulars of the changes introduced in the older French ships will be found below.

Further preliminary trials of the so-called commerce destroyer (cf. *Annual*, 1900, p. 25) Châteaurenault took place at La Seyne, with satisfaction, on August 8. With 14,400 I.H.P. and 111 revolutions she maintained, for 20 hours, a mean of 21 knots,

while with 18,000 I.H.P. and 120 revolutions the mean on a two hours' run was 22·697 knots. It was therefore believed that with her full 23,000 I.H.P. she would easily exceed her contract of 23 knots. The coal consumption was satisfactory, the average during the second series of trials being one-eighth less than the contract for the first series, when the power to be developed was less. The trials were continued in October. Great vibration had resulted when the engines were working at high pressure, but some changes had been introduced, and with the engines working up to 120 revolutions, the conditions were considered satisfactory, but the trials were not concluded.

Infernet.

The third-class cruiser Infernet steamed at 21 knots, with 8,625 I.H.P., the contract being 20·5 knots, with 8,500 I.H.P.

Ships
launched.

The vessels which took the water in 1900 were four armoured cruisers—the Dupleix at Rochefort, the Montcalm at Toulon, the Gloire at Lorient, and the Marseillaise at Brest; the four destroyers mentioned above as completed, with the Pique and Epée at Havre, and the Pertuisane and Escopette at Rochefort, as well as several first-class torpedo boats. The four cruisers named are representative of the progressive variation of the same type described in the *Annual* last year (pp. 28, 29). It may be enough to add here that the Dupleix displaces 7,700 tons and has a principal armament of ten 6·4-in. guns; the Montcalm, 9,517 tons, with two 7·6-in. guns; the Gloire, 10,000 tons, with the same principal armament, but with an increase in the secondary guns; and the Marseillaise, 10,014 tons, with the same armament, but slightly better protection. The Desaix, a sister of the Dupleix, was launched at St. Nazaire in March, 1901.

New
ships.

Others of the same classes are in hand, and two of a still stronger type, the Léon Gambetta (Brest) and Jules Ferry (Cherbourg) have been laid down. The latter will be the largest vessel ever built at Cherbourg. She will displace nearly 12,500 tons and have a speed of 21 knots or more. The general characteristics of the still larger new armoured cruisers were described in the *Annual* last year, as also of the battleships of 14,865 tons, and full descriptions are not yet accessible. A list of the ships to be laid down in 1901 will be found below.

Destroyers
and
torpedo
boats.

The destroyer Yatagan, constructed at Nantes by the Chantiers de la Loire, which is provided with four Normand water-tube boilers, and has a contract speed of 26 knots, attained 25½ knots without using her full power, and with complete satisfaction. She has been passed into the service and commissioned. The Pique, launched on March 31, 1900, at Graville, near Havre, by the Forges et Chantiers de la Méditerranée, is of the Durandal type modified, and resembles

the Fauconneau. The *Epée*, also constructed at Havre, is of the same type. Many of these boats have been under trial during the year. The sea-going boats *Audacieux* and *Trombe*, completed at Nantes, deserve to be noted because of the fact that they are armoured over the engine and boiler-room spaces with thin plates of nickel steel. The former steamed on her full power two hours' trial at 26·2 knots, the contract being 26 knots. The *Trombe* struck upon a rock during one of her runs near Port Melin, and was seriously damaged, repairs to the extent of about £4,000 being necessary. The *Lance* and *Salve* have been put in hand to receive water-tube boilers of the Normand type, and it is hoped that they may now attain their reputed speed of 19 knots. The *Lansquenet*, which has never attained her intended speed, has been struck off the list.

The organisation for the torpedo boats of the mobile defences of the coasts was explained by M. Fleury-Ravarin in his report upon the estimates. The chief centres are both strategic and administrative, and offer to torpedo boats at all times a safe refuge, with complete means of repair, and barracks for their men. The station centres have neither boats nor *personnel* in permanence, but will offer the same facilities (though on a smaller scale) as the principal centres in war time; while the refuge posts will be able to supply torpedoes, and to make small repairs, besides furnishing stores; and smaller refuge posts for temporary shelter will furnish water, coal, and provisions. The reporter stated that in 1900 and 1901 four destroyers (the *Pique*, *Epée*, *Pertuisane*, and *Escopette*), ten sea-going torpedo boats, eighteen first-class boats, six submarines, and two submersibles would be added to the Fleet.

Mobile
defences.

In the *Annual* last year a description was given of the submersible boat *Narval* (page 30). Considerable attention has been attracted during the year to the experiments which have been made with this vessel and the submarine boats *Morse* and *Gustave Zédé*. The following account is given by the *Petit Havre* of a visit paid by the Minister of Marine to the latter at the end of October: "The Minister went on board from a steam launch, and was accompanied by M. Cuvinot, Admiral Bienaimé, and some other officers. The manhole was then closed and the vessel submerged, the operation occupying nine minutes, but it was said that it could be performed much more quickly when the boat was in movement. The submersion left visible a flag at each end and the tube of the periscope in the centre. The range of the periscope was very limited, but sufficient for a man with a practised eye familiar with the surroundings. The commander, Lieutenant Jobard, took his craft out of the harbour into the open, and a steam launch followed close in her wake, the

Submarine
boats.

Gustave
Zédé.

submarine with her companion making the round of the warships lying in the roads. On her way she discharged one torpedo, which did not go straight, but this was stated to have been the fault of the torpedo and to have had nothing to do with its discharge. When near the Charlemagne the boat emerged and the passengers went on board the battleship. They had found the supply of oxygen in the submerged boat scarcely sufficient for their needs. The boat was kept at a uniform depth throughout the run, her speed being 9 knots. There was no rolling or pitching. The Minister expressed himself satisfied with the performance. He was especially pleased that it was possible to discharge a torpedo from the vessel while she was in motion." M. Loubet inspected the boat in April, 1901.

Narval.
Morse.

Early in January, 1901, M. de Lanessan, accompanied by General André, Minister of War, proceeded to Cherbourg in order to take part in the trials of the submersible Narval and the Morse, which is an improved Zédé, and a somewhat sensational account of the incidents was given in the *Figaro* by M. Gaston Calmette, a journalist who accompanied General André and Dr. Vincent, of the French Navy, in the Morse. The following is his report of his impressions: "The plunge is so gentle that in the perfect silence of the waters one does not perceive the process of descent, and there is only an instrument capable of indicating, by a needle, the depth to which the Morse is penetrating. The vessel is advancing while at the same time it descends, but there is no sensation of either advance or roll. As to respiration, it is as perfect as in any room. M. de Lanessan, who since entering office has ordered eight more submarine vessels, has concerned himself with the question as a medical man also, and, thanks to the labours of a commission formed by him, the difficulty of respiration is entirely solved. The crew can remain under water sixteen hours without the slightest strain. Our excursion on this occasion lasted scarcely two hours. Towards noon, by means of the mysterious periscope, which, always invisible, floats on the surface and brings to the vessel below a reflection of all that passes up above, the captain shows us the Narval, which has just emerged with its two flags near the old battery Imprenable. From the depths in which we are sailing we watch its slightest manœuvres until the admiral's flag, waving on the top of a fort, reminds us that it is time to return."

Meanwhile the Minister of Marine had been making a trip, apparently with perfect success, in the Narval, and General André joined him when the Morse came to the surface. The very great attention which has been paid to the subject of submarine navigation since these trials will lend interest to the following abstract of a very

judicial article upon the subject by M. Rousseau in the *Moniteur de la Flotte* :—

Mr. Rousseau says that the trials did not throw any new light upon these engines of war, but that they had the merit of bringing the two types of boats into direct comparison, and that the opinion of officers, who had been in command of them, was unanimous. They all indicated their preference for the submarine boat properly so called, having evidently some distrust of the submersible. M. Rousseau, however, points out, that the Morse represents a type of boat more or less established, and that the submersible Narval is of a new class altogether, and insists that the trials must not be interrupted of a class of boats which will have the advantage of being offensive. He has been on board the Morse, and says that she navigates with perfect ease below water, that those in her are able to discern by means of the periscope what is going on upon the surface, and that torpedoes are discharged with an accuracy and certainty which might be the envy of officers of ordinary torpedo boats. It asserts that the periscope can be employed up to a depth of about 20 ft. below the surface, and, according to M. Rousseau, it is quite adequate to prevent collisions, and, being turned round, enables those below to scan the whole horizon. It has been suggested that the instrument would be valueless except in smooth water, but the writer cited asserts that, during the Cherbourg experiments, the sea was very rough, and that the appliance gave, nevertheless, a very clear view. At a greater depth than 20 ft. the course of the Morse is directed by the compass. The plunge is effected by suppressing her floatability, by admitting water into special chambers, and there is equilibrium, so that the descent is made in the horizontal position, and the required level is maintained by lateral wings or rudders, to the movement of which the boat is very sensitive. The class of boat thus described is available purely for local defences, but the Narval, the system of which is described by M. Rousseau (his account not differing from that given in the *Annual*, 1900), could be employed in offensive operations. He says that the advantages of the submersible system would be incontestable, but, that certain problems have arisen, of which the solution has not yet been altogether realised. Larger water chambers and more powerful pumps are required for the plunging and raising of the boat. The steam not used during surface navigation must be condensed. These difficulties, combined with the necessity of coupling the electric mechanism with the driving apparatus, make it impossible to plunge the boat within less than seventeen or eighteen minutes. The period, he believes, will be reduced to ten minutes in the *Silure*, *Triton*, *Sirène*, and *Espadon*, but will still be too long, and in an actual encounter would leave the boat helpless before her adversary. He thinks, however, that the type of the submersible is perfectible, and that the difficulties will be overcome.

The following account of the optical arrangements of the *Zédé* has been given by a French engineer in the *Naval and Military Record* : "The Gustave Zédé possesses an optical tube and a periscope, of which the chief dimensions are as follows—outer diameter 364 millimètres (about 14 inches); distance from the image to the emerged part of the apparatus, 1 mètre (39 inches); total field 27 degrees, of which 20 degrees are above and 7 degrees below the horizon; angle under which the upper part of the point of convergence of the rays can be seen 3 degrees; reduction 1-9th. The image obtained was examined by a rather complicated process by means of an eye-glass; the results obtained were very poor. This carefully-studied and precise periscope was constructed by the firm of Sautter-Harlé, but it did not answer its purpose. It nevertheless still figures in the Gustave Zédé."

Visual
apparatus
for
submerged
boats.

In a book entitled "*La Navigation Sous-Marine*," by M. Maurice Gaget (Paris, 1901), is an account of the various devices which have been employed in France to give a measure of surface vision to submerged boats. The first apparatus was the optic tube, or

"prismoscope," proposed by Major Daudenard, which was based upon the principle of reflection, two prisms being placed one above the other in such a way that their reflecting surfaces were parallel, and inclined at an angle of 45° to the horizontal plane. These prisms were connected by a rigid vertical tube, and a clear vision was given, but with restricted field, and, owing to the difficulties set up when it was attempted to make a revolution upon its axis, the apparatus proved unsuccessful. The "periscope" is a later invention, due to Commandant Mangin, and perfected by Colonel Laussedat. Its effect rests upon the well-known and characteristic properties of the parabola, the arc of the parabola being curved about a vertical axis, and therefore reflecting the panoramic image to its focus. M. Gaget says that great difficulty arises from the reduction of objects varying with the distance from the mirror, the panoramic picture being thus distorted, and not enabling the relative distances of floating objects to be estimated. He accordingly describes the apparatus as presenting a phantastic panorama, and as being an illusory guide to the navigator. Light is also sacrificed by the method of reflection, and, although some elaborate instruments of the class have been constructed, the apparatus, according to M. Gaget, is almost valueless. He states that another means of indirect vision has been devised by M. Garnier, but details concerning it have not been disclosed. M. Gaget also describes at length, and in technical detail, an apparatus for panoramic vision which he has himself designed, and which he puts forward for experiment.

Three submarines—*Farfadet* (Rochefort), and *Algérien* and *Français* (Cherbourg)—have been recently launched, and the two last named have been under trial.

Vessels
recon-
structed.

Allusion has been made above to the modifications which have been introduced in the *Hoche*, and the following particulars of changes in the armament may be added. On each side there are now two of the twelve 5·5-in. Q.F., placed near the bases of the lateral turrets, with which they form groups or sections. Of the eight other guns of this calibre four are disposed further forward and four aft, and are arranged on two levels, the lowest being that of the battery; but the forward guns on this level could not be fought, it is believed, in bad weather, notwithstanding that the ship has more freeboard than before. The ship has also four 2·5-in. guns on the upper deck, and there is now only one fighting mast.

The *Amiral Duperré* is to be put in hand this year for reconstruction, at a cost of about £60,000, and will receive new boilers, and undergo general repairs to her machinery, while the central turret for the 13·3-in. gun will be replaced by two redoubts for 6·4-in. guns.

The Neptune is also to be put in hand, and will receive Belleville boilers, and have her superstructure cut down. The total cost will be about £62,000. The D  vastation approaches completion. The 12.5-in. guns have been replaced by four of 10.8-in. calibre, and the eight old guns of the latter calibre on the upper deck have been disembarked and replaced by two of 9.4-in. and four of 3.9-in. Belleville boilers have been supplied, and the engines have been altered to the triple-expansion type. The reconstruction of the coast-defence ironclads Indomptable and Caïman is to be completed this year.

A serious disaster occurred in August during the return of the Mediterranean squadron to Toulon after the man  uvres in the Channel. The squadron was steaming in line ahead, 70 miles to the south-east of Cape St. Vincent, when, about midnight, the new destroyer Fram  e, under command of Lieut. de Mauduit-Duplessis, was directed to approach the flagship Brennus to receive an order. Owing to circumstances which have never been fully explained, but apparently through the misunderstanding of an order, or mis-direction, the boat came into collision with the flagship, and in a few minutes disappeared. There perished with her the officer in command, Lieut. Epailard, and nearly the whole of her company, and the catastrophe aroused universal sympathy. Disasters.

On the night of August 31 the sea-going torpedo boat Bou  t-Willaumez ran on a rock near Br  hat, and sank in 10 fathoms of water, the crew being saved by torpedo boat No. 108.

The transport Caravane, 2,065 tons, was lost in the Japanese Inland Sea on October 23, through collision at night with the Japanese steamship Yamaguchi Maru. There was excellent discipline on board. One officer perished.

The vessels ordered, or in construction at the different ports, at the end of 1900, were as follows—Havre: the destroyers Arquebuse, Arbal  te, Mousquet, Javeline, Saga  e, Epieu, Harpon, and Fronde, all of the type of the Fauconneau, and to be delivered in 1903. Also the sea-going torpedo boats Simoun and Typhon; the first-class boats Nos. 243 and 253 to 257, and the Libellule, a boat with turbine motor. Cherbourg: Henri IV., battleship, which had her armament, but was awaiting her boilers, and will not be ready for her trials until the summer; Jules Ferry, cruiser, the laying down of which had been retarded by a disastrous fire at the steam saw works; the submarines Fran  ais and Alg  rien, now under trial, and the Sir  ne, Triton, Silure, and Espadon; the coast-defence ship Requin, having nearly completed her transformation, and the Furieux, about to be put in hand; and, lastly, two first-class torpedo boats, Nos. 223 and 224. Brest: the battleship Suffren, well advanced and to be ready Vessels in hand.

for her trials at the end of the year; the armoured cruisers Marseillaise and Léon Gambetta; the battleship Dévastation, undergoing transformation; and the Amiral Duperré and Neptune, about to be transformed. Lorient: four cruisers—the Jurien de la Gravière, to be finished this year; the Gueydon, which may also be finished then; the Gloire, to be finished in the autumn of 1902; and the Condé, barely begun. Nantes and Saint Nazaire: the cruisers Desaix and Amiral Aube, the first since launched and the second not to be delivered until 1903. Rochefort: the cruiser Duplex, to be finished October 1, 1902; the destroyers Pertuisane and Escopette, already launched, and to be followed this year, first by the Flamberge and Rapière, and then by the Sarbacane and Carabine, all of the Fauconneau type; Vaucluse, aviso-transport, on which work is suspended; the cruiser Davout, undergoing transformation; four submarines, the Farfadet, Korrigan, Gnome, and Lutin, the first nearly finished, and all to be ready this year. Bordeaux: Kléber, cruiser, to be finished 1903; Borée and Tramontane, sea-going torpedo boats, nearly finished; six first-class boats, Nos. 258 to 261, to be delivered the end of this or the beginning of next year, and Nos. 264 and 265 in 1902. Toulon: battleships Jeanne d'Arc, nearly finished, and Dupetit-Thouars, to be launched this year and finished next; Marceau, battleship, undergoing transformation. La Seyne: Montcalm, cruiser, to be finished in June; Sully, cruiser, to be ready in 1903. Châlon sur Saône (Creusot): first-class torpedo boats, Nos. 245 to 250 and 261 to 263. Saigon: torpedo boats, Nos. 244 and P 96, to be finished, one in 1902 and the other in 1903.

Vessels to
be laid
down.

The vessels to be laid down in 1901, in accordance with the programme described above, are two battleships, A 8 and A 10, one armoured cruiser, C 13 (the Victor Hugo, to be built at Toulon), ten destroyers, twenty submarines intermediate between the Gymnote (30 tons) and the Morse (146 tons), and twelve first-class torpedo boats. The dimensions of these, so far as they are known, will be found in the tables.

Naval
bases.

In relation to the measure for improving and strengthening the naval bases, the *Army and Navy Gazette* has given the following particulars:—The Government proposal was voted by the Chamber, which increased it by a sum of nearly 29,000,000 francs, making a total of 196,871,000 francs, the chief additions being for the works at the Etang de Berre, in Corsica, and Algeria, and at Diego Suarez. On the other hand, the transfer of the Colonial troops to the War Department has enabled a large reduction to be made in the Naval Budget. At the Etang de Berre, the entrance passage at Port de Boue is intended to be deepened to 23 ft., and to be about 100

yards wide, and the canal which unites Port de Bouc with Martigues is to have a depth of over 19 ft. and a width of nearly 100 ft. This canal is to be prolonged through Martigues by the Canal du Roi, giving an approach to the lake. This great inland water would thus form a perfect refuge and base for destroyers, torpedo boats and small cruisers. The works intended in Corsica are to be chiefly at Ajaccio, where there is to be a station for two divisions of torpedo boats—eighteen in all—as well as for submarine boats. The existing facilities are to be developed, a fresh area of land is to be secured, barracks are to be built, and the whole capabilities of the place are to be largely augmented. Two new signal stations will be established. Bonifacio is to be improved as a secondary station of the mobile defence, with facilities for recharging the accumulators of submarine boats; while Bastia is to be fitted to receive a division of torpedo boats, and to be provided with a floating dock; and shelter stations for torpedo craft are to be created at Calvi and the Ile Rousse. More considerable works are to be undertaken at Porto Vecchio, which is to be made a centre of the mobile defence, boats being placed in permanence there, with every facility for repair and the recharging of accumulators. In Algeria there is to be an expenditure of three and a half million francs. The docking facilities at Algiers are to be increased, and a station for eight torpedo boats and a division boat is to be created, with provision for submarine boats also. It is proposed to make Mers-el-Kebir a *point d'appui*, or secondary base, and a centre of torpedo-boats and submarine vessels, placed within striking distance of the course from Gibraltar to Malta. Stores for the fleet are to be erected there, and a sheltered harbour is to be formed for torpedo boats. At Oran and Bona it is intended to establish refitting basins, which may be used at any time, and will be of special value in case of war. In regard to Diego Suarez, it is intended to improve the facilities of the fort and to provide a refitting basin.

Considerable attention was directed to the French manœuvres, which took place in July, 1900, owing to the fact that the Mediterranean Squadron proceeded to the Channel, and engaged in operations with the Northern Squadron, the whole of the manœuvres being under the supreme direction of Vice-Admiral Gervais, who, as Admiral-in-Chief, hoisted his flag in the Bouvet. The Mediterranean Squadron was thus constituted:—battleships: Bouvet, Brennus (flag of Vice-Admiral Fournier), Charles Martel (flag of Rear-Admiral Roustan), Charlemagne, Gaulois, and Jauréguiberry; armoured cruisers: Chanzy, Latouche-Tréville and Pothuau (flag of Rear-Admiral Maréchal); protected cruisers: Cassard, Du Chayla, D'Assas,

The man-
œuvres.

Linois, Lavoisier and Gallilée; two destroyers and four squadron torpedo boats. Attached to the fleet was the coast-defence squadron, comprising the Bouvines (flag of Rear-Admiral Mallarmé), Amiral Tréhouart, Jemmapes and Valmy, as well as the torpedo transport Foudre. The Northern Squadron consisted of the Masséna (flag of Vice-Admiral Ménard), Carnot, Amiral Baudin, Formidable (flag of Rear-Admiral Touchard), Amiral Duperré, and Redoubtable; the armoured cruisers Dupuy de Lôme and Bruix, the protected cruiser D'Estrées, five destroyers, and two torpedo boats.

The Mediterranean Squadron left Toulon on June 21st, and, after steam tactics and certain exercises, passed through the Straits of Gibraltar, and reached the neighbourhood of Quiberon on July 5th, and the combined fleet anchored in four lines in the bay. The meeting had taken place at daybreak on July 2nd, when the formation in four columns line ahead was assumed. One of the exercises was an attack by the squadron upon Forts Saint Julien and Riberen at Quiberon, these being subjected to a tremendous cannonade from the ships under the orders of Vice-Admiral Ménard, while Admiral Fournier made a similar attack upon the elevated forts which defend the port of Le Palais at Belle Ile. It is impossible to say what lessons could be learned from these operations, which were probably more an exercise for the officers and men than anything else. The evolutions were continued on subsequent days, and included a torpedo attack upon the squadron anchored at Morgat on the night of July 8th. The following was the theme: A naval force anchors off an enemy's coast in daylight, and the torpedo boats of the local defence are informed of its position; in order to protect itself the squadron is surrounded by picket boats at some little distance from the ships, while other vessels at a greater distance, circling round, make an illuminated ring by means of their searchlights. In this way it was hoped to discern the boats as they approached, and two attacks were repulsed. In the third attack, however, the Jauréguiberry and Charlemagne were torpedoed, but not until their assailants had been subjected to a destructive fire. The opinion was that the guard boats had been too numerous to give five or six assailants any real chance of success.

On July 9th the combined squadron proceeded to Brest, and Admiral Gervais conducted the somewhat delicate operation of entering the Goulet in three columns, followed by the cruisers. The passage is about 2,000 yards across, and is divided into two channels by a series of reefs stretching out from the Roche Mengam to the Fillettes. Two of the columns entered through the northern passage, and the third through the southern, and the whole of the

ships anchored together in the formation described in Brest harbour. The fleet had been at sea for ten days engaged in various evolutions, in steam tactics, and in scouting and fighting formations, and on several occasions had anchored, thus giving excellent training to the men. There were 41 vessels of all classes, and no mishap had occurred, except in the case of the *Jemmapes*, which had had a boiler trouble before leaving the Mediterranean. The Northern Squadron left Brest on the next morning, the 10th, and proceeded northward, the ships bombarding the batteries at Querqueville and at the Cherbourg Mole, but this again was only an exercise for those on board. On the 13th the combined squadron was in Cherbourg harbour, and on the 17th Admiral Gervais reviewed a body of seamen landed from the fleet. A naval review took place on July 19th, the President of the Republic visiting Cherbourg for the purpose. It was a brilliant ceremony and was the conclusion of the operations. The Mediterranean Squadron then returned to the south, and it was in the course of the cruise that the new destroyer *Framée* was lost, as is related above.

Although the operations were conducted on a large scale, it cannot be said that they threw any new light upon naval problems. No ambitious strategic schemes were laid down, and Admiral Gervais was content to put the fleet through a great many useful exercises, and doubtless the officers and men profited much by the various experiences. Nothing appears to have been disclosed in regard to the special steam tactics employed, but it is understood that certain methods employed in the Mediterranean by Admiral Fournier, apparently analogous to the "T.A." system of Sir George Tryon, have been introduced into the Northern Squadron.

GERMANY.

In the *Naval Annual* last year, Part IV., pp. 429-443, the Bill for the increase of the German fleet was given *in extenso*. The measure, as amended by the Budget Committee, and finally adopted on June 14, 1900, differs in some important respects from it. Whereas the first proposal of the Government was in form an amendment to the Navy Act of 1898 (the Sexennate), the new measure supersedes the earlier one by a fresh scheme which is really more in accordance with present official views. Its first clause fixes the future strength of the navy at two double squadrons, each consisting of a flagship and of two squadrons severally of eight battleships, eight large and twenty-four small cruisers for service with the fleets; three large and ten small cruisers for service on foreign stations; and a reserve

The Navy
Act, 1900.

of four battleships and three large and four small cruisers. The Navy Act of 1898, as amended by the Government Bill, would have fixed the strength of the squadrons and their attached cruisers as is stated above, but would have provided for eight large and fifteen small cruisers for service on foreign stations, and a reserve of four battleships, and four large and six small cruisers.

The Centre Party, which was responsible for the changes made, thus met the wishes of the Government so far as the strength of the fleet in home waters was concerned, but reduced the number of ships intended to be provided for foreign service. A final paragraph was added, ensuring that the money required should be raised in a manner approved by the Centre Party, *i.e.*, by an increase of the stamp and certain customs duties. In the course of the debate Admiral Tirpitz, Secretary of State for the Navy, announced that the Government, though insisting upon the necessity of maintaining the number of ships on foreign stations, would agree to postpone the final settlement of the question.

Ships
launched.

In the year 1900 seven vessels were launched—the battleship Kaiser Barbarossa at the Schichau Yard, Danzig, and the Wittelsbach at Wilhelmshaven; the armoured cruiser Prinz Heinrich at Kiel; and four third-class cruisers, the Amazone at the Germania Yard, Kiel; the Ariadne and Medusa at the Weser Yard, Bremen; and the Thetis at Danzig. All these classes were described in the *Annual* last year, pp. 36–37. Four battleships, one armoured cruiser, and a gunboat were in hand at the end of the year.

Types of
the new
battle-
ships.

The new battleships are of three types, all marking distinct advances upon the Brandenburg class. The first of these developments is the "Kaiser" class, consisting of five ships, the Friedrich III., Wilhelm II., Wilhelm der Grosse, Karl der Grosse, and Barbarossa, all of which are now afloat. The Wilhelm der Grosse was to be completed in March, 1900. The second class is that to which the Wittelsbach (launched at Wilhelmshaven on July 3) belongs, as well as "D," "E," "F," and "G," which are respectively in hand at Danzig; the Germania Yard, Kiel; the Vulcan Yard, Stettin; and Wilhelmshaven, and are all expected to be launched in 1901. The chief difference between the two types consists in their larger displacement, greater engine power, and their defensive armour, the ships of the "Wittelsbach" class being plated with Krupp steel 9 in. thick amidships, tapering to 6 in., and with somewhat thicker plating of the same steel on the chief gun positions. As in all the modern German battleships, the heaviest guns have a calibre of 9.4 in., and have been described, though not with technical accuracy, as quick-firers. The two ships, "H" and "J," which

are to be laid down in 1901, will have a much more considerable armament than the other type, both in regard to calibre of the heavy guns and the number of the secondary and smaller armament, but full particulars are not known. All the new battleships are being fitted with a combination of cylindrical and Thornycroft-Schultz water-tube boilers.

The armoured cruiser "B," which is in hand at Kiel, is a sister of the Prinz Heinrich, but considerable changes have been introduced. She will have an armament of four 8·2-in. guns (instead of two of 9·4-in.) and ten 5·9-in., twelve 3·4-in. and ten 1·4-in. quick-firers. She will probably be launched in 1901.

Armoured
cruiser
Prinz
Heinrich.

Another third-class cruiser, "G," of the improved Gazelle type, being a sister of the Nymphe (which was at Spithead on the occasion of Queen Victoria's funeral) and of the four launched last year, is in hand at the Germania Yard, Kiel. Others of this small class will be laid down in accordance with the programme. The Niobe, of the same class, built at Bremen, has passed through her trials with perfect satisfaction. With 926 I.H.P. her speed was 11·1 knots, and it rose to 19·45 knots with 4,921 I.H.P., and finally, with forced draught of from 8,113 to 8,631 I.H.P., she steamed at 22 knots with 166·5 revolutions, the contract being 8,000 I.H.P. and 21·5 knots. The Thornycroft-Schultz boiler has been adopted for vessels of the class.

Third-
class
cruisers.

The Schichau torpedo boats 90 and 91 have completed their trials, exceeding by 0·8 the contract speed of 25 knots. These two boats belong to a series of twelve, S90 to S101, which are being built by Herr Schichau. Not all are of the same type, some of the later numbers being destroyers of 350 tons. No. 100 and some others have been launched. The engines are of 6,000 I.H.P., intended for a speed of 26 knots, and the trials of No. 100 gave satisfaction.

Torpedo
vessels.

The coast defence armoured Hagen, which was one of the German vessels sent to Spithead for the late Queen's funeral, had just undergone a complete reconstruction. She belongs to the Siegfried class of vessels, which were all built for the purpose of local defence, their range of action being very restricted. The Hagen was cut in two, and a new section built in amidships, lengthening her to the extent of 27 ft. Her coal capacity was thus increased from 225 to 580 tons, and her four locomotive boilers have been replaced by eight Thornycroft water-tube boilers, giving her 5,250 I.H.P. and a speed of 15 knots.

Recon-
struction
of the
Hagen.

The armament has also been augmented and now consists of three 9·4-in., ten 3·4-in., and six 1·4 in. guns, as well as eight machine guns, while the torpedo armament now provides for 18-in.

torpedoes, and the above-water tube has been armoured. A further improvement has been the heavier plating with nickel steel (7 in.) of the conning tower, and instead of the signal mast there is an armoured fighting-mast. Provision has also been made for increasing the ship's company from 276 to 297. It is intended that the whole of the seven ships belonging to this type shall undergo a like transformation.

Loss of
the
Gneisenau

A serious disaster, unhappily attended by much loss of life, occurred through the loss of the training ship *Gneisenau*, at Malaga, on December 16. She was a full-rigged ship, but was fitted also for steam propulsion. She had on board 14 naval officers, including Captain Kretschmann in command, 49 cadets and 6 other officers, and about 380 men. The unfortunate ship was lying outside the harbour at Malaga, when a great storm arose, causing her to drag her anchors, and she was driven with much force against the Eastern Mole and completely wrecked. The officer in command was among those who went down with her. The disaster aroused great sympathy.

Kaiser
Friedrich
III.

The battleship *Friedrich III.* was damaged on the *Adlergrund* in April, 1901. Water-tight compartments were flooded and petroleum reservoirs broken open, the escaped oil taking fire and greatly imperiling the ship. The repairs will occupy many months.

The Navy
League.

The German Navy League is a most prosperous organisation which has exerted a great deal of influence during the campaign in favour of the Navy Act. In support of this agitation more than six million books and pamphlets were published at the expense of the League, while 3,000 lectures and addresses were delivered, followed by 600 more in the latter part of the year. So prosperous is the League that it has established a fund for the benefit of sailors and soldiers taking part in the Chinese Expedition, and has otherwise expended money for the advantage of the German Navy. At the annual meeting of the League in January, under the presidency of Prince zu Wied, it was announced that during the year 1900 the number of members had increased from 246,967 to 599,141, and the number of branches from 286 to 1010. Central committees had been established during the past year for Bavaria, Alsace-Lorraine, Saxe-Weimar, Lippe-Detmold, the principalities of Hohenzollern and Reuss (the younger line), the Duchies of Coburg and Gotha, and the Prussian provinces of Brandenburg and Posen. The organisation of the League now extends over the whole country, and there were only three small German States in which central committees had not been established, and in two of these local committees had already been formed.

New
docks.

Great additions are being made to the docking accommodation at Kiel, and two immense dry docks at Wilhelmshaven have been


begun, which, it is estimated, will require five years to complete. The total outlay will be 12,000,000 marks, of which ten and a half millions will fall upon the Empire. The remainder is a contribution of the North-German Lloyd at Bremen, in consideration of the Navy foregoing the right to precedence over all vessels of the German Mercantile Marine as regards use of the company's dock at Bremerhaven, at present the largest of the kind on the Continent, a renunciation only to apply to times of peace. The preliminary works at Wilhelmshaven, for which 500,000 marks were granted by the Reichstag, have so far progressed that the task of excavation has commenced. Both docks will admit the largest German men-of-war, even if lying deep in the water, through the flooding of compartments, and will suffice for many years to come. Gigantic pumps will be able to empty these docks (two similar to which are under construction at Kiel) in two and a half hours.

The German manœuvres took place during August and September, 1900, in the North Sea and the Baltic. The fleet was organised as follows: First squadron (Vice-Admiral Hoffmann), the new battle-ships, Kaiser Wilhelm II. and Kaiser Friedrich III., and the older ships Sachsen and Württemberg. Second squadron (Rear-Admiral von Arnim): First division, the coast-defence armour-clads, Aegir, Odin and Heimdall; Second division (Rear-Admiral von Bodenhausen), the Hildebrand, Frithjof and Siegfried, of the same class. The cruisers were the Greif, Jagd, Blitz, and Pelikan in one group, and the Pfeil and Grille in another, and there were two torpedo flotillas, each in two divisions. The manœuvres lost something of their importance owing to the fact that many ships had been despatched to China, and the squadrons were particularly weak in the matter of cruisers. The operations began with inspections and drills, and after a day in Wilhelmshaven there were steam tactics and night torpedo attacks. It is reported that in the latter the assailants were several times successful, but whether reasonably so or not could not be determined without a better knowledge of the conditions than the information accessible makes possible. On August 23rd there were exercises at a mine-field, which was defended by boats manned by naval artillerymen. Another event was an attack on Cuxhaven, which appears not to have been instructive. On August 25th the fleet left for the Baltic by way of the Skaw, where there was a torpedo attack unsuccessfully conducted. After coaling at Neufahrwasser, there were tactical exercises from September 3rd to September 8th, after which the squadrons proceeded to Swinemünde, where the officers took part in the military parade before the Emperor.

The man-
œuvres.

On September 10th and 11th there were further tactical exercises

at Stettin, and then three days were given up to the strategical scheme. Germany was supposed to be at war with a superior power, and a "Yellow" hostile fleet coming from the east designed to land troops on the island of Rügen, whilst Stettin and Swinemünde were to be attacked, and the sea defences of the latter place destroyed. It was the business of the German fleet to interrupt or prevent these operations on the part of "Yellow," and Vice-Admiral Hoffmann acted as umpire in the Kaiser Wilhelm II. "Yellow" had an advantage in the matter of strength; and on the morning of September 13th succeeded in forcing his way through the passage on the south side of Bornholm, with the loss of two ships, the Germans being unable to watch both sides of the island. He then sent on his transports to secure the landing, while he kept the pursuing German squadron at bay, disabling several of its cruisers. On nearing Rügen the "Yellow" leader ordered an attack on Sassnitz to secure the railway, while the Kaiser Friedrich III. and Frithjof, on the German side, attempted to prevent the landing, engaging four ships of the nominal value of the former. They were driven off damaged and with loss of speed, and the troops were successfully put on shore without further opposition. A great bombardment of Swinemünde took place on the next day, and two gunboats of the defenders, as well as the Odin, which attempted to join her friends outside, were put out of action. It is unnecessary to describe the operations further, but the following remarks by a correspondent of the *Times* may be quoted: "As in the previous year, the final operations involved a great deal of 'make-believe'; there is thus a certain air of unreality about them. The *maximum* speed for battleships was exceedingly low, and large cruisers were conspicuous by their absence. The German commander seems to have made no attempt to harass the enemy with his torpedo boats, even on the night of September 13th, and nothing seems to have been done by the German cruisers to stop the transports when they had forced the passage. If the German fleet was so strong, as it must have been *ex hypothesi*, as to be able to watch both sides of the Bornholm, it is clear that a few cruisers might well have been kept back for this purpose. Again, the 'Yellow' fleet, even after losing two ships to the German three or four, cannot well have been so superior as to be able to risk an engagement with forts and fleet at once. The unreal element in the operations seems, on the whole, to have been too prominent for any lessons of great value to be drawn from them, at any rate by those who were not in a position to follow the strategy from inside."



"GROMOBOI,"
RUSSIAN FIRST-CLASS ARMoured CRUISER.

RUSSIA.

The year 1900, and the beginning of 1901, were remarkable for the large number of vessels which took the water. Four battleships were launched—the Retvisan at Philadelphia, the Pobieda at the Baltic yard, St. Petersburg, the Kniaz Potemkine Tavritchesky at Nikolaieff, and the Cesarevitch at La Seyne. The armoured cruiser Bayan was also launched at La Seyne, and of protected cruisers the Bogatyr at the Vulcan Yard, Stettin, the Aurora at Galerny Island, St. Petersburg, the Askold at the Germania Yard, Kiel, the Boyarin at Copenhagen, and the Novik at Elbing. The Retvisan was very fully described in the *Naval Annual*, 1899, and some particulars have also been given of the Pobieda and Potemkine classes. The *Kronstadtski Viestnik* states that the Pobieda, which was launched on May 24th, 1900, was begun on August 1, 1898, being thus nearly 22 months on the stocks. Her length over all is 434 ft. 3 in.; between perpendiculars, 401 ft. 3 in.; beam, 71 ft. 6 in.; mean draught, 25 ft. 3 in.; displacement, 12,674 tons; engines, 14,500 I.H.P.; speed, 18 knots; coal capacity, 2056 tons. Her armament is given in the tables. The following are later particulars of the Potemkine, which was begun on December 27, 1897, and was launched on October 29, 1900:—Displacement, 12,480 tons; length, 372 ft. 4 in.; beam, 72 ft. 10 in. draught, 27 ft.; armament, four 12-in., coupled in turrets, protected by 11 $\frac{3}{4}$ in. and 9 $\frac{3}{4}$ in. nickel steel, with an arc of fire of 270°; sixteen 6-in. Q.F. in the redoubt in pairs on double Canet mountings; four 4.7-in. Q.F.; and twenty others of smaller calibre; five torpedo tubes; two vertical triple-expansion engines, and fourteen Belleville boilers, developing 10,600 I.H.P., to give a speed of 17 knots; range of action, 4,000 miles at 10 knots. The side plating extends for two-thirds of the ship's length, and is from 10 in. to 9 in. thick, with transverse bulkheads fore and aft of the latter thickness, a citadel thus being formed, above which is the redoubt covered with 5 in. of steel.

Battle-ships launched.

Retvisan.

Pobieda.

Kniaz Potemkine

The Cesarevitch was launched at the Forges et Chantiers de la Méditerranée at La Seyne on February 23rd, 1901. She has been built from the designs of M. Lagane. The following are the principal particulars:—Displacement, 13,110 tons; length, 388 ft. 8 in.; beam, 76 ft. 2 in.; normal draught, 26 ft. 3 in. Protection is given by a complete belt of steel, 9.8 in. thick amidships at its upper edge and 6.6 in. at its lower edge, these measurements being reduced to about one-third the thickness at the bows and the stern. The side armour is to emerge 20 in. above the water-line, and to descend about 5 ft. below it. Further protection is afforded by steel plating 8.8 in. thick covering the space between the two armoured decks, which are

Cesarevitch.

at the levels of the upper edges of the two ranges of side armour. The principal and uppermost armoured deck is of nickel steel, 2·5 in. thick, while the lower one is merely for protection against splinters, but is curved downward at the sides to a depth of 23 ft. below the water line, there joining the structure of the hull. The armament comprises four 12-in. guns coupled in turrets fore and aft, the turrets being protected by 10 in. and 11 in. of steel. Twelve 6-in. Q.F. are also mounted in pairs in turrets covered with 6½ in. of steel, and there are twenty 3-in. Q.F., twenty Hotchkiss 1·8-in., six Hotchkiss 1·4-in., and two Baranovsky 2·5-in. guns for landing purposes. The torpedo armament comprises six tubes, of which two are submerged. The guns are so mounted that for bow and stern fire there are two 12-in. and eight 6-in. guns, and for broadside fire four 12-in., six 6-in., and one half the other guns. The whole of the ordnance is provided with electric gear for training, provided by MM. Savateur and De Lagalbe. Triple-expansion engines of 16,300 I.H.P. are to give a speed of 18 knots, and there are twenty Belleville boilers in two groups. The normal coal supply will be 900 tons, capable of being increased to 1350 tons. The ship was laid down in May, 1899, and is to be completed in September, 1902.

New bat-
tleships,
Borodino,
Alexander
III.,
Orel.

Particulars were given of the battleships lately laid down—the Borodino, Imperator Alexander III., and Orel—in the *Annual* last year, and the following details concerning the first two are taken from the *Kronstadtski Viestnik*. They would indicate slight differences, but in view of the uncertainty existing, the tables have not been altered:—Borodino, begun May 26, 1899; length between perpendiculars, 397 ft.; beam, 76 ft.; displacement, 13,566 tons; engines, 16,300 I.H.P.; speed, 18 knots. The Imperator Alexander III.: begun September 5, 1899; length over all, 398 ft.; between perpendiculars, 376 ft.; beam, 76 ft.; mean draught, 26 ft.; displacement, 13,516 tons; engines, 15,800 I.H.P.; capacity of coal bunkers, 1250 tons; speed, 18 knots. She will probably be launched in the spring of 1901. The Kniaz Souvaroff, laid down at the Baltic Yard, St. Petersburg, is of the same type.

Kniaz
Souvaroff.

Coast-
defence
ship,
Admiral
Boutakoff.

Some doubt has prevailed as to the characteristics of the coast-defence ship Admiral Boutakoff, which has, at length, been laid down at the New Admiralty Yard, St. Petersburg, and the following particulars have been taken from the *Kronstadtski Viestnik*:—Length, 341 ft. 6 in.; beam, 59 ft. 3 in.; draught, 17 ft. 3 in.; displacement, 5985 tons; engines, 7000 horse-power. According to this authority, she will carry six 8-in. and sixteen 1·85-in. guns; four Maxims; and four torpedo tubes, two above water and two submerged; but there is no certainty as to the actual armament intended, and the particulars

given in the tables are probably more trustworthy. The greatest thickness of her armour belt will be 7 in. Her coal supply will be sufficient to take her 750 miles at 16 knots, and 1400 miles at 8 knots.

The following are particulars of the armoured cruiser Bayan, launched at La Seyne on June 12, 1900. Length, 445 ft.; beam, 57 ft.; mean draught, 22 ft.; displacement, 7800 tons; protection, Krupp water-line armour, varying from 8 in. to 4 in. in thickness, and extending from the bows more than three-quarters of the ship's length; above this, 3 in. of steel from the bows, for a length of about 335 ft., protecting the lower deck, and rising to cover three redoubts, that amidships containing four 6-in. Q.F. at the angles and eight 3-in. Q.F., and those forward and aft each mounting two 6-in. Q.F. at the corners. The 3-in. guns are twenty in all, and there are seven 1·8-in. Q.F., while singly in turrets on the upper deck, forward and aft, are two 8-in. guns, with 7 in. protection and armoured ammunition hoists. Electric gear is provided for loading and training. There are two vertical engines of 16,500 I.H.P., the steam being developed by twenty-six Belleville boilers, and the intended speed is 21 knots, to be maintained on trial for twenty-four hours.

Of the protected cruisers launched in 1900, the Aurora, Askold and Novik have been fully described in the *Naval Annual*. The following particulars have been given by the *Kronstadtski Vestnik* of the Bogatyr, which was launched at the Vulkan Shipbuilding Works, Stettin, on January 31. Her extreme length, 440 ft. 2 in.; beam, 54 ft. 6 in.; depth of hold, 34 ft. 1½ in.; with all her armament and 720 tons of coal, her displacement is 6750 tons, and her draught 20 ft. 10 in.; her engines are triple expansion, with four cylinders, and of 20,000 I.H.P., and are to give her a speed of 23 knots; steam is generated by sixteen Normand water-tube boilers; her bunker capacity is 1100 tons. Below the water-line she is divided into watertight compartments, and amidships, under her boilers, machinery, and ammunition room, she has a double bottom extending up her sides to the armour deck, which is 1·3 in. thick where horizontal, 2·7 in. approaching the vertical, and 2·12 in. towards the ends. The cruiser will carry twelve 6-in., twelve 3-in., six 1·8-in. (Hotchkiss), one 2·56 (Baranovsky), and two 1·45-in. (Hotchkiss) guns, the last three guns for landing purposes. She will also carry six torpedo tubes, one each forward and aft above water, and two above water and two submerged on the broadside. Six dynamos, four large and two small, will work the ventilators and ammunition hoists, and supply the electric lighting and six searchlights.

Armoured
cruiser
Bayan.

Protected
cruisers
launched:
Aurora,
Askold,
Novik,
Bogatyr.

Boyarin.

The Boyarin, which has been launched at Messrs. Burmeister & Wain's, Copenhagen, is a cruiser of about 3000 tons, of the Novik class.

Trials—
Varyag.

The official trials of the protected cruiser Varyag (6500 tons), built by Messrs. Cramp, at Philadelphia, took place off the New England coast at the end of July, 1900. Although an accident interfered with the proposed continuous twelve hours' run, the speed developed during seven hours and a half was so far in excess of the contract requirement that the Russian Board unanimously agreed that the essential elements of the trial had been complied with. During the run from Boston the speed trial began off Nantucket Shoals. A continuous speed of 23·6 to 23·7 knots was developed for seven and a half hours. At that point an accident occurred to one of the high-pressure cylinders, which compelled the shutting off of the engine affected. The remaining part of the contemplated trial was, therefore, abandoned. The Russian Board, however, took not only into consideration the speed developed in the first seven and a half hours, but also the speed which the vessel displayed previously on the run off Boone Island, when she made 24·6 knots in a spurt, and decided that there could be no reasonable doubt of the ability of the vessel to maintain a speed considerably in excess of the contract requirement of 23 knots an hour. She proceeded from Philadelphia to Cronstadt.

Trials—
Nicolai I.

The *Kronstadtski Viestnik* stated that at the machinery trials of the reconstructed battleship Nicolai I., on October 30, 1900, the engines developed only 5000 I.H.P., instead of the 8000 I.H.P. contracted for. This was attributed to the fact that the heating surface of the sixteen new Belleville boilers was too limited. The Admiral Nahimoff has been reconstructed at Cronstadt, and her new engines and Belleville boilers (9000 I.H.P.) are expected to give a speed of 18 knots. The whole of the artillery will be quick-firing.

Sevastopol

The battleship Sevastopol was under trial in August. The fore turret jammed and the base was damaged, and other damage was done. It was also found that the ship had touched a sunken rock, but without great injury.

Torpedo
craft.

The destroyer Forel, built by M. Normand, at Havre, was launched on December 8, 1900, and the Ossetr, built at the Forges et Chantiers, Gravelle, near Havre, on January 23, 1901. They are sister boats, displacing 300 tons, having two torpedo tubes, and armed with one 12-pounder and five 3-pounders, and are intended to steam at 27 knots. The destroyer Som, built by Messrs. Laird, at Birkenhead, attained a speed of nearly 28 knots as the mean of six runs, thus exceeding the contract by almost a knot. It is said

that four destroyers will be built at Nikolaieff, and that five sea-going torpedo-boats are to be built at the Nevsky Works, in addition to five others ordered at Messrs. Creighton's yard at Abo.

ITALY.

Owing to financial exigencies and Ministerial instability the Italian shipbuilding programme has been retarded and modified. Lack of means has caused Italy to fall behind other nations in the matter of naval expansion, and she no longer holds the same relative position that she did. In naval circles it has therefore been felt that a programme was needed which would be accepted by the Parliament, and would remove the difficulties that arise from changes in the Cabinet and the naval administration.

Financial
diffi-
culties.

A programme of Naval Construction, extending from 1901 to 1912, which has been under discussion, but has not been definitely adopted, is divided into three periods as follows: (1) 1901-1904, 203 million lire for work in hand and five ironclads of about 10,000 tons—24 millions each—sixteen destroyers, two auxiliary vessels, and reconstruction of the Italia and Lepanto. (2) 1905-1909, 139 millions for five more 10,000-ton armour-clads, two auxiliary ships, and eleven torpedo-boats, to replace obsolete ones. (3) 1910-1912, 77 millions to replace obsolete vessels.

The pro-
gramme.

The class of small battleships or armoured cruisers of 8,000 tons, described in the *Naval Annual* last year, of which four—the Amalfi, Genova, Pisa, and Venezia—were to be built, has been abandoned, and instead two battleships of a new type, the Regina Elena and Vittorio Emanuele III., are to be built respectively at Spezia and Castellamare, and a third ship of the same class, the Roma, is contemplated. Probably only one will be laid down in 1901. These vessels will be of 12,624 tons, and will be well protected, heavily armed, and have a speed of 22 knots. There will be two 12-in. guns mounted singly in axial turrets, and twelve 8-in. guns coupled in six turrets, three on each side, the turrets amidships being at the level of the forward 12-in. gun. The distinguishing feature is the abandonment of the 6-in. Q.F., and the type is novel, presenting analogies both to the battleship and the armoured cruiser. The armour will be of Harveyised steel, and be produced at the Terni works; the other data of the ships will be found in the Tables. By the time this volume appears the battleship Regina Margherita, of 13,427 tons, should have been launched at Spezia. The class has already been described in the *Naval Annual*. The ship has a very powerful armament, consisting

The aban-
doned
type.

New
battle-
ships—
Regina
Elena,
Vittorio
Emanuele
III.,
Roma.


Regina
Marghe-
rita.

Benedetto Brin. of four 12-in., four 8-in., twelve 6-in. Q.F., eighteen 3-in. Q.F. and eight smaller guns. It is expected that the Benedetto Brin will be launched in September, being a sister of the Regina Margherita.

Trials, Varese. The trials of the armoured cruiser Varese took place in October and November, 1900. In the six hours' trial, with natural draught and 98 revolutions, the force developed being 9,479 I.H.P., the mean speed was 18.36 knots. In the forced draught trial in November, with a pressure of 201 lbs. per square inch, and 105 revolutions, the force being 13,885 I.H.P., the mean speed was 20.02. It has been stated by Signor Giuseppe Orlando that the Belleville boilers, as well as the engines, gave perfect satisfaction. They were in the hands of inexperienced stokers, were severely tried, and enabled the contract forced draught power to be exceeded and the engines to be stopped and suddenly started without injury. The ship has been built by Messrs. Orlando at Leghorn. The armoured cruiser Garibaldi. Giuseppe Garibaldi has also been under trial, her Niclausse boilers giving satisfaction. With natural draught the engines worked up to 10,000 I.H.P., being 1,000 more than the contract, and in the full speed trials the engines worked at 14,713 I.H.P., the contract speed of 20 knots was successfully attained. The cruiser has been built by Messrs. Ansaldo at Sestri-Ponente. The third-class cruiser Puglia. The natural draught speed was 17.6 knots as the mean of a six hours' run, the maximum I.H.P. being 5,250, and the mean of the trials 4,900 I.H.P., with 125 revolutions. In the forced draught trial, lasting an hour and a half, the speed was 19.5 knots, with 7,500 I.H.P. The cruiser has been built by Messrs. Orlando at Leghorn.

Torpedo craft. The destroyer Ostro was launched by Herr Schichau at Elbing on February 9th, 1901. She is a sister of the Lampo, Freccia, Dardo, Strale and Euro, which are all in the water, and displace 320 tons, with a speed of 30 knots. The Nembo, Turbine, Aquilone, Borea, Meteoro and Tuono are in hand at Messrs. Pattison's yard, Naples, and are somewhat larger boats, displacing 330 tons.

Ships removed from the list. The *Italia Militare e Marina* states that the following ships are struck off the list:—Folgore, torpedo despatch vessel; Maria Adelaide and Vittoria Emanuele, training ships; Palestro and Conte di Cavour, harbour vessels. Notwithstanding this, the total value of the ships composing the Italian Navy, calculated at about £20,000,000 in the Navy Budget of 1900–1901, still shows an increase upon that of the previous year. This sum does not include the auxiliary vessels Ciclope and Velino, which the Minister of Marine expects to be added to the Navy during 1901.



"ALABAMA."
UNITED STATES FIRST-CLASS BATTLESHIP.

THE UNITED STATES.

In the *Naval Annual* last year particulars were given of the builder's trial of the battleship Alabama, in which she attained a speed of 17·2 knots over a distance of 11½ miles. Her official trials took place on August 28 over the measured course between Cape Anne and Cape Porpoise, when, during a run of four hours, she made a mean speed of 17 knots, being one knot in excess of the contract. It is stated that the boilers maintained a steam pressure of 180 lb. and that an approximate horse power of 11,500 was developed. The number of revolutions averaged 114·6 over the whole course. No mishap occurred of any kind; the machinery ran with great smoothness, and the Cramp Company received the congratulations of the Navy Department. The final trials took from March 11th to 13th, 1901, with satisfaction. On a two hours' natural draught trial with 7,506 I.H.P. the speed was 15·2 knots.

Trials
of the
Alabama.

The trials of the Kearsarge took place on April 3, 1900, and some reference to them was made in the *Annual* last year. The following are the details:—During the two-hour full-power speed trial with natural draft, all fires being lighted and the coal used being Pocahontas of fair quality, containing a large proportion of slack, the speed attained was 14·99 knots per hour. The machinery, both main and auxiliary, worked very satisfactorily, with the exception of a heavy steam leak in the high-pressure starboard piston rod stuffing-box. The boilers steamed freely. The following are the data: Average revolutions, starboard, 98·7; port, 96·9. Vacuum, starboard, 26 in.; port, 25·5 in. Average steam pressure, 154 lb. Coal per hour, 18,480 lb. I.H.P., 8,483·35. Main and auxiliary engines, pounds of coal per horse power 2·18. Speed by patent log 1 to 2 p.m., 14·18 knots. Speed by patent log to 3 p.m. 15·80 knots. Average speed, 14·99 knots, as given above. The turret guns were then tested, the four in each turret being fired simultaneously. During this test, the blast from the 8-in. guns in the super-posed turrets did not inconvenience the people in the 13-in. turrets below. Observation in the forward turret showed a slight deflection of the upper portion of the turret support, due to the firing. When all four guns were fired together, the socket of the turret securing-bolt slightly fouled the inner face of the barbette, but the turret support regained completely and immediately its normal form and the damage was small.*

Kear-
sarge.

The preliminary trials of the battleship Wisconsin took place in Wisconsin.

* For Captain Folger's remarks on the ordnance trials, cf. *Naval Annual*, 1900, p. 45.

the Santa Barbara Channel, on October 11, when the mean speed was 17.158 knots in two runs over a measured course of 32 nautical miles. When corrected for tide and current the average became 17.174 knots. The mean draught at the trial was 23 ft. 6 in., according to the contract. The ship was under steam for four consecutive hours, and was found to be remarkably free from vibration, but her nautical qualities were not tried, the sea being quite calm at the time. The steering gear at all speeds answered very satisfactorily, including the hydraulic machinery, and the Board appointed to be present reported very favourably. They said that she answered remarkably well to her helm, turning in a noticeably short space, and holding a straight course with a minimum of attention to the helm. When she returned from Santa Barbara she steamed at 16 knots against wind and sea, and was pronounced to be a thoroughly efficient battleship.

Vessels
launched:
Wyoming,
Arkansas,
Nevada.

Three of the single-turret monitors were launched during the year: the Wyoming at the Union Iron Works, San Francisco, on September 8, the Arkansas at Newport News on November 10, and the Nevada (lately known as No. 8) at the Bath Ironworks on November 24. The following are the particulars of these vessels, which were designed by Rear-Admiral Hichborn, late Chief Naval Constructor. They have a single balanced turret on the keel line forward, containing two 12-in. guns, recently designed and to be used with smokeless powder, four 4-in. Q.F., three 6-pounder Q.F., and four 1-pounder machine guns. The monitors are of steel, not sheathed, with double bottoms and watertight subdivisions. The protection of the hull against injury to the water-line region is afforded by means of a side armour belt, the maximum thickness being 11 in., tapering to 5 in. at the armour shelf, the depth being 5 ft. The maximum thickness is abreast the engine and boiler spaces; from thence forward and aft it is reduced by steps to a minimum thickness of 5 in. at the bow and stern. The barbettes for the 12-in. guns have armour about 10 in. thick.

Torpedo
craft.

The following destroyers have been launched: the Dale on July 24, the Decatur on September 26, the Lawrence on November 7, the Macdonough on December 24, and the Preble on March 2, 1901. The Perry has also taken the water during the year. All these are of the same type, though varying somewhat in dimensions, and the details will be found in the torpedo tables. All are fitted with twin-screw vertical inverted triple-expansion engines and Thornycroft boilers, estimated to give a speed of 30 knots with 8,400 I.H.P. in the case of the Macdonough and Lawrence, the others, with less power, being 29-knot boats. The torpedo equipment consists of two long 18-in. Whitehead tubes, one aft of the after conning tower

and one amidships. The complement consists of four officers and sixty-nine men, the ward-room officers and petty officers being located forward, and the crew aft.

During the year a number of first-class torpedo boats have also been launched, including the Bagley, Barney, Blakely, Cushing, De Long, O'Brien, and Thornton.

The torpedo boat Stringham has been under trial. The Bailey attained a speed of 30.06 knots as a mean of three runs. The Stockton steamed at various speeds up to 26 knots, with 360 revolutions and 300 I.H.P., but there was some damage to the machinery, and the boat went to her constructor to be repaired.

Very great attention has been directed to the question of submarine boats, and in the last Report of the Bureau of Construction it was stated that the past year had brought to fruition experimental work covering a considerable period, and had demonstrated the practicability of such boats. The Holland had shown herself capable of such perfect control in the vertical plane, that she could be kept within a few inches of any desired depth while moving, or be brought to the surface, and taken under water again in a very short time. Her direction and control in the horizontal plane on the surface were effected with the same facility as any other craft, and submerged were limited only by the difficulties of vision. The crew were provided for with reasonable comfort and perfect safety, working upon the surface or submerged, and the Bureau attributed to the submarine great offensive power. As regards the interior, Lieutenant Caldwell thus describes his experiences: "I did nothing at all except sit quietly on a stool and watch the manipulation of the boat. You can see it all. It is all open. You can see what every man is doing except the engineer, who is a little hidden from this big room. It is all in one room. Each man has his station, sitting on a stool. I took a position where I could watch the pressure gauge and watch the immersion. I could not have told sometimes if we were on the water or below if I had not watched that gauge. I watched the man steering. He had nothing to do but work the little wheel which regulates the immersion, and you saw how well it was done from the gauge. The captain stood on the steps under the tower with his head in the tower, and steered the boat and gave orders about going ahead, when to dive, and when to come up, and about filling the tanks and generally about running the boat."

Submarine
boats.

Admiral Hichborn, recently Chief of the Bureau of Construction, has great confidence in these boats. Giving evidence before a Committee of the House of Representatives, he insisted upon the view of Admiral Dewey, that the attack upon Manila would have been

impossible if submarine boats had been in the harbour. The nervous strain thrown upon officers and men would have been too great. It deserves to be noted, however, that Admiral Dewey has since explained that he had no small boats capable of dealing with such craft. Admiral Hichborn also said that such boats "would be a help to nervous people" at home, and he reminded the Committee, that, during the war with Spain, old monitors, condemned more than thirty years ago, had been sent down the New England coast to pacify the people. Admirals Dewey and Hichborn were supported by Admiral Farquhar, Captain Folger, Commanders Mason and Wainwright, Lieut. Caldwell, and others. Admiral O'Neil strongly opposed the submarine boat, on the ground that it was still experimental, and he insisted upon the dependence of such boats upon their base or upon convoy, their insufficient speed, and the difficulty of keeping them in order. "The only use of the Holland is to discharge torpedoes, and no weapon is more erratic and uncertain in its flight. It must be adjusted and launched with the greatest accuracy to have even a possibility of hitting its mark, and when discharged from a boat, as erratic in its movements as the Holland, the possibility is reduced to a minimum." Admiral Melville also argued against the boats. He said they would soon get out of order, and would be of little value in any case, and Admiral Bradford adopted the same line of argument.

In addition to the Holland and the Plunger there are already in hand, or provided for, six boats, of which the Adder, Moccasin, Porpoise, and Shark are in the yard of Lewis Nixon, at Elizabethport, New Jersey, and the Grampus and Pike at the Union Ironworks, San Francisco. The boats will be 63 ft. 4 in. long and 11 ft. 9 in. in diameter, and will displace 120 tons. Each will be driven by a single-screw 4-cylinder Otto gasoline engine of 160 I.H.P., giving a speed of 8 knots on the surface, while the main motor will be of the "electric water-proof" type, developing 70 horse power and giving a speed of 7 knots a-wash or submerged. The tank capacity for gasoline will be 850 gallons. Each of the boats will have a conning tower 21 in. in diameter, protected by 4-in. armour, and will carry five 18-in. Whitehead torpedoes. The price of each boat is 170,000 dols., and according to contract all should be completed before July 25, 1901.

Congress authorised, on March 3, 1899, the construction of three battleships of about 13,500 tons, but, owing to difficulties in regard to armour, many months elapsed before contracts were invited. Two other battleships were authorised on June 7, 1900, and designs for the whole five have been prepared. A compromise was effected in regard to the types, it being decided that three of the ships should be provided with superposed turrets, as in the Kearsarge and Kentucky,

and two with the 8-in. guns mounted in independent turrets. In February, 1901, however, an augmented board on naval construction presented a report, from which only two of its members dissented, in favour of the superposed turret plan for all five ships, and the Secretary of the Navy has approved the recommendation. The report was signed by Rear-Admirals O'Neil, Bradford, and Melville, and Captains Sigsbee, Evans, A. Walker, Chadwick, Converse, C. E. Clark, and Taylor. Three of the ships were intended to be sheathed and coppered, while the others were to be unsheathed, but it has recently (March, 1901) been decided that all shall be unsheathed, as also the new cruisers, with the exception of those of the Denver class.* It may, in this place, be enough to say that the trial displacement of the battleships will probably be about 15,000 tons. The other particulars will be found in the tables. Propulsion will be by a pair of vertical, twin-screw, 4-cylinder triple-expansion engines of 19,000 I.H.P., running at about 120 revolutions per minute, and steam at 250 lb. per square inch will be generated by twenty-four straight water-tube boilers placed in six water-tight compartments. In the *Naval Annual* last year many particulars were given of the armament of the new ships, but some changes have now been introduced and the following particulars will be interesting. It may be useful to compare the armament proposed with that in the Duncan class, with the remark that the latter has no answer to the 8-in. guns, and has six fewer 3-pounders:—

NEW AMERICAN TYPE.

Four 12-in.
Eight 8-in.
Twelve 6-in.
Twelve 14-pounders.
Twelve 3-pounders.

DUNCAN CLASS.

Four 12-in.
—
Twelve 6-in.
Twelve 12-pounders.
Six 3-pounders.

The 12-inch guns, which are to be of 40 calibres length, will be in pairs in balanced turrets, training on an arc of 270 deg. Four of the 8-in. guns will be coupled in the superposed turrets, while the other four will be in pairs in turrets, one on each beam, these having a training arc of 145 deg. The 6-in. guns will be on the main-deck in the armoured citadel, and will have an arc of fire of 110 deg., while the other guns are to be in advantageous positions, and there will be four machine guns mounted, two in each of the lower tops, and four single-shot 1-pounders, two in each of the upper tops. The whole of the turrets will be controlled and operated electrically. The particulars given last year of the armour were accurate, but the fact

* The battleships Georgia, Virginia, and Nebraska will be built respectively by the Bath Ironworks, the Newport News Company, and the Moran Company, of Seattle, Washington, and the New Jersey and Rhode Island by the Fore River Engine Company.

that a citadel for the 6-in. guns will be formed by 6-in. transverse bulkheads deserves to be noted. The magazines will contain 60 rounds for each 12-in. gun, 125 for each 8-in., 200 for each 6-in., 250 for each 14-pounder, and 500 for each 3-pounder, besides a large supply of small ammunition.


Armoured
cruisers.

Three armoured cruisers were authorised in March, 1899, and three in June, 1900—the California, Pennsylvania, West Virginia, Maryland, Colorado, and South Dakota. The type was generally described in the *Annual* last year in regard to protection and armament. These cruisers are to be propelled by twin-screw four-cylinder triple-expansion engines of 23,000 I.H.P., the steam to be generated by water-tube boilers in eight water-tight compartments, and the speed to be not less than 22 knots. Three other armoured cruisers, described in America as “protected,” were provided for in June, 1900—the Charleston, Milwaukee, and St. Louis. The particulars given in the tables are according to specification. The proposed armament of fourteen 6-in. quick-firers is intended to be distributed thus: six on pedestal mounts with shields on the main deck, and four in sponsons at the corners of the super-structure, the other eight being on the gun-deck, mounted four on each broadside in a central casemate. Here also will be twelve 14-pounder guns, while six more will be on the super-structure, as well as twelve 3-pounders, and there will be four 1-pounder and machine guns in the tops, and four 1-pounder quick-firers forward and aft on the gun deck. Arrangements are to be made whereby all the guns which do not train fore and aft, or nearly so, can be quickly and conveniently dismounted, housed, and secured, so as to leave the ship’s side practically clear. Protection will be provided by central water-line armour 4 in. thick, above which will be another range of plating of the same thickness, connected forward and aft by transverse bulkheads 3 in. thick. The ships will also be protected with steel of 4 in. thickness above the lower casemate, and there will be protection for the guns at the angles of the super-structure as well as an armoured deck.

Pro-
gramme of
1901.

In the Naval Appropriation Bill, as presented by the Naval Committee of the House of Representatives on January 19, 1901, the following occurs:—

The Committee recommends building by contract two unsheathed sea-going battle-ships, carrying the heaviest armour and the most powerful ordnance for vessels of their class, upon a trial displacement of about 14,000 tons each, to have the highest practicable speed and great radius of action, and to cost, exclusive of armour and armament, not exceeding \$3,850,000 each, and two unsheathed armoured cruisers, carrying the heaviest armour and most powerful ordnance for vessels of their class, upon a trial displacement of about 14,000 tons each, and to have the highest practicable speed and great radius of action, and to cost, exclusive of armour and armament, not exceeding \$4,000,000 each. Maximum cost of the vessels herein authorised, exclusive of armour and armament, will be \$15,700,000.



"MIKASA,"
JAPANESE FIRST-CLASS BATTLESHIP.

As finally passed, the Naval Appropriation Bill sanctioned this programme, but only in general terms, the Senate Amendment for the building of three additional submarine boats being rejected; and the Secretary of the Navy was directed to prepare plans and descriptions to be presented to the new Congress in December, 1901. By directing this delay, Congress failed to make provision for any additions to the Navy in the new Bill.

JAPAN.

The Mikasa, the last of the battleships of the present programme building in England, was launched at Messrs. Vickers's, Barrow-in-Furness, on November 8th, 1900. She is a sister of the Asahi and Hatsuse, which she closely resembles in the matter of displacement, dimensions and armament, though there are important differences in regard to protection. The following account of her characteristics is from the *Times* :—

Battle-
ships.
Mikasa
launch.

Length between perpendiculars, 400 feet; over all, 432 feet; beam, 76 feet; and at a draught of 27 feet 2 inches the displacement is about 15,150 tons. The engines will develop 15,000 horse-power, calculated to give a speed of 18 knots. Her normal coal supply will be 700 tons, with capacity for 1,400 tons, which will allow of her travelling about 9,000 miles at a speed of ten knots. The engines will be of the triple expansion type with three cylinders, and there will be 25 Belleville boilers, with economisers. She is protected by a complete armour belt consisting of Harveyed nickel steel of Vickers's manufacture, of 9-inch thickness over a space of 156 feet amidships, covering the vital portions of the vessel; this is continued forward and aft by armour tapering from 7 inches to 4 inches, terminated at the after-end by a 6-inch bulkhead, thus forming a complete protection over the entire water-line of the ship. The belt extends from 5 feet 3 inches below the water-line to 2 feet 6 inches above, and is there met by the 6-inch citadel armour, which continues the protection from the top of the belt to the upper deck. The citadel comprises the chief departure from ordinary practice in the design, as, besides protecting the space between the belt and the main deck battery, it takes the place of the ordinary arrangement of casemates usually found in British and foreign battleships, and entirely protects the 6-in. guns on the fighting deck. By this arrangement throughout the whole of the centre portion of the ship the crew are protected from injury when working the guns, while the gun positions themselves are equally protected in front as in the casemate arrangement, and are infinitely less vulnerable from behind, which is protected now by the 6-inch armour on the opposite side of the ship, as well as by the thick steel bulkheads which divide the gun positions one from another. The conning tower is protected by 14 inches and the observer tower aft by 3 inches of armour. In addition to the above protection there is a protective deck below the main deck, which extends throughout the whole length of the ship, and consists of 2 inches of armour on the flats and 3 inches on the slopes. The heavy armament is four 12-in. breech-loading guns, mounted in pairs forward and aft. These are placed in armoured barbets 14 inches thick above the upper deck, and 10 inches thick below, where they are covered by the screen bulkhead. The heavy quick-firing armament is composed of fourteen 6-in. guns, ten of them mounted in the armoured citadel above described, and four of them mounted on the upper deck in casemates. In addition to these there are twenty 12-prs., eight 3-prs., and four 2½-prs., all quick-firing guns; and the torpedo equipment consists of four submerged tubes, two forward and two aft. The weight of metal discharged by this armament in one minute is 11½ tons, representing a striking energy of 1,337,130 foot tons, while the weight of metal discharged from the guns available on one broadside in a minute is 7½ tons, giving a striking energy of just under 1,000,000 foot tons. The ship is divided thoroughly by watertight compartments.

The trials of the Asahi, built and engined by Messrs. John Brown & Co., Ltd., of Clydebank, took place in March, 1900, on the

Asahi
trials.

measured mile in Stokes Bay and in the Channel. In Stokes Bay the following were the results:—613 I.H.P., 6·69 knots; 1,610 I.H.P., 9·28 knots, and 4,355 I.H.P., 13·06 knots. The high-speed consumption trial showed that with 12,947 I.H.P., the consumption was only 1·59 lb. per horse-power per hour. There was a high wind and a heavy sea, but the records taken gave an approximate speed of 17·5 knots. The ship then made her full-power trial between Start Point and Berry Head, a distance of 12·26 nautical miles. Four runs were made, the first and third being in the teeth of a north-easterly gale; but with this disadvantage the mean speed was 18·3 knots. The speeds on the four runs were:—First run, 17·92 knots; second run, 18·08 knots; third run, 18·65 knots; fourth run, 18·3 knots. The mean I.H.P. for the entire series of runs was slightly over 16,000. After the full-speed trial circles were made to port and starboard with each steam-steering engine, the vessel being still at full speed, and at a speed of 15 knots the hand-steering gear was successfully tried. On the return to Spithead, at 17 knots, the stopping, starting, and reversing trials were carried out. After the trials, through misadventure, the ship was carried by the current upon the beach at Southsea, and, when she was placed in dry dock at Portsmouth, it was found that the plates under the fore barrette had buckled in for about 40 ft. on the starboard side and 20 ft. on the port side, some of the frames being broken. The damage done has since been made good. The sister ship *Hatsuse*, built at Elswick, which represented Japan at Queen Victoria's funeral, has also been successful at her trials.

Cruisers
launched.
Iwate.
Chihaya.

The armoured cruiser *Iwate* was launched at Elswick, in April, 1900, and has steamed at 21·8 knots. She is a sister of the *Idzumo*, which was fully described in the *Annual* last year. At Yokosuka the torpedo-gunboat *Chihaya* has been launched. Information from Japan shows her to have a displacement of 857 tons, but she has been described as a cruiser of 1,230 tons. She has engines of 5,500 horse-power, steam being developed by Normand boilers, and is to steam at 21 knots.

Torpedo
craft.

Messrs. Thornycroft have received an order from the Japanese Government to build two 31-knot destroyers, similar to the six which the same firm has built, and a similar order has been received by Messrs. Yarrow. It is stated that at Kure six 120-ton torpedo-boats will be built, and will receive the names of *Awataka*, *Hato*, *Hibari*, *Kari*, *Kiji*, and *Tsubamo*.

MINOR NAVIES.

AUSTRIA-HUNGARY.

The coast-defence battleship Habsburg, built from the designs of Herr Popper, who made the plans for the Monarch, was launched at Trieste in October, 1900. She displaces 8,340 tons, and her other data will be found in the tables. She represents a stronger type than the Monarch, and has larger coal capacity, giving her greater range of action. The hull is built of Martin steel, and the double bottom extends for 63 per cent. of the ship's length, with watertight compartments to the number of 174, and extensive pumping apparatus. The maximum thickness of the armour plating, which is of special steel, is $8\frac{3}{4}$ in., and, like the double bottom, it extends for 63 per cent. of the length, with a breadth of nearly 8 ft. Transverse bulkheads unite the side armour at the ends, and above is the steel deck. In this way a citadel is formed, and there is deck protection forward and aft. Above the main belt thinner plating covers the sides up to the main deck. The three 9·4-in. guns are placed two in the forward barbette, and one in the after barbette. There are also twelve 5·9-in. Skoda quick-firers, placed in casemates, which are superposed in pairs, three on a side, the guns thus being on two stages. It seems likely that in bad weather the lower casemates might be out of action. Sixteen Belleville boilers are in two watertight compartments, and there are four stoke-holds. The two principal engines are of the triple-expansion four-cylinder type. The ship is provided with bilge keels. She was eighteen months on the stocks from the date of laying down, and was to be completed within three years from the same date.

Ships
launched.
Monarch.

The torpedo-cruiser Szigetvár, which is a sister of the Aspern, was launched at Pola on October 29th; she has Yarrow boilers and engines, of 7,800 tons, and is to have a speed of 14 knots.

Szigetvár.

The trials of the Kaiser Karl VI. were successfully completed in September, 1900. The engines worked up to 12,900 horse-power instead of 12,800 horse-power as required, and the speed attained was $20\frac{3}{4}$ knots per hour, or three-quarters of a knot per hour in excess of the rate provided for.

Trials.

The following statement indicates the work now in hand and contemplated for the Austrian Navy—(1) A protected cruiser "E," of 7,400 tons, to supersede the frigate Radetzky. (2) The torpedo-gunboat Szigetvár. (3 and 4) Two battleships of 8,300 tons, with engines of 11,000 horse-power and a speed of 18 knots, building at the Stabilimento Tecnico Triestino. The armour-belt and the pro-

tection of the turrets will be 7·8, 8·2, and 8·6 in. thick, and the armour deck 2·6 in. thick, all of nickel steel. Each ship will carry three 9·4-in. Krupp and twelve 5·9-in. Skoda Q.F., and twenty-four smaller guns, including machine guns, and several torpedo-tubes. Both ships will probably be launched this autumn. (5) A third battleship of the same type as the two preceding, proposed to be laid down this year, to replace the obsolete *Erzherzog Albrecht*. (6) A fourth battleship, of 10,000 tons, proposed for 1901, which is to take the place of the *Laudon*. The *Laudon* (frigate), the *Hun* (gunboat) and the paddle-steamer *Andreas Hofer* are to be struck off the list, though the *Laudon* will still be used as a training-ship. The increase in the *personnel* of the navy will amount altogether to 2,500 men.

CHINA.

The most important event in the history of the Chinese Navy since the *Annual* last appeared was the capture by the Allies at Taku of the four destroyers built at Elbing in 1898 and 1899, which have now been added to the navies of Great Britain, France, Russia, and Germany, each boat bearing the name of Taku.

DENMARK.

A torpedo transport, to be known as the *Beskytteren*, is in hand. The following are the particulars:—Displacement, 389 tons; length, 142 ft. 5 in.; beam, 25 ft.; draught, 10 ft. 10 in. Steam will be developed by Babcock and Wilcox boilers, and the engines will develop 600 I.H.P., to give a speed of 12 knots. The armament will comprise three 1·8-in. Q.F.

GREECE.

The armouredclads *Hydra* and *Spetsai* of 4,885 tons, which, owing to the outbreak of war with Turkey could not receive in 1897 the changes introduced into the *Psara*, have been completed. Their armament now comprises three 10·6-in. Canet guns, five 5·9-in., one 3·9-in., eight 2·5-in., and sixteen smaller guns.

LIBERIA.

The two gunboats which composed the whole navy of the Republic, the *Gorronomonah* and *Rocktown*, have both perished. The first sank as she lay at anchor, while the other was wrecked in the St. Paul river.

MEXICO.

The *Mittheilungen aus dem Gebiete des Seewesens* states that a naval programme has been adopted for which £200,000 has already been voted. It is to be carried out in the course of five years, eight gunboats of 1,000 tons' displacement and a speed of 18 knots being built; also two torpedo-boats. Four of the gunboats will be for the Pacific coast, and four for the Gulf of Mexico.

THE NETHERLANDS.

The Naval budget for 1901 amounts to £1,383,000, being about £25,000 more than in the previous year. The amount for ship-building alone is £350,000, and this will be sufficient to pay for the completion of the *Koningin Regentes*, 4,950 tons, and three torpedo-boats; the continuation of the two sister ships of the *Koningin Regentes*, the *De Ruyter*, and another vessel yet unnamed; and the commencement of a coast-defence ship. The *Koningin Regentes*, which has been launched, may be described as an improved *Evertzen*, but with many differences. Her general particulars will be found in the tables. She has a complete armour belt of Harveyized steel, with a maximum thickness of 6 in., and the turret protection is 10 in. thick, and are practically armoured towers containing all the hoisting, turning, and elevating gear, protected at their base by the side armour. She is the first ship of her size (5,000 tons) to be completely fitted with Yarrow boilers. The type is now adopted for the Dutch Navy, and has been fitted in the cruisers of the *Gelderland* class.

Messrs. Yarrow have in hand at Poplar three first-class torpedo-boats of 130 tons, 152 ft. 6 in. long, the *Ophir*, *Pangrango*, and *Rindjani* which, like all the other Poplar destroyers built for the Netherlands Government, have Yarrow water-tube boilers. The first-named was launched in March, 1901. The *Hydra* was under trial in May, 1900, when a mean speed of 24·37 knots was attained with a load of 17½ tons. The trials of the *Scylla* was equally satisfactory. Both vessels have been built for service in the Dutch East Indies.

A full account of the shipbuilding programme and of the new cruiser type was given in the *Annual* last year.

NORWAY.

The coast-defence armoured *Eidsvold* was launched on June 14th, 1900, from the Elswick shipyard. The following are the particulars: 290 ft. long, 50 ft. 6 in. beam, 16 ft. 6 in. draft, and displacement 3,847 tons, with a guaranteed speed of 16½ knots.

The ship is to be armed with two 8·2-in. Q.F. guns, six 5·9-in., eight 12-pdrs., six 3-pdrs., and two torpedo-tubes (submerged). The vessel has an armour belt of Harveyized steel 6 in. in thickness. The casemates, four in number, are of nickel-steel armour, 5 in. thick. The barbettes are of nickel-steel, 6 in. thick. The machinery is of the twin-screw vertical triple expansion type, with Yarrow boilers to develop 4,500 I.H.P. A sister ship is in hand.

PORTUGAL.

It is stated that the central battery ship Vasco da Gama, intended for the defence of the port of Lisbon, is to be modernised, and to receive water-tube boilers in two water-tight compartments protected by coal bunkers. The proposed armament is four 7·8-in. Q.F. guns, in barbette turrets, protected by $7\frac{3}{4}$ inches of steel, four 4·7-in. Q.F., eight semi-automatic 1·8-in. and two machine guns. The cruiser Rainha Amelia is being completed at Lisbon for her trials.

SPAIN.

The loss of the Spanish colonies, and therefore the new strategic condition that has arisen in regard to national defence, casts great doubt upon the future of the Spanish Navy. There is a strong movement on foot for the maintenance of the fleet upon its old level, and a Navy League, largely supported, has been founded to further the project; but on the other hand a considerable party desires to devote the means at the disposal of the government to other purposes.

Vessels
launched.
Cataluña.

Two cruisers have been launched during the year. The armoured cruiser Cataluña, which took the water at Cartagena on September 24th, is described as follows:—Length between perpendiculars, 348 ft.; beam, 61 ft.; depth of hold, 38 ft.; draught, $21\frac{1}{2}$ ft.; displacement, 7,000 tons; engines, vertical and triple expansion, 10,000 I.H.P. with natural draught, and 15,000 horse-power with forced draught, giving speeds of 18 and 20 knots. The coal capacity of the bunkers is 1,200 tons, giving her a range of action of 10,000 miles at 10 knots. The armour belt is 230 ft. 6 in. long, 5 ft. 6 in. wide, and from 10 in. to 12 in. thick, the protection of her turrets being about the same. The armour deck is from 2 in. to $2\frac{3}{4}$ in. thick. The machinery is also protected by a layer of coal above it and at the sides. She will carry two 11-in., ten 5·5-in., two 2·7-in., four 2·2-in., four 1·45-in., and four machine guns; also five torpedo-tubes submerged. Wood has been used as little as possible in her construction.

Estremadura.

A smaller cruiser, the Estremadura, built out of subscriptions collected by Spanish colonists in Mexico, was launched at Cadiz on April 29th, 1900. Her length is 290 ft.; beam, 36 ft.; draught, 14 ft.;

displacement, 2,030 tons. Her armour deck is composed of two layers of plates each an inch thick. She carries four Hontoria 5·9-in. Q.F. guns, four Krupp 4·2-in. Q.-F., four 2·2-in., two machine guns, but no torpedo-tubes. Her two engines are vertical and triple expansion, with eight Thornycroft boilers, developing 7,000 I.H.P., to give her a speed of 20 knots.

It is stated that a number of vessels are being struck off the effective strength of the navy, and the following names are given. In view of the uncertainty of the Government policy several of the vessels are, however, at present retained in the lists :—Alfonso XII. and Alfonso XIII., first-class cruisers ; Conde de Venadito, Isabel II., and Marques de la Enseñada, second-class cruisers ; Temerario, Martin Alonzo Pinzon, Vicente Yañez Pinzon, Marques de Molins, and General Valdes, torpedo-gunboats ; Eulalia, Pilar, Condor, Aguila, Seguira, Cuervo, and Tarifa, gunboats ; Retamosa, Rigel, Ejército, and Castor, torpedo-boats ; and five coast-defence ships. The armoured cruisers Numancia and Vitoria, and the unarmoured cruiser Infanta Isabel, will, it is said, be treated in the same manner as soon as their boilers require renewing or any other important repair is called for.

Removals
from list.

SWEDEN.

Provision is made in the budget for the completion of the three coast-defence vessels, A, B, and C, which were fully described in the *Annual* last year, and for the modifications which are in progress in the Svea, Göta and Thule, as well as in the monitors, Thordön and Tifring. The Dristigheten has been launched at Gothenborg. She is a coast-defence turret ship of 3,500 tons, well protected and heavily armed, and like the other new Swedish ships, provided with Yarrow water-tube boilers, these being for 6,000 I.H.P., and to give a speed of 16·5 knots.

The torpedo-cruiser Psilander, built at the Bergsund Yard, Stockholm, has undergone satisfactory trials. With natural draught (2,946 I.H.P.) she steamed at 19 knots, and with forced draught (4,475 I.H.P.) at 20·5 knots.

With the development of the fleet, the naval yards on the islands of Skeppsholmen and Kastellholmen have become inadequate, and new establishments are to be founded nearer Stockholm.


TURKEY.

Messrs. Ansaldo, of Sestri Ponente, are now well advanced with the re-construction of the old central battery ironclad Messoudieh, to which allusion was made last year. The hull has been partially

rebuilt for the emplacement of the new guns which have been supplied, two 9·2-in., twelve 6-in. Q.F., fourteen 3-in. Q.F., ten 6-pdrs. Q.F., and two 3-pdrs. Q.F. The engines have been built by the same firm, and are of 11,000 I.H.P., the force being supplied by water-tube boilers. Messrs. Ansaldo have launched, or will do so during the year, two small destroyers or large torpedo-boats for the Ottoman Navy. They displaced 145 tons and are 156 ft. long, with 18 ft. 6 in. beam, and 4 ft. draught. The engines are of 2,400 I.H.P. and are to give a speed of 26 knots. There are two torpedo-tubes, and the guns are two 1-pdrs.

As an indication of the intention of the Ottoman Government to re-constitute the navy if possible, it may be interesting to note that a contract has been signed with Messrs. Krupp for the supply of 208 quickfiring guns, including four 8·2-in., fifty-two 5·9-in., fifty-six 2·9-in., eighty 2·2-in., and sixteen 1·8-in.

JOHN LEYLAND.



"NORGE,"
NORWEGIAN COAST-DEFENCE SHIP.

CHAPTER IV.

COMPARATIVE STRENGTH.

ACCORDING to the custom of the *Naval Annual*, the first place in this chapter is devoted to the distribution of naval force, concerning which the accompanying tables are almost sufficiently explanatory. The Channel Squadron remains unchanged in its composition, but the Niobe, which was detached to South Africa at the outbreak of the war, has returned. In the Mediterranean, eight destroyers and four first-class torpedo boats have reinforced the squadron, and the Hood has replaced the Ocean, which was sent to China. The increase of torpedo craft is timely, but it is certainly not too considerable, in view of the large additions now being made to the French flotillas in those waters, and of the new importance which is being given to the stations of the mobile defence, not only in France, but also in Corsica, Algeria and Tunis. In both the Channel and Mediterranean the number of cruisers attached to the squadrons still leaves very much to be desired.

Ships in
Commis-
sion—
Mediterranean
and
Channel.

A notable step has been taken in reorganizing the Reserve Squadron, composed of the coastguard and portguard ships, which, instead of having only part complements on board, are now kept fully manned, and are intended to assemble twice or three times in the course of the year for cruising and steam tactics. Its first cruise in the new conditions was in March, 1901. An additional coastguard ship, the Camperdown, has been established at Rathmullen. The Reserve Squadron is thus in a better posture to support the Channel Squadron, and when some of the old ships have been relieved by the comparatively modern vessels which will presently be available from the Mediterranean and other stations, it will become an effective fighting force.

British
Reserve
Squadron.

The French Northern or Channel Squadron remains unchanged, except that the Hoche, which has been undergoing considerable modifications, has replaced the Redoutable, despatched to China. The coast-defence squadron, consisting of the four ships of the Valmy class, which was last year in the Mediterranean, has returned to the Channel. Through this change the Reserve Division in the Mediterranean has for the present ceased to be an effective force. There, however, the squadron has been strengthened by the addition of the St. Louis, and has now seven modern battleships, forming a force which may be regarded as practically homogeneous. In both

The
French
Squad-
rons.

| CLASS. | MEDITERRANEAN FLEET. | CHANNEL FLEET. | RESERVE SQUADRON of Coast and Port Guard Ships. | MEDITERRANEAN FLEET. | | NORTHERN SQUADRON. | RUSSIA. |
|-------------------------------|--|--|---|---|---|---|---------------|
| | | | | Permanent Squadron. | Reserve Ships. | | |
| BATTLESHIPS . . | Canopus Cesar Empress of India Hood Illustrious Ramillies Renown Royal Oak Royal Sovereign Victorious Devastation (Gibraltar) Rupert (Alexandria) Orion (Malta) | Hannibal Jupiter Majestic Magnificent Mars Prince George Repulse Resolution | Alexandra (c.g.) Benbow (c.g.) Camperdown (c.g.) Collingwood (c.g.) Colossus (c.g.) Howe (p.g.) Nile (p.g.) Rodney (c.g.) Sans Pareil (p.g.) Trualgar (p.g.) | Gaulois Charlemagne Bouvot Brennus Charles Martel Jauréguiberry Saint Louis | Terrible * Magenta * | Carnot Masséna Amiral Baudin Courbet Formidable Hoche Iéna ** | Alexander II. |
| COAST-DEFENCE SHIPS | | .. | .. | D'Entrecasteaux* Châteaurenault * | Tenpête (Bizerla) | Amiral Tréhouart Bouvines Jennapes Valmy Cocyte (Dunkirk) | Khraby |
| CRUISERS, 1st Class . | Andromeda Thesens | Diadem Niobe | Australia Galatea | Chanzy, Latouche-Tréville Pothuau | .. | Dupuy-de-Lôme Bruix Tage ** | .. |
| CRUISERS, 2nd Class . | Diana, Gladiator Vindictive | Arrogant Furious | Severn | Du Chayla Cassard | .. | D'Assas | .. |
| SMALLER CRUISERS AND GUNBOATS | 9 | Pactolus Pelorus | Melampus | Galilée, Lavoisier Linois | .. | Surcouf | 1 |
| TORPEDO-GUNBOATS . | Halcyon, Hussar, Dryad, Speedy Salamander Sandfly (reserve) Torpedo Depot Ship. Vulcan | .. | 8 | Condor (Crete) Dunois Torpedo Depot Ship. Foudre | Lévrier (Corsica) Dague (Algeria) Écluse (Tunis) Casabianca (Tunis) Mouette, Vautour (Constantinople) | Cassini Durandal La Hire S ^{te} Barbe (Dunkirk) | Abrek |
| DESTROYERS . . | 14 | .. | 5 | 12† | .. | 5† | 2 |

* At Toulon; not attached to Mediterranean Squadron.
† Fauconneau and 4 sea-going boats.

† Hallebarde, Espingole and 10 sea-going boats, including 6 at Toulon and at Tunisian and Algerian ports.
|| To be reconstructed at La Seyne.

** At Brest; not attached to squadron.

the Mediterranean and Channel the cruisers have been organized as light divisions under rear-admirals.

The Italian Squadron at present in commission in the Mediterranean, under command of the Duke of Savoy, consists of the battleships Lepanto, Sardegna, Sicilia, Dandolo, Doria and Morosini, the torpedo gunboats or destroyers Urania, Partenope, Lampa and Rapido, and the torpedo-boats included within the inspectorate at Genoa, Spezia, Gaeta, Taranto, Civita Vecchia and Venice. Italy.

The Boxer rising in China, and the difficulties with the Chinese Government which ensued, leading to hostile operations in the Peiho, and an advance of the forces of the Allies to Peking brought about a considerable accession to the naval strength of the Powers in the Far East. Never before have such fleets been assembled in Chinese waters, and it may be taken for granted that the additions to the squadrons represent a considerable permanent augmentation of maritime force which will throw new burdens upon the countries concerned. The large increase now being made in the Russian Pacific Squadron is, no doubt, the determining factor, and it is worthy of note, since many of the new Russian ships have been, and are being, built for service in those waters, that the Boxer trouble merely accelerated a development which would sooner or later have become inevitable on other grounds. Naval strength in the Far East.

The British Squadron on the China station has been augmented by the arrival of two new battleships, the Ocean and Glory, making five in all. The Blenheim has been added to the first-class cruisers and the Argonaut has relieved the Undaunted. The Dido, Isis, and Astræa have joined the flag from the Mediterranean, and the first two named will remain in China. The Arethusa came from the Pacific, and the Wallaroo, Mohawk, and Lizard were detached from Australia; but the Mohawk returns home, while the Marathon was for some months in Chinese waters, but has returned to her station in the East Indies. Two destroyers, the Otter and Janus, have been added to the squadron, and the river-gunboat Robin has been commissioned for service in the West River, while the steamer Pioneer has been purchased as a gunboat for the Yang-tse, where she has done good work. Vice-Admiral Sir Cyprian A. G. Bridge succeeds Sir Edward Seymour in command. Great Britain.

Notwithstanding these considerable additions to British strength, there was a tendency in some quarters to censure the Admiralty for not having done more. In effect the German Government turned the balance of force on the China station by despatching thither the major part of the effective fleet, and assembled at Kiao-Chau and off the Chinese ports a very imposing naval force. It may be Germany.

remarked, however, that, inasmuch as the Powers were allied in their efforts to obtain reparation from China, there was no necessity for a competition of strength in their naval forces, and if the contrary should be held, it is reasonable to point out that the Germans, by making a demonstration which was perhaps exaggerated in China, seriously weakened the available forces in home waters. It may be surmised, however, that the despatch of the second division of the battle squadron, comprising the Kurfürst Friedrich Wilhelm, Brandenburg, Weissenburg and Wörth, with the third-class cruiser Hela, was intended to impress upon the legislature the necessity of building those cruisers for foreign service, which were originally included in the Navy Bill, but were withdrawn, under parliamentary pressure, from the Government proposals. In addition to the second division of the battle squadron and the ships of the cruising squadron in Chinese waters, four third-class cruisers and a gunboat were detached from the American, Australian and East African stations. It has been stated that the four battleships, and possibly some other vessels named in the table, would return to Germany about May, 1901, but this is improbable, for officers and men to relieve those on the station have recently left Germany. All the ships are temporarily under the Admiral commanding the cruising squadron.

Russia.

The Russian battleships in the Far East at the beginning of the Boxer trouble were the Petropavlovsk, Navarin, and Sissoi Veliky, and the Poltava and Sevastopol, leaving European waters in December 1900, have since joined them. To the five first-class cruisers on the station the Gromoboi was added shortly afterwards, as well as the destroyers Kassatka, Skat, Kit, Delphin and Som. The Moskva of the Volunteer Fleet has also been commissioned to serve as a cruiser in Chinese waters. It is understood that the squadrons are to be still further strengthened by the despatch of several ships which are now under trial or approaching completion. The *Marine Rundschau* reports that during the year 1901 the Peresviet and Retvisan will join the force, making in all seven battleships with an aggregate displacement of about 76,700 tons, and complements numbering 4,470, as well as the armoured cruiser Bayan, making seven vessels of the class, aggregating 63,500 tons, with complements of 4,586. According to the same authority, the new protected cruisers Varyag, Bogatyr, Askold and Novik are also to be despatched, making five vessels of the class, of 30,000 tons, with 2,550 officers and men. To these ships must be added two armoured gunboats, seven small cruisers and gunboats, three torpedo-gunboats, twenty torpedo-boats, seven harbour torpedo-boats, and three mining vessels, giving a total of sixty-one vessels, and about 14,000 officers and men.

SHIPS IN COMMISSION.

EASTERN ASIA.

| CLASS. | BRITISH. | FRENCH. | RUSSIAN. | GERMAN. | UNITED STATES. |
|----------------------|--|---|--|--|------------------------------------|
| BATTLESHIPS | Glory Ocean Goliath Centurion Barfleur | Redoutable | Petropavlovsk Poltava Sevastopol Navarin Sissoi Veliky | K. Friedrich Wilhelm Brandenburg Weissenburg Wörth | Oregon Kentucky |
| 1st-Cl. CRUISERS | Blenheim Orlando Argonaut Aurora Endymion Terrible | Vauban Amiral Charner Guichen | Rossia Rurik Gromoboi Ad. Nahimoff Dmitri Donskoi Vladimir Monomach Moskva (as cruiser) | Kaiserin Augusta Fürst Bismarck | Brooklyn |
| 2nd-Cl. CRUISERS | Arethusa Bonaventure Hermione Pique Astræa Dido Isis | Descartes Pascal Bugeaud Chasseloup- Laubat Friant | Ad. Korniloff | Hertha Hansa Irene Gefion | Albany Newark New Orleans |
| 3rd-Cl. CRUISERS | Alacrity Brisk Wallaroo | .. | Zabiaka Razboynik | Hela Seeadler Geier Schwalbe Bussard | .. |
| SLOOPS, etc. . | 18* | 7 8 (Cochin- China and Tonquin) | 6 | 4 | 16† |
| TORPEDO- GUNBOATS | .. | .. | 3 | .. | .. |
| DESTROYERS | 6 | 1 | 6 | 1‡ | .. |
| ARMoured GUNBOATS | .. | Achéron Styx | Gremiastchy Otvajny | .. | .. |
| MONITORS | | | | | Monadnock Monterey |

* Including 5 river gunboats.

† This includes the Isla de Cuba, Isla de Luzon and Don Juan de Austria, captured from the Spaniards at Manila. The United States have besides several auxiliary cruisers and other vessels in commission in the Philippines, as well as about 20 gunboats bought and captured from Spain, and a small "mosquito squadron" has recently been despatched.

‡ And 3 torpedo-boats.

SHIPS IN COMMISSION.

EAST INDIES.

| CLASS. | BRITISH. | FRENCH. |
|-------------------------|--|--------------------|
| 2nd-CL. CRUISER . . . | Highflyer | Catinat |
| 3rd-CL. CRUISERS . . . | Marathon Cossack Pomone Raccoon* | Infernet Nielly |
| SLOOPs and GUNBOATS . . | 2 | 2 |
| TORPEDO-GUNBOATS . . | 1 <i>in reserve</i> | |
| COAST-DEFENCE SHIPS . . | Magdala Abyssinia (<i>In reserve</i>) | |

* To be relieved by Perseus.

ATLANTIC.

| CLASS. | BRITISH. | | FRENCH. | UNITED STATES. |
|--------------------------------------|---|---|---------------------------|---------------------------------------|
| | CAPE. | AMERICA. | | |
| BATTLESHIPS . . . | Monarch (<i>In reserve</i> , Capetown) | | | Massachusetts Kearsarge Alabama |
| COAST-DEFENCE SHIPS | .. | Hotspur (<i>In reserve</i> , Bermuda) | | |
| 1st-CL. CRUISERS . . | .. | Crescent | | |
| 2nd-CL. CRUISERS . . | Gibraltar Forte Thetis* Sappho* Terpsichore | Indefatigable Flora† Tribune Charybdis | Cécille Suchet Isly | Chicago |
| 3rd-CL. CRUISERS . . | Magicienne Philomel Barracouta Barrosa Tartar | Pallas Proserpine Psyche | | Atalanta |
| SLOOPs and 1st-CL. GUNBOATS . . . | 6 | 4 | 2 | 3 |
| DESTROYER . . . | | 2 | | |

* Temporarily detached from the Channel and South-East Coast of American stations.

† To be relieved by Cambrian.

The Russian Naval Commander-in-Chief is Vice-Admiral Alexieff, who is also Military Governor, while Vice-Admiral Shrydloff is in command of the Pacific forces.

The French squadron was strengthened by the addition of the reconstructed battleship *Redoutable*, the armoured cruisers *Amiral Charner* and *Vauban*, and the protected cruiser *Guichen*, while the number of second-class cruisers was brought up to six. The *D'Entrecasteaux*, which had been flagship of Rear-Admiral Courrejolles, has, however, returned to Toulon to undergo some modifications. The Italians have also maintained a considerable force in Chinese waters, being the Ocean Division, with the exception of the *Dogali*, comprising the armoured cruiser *Vettor Pisani* (flagship of Rear-Admiral Candiani), and the *Fieramosca*, *Stromboli*, *Vesuvio*, *Elba*, and *Calabria*. Austria has likewise been well represented.

France.
Italy.
Austria.

The decreased tension of affairs in South Africa has enabled several cruisers detached from other stations to return. The Gibraltar relieves the *Doris* as flagship of Rear-Admiral A. W. Moore, who succeeds Sir Robert Harris in the command of the station.

Cape of
Good
Hope.

The following table of ships in commission in the Pacific calls for no comment :—

SHIPS IN COMMISSION. PACIFIC.

| CLASS. | BRITISH. | | UNITED STATES. |
|----------------------------------|---|--------------------------------|----------------|
| | AUSTRALIAN STATION. | PACIFIC STATION. | |
| BATTLESHIP . . | .. | .. | Iowa |
| 1st-CL. CRUISERS . | Royal Arthur | Warspite | .. |
| 2nd-CL. CRUISERS . | .. | Arethusa Leander Phaeton | Philadelphia |
| 3rd-CL. CRUISERS . | Katoomba (Sydney re- Mildura serves). Ringarooma Tauranga Wallaroo Mohawk Porpoise Pylades | .. | Marblehead |
| SLOOPs and GUN- BOATS | 3 | 2 | 2 |
| TORPEDO-GUNBOATS | 1 | .. | .. |
| DESTROYER | .. | 1 | .. |

The French have the second-class cruiser *Protet* and 2 sloops, and the Germans two small cruisers, in commission in the Pacific.

Compara-
tive
strength.

In regard to the important question of comparative strength, the present writer has not introduced many modifications into the tables which follow. Certain vessels which last year appeared as third-class battleships have been deemed unworthy to retain their place in that comparatively unimportant list, and are included among coast-defence ships, and it is evident that other ships in the same category must soon receive the same treatment. A number of old and useless vessels have been eliminated from the coast-defence list, and it has been thought unnecessary to retain the distinction between coastguard and harbour-defence ships. In the lists of new vessels, both battleships and cruisers, the new ships have been included, and the fact that many of them are still unfinished is indicated by the names being printed in italics. It is believed that no ship has been included in these lists that has not been laid down, or that is not actually provided for, to be at once put in hand, and the programme ships are indicated in footnotes.

First-class
battle-
ships.
Great
Britain,
France,
Russia.

From the list of first-class battleships given on p. 80, it will be seen that our situation is generally satisfactory in regard to numbers. It includes, in effect, thirty-eight vessels, while three more are in the programme of 1901-2, as compared with thirteen ships for France and fourteen for Russia, making twenty-seven in all. It will be observed that not less than fourteen out of our thirty-eight ships are still uncompleted, though some should soon be ready for the pennant, in comparison with eleven uncompleted ships in the case of the Powers of the Dual Alliance. The question of retarded construction is fully dealt with in another chapter in this volume. It may also be pointed out that France and Russia have lost their lead as the great foreign ship-building Powers, and that Germany and the United States are taking their place. Most friendly relations happily exist between Great Britain and these two Powers, but it should not, nevertheless, be lost sight of that, contrasted with their combined strength, our situation does not appear in a light so decidedly favourable, while the vigorous shipbuilding policy adopted by these Powers promises most rapid expansion. As an indication of this promise and of the recent character of the development, it will be instructive to note that while of battleships actually on the stocks or just about to be commenced, we have four, Germany and the United States have six and eight respectively.

Germany.
United
States.

Second-
class
battle-
ships.

It is not enough, however, to consider first-class battleships only; the list of second-class ships is instructive. It includes eleven British ships and twenty French and Russian, while, of the ten French vessels, nine have recently been or are now being reconstructed, receiving new armament and new machinery, and the tenth is a new

ship just on the point of completion. Moreover, three of the Russian ships are quite modern; only two of the British ships can be so described.

Turning now to the cruiser list, we find that we have forty-three Cruisers. of the first-class built and building, as compared with thirty-two in the case of France and Russia. This would seem encouraging, but many of our vessels have been delayed; and, looking to the whole cruiser class and realizing the great demand for such vessels in time of war, it cannot be said that the position is yet satisfactory. Indeed during the last ten years, the Powers of the Dual Alliance have begun almost as many cruisers as ourselves. In reckoning cruiser needs we have, however, to consider rather the vast demands of the fleet than the lists of other Powers.

There is a difficulty in estimating the comparative naval strength Estimated strength. at the close of the present year, but the following statement is probably accurate in regard to completed battleships:—

| Battleships. | ENGLAND. | FRANCE. | RUSSIA. | FRANCE AND RUSSIA. |
|--------------|----------|---------|---------|-----------------------|
| First-class | 26 | 10 | 8 | 18 |
| Second-class | 11 | 10 | 10 | 20 |
| Third-class | 10 | 11 | 1 | 12 |
| Total . . . | 47 | 31 | 19 | 50 |

It may therefore be concluded that we shall have a distinct superiority in completed first-class battleships over the Dual Alliance, but that, in view of the modernizing of the second-class battleships of France, the practical equality of numbers in the first two classes possessed by England on the one hand and France and Russia on the other, is not reassuring, and that the need is urgent for pushing forward the ships in course of construction.

JOHN LEYLAND.

Comparative Tables of British, French, Russian, Italian, German, United States, and Japanese Ships.

TABLE I.—FIRST-CLASS BATTLESHIPS.

| GREAT BRITAIN. | | | FRANCE. | | | RUSSIA. | | | ITALY. | | | GERMANY. | | | UNITED STATES. | | | JAPAN. | | |
|----------------|------------------|---------------|------------|----------------|---------------|-----------|--------------------|---------------|-----------|-----------------|---------------|-----------|-----------------|---------------|----------------|---------------|---------------|-----------|------------|---------------|
| Launched. | Name. | Displacement. | Launched. | Name. | Displacement. | Launched. | Name. | Displacement. | Launched. | Name. | Displacement. | Launched. | Name. | Displacement. | Launched. | Name. | Displacement. | Launched. | Name. | Displacement. |
| 1891 | Empress of India | 12,320 | 1891 | Brennus | 11,335 | 1892 | Tri Sviatitelia... | 12,480 | 1888 | Re Umberto | 13,825 | 1891 | Brandenburg | 11,000 | 1893 | Indiana | 11,526 | 1896 | Fuji | 12,320 |
| 1891 | Hood | 12,008 | 1894 | Carnot | 11,880 | 1900 | Kniaz Potem- | 12,480 | 1899 | Sardagna | 13,860 | 1891 | Kurfürst Fried- | 11,000 | 1893 | Massachusetts | 10,288 | 1896 | Yashima | 15,000 |
| 1892 | Ramilles | 11,824 | 1893 | Charles Martel | 11,824 | | kine Tavit- | | 1891 | Stella | 13,375 | 1891 | Rich Wilhelm | | 1893 | Oregon | 11,340 | 1899 | Asahi | 14,850 |
| 1892 | Republie | 14,150 | 1893 | Jauréguiberry | 11,824 | | chey | | 1897 | E. Filiberto | 9,800 | 1891 | Weissenburg | | 1896 | Iowa | 11,565 | 1899 | Hatsue | 15,200 |
| 1892 | Resolution | 11,824 | 1895 | Massena | 12,290 | 1894 | Petropavlovsk... | 10,360 | 1897 | Son Bon | 12,427 | 1892 | Wörth | | 1898 | Kearsarge | | 1898 | Shikishima | |
| 1892 | Revenge | 11,824 | 1896 | Bouvet | 12,290 | 1894 | Pollava | 10,360 | 1897 | Re Margherita | 12,427 | 1896 | Kaiser Fried- | | 1898 | Kentucky | | 1898 | Mikasa | |
| 1892 | Royal Oak | 11,824 | 1896 | Charlemagne | 12,290 | 1894 | Sevastopol | 10,360 | 1897 | Enedetto Brin | 12,427 | 1896 | rich III. | | 1898 | Alabama | | | | |
| 1891 | Royal Sovereign | 12,350 | 1896 | Gaulois | 11,275 | 1898 | Peresviet | 12,674 | 1897 | Re Elena | 12,624 | 1897 | Kaiser Wilhelm | | 1898 | Illinois | | | | |
| 1895 | Renown | 12,350 | 1898 | St. Louis | 12,052 | 1900 | Osliava | 12,674 | 1897 | Emmanuele III. | 12,624 | 1899 | der Grösse | | 1898 | Wisconsin | | | | |
| 1895 | Majestic | 12,350 | 1898 | Iona | 12,052 | 1900 | Poltava | 12,700 | 1899 | Kaiser Wilhelm | 12,624 | 1899 | Kaiser Wilhelm | | 1898 | Maine | | | | |
| 1895 | Prince George | 12,350 | 1899 | Suffren | 12,728 | 1900 | Revanon | 12,700 | 1899 | der Grösse | 12,624 | 1900 | Kaiser Barba- | | 1898 | Missouri | | | | |
| 1895 | Victorious | 14,900 | 2 A S A 10 | | 14,863 | 1901 | Csaravitch | 13,110 | 1900 | Kaiser Barba- | 12,624 | 1900 | rossa | | 1898 | Ohio | | | | |
| 1896 | Cesar | 14,900 | | | | | Alexander III. | 13,000 | 1899 | Kaiser Karl der | 12,624 | 1899 | Kaiser Karl der | | 1898 | New Jersey | | | | |
| 1896 | Hannibal | 14,900 | | | | | Borodino | 13,000 | 1899 | Wittelsbach | 12,624 | 1899 | Kaiser Karl der | | 1898 | Georgia | | | | |
| 1896 | Illustratus | 14,900 | | | | | Orel | 13,000 | 1900 | D | 12,624 | 1900 | Wittelsbach | | 1898 | Virginia | | | | |
| 1896 | Jupiter | 14,900 | | | | | Kniaz Souveroff | 13,000 | 1900 | E | 12,624 | 1900 | Wittelsbach | | 1898 | Nebraska | | | | |
| 1896 | Mars | 14,900 | | | | | | | 1900 | F | 12,624 | 1900 | Wittelsbach | | 1898 | Rhode Island | | | | |
| 1897 | Canopus | 14,900 | | | | | | | 1900 | G | 12,624 | 1900 | Wittelsbach | | 1898 | | | | | |
| 1899 | Glory | 12,950 | | | | | | | 1900 | H | 12,624 | 1900 | Wittelsbach | | 1898 | | | | | |
| 1898 | Albat | 12,950 | | | | | | | 1900 | I | 12,624 | 1900 | Wittelsbach | | 1898 | | | | | |
| 1898 | Goliath | 12,950 | | | | | | | 1900 | J | 12,624 | 1900 | Wittelsbach | | 1898 | | | | | |
| 1898 | Ocean | 12,950 | | | | | | | 1900 | | 12,624 | 1900 | Wittelsbach | | 1898 | | | | | |
| 1899 | Vengeance | 15,000 | | | | | | | 1900 | | 12,624 | 1900 | Wittelsbach | | 1898 | | | | | |
| 1898 | Formidable | 15,000 | | | | | | | 1900 | | 12,624 | 1900 | Wittelsbach | | 1898 | | | | | |
| 1898 | Invincible | 15,000 | | | | | | | 1900 | | 12,624 | 1900 | Wittelsbach | | 1898 | | | | | |
| 1899 | Impacable | 15,000 | | | | | | | 1900 | | 12,624 | 1900 | Wittelsbach | | 1898 | | | | | |
| 1899 | London | 15,000 | | | | | | | 1900 | | 12,624 | 1900 | Wittelsbach | | 1898 | | | | | |
| 1899 | Venerable | 15,000 | | | | | | | 1900 | | 12,624 | 1900 | Wittelsbach | | 1898 | | | | | |
| 1899 | Buteark | 15,000 | | | | | | | 1900 | | 12,624 | 1900 | Wittelsbach | | 1898 | | | | | |
| 1899 | Cornwallis | 15,000 | | | | | | | 1900 | | 12,624 | 1900 | Wittelsbach | | 1898 | | | | | |
| 1901 | Duncan | 14,000 | | | | | | | 1901 | | 12,624 | 1901 | Wittelsbach | | 1898 | | | | | |
| 1901 | Lexmonth | 14,000 | | | | | | | 1901 | | 12,624 | 1901 | Wittelsbach | | 1898 | | | | | |
| 1901 | Russell | 14,000 | | | | | | | 1901 | | 12,624 | 1901 | Wittelsbach | | 1898 | | | | | |
| 1901 | Albemarle | 14,000 | | | | | | | 1901 | | 12,624 | 1901 | Wittelsbach | | 1898 | | | | | |
| 1901 | Montagu | 14,000 | | | | | | | 1901 | | 12,624 | 1901 | Wittelsbach | | 1898 | | | | | |
| 1901 | Queen | 15,000 | | | | | | | 1901 | | 12,624 | 1901 | Wittelsbach | | 1898 | | | | | |
| 1901 | Prince of Wales | 15,000 | | | | | | | 1901 | | 12,624 | 1901 | Wittelsbach | | 1898 | | | | | |

* 3 projected.

† 1 projected.

‡ 2 projected.

38 ships.*

13 ships.

14 ships.

9 ships.†

16 ships.

17 ships.‡

6 ships.

TABLE II.—SECOND-CLASS BATTLESHIPS.

| GREAT BRITAIN. | | | FRANCE. | | | RUSSIA. | | | ITALY. | | | GERMANY. | | | UNITED STATES. | | | JAPAN. | | |
|----------------|-----------------|------------------------|-----------|-----------------|------------------------|-----------|----------------------------|------------------------|-----------|------------------|------------------------|-----------|-------|---------------|----------------|-------|---------------|-----------|-------|---------------|
| Launched. | Name. | Displacement. tons. | Launched. | Name. | Displacement. tons. | Launched. | Name. | Displacement. tons. | Launched. | Name. | Displacement. tons. | Launched. | Name. | Displacement. | Launched. | Name. | Displacement. | Launched. | Name. | Displacement. |
| 1888 | Nile ... | 11,940 | 1883 | Baudin ... | 11,911 | 1892 | (Georgi Pobiedonosetz ...) | 10,280 | 1880 | Italia ... | 14,387 | | | | | | | | | |
| 1887 | Trafalgar ... | 11,940 | 1879 | Duperré ... | 11,209 | 1891 | Navarin ... | 10,206 | 1883 | Lepanto ... | 14,400 | | | | | | | | | |
| 1886 | Anson ... | 10,600 | 1881 | Courbet ... | 10,808 | 1886 | Catherine II ... | | 1885 | Andrea Doria ... | | | | | | | | | | |
| 1885 | Benbow ... | 10,600 | 1879 | Dévastation ... | 10,704 | 1887 | Sinope ... | 10,181 | 1884 | Lauria ... | 11,000 | | | | | | | | | |
| 1885 | Camperdown ... | 10,600 | 1885 | Formidable ... | 12,165 | 1886 | Tchesmé ... | | 1885 | Morsini ... | | | | | | | | | | |
| 1882 | Collingwood ... | 9,500 | 1886 | Hoche ... | 10,997 | 1894 | Sissoi Veliky ... | 8,880 | | | | | | | | | | | | |
| 1885 | Howe ... | 10,300 | 1890 | Magenta ... | 10,851 | 1896 | Rostislav ... | | | | | | | | | | | | | |
| 1884 | Rodney ... | 10,300 | 1887 | Marceau ... | 10,350 | 1889 | Nicolai I ... | 9,672 | | | | | | | | | | | | |
| 1887 | Sas Pareil ... | 10,470 | 1887 | Neptune ... | 10,983 | 1887 | Alexander II ... | 9,927 | | | | | | | | | | | | |
| 1893 | Barfleur ... | 10,500 | 1899 | Henri IV ... | 8,948 | 1890 | (Drenadzat Apostoloff ...) | 8,076 | | | | | | | | | | | | |
| 1892 | Centurion ... | 10,500 | | | | | | | | | | | | | | | | | | |
| 11 ships. | | | 10 ships. | | | 10 ships. | | | 5 ships. | | | | | | | | | | | |

TABLE III.—THIRD-CLASS BATTLESHIPS.

| GREAT BRITAIN. | | | FRANCE. | | | RUSSIA. | | | ITALY. | | | GERMANY. | | | UNITED STATES. | | | JAPAN. | | |
|----------------|-----------------|------------------------|-----------|-----------------|------------------------|-----------|------------------|------------------------|-----------|-----------------|------------------------|-----------|-------------|------------------------|----------------|-----------|------------------------|-----------|--------------|------------------------|
| Launched. | Name. | Displacement. tons. | Launched. | Name. | Displacement. tons. | Launched. | Name. | Displacement. tons. | Launched. | Name. | Displacement. tons. | Launched. | Name. | Displacement. tons. | Launched. | Name. | Displacement. tons. | Launched. | Name. | Displacement. tons. |
| 1875 | Alexandra | 9,490 | 1873 | Friedland... | 8,994 | 1872 | Peter Veliky ... | 9,891 | 1878 | Dandolo ... | 11,202 | 1880 | Baden ... | ... | 1892 | Texas ... | 6,315 | 1882 | Chin Yen ... | 7,400 |
| 1882 | Colossus ... | 9,420 | 1876 | Redoutable ... | 9,437 | 1876 | Dulko ... | 10,138 | 1878 | Bayern ... | 7,441 | 1877 | Sachsen ... | ... | ... | ... | ... | ... | ... | ... |
| 1882 | Edinburgh ... | 9,330 | 1885 | Caïman ... | 7,239 | 1878 | Württemberg... | ... | 1874 | Deutschland ... | 7,319 | 1874 | Kaiser ... | ... | ... | ... | ... | ... | ... | ... |
| 1871 | Devastation ... | 7,234 | 1883 | Indomptable ... | 7,234 | 1874 | Oldenburg ... | 5,200 | 1874 | Oldenburg ... | 5,200 | ... | ... | ... | ... | ... | ... | ... | ... | ... |
| 1872 | Thunderer ... | 7,822 | 1885 | Requin ... | 7,822 | ... | ... | ... | ... | ... | ... | ... | ... | ... | ... | ... | ... | ... | ... | ... |
| 1875 | Dreadnought ... | 10,820 | 1881 | Terrible ... | 7,575 | ... | ... | ... | ... | ... | ... | ... | ... | ... | ... | ... | ... | ... | ... | ... |
| 1876 | Inflexible... | 11,880 | 1879 | Vauban ... | 6,208 | ... | ... | ... | ... | ... | ... | ... | ... | ... | ... | ... | ... | ... | ... | ... |
| 1870 | Sultan ... | 9,290 | 1892 | Bouvines ... | 6,010 | ... | ... | ... | ... | ... | ... | ... | ... | ... | ... | ... | ... | ... | ... | ... |
| 1875 | Superb ... | 9,170 | 1893 | Trehouart... | 6,629 | ... | ... | ... | ... | ... | ... | ... | ... | ... | ... | ... | ... | ... | ... | ... |
| 1876 | Temeraire ... | 8,540 | 1892 | Jennapes ... | 6,592 | ... | ... | ... | ... | ... | ... | ... | ... | ... | ... | ... | ... | ... | ... | ... |
| ... | ... | ... | 1892 | Valmy ... | 6,592 | ... | ... | ... | ... | ... | ... | ... | ... | ... | ... | ... | ... | ... | ... | ... |
| 10 ships. | | | 11 ships. | | | 1 ship. | | | 2 ships. | | | 7 ships. | | | 1 ship. | | | 1 ship. | | |

TABLE IV.—FIRST-CLASS CRUISERS.

| GREAT BRITAIN. | | | FRANCE. | | | RUSSIA. | | | ITALY. | | | GERMANY. | | | UNITED STATES. | | | JAPAN. | | |
|----------------|--------------|---------------|---------|-----------------|---------------|---------|--------------|---------------|--------|--------------------|---------------|----------|------------------|---------------|----------------|---------------|---------------|--------|--------|---------------|
| Speed. | Name. | Displacement. | Speed. | Name. | Displacement. | Speed. | Name. | Displacement. | Speed. | Name. | Displacement. | Speed. | Name. | Displacement. | Speed. | Name. | Displacement. | Speed. | Name. | Displacement. |
| 16 | Impérieuse | 8,400 | 20 | Dupuy de Lôme | 6,406 | 16½ | Admiral | 8,524 | 20 | Carlo Alberto | 6,386 | 21 | Kaiserin Augusta | 6,231 | 21-9 | Brooklyn | 9,215 | 21 | Asama | 9,750 |
| 16 | Warspite | 8,114 | 19 | D'Entrecasteaux | 8,114 | 18 | Nabimoff | 8,524 | 20 | Vettor Pisani | 6,386 | 21 | Fürst Bismarck | 10,650 | 21 | New York | 8,200 | 21½ | Tokiwa | 9,750 |
| 21½ | Blake | 9,000 | 23 | Guichen | 8,277 | 18 | Pamyat Azova | 6,675 | 20 | Giuseppe Garibaldi | 7,282 | 19 | Prinz Heinrich | 10,650 | 22-8 | Columbia | 7,375 | 21 | Azuma | 9,436 |
| 21½ | Blenheim | 9,000 | 23 | Joanne d'Arc | 11,329 | 18 | Rurik | 10,933 | 20 | Varese | 7,282 | 20½ | B. Wilhelm | 8,868 | 23 | Minneapolis | 7,375 | 21 | Yakumo | 9,850 |
| 19½ | Gresnet | 7,700 | 23 | Châteaurenault | 8,018 | 20 | Rossii | 12,130 | 20 | F. Ferruccio | 7,282 | 20½ | K. Ersatz (G) | 8,868 | 22 | West Virginia | 9,850 | 21 | Izumo | 9,750 |
| 20 | Edgar | 7,350 | 21 | Dupetit Thouars | 9,517 | 20 | Aurora | 6,630 | 20 | | | 20½ | Ersatz (G) | 8,868 | 22 | California | 13,880 | 21 | Iwate | 9,750 |
| 20 | Endymion | 7,350 | 21 | Guédon | 9,517 | 20 | Diana | 6,630 | 20 | | | 20½ | K. Ersatz (G) | 8,868 | 22 | Pennsylvania | 13,880 | 21 | | |
| 19½ | Gibraltar | 7,700 | 21 | Montcalm | 10,000 | 20 | Palлада | 6,630 | 20 | | | 20½ | K. Ersatz (G) | 8,868 | 22 | Colorado | 13,880 | 21 | | |
| 20 | Grafton | 7,350 | 21 | Sully | 10,000 | 20 | Gromobol | 12,236 | 20 | | | 20½ | K. Ersatz (G) | 8,868 | 22 | Maryland | 13,880 | 21 | | |
| 20 | Hawke | 7,350 | 21 | Glacé | 10,000 | 21 | Bayan | 7,800 | 20 | | | 20½ | K. Ersatz (G) | 8,868 | 22 | South Dakota | 13,880 | 21 | | |
| 19½ | Royal Arthur | 7,700 | 21 | Desaix | 7,700 | 23 | Askold | 7,800 | 20 | | | 20½ | K. Ersatz (G) | 8,868 | 22 | St. Louis | 9,700 | 21 | | |
| 19½ | St. George | 7,700 | 21 | Dupleix | 7,700 | 23 | Pogotyr | 6,500 | 20 | | | 20½ | K. Ersatz (G) | 8,868 | 22 | Charleston | 9,700 | 21 | | |
| 20 | Theeues | 7,350 | 21 | Klober | 7,700 | 23 | Varyag | 6,500 | 20 | | | 20½ | K. Ersatz (G) | 8,868 | 22 | Milwaukee | 9,700 | 21 | | |
| 22 | Powerful | 14,200 | 21 | Marseillaise | 10,014 | 23 | Unamed | 6,375 | 20 | | | 20½ | K. Ersatz (G) | 8,868 | 22 | | | 21 | | |
| 22 | Terrible | 14,200 | 21 | Amiral Aube | 10,014 | 23 | Unamed | 6,375 | 20 | | | 20½ | K. Ersatz (G) | 8,868 | 22 | | | 21 | | |
| 20½ | Andromeda | 11,000 | 21 | León Gambetta | 12,416 | 23 | Unamed | 6,375 | 20 | | | 20½ | K. Ersatz (G) | 8,868 | 22 | | | 21 | | |
| 20½ | Diadem | 11,000 | 21 | Jules Ferry | 12,416 | 23 | Unamed | 6,375 | 20 | | | 20½ | K. Ersatz (G) | 8,868 | 22 | | | 21 | | |
| 20½ | Europe | 11,000 | 21 | Victor Hugo | 12,416 | 23 | Unamed | 6,375 | 20 | | | 20½ | K. Ersatz (G) | 8,868 | 22 | | | 21 | | |
| 20½ | Niobe | 11,000 | 21 | | | 23 | Unamed | 6,375 | 20 | | | 20½ | K. Ersatz (G) | 8,868 | 22 | | | 21 | | |
| 20½ | Amphitrite | 11,000 | 21 | | | 23 | Unamed | 6,375 | 20 | | | 20½ | K. Ersatz (G) | 8,868 | 22 | | | 21 | | |
| 20½ | Ariadne | 11,000 | 21 | | | 23 | Unamed | 6,375 | 20 | | | 20½ | K. Ersatz (G) | 8,868 | 22 | | | 21 | | |
| 20½ | Spartiate | 11,000 | 21 | | | 23 | Unamed | 6,375 | 20 | | | 20½ | K. Ersatz (G) | 8,868 | 22 | | | 21 | | |
| 21 | Aboukir | 12,000 | 21 | | | 23 | Unamed | 6,375 | 20 | | | 20½ | K. Ersatz (G) | 8,868 | 22 | | | 21 | | |
| 21 | Cressy | 12,000 | 21 | | | 23 | Unamed | 6,375 | 20 | | | 20½ | K. Ersatz (G) | 8,868 | 22 | | | 21 | | |
| 21 | Hogue | 12,000 | 21 | | | 23 | Unamed | 6,375 | 20 | | | 20½ | K. Ersatz (G) | 8,868 | 22 | | | 21 | | |
| 21 | Sutlej | 12,000 | 21 | | | 23 | Unamed | 6,375 | 20 | | | 20½ | K. Ersatz (G) | 8,868 | 22 | | | 21 | | |
| 21 | Everatus | 12,000 | 21 | | | 23 | Unamed | 6,375 | 20 | | | 20½ | K. Ersatz (G) | 8,868 | 22 | | | 21 | | |
| 21 | Bacchante | 12,000 | 21 | | | 23 | Unamed | 6,375 | 20 | | | 20½ | K. Ersatz (G) | 8,868 | 22 | | | 21 | | |
| 23 | Drake | 14,100 | 23 | | | 23 | Unamed | 6,375 | 20 | | | 20½ | K. Ersatz (G) | 8,868 | 22 | | | 21 | | |
| 23 | Good Hope | 14,100 | 23 | | | 23 | Unamed | 6,375 | 20 | | | 20½ | K. Ersatz (G) | 8,868 | 22 | | | 21 | | |
| 23 | King Alfred | 14,100 | 23 | | | 23 | Unamed | 6,375 | 20 | | | 20½ | K. Ersatz (G) | 8,868 | 22 | | | 21 | | |
| 23 | Leviathan | 14,100 | 23 | | | 23 | Unamed | 6,375 | 20 | | | 20½ | K. Ersatz (G) | 8,868 | 22 | | | 21 | | |
| 23 | Monmouth | 14,100 | 23 | | | 23 | Unamed | 6,375 | 20 | | | 20½ | K. Ersatz (G) | 8,868 | 22 | | | 21 | | |
| 23 | Kent | 14,100 | 23 | | | 23 | Unamed | 6,375 | 20 | | | 20½ | K. Ersatz (G) | 8,868 | 22 | | | 21 | | |
| 23 | Bellford | 14,100 | 23 | | | 23 | Unamed | 6,375 | 20 | | | 20½ | K. Ersatz (G) | 8,868 | 22 | | | 21 | | |
| 23 | Essex | 14,100 | 23 | | | 23 | Unamed | 6,375 | 20 | | | 20½ | K. Ersatz (G) | 8,868 | 22 | | | 21 | | |
| 23 | Barnard | 14,100 | 23 | | | 23 | Unamed | 6,375 | 20 | | | 20½ | K. Ersatz (G) | 8,868 | 22 | | | 21 | | |
| 23 | Cornwall | 14,100 | 23 | | | 23 | Unamed | 6,375 | 20 | | | 20½ | K. Ersatz (G) | 8,868 | 22 | | | 21 | | |
| 23 | Cumberland | 14,100 | 23 | | | 23 | Unamed | 6,375 | 20 | | | 20½ | K. Ersatz (G) | 8,868 | 22 | | | 21 | | |
| 23 | Donegal | 14,100 | 23 | | | 23 | Unamed | 6,375 | 20 | | | 20½ | K. Ersatz (G) | 8,868 | 22 | | | 21 | | |
| 23 | Lancaster | 14,100 | 23 | | | 23 | Unamed | 6,375 | 20 | | | 20½ | K. Ersatz (G) | 8,868 | 22 | | | 21 | | |
| 23 | Suffolk | 14,100 | 23 | | | 23 | Unamed | 6,375 | 20 | | | 20½ | K. Ersatz (G) | 8,868 | 22 | | | 21 | | |
| 23 | 43 ships.* | | 23 | | | 23 | Unamed | 6,375 | 20 | | | 20½ | K. Ersatz (G) | 8,868 | 22 | | | 21 | | |

* 6 projected.

† 4 projected.

‡ 3 projected.

|| 1 projected.

§ 2 projected.

6 ships.

5 ships.

5 ships.

13 ships.†

19 ships.†

43 ships.*

G 12

TABLE V.—SECOND-CLASS CRUISERS.

| GREAT BRITAIN. | | | FRANCE. | | | RUSSIA. | | | ITALY. | | | GERMANY. | | | UNITED STATES. | | | JAPAN. | | |
|----------------|-------------------|---------------|---------|---------------------------|---------------|---------|-----------------------|---------------|--------|--------------------|---------------|----------|------------------------------|---------------|----------------|--------------------------|---------------|--------|-----------------|---------------|
| Speed. | Name. | Displacement. | Speed. | Name. | Displacement. | Speed. | Name. | Displacement. | Speed. | Name. | Displacement. | Speed. | Name. | Displacement. | Speed. | Name. | Displacement. | Speed. | Name. | Displacement. |
| 16 | Aurora ... | tons. | kts. | Bruk ... | tons. | kts. | Dimitri Donskoi ... | tons. | kts. | Marco Polo ... | tons. | kts. | Geflon ... | tons. | kts. | Albany ... | tons. | kts. | Hashidate ... | tons. |
| 16 | Anstralia ... | 4,754 | 18 | Chauzy ... | 4,933 | 19 | Vladimir Monomach ... | 5,882 | 20 | Vesuvio ... | 4,597 | 20 | Irene... (Prinzess Wilhelme) | 4,207 | 20 | Baltimore... Chicago ... | 4,413 | 17 | Itsukushima ... | 4,277 |
| 16 | Galatea ... | 4,792 | 18 | Charner ... | 4,792 | 14 | Minin ... | 6,061 | 18 | Etna ... | 3,474 | 19 | Freya ... | 4,400 | 18 | Newark ... | 4,500 | 17 | Matsumama ... | 3,700 |
| 16 | Immortalité ... | 5,600 | 18 | Latouche Tréville ... | 4,756 | 15 | Gervoz ... | 6,136 | 17 | Fieramosca ... | 3,542 | 21 | Hausa ... | 5,650 | 20 | New Orleans ... | 4,098 | 18 | Naniwa ... | 3,700 |
| 16 | Narcissus ... | 5,360 | 19 | Pothuan ... | 5,360 | 14 | Edinburgski ... | 5,050 | 19 | Stromboli ... | 3,420 | 21 | Hertha ... | 5,650 | 21 | Olympia ... | 5,800 | 22 | Chitose ... | 4,760 |
| 16 | Orlando ... | 5,933 | 19 | Cécile ... | 5,933 | 14 | General Admiral ... | 4,722 | 21 | Victoria Luise ... | 5,650 | 21 | Hertha ... | 5,650 | 19 | Philadelphia ... | 4,324 | 22 | Kasagi ... | 4,160 |
| 17 | Undaunted ... | 7,589 | 19 | Tage ... | 7,589 | 17 | Korniloff ... | 5,817 | 21 | Vineta ... | 5,817 | 19 | Raleigh ... | 4,098 | 19 | Cincinnati ... | 3,213 | 23 | Takasago ... | 4,180 |
| 17 | Amphion ... | 4,332 | 19 | Alger ... | 4,332 | 20 | Sietiana ... | 3,823 | 21 | Stromboli ... | 3,823 | 19 | San Francisco ... | 4,098 | 19 | Baltimore ... | 4,098 | 23 | Yoshino ... | 4,160 |
| 17 | Arethusa ... | 4,300 | 19 | Isly ... | 4,477 | 20 | Isly ... | 4,477 | 20 | Stromboli ... | 3,823 | 19 | San Francisco ... | 4,098 | 19 | Baltimore ... | 4,098 | 23 | Yoshino ... | 4,160 |
| 17 | Leander ... | 4,109 | 19 | Jean Bart ... | 4,109 | 20 | Isly ... | 4,477 | 20 | Stromboli ... | 3,823 | 19 | San Francisco ... | 4,098 | 19 | Baltimore ... | 4,098 | 23 | Yoshino ... | 4,160 |
| 17 | Phaeton ... | 3,740 | 19 | Eugene ... | 3,740 | 20 | Isly ... | 4,477 | 20 | Stromboli ... | 3,823 | 19 | San Francisco ... | 4,098 | 19 | Baltimore ... | 4,098 | 23 | Yoshino ... | 4,160 |
| 17 | Forth ... | 3,753 | 19 | Chasseloup-Laubat ... | 3,753 | 20 | Isly ... | 4,477 | 20 | Stromboli ... | 3,823 | 19 | San Francisco ... | 4,098 | 19 | Baltimore ... | 4,098 | 23 | Yoshino ... | 4,160 |
| 17 | Mersey ... | 3,739 | 19 | Triant ... | 3,739 | 20 | Isly ... | 4,477 | 20 | Stromboli ... | 3,823 | 19 | San Francisco ... | 4,098 | 19 | Baltimore ... | 4,098 | 23 | Yoshino ... | 4,160 |
| 17 | Severn ... | 4,015 | 19 | Pascal ... | 4,015 | 20 | Isly ... | 4,477 | 20 | Stromboli ... | 3,823 | 19 | San Francisco ... | 4,098 | 19 | Baltimore ... | 4,098 | 23 | Yoshino ... | 4,160 |
| 17 | Thames ... | 3,990 | 19 | Descartes ... | 3,990 | 20 | Isly ... | 4,477 | 20 | Stromboli ... | 3,823 | 19 | San Francisco ... | 4,098 | 19 | Baltimore ... | 4,098 | 23 | Yoshino ... | 4,160 |
| 18 | Astrea ... | 4,728 | 17 | Sfax ... | 4,728 | 20 | Isly ... | 4,477 | 20 | Stromboli ... | 3,823 | 19 | San Francisco ... | 4,098 | 19 | Baltimore ... | 4,098 | 23 | Yoshino ... | 4,160 |
| 19 | Bonaventure ... | 3,440 | 20 | Suchet ... | 3,440 | 20 | Isly ... | 4,477 | 20 | Stromboli ... | 3,823 | 19 | San Francisco ... | 4,098 | 19 | Baltimore ... | 4,098 | 23 | Yoshino ... | 4,160 |
| 19 | Cambrian ... | 3,952 | 19 | D'Assas ... | 3,952 | 20 | Isly ... | 4,477 | 20 | Stromboli ... | 3,823 | 19 | San Francisco ... | 4,098 | 19 | Baltimore ... | 4,098 | 23 | Yoshino ... | 4,160 |
| 19 | Charybdis ... | 4,000 | 19 | Duchayla ... | 4,000 | 20 | Isly ... | 4,477 | 20 | Stromboli ... | 3,823 | 19 | San Francisco ... | 4,098 | 19 | Baltimore ... | 4,098 | 23 | Yoshino ... | 4,160 |
| 19 | Flora ... | 4,360 | 19 | Catinat ... | 4,055 | 20 | Isly ... | 4,477 | 20 | Stromboli ... | 3,823 | 19 | San Francisco ... | 4,098 | 19 | Baltimore ... | 4,098 | 23 | Yoshino ... | 4,160 |
| 19 | Forté ... | 4,000 | 19 | Protet ... | 4,055 | 20 | Isly ... | 4,477 | 20 | Stromboli ... | 3,823 | 19 | San Francisco ... | 4,098 | 19 | Baltimore ... | 4,098 | 23 | Yoshino ... | 4,160 |
| 19 | Fox ... | 4,055 | 19 | Jurien de la Gravière ... | 5,605 | 20 | Isly ... | 4,477 | 20 | Stromboli ... | 3,823 | 19 | San Francisco ... | 4,098 | 19 | Baltimore ... | 4,098 | 23 | Yoshino ... | 4,160 |
| 19 | Hermione ... | 4,055 | 19 | Jurien de la Gravière ... | 5,605 | 20 | Isly ... | 4,477 | 20 | Stromboli ... | 3,823 | 19 | San Francisco ... | 4,098 | 19 | Baltimore ... | 4,098 | 23 | Yoshino ... | 4,160 |
| 19 | Eolus ... | 3,600 | 23 | Jurien de la Gravière ... | 5,605 | 20 | Isly ... | 4,477 | 20 | Stromboli ... | 3,823 | 19 | San Francisco ... | 4,098 | 19 | Baltimore ... | 4,098 | 23 | Yoshino ... | 4,160 |
| 20 | Andromache ... | 3,400 | 23 | Jurien de la Gravière ... | 5,605 | 20 | Isly ... | 4,477 | 20 | Stromboli ... | 3,823 | 19 | San Francisco ... | 4,098 | 19 | Baltimore ... | 4,098 | 23 | Yoshino ... | 4,160 |
| 20 | Apollo ... | 3,400 | 23 | Jurien de la Gravière ... | 5,605 | 20 | Isly ... | 4,477 | 20 | Stromboli ... | 3,823 | 19 | San Francisco ... | 4,098 | 19 | Baltimore ... | 4,098 | 23 | Yoshino ... | 4,160 |
| 19 | Brilliant ... | 3,600 | 23 | Jurien de la Gravière ... | 5,605 | 20 | Isly ... | 4,477 | 20 | Stromboli ... | 3,823 | 19 | San Francisco ... | 4,098 | 19 | Baltimore ... | 4,098 | 23 | Yoshino ... | 4,160 |
| 19 | Indefatigable ... | 3,600 | 23 | Jurien de la Gravière ... | 5,605 | 20 | Isly ... | 4,477 | 20 | Stromboli ... | 3,823 | 19 | San Francisco ... | 4,098 | 19 | Baltimore ... | 4,098 | 23 | Yoshino ... | 4,160 |

| | | |
|----|-----------------|-------|
| 19 | Intrepid ... | 3,600 |
| 19 | Iphigénie ... | 3,600 |
| 20 | Latona ... | 3,400 |
| 20 | Melampus ... | 3,400 |
| 20 | Naiad ... | 3,400 |
| 19 | Pique ... | 3,600 |
| 19 | Rainbow ... | 3,600 |
| 19 | Retribution ... | 3,600 |
| 20 | Serphe ... | 3,400 |
| 20 | Scylla ... | 3,400 |
| 19 | Sirtus ... | 3,600 |
| 19 | Spartan ... | 3,600 |
| 20 | Sybilie ... | 3,400 |
| 20 | Terpsichore ... | 3,400 |
| 20 | Thetis ... | 3,400 |
| 20 | Tribune ... | 3,400 |
| 19 | Diana ... | 3,400 |
| 19 | Dido ... | 3,400 |
| 19 | Doris ... | 3,400 |
| 19 | Eclipse ... | 3,400 |
| 19 | Isis ... | 3,400 |
| 19 | June ... | 3,400 |
| 19 | Minerva ... | 3,400 |
| 19 | Talbot ... | 3,400 |
| 19 | Venus ... | 3,400 |
| 19 | Arrogant ... | 3,400 |
| 19 | Furious ... | 5,750 |
| 19 | Gladiator ... | 5,750 |
| 19 | Vindictive ... | 5,750 |
| 20 | Hermes ... | 5,750 |
| 20 | Highflyer ... | 5,600 |
| 20 | Hyacinth ... | 5,600 |
| 21 | Challenger ... | 5,600 |
| 21 | Encounter ... | 5,600 |

62 ships.

23 ships.

7 ships.

5 ships.

8 ships.

16 ships.

10 ships.

TABLE VI.—THIRD-CLASS CRUISERS.

| GREAT BRITAIN. | | | FRANCE. | | | RUSSIA. | | | ITALY. | | | GERMANY. | | | UNITED STATES. | | | JAPAN. | | |
|----------------|-----------------|---------------|-----------|---------------|---------------|----------|---------------|---------------|-----------|----------------|---------------|-----------|---------------|---------------|----------------|----------------|---------------|----------|--------------|---------------|
| Speed. | Name. | Displacement. | Speed. | Name. | Displacement. | Speed. | Name. | Displacement. | Speed. | Name. | Displacement. | Speed. | Name. | Displacement. | Speed. | Name. | Displacement. | Speed. | Name. | Displacement. |
| 18 | Iris ... | 3,730 | 18 | Milan ... | 1,733 | 15 | Rynda ... | 3,503 | 21 | Piemonte ... | 2,500 | 16 | Blitz ... | 1,360 | 16½ | Albatross ... | 3,000 | 20 | Akasu ... | 2,700 |
| 18 | Mercury ... | 1,932 | 19½ | Costlogon ... | 1,932 | 15½ | Panyat ... | 3,000 | 19 | Calabria ... | 3,508 | 16 | Prefi ... | 1,827 | 18½ | Boston ... | 3,150 | 19 | Akitsu ... | 2,950 |
| 16½ | Earless ... | 1,580 | 20½ | Osmao ... | 1,934 | 15½ | Merkuria ... | 3,000 | 19½ | Dogali ... | 2,055 | 16½ | Bussard ... | 1,827 | 18½ | Detroit ... | 2,950 | 18 | Izumi ... | 1,600 |
| 16½ | Scout ... | 1,580 | 20½ | Fortin ... | 1,820 | 25 | Xonik ... | 3,000 | 18 | Elba ... | 2,690 | 16 | Condor ... | 1,827 | 18½ | Marblehead ... | 2,089 | 20 | Yayeyama ... | 1,800 |
| 16½ | Archer ... | 1,580 | 20½ | Lalande ... | 1,926 | 25 | Bojavin ... | 3,000 | 17½ | Giovanni ... | 2,922 | 16 | Cormoran ... | 1,614 | 18½ | Monterey ... | 2,700 | 20 | Miyako ... | 1,800 |
| 16½ | Brisk ... | 1,580 | 20½ | Surcouf ... | 2,014 | 25 | Unanimité ... | 3,000 | 19 | Etruria ... | 2,245 | 16 | Geler ... | 1,703 | 18½ | See-Adler ... | 2,700 | 20 | Suna ... | 2,700 |
| 16½ | Cossack ... | 1,770 | 20½ | Troude ... | 2,026 | 25 | | | 21 | Lombardia ... | 2,245 | 16½ | See-Adler ... | 1,703 | 18½ | See-Adler ... | 2,700 | 20 | Suna ... | 2,700 |
| 16½ | Mohawk ... | 1,770 | 20 | Davout ... | 2,291 | 20 | | | 18 | Liguria ... | 2,550 | 16½ | See-Adler ... | 1,703 | 18½ | See-Adler ... | 2,700 | 20 | Suna ... | 2,700 |
| 16½ | Porpoise ... | 1,770 | 20 | Linois ... | 2,343 | 20 | | | 18 | Umbria ... | 2,550 | 16½ | See-Adler ... | 1,703 | 18½ | See-Adler ... | 2,700 | 20 | Suna ... | 2,700 |
| 16½ | Racon ... | 1,770 | 20 | Galilee ... | 2,317 | 20 | | | 20 | Puglia ... | 2,675 | 16½ | See-Adler ... | 1,703 | 18½ | See-Adler ... | 2,700 | 20 | Suna ... | 2,700 |
| 16½ | Tarar ... | 1,770 | 20 | Lavoisier ... | 2,317 | 20 | | | 16 | C. Colombo ... | 2,675 | 16½ | See-Adler ... | 1,703 | 18½ | See-Adler ... | 2,700 | 20 | Suna ... | 2,700 |
| 17 | Alacrity ... | 1,700 | 20½ | D'Estrees ... | 2,452 | 20½ | | | | | | | | | | | | | | |
| 17 | Surprise ... | 1,700 | 20½ | Infant ... | 2,452 | 20½ | | | | | | | | | | | | | | |
| 17½ | Barham ... | 1,820 | | | | | | | | | | | | | | | | | | |
| 17½ | Bellona ... | 1,820 | | | | | | | | | | | | | | | | | | |
| 16½ | Barraclough ... | 1,580 | | | | | | | | | | | | | | | | | | |
| 16½ | Barrosa ... | 1,580 | | | | | | | | | | | | | | | | | | |
| 16½ | Blanche ... | 1,580 | | | | | | | | | | | | | | | | | | |
| 16½ | Blonde ... | 1,580 | | | | | | | | | | | | | | | | | | |
| 19 | Magicienne ... | 2,950 | | | | | | | | | | | | | | | | | | |
| 19 | Marathon ... | 2,950 | | | | | | | | | | | | | | | | | | |
| 19 | Melpomene ... | 2,900 | | | | | | | | | | | | | | | | | | |
| 19 | Medea ... | 2,900 | | | | | | | | | | | | | | | | | | |
| 19 | Medusa ... | 2,900 | | | | | | | | | | | | | | | | | | |
| 19 | Pallas ... | 2,900 | | | | | | | | | | | | | | | | | | |
| 19 | Pearl ... | 2,900 | | | | | | | | | | | | | | | | | | |
| 19 | Philemel ... | 2,900 | | | | | | | | | | | | | | | | | | |
| 19 | Phebe ... | 2,900 | | | | | | | | | | | | | | | | | | |
| 19 | Katoomba ... | 2,575 | | | | | | | | | | | | | | | | | | |
| 19 | Mildura ... | 2,575 | | | | | | | | | | | | | | | | | | |
| 19 | Ringarooma ... | 2,575 | | | | | | | | | | | | | | | | | | |
| 19 | Tauranga ... | 2,575 | | | | | | | | | | | | | | | | | | |
| 19 | Wallaroo ... | 2,575 | | | | | | | | | | | | | | | | | | |
| 20½ | Pelorus ... | 2,135 | | | | | | | | | | | | | | | | | | |
| 20 | Proserpina ... | 2,135 | | | | | | | | | | | | | | | | | | |
| 20 | Pactolus ... | 2,135 | | | | | | | | | | | | | | | | | | |
| 20 | Pegasus ... | 2,135 | | | | | | | | | | | | | | | | | | |
| 20 | Persues ... | 2,135 | | | | | | | | | | | | | | | | | | |
| 20 | Pomone ... | 2,135 | | | | | | | | | | | | | | | | | | |
| 20 | Prometheus ... | 2,135 | | | | | | | | | | | | | | | | | | |
| 20 | Psyche ... | 2,135 | | | | | | | | | | | | | | | | | | |
| 20 | Pyramus ... | 2,200 | | | | | | | | | | | | | | | | | | |
| 20 | Pandora ... | 2,200 | | | | | | | | | | | | | | | | | | |
| 20 | Pioneer ... | 2,200 | | | | | | | | | | | | | | | | | | |
| 44 ships.* | | | 13 ships. | | | 5 ships. | | | 11 ships. | | | 18 ships. | | | 5 ships. | | | 6 ships. | | |

† Several others of this class are said to be included in the programme.

* 2 projected.

TABLE VII.—COASTGUARD AND HARBOUR DEFENCE SHIPS.

| GREAT BRITAIN. | | | FRANCE. | | | RUSSIA. | | | ITALY. | | | GERMANY. | | | UNITED STATES. | | | JAPAN. | | |
|----------------|-----------------|---------------|-----------|---------------|---------------|-----------|------------------------|---------------|-----------|-----------------|---------------|-----------|----------------|---------------|----------------|-----------------|---------------|-----------|-------------|---------------|
| Launched. | Name. | Displacement. | Launched. | Name. | Displacement. | Launched. | Name. | Displacement. | Launched. | Name. | Displacement. | Launched. | Name. | Displacement. | Launched. | Name. | Displacement. | Launched. | Name. | Displacement. |
| 1876 | Agamemnon ... | 8,660 | 1877 | Fulminant ... | 5,965 | 1894 | Adm. Senjavin ... | 4,126 | 1865 | Affondatore ... | 4,062 | 1890 | Beowulf ... | ... | 1883 | Amphitrite ... | ... | 1890 | Hei-Yen ... | ... |
| 1880 | Ajax ... | ... | 1883 | Furieux ... | 5,013 | 1893 | Adm. Onsiakoff ... | ... | 1863 | Maria Pia ... | 4,268 | 1891 | Frithjof ... | ... | 1876 | Miantonomoh ... | 3,990 | | | |
| 1865 | Bellerophon ... | 7,550 | 1876 | Tenpête ... | 4,869 | 1896 | Gen. Adm. Apraxine ... | 4,200 | 1863 | San Martino ... | ... | 1893 | Hagen ... | ... | 1883 | Monadnock ... | ... | | | |
| 1868 | Hercules ... | 8,680 | 1880 | Tonnant ... | 5,091 | | Adm. Boutakoff ... | 5,985 | | | | 1892 | Heimdall ... | ... | 1883 | Terror ... | ... | | | |
| 1868 | Monarch ... | 8,320 | 1875 | Tonnerre ... | 5,858 | 1868 | Adm. Chicagoff ... | 3,505 | | | | 1892 | Hildebrand ... | ... | 1891 | Monterey ... | 4,084 | | | |
| 1870 | Swiftsure ... | 6,910 | 1878 | Vengeur ... | 4,709 | 1867 | Adm. Greig ... | 3,462 | | | | 1889 | Siegfried ... | ... | 1884 | Puritan ... | 6,060 | | | |
| 1881 | Conqueror ... | 6,200 | 1885 | Achéron ... | 1,721 | 1868 | Adm. Lazareff ... | 3,462 | | | | 1895 | Aegir ... | ... | 1900 | Arkansas ... | ... | | | |
| 1885 | Hero ... | ... | 1887 | Cocyte ... | 1,714 | 1867 | Adm. Spiridoff ... | 3,500 | | | | 1894 | Odin ... | ... | 1900 | Nevada ... | 4,000 | | | |
| 1872 | Rupert ... | 5,440 | 1892 | Phalégton ... | 1,796 | 1864 | Charodelka ... | 2,026 | | | | 1878 | Basilik ... | ... | 1900 | Florida ... | ... | | | |
| 1870 | Abyssinia ... | 2,900 | 1892 | Skyx ... | 1,796 | 1875 | Kniaz Polarski ... | 5,138 | | | | 1876 | Biene ... | ... | 1900 | Wyoming ... | ... | | | |
| 1879 | Orion ... | 4,870 | 1885 | Flamme ... | 1,128 | 1873 | Popoff ... | 3,596 | | | | 1878 | Camaleon ... | ... | | | | | | |
| 1870 | Magdala ... | 3,340 | 1884 | Fusée ... | 1,142 | 1892 | Novgorod ... | 2,706 | | | | 1879 | Crocodil ... | ... | | | | | | |
| 1871 | Glatton ... | 4,910 | 1888 | Grenade ... | 1,089 | 1890 | Gremiastchy ... | 1,500 | | | | 1881 | Hummel ... | ... | | | | | | |
| 1871 | Cyclops ... | ... | 1886 | Mitraille ... | 1,128 | 1892 | Grostjastchy ... | 1,492 | | | | 1887 | Mucke ... | ... | | | | | | |
| 1871 | Gorgon ... | 3,560 | | | | 1895 | Otvazny ... | 1,500 | | | | 1880 | Natter ... | ... | | | | | | |
| 1871 | Hecate ... | ... | | | | 1898 | Khraby ... | 1,492 | | | | 1880 | Salamander ... | ... | | | | | | |
| 1870 | Holspur ... | 4,010 | | | | | | | | | | 1877 | Skorpion ... | ... | | | | | | |
| | | | | | | | | | | | | 1876 | Viper ... | ... | | | | | | |
| | | | | | | | | | | | | 1876 | Wespe ... | ... | | | | | | |
| 17 ships. | | | 14 ships. | | | 16 ships. | | | 3 ships. | | | 19 ships. | | | 10 ships. | | | 1 ship. | | |

TABLE VIII.—TORPEDO GUNBOATS.

| GREAT BRITAIN. | | | FRANCE. | | | RUSSIA. | | | ITALY. | | | GERMANY. | | | UNITED STATES. | | | JAPAN. | | |
|----------------|--------------|---------------|-----------|--------------|---------------|----------|-----------------|---------------|-----------|------------|---------------|----------|---------|---------------|----------------|---------|---------------|--------|---------|---------------|
| Speed. | Name. | Displacement. | Speed. | Name. | Displacement. | Speed. | Name. | Displacement. | Speed. | Name. | Displacement. | Speed. | Name. | Displacement. | Speed. | Name. | Displacement. | Speed. | Name. | Displacement. |
| kts. | | tons. | kts. | | tons. | kts. | | tons. | kts. | | tons. | kts. | | tons. | kts. | | | kts. | | tons. |
| 19 | Grasshopper | ... | 17½ | Condor | 1243 | 20 | Captain Sacken | 742 | 20 | Aretusa | 833 | 19 | Jagd... | 1230 | 21 | Tatsuta | 875 | 21 | Chitaya | 875 |
| 19 | Sandfly | 525 | 17 | Epervier | 1288 | 20 | Lieutenant Ilyn | 714 | 20 | Caladimi | 833 | 19 | Wacht | ... | 21 | ... | ... | ... | ... | ... |
| 19 | Spider | ... | 17½ | Faucon | 1239 | 22 | Gaidamak | ... | 21 | Capra | 833 | 22½ | Komet | 931 | 21 | ... | ... | ... | ... | ... |
| 18½ | Rattlesnake | 550 | 18 | Fleurbaey | 1310 | 22 | Vladimir | 400 | 17 | Confianza | 768 | 21 | Meteor | ... | 21 | ... | ... | ... | ... | ... |
| 20 | Assaye | ... | 17½ | Vautour | 1235 | 22 | Giden | ... | 20 | Euridice | 833 | 21 | ... | ... | 21 | ... | ... | ... | ... | ... |
| 20 | Boomerang | ... | 18½ | Wattignies | 1292 | 21 | Kazarsky | 462 | 19 | Goto | 812 | 21 | ... | ... | 21 | ... | ... | ... | ... | ... |
| 20 | Gleaner | ... | 18½ | Bombe | 420 | 22 | Posadnik | 448 | 19 | Irde | 833 | 21 | ... | ... | 21 | ... | ... | ... | ... | ... |
| 20 | Gossamer | ... | 18 | Condeuvre | 435 | 22 | Yoevoda | 535 | 19 | Minerva | 814 | 21 | ... | ... | 21 | ... | ... | ... | ... | ... |
| 20 | Karakatta | ... | 18 | Dague | 408 | 21 | Abrek | ... | 19 | Montebello | 840 | 21 | ... | ... | 21 | ... | ... | ... | ... | ... |
| 20 | Passy | 735 | 18 | Dragonne | 410 | 21 | ... | ... | 19 | Partenope | 833 | 21 | ... | ... | 21 | ... | ... | ... | ... | ... |
| 20 | Salamander | ... | 18 | Lance | 425 | 21 | ... | ... | 18 | Tripoli | 848 | 21 | ... | ... | 21 | ... | ... | ... | ... | ... |
| 20 | Seagull | ... | 18 | Sainte-Barbe | 437 | 21 | ... | ... | 20 | Urania | 833 | 21 | ... | ... | 21 | ... | ... | ... | ... | ... |
| 20 | Sharpshooter | ... | 18 | Salve | 413 | 21 | ... | ... | 20 | Setta | 400 | 21 | ... | ... | 21 | ... | ... | ... | ... | ... |
| 20 | Sheldrake | ... | 18½ | Léger | 517 | 21 | ... | ... | 20 | Folgore | 370 | 21 | ... | ... | 21 | ... | ... | ... | ... | ... |
| 20 | Skylark | ... | 18½ | Levier | 505 | 21 | ... | ... | 20 | Agordat | 1313 | 21 | ... | ... | 21 | ... | ... | ... | ... | ... |
| 20 | Spanker | ... | 21½ | Casablanca | 960 | 21 | ... | ... | 20 | Coatit | ... | 21 | ... | ... | 21 | ... | ... | ... | ... | ... |
| 20 | Speedwell | ... | 21½ | Cassini | 958 | 21 | ... | ... | 20 | ... | ... | 21 | ... | ... | 21 | ... | ... | ... | ... | ... |
| 19 | Alarm | ... | 21½ | D'Arville | 967 | 21 | ... | ... | 20 | ... | ... | 21 | ... | ... | 21 | ... | ... | ... | ... | ... |
| 19 | Antelope | ... | 23 | Dunois | 896 | 21 | ... | ... | 20 | ... | ... | 21 | ... | ... | 21 | ... | ... | ... | ... | ... |
| 19 | Circé | ... | 23 | Labre | ... | 21 | ... | ... | 20 | ... | ... | 21 | ... | ... | 21 | ... | ... | ... | ... | ... |
| 19 | Hebe | ... | 23 | ... | ... | 21 | ... | ... | 20 | ... | ... | 21 | ... | ... | 21 | ... | ... | ... | ... | ... |
| 19 | Jaseur | 810 | 20 | ... | ... | 21 | ... | ... | 20 | ... | ... | 21 | ... | ... | 21 | ... | ... | ... | ... | ... |
| 19 | Leda | ... | 20 | ... | ... | 21 | ... | ... | 20 | ... | ... | 21 | ... | ... | 21 | ... | ... | ... | ... | ... |
| 19 | Nier | ... | 20 | ... | ... | 21 | ... | ... | 20 | ... | ... | 21 | ... | ... | 21 | ... | ... | ... | ... | ... |
| 19 | Onyx | ... | 20 | ... | ... | 21 | ... | ... | 20 | ... | ... | 21 | ... | ... | 21 | ... | ... | ... | ... | ... |
| 19 | Renard | ... | 20 | ... | ... | 21 | ... | ... | 20 | ... | ... | 21 | ... | ... | 21 | ... | ... | ... | ... | ... |
| 20 | Speedy | ... | 20 | ... | ... | 21 | ... | ... | 20 | ... | ... | 21 | ... | ... | 21 | ... | ... | ... | ... | ... |
| 19 | Dryad | ... | 20 | ... | ... | 21 | ... | ... | 20 | ... | ... | 21 | ... | ... | 21 | ... | ... | ... | ... | ... |
| 19 | Halcyon | 1070 | 20 | ... | ... | 21 | ... | ... | 20 | ... | ... | 21 | ... | ... | 21 | ... | ... | ... | ... | ... |
| 19 | Harrier | ... | 20 | ... | ... | 21 | ... | ... | 20 | ... | ... | 21 | ... | ... | 21 | ... | ... | ... | ... | ... |
| 19 | Hazard | ... | 20 | ... | ... | 21 | ... | ... | 20 | ... | ... | 21 | ... | ... | 21 | ... | ... | ... | ... | ... |
| 19 | Hussar | ... | 20 | ... | ... | 21 | ... | ... | 20 | ... | ... | 21 | ... | ... | 21 | ... | ... | ... | ... | ... |
| 18 | Polypheumus | 2640 | 20 | ... | ... | 21 | ... | ... | 20 | ... | ... | 21 | ... | ... | 21 | ... | ... | ... | ... | ... |
| 34 ships. | | | 21 ships. | | | 9 ships. | | | 17 ships. | | | 4 ships. | | | 2 ships. | | | | | |

EFFECTIVE FIGHTING SHIPS, BUILT AND BUILDING.

| CLASS. | GREAT BRITAIN. | | | FRANCE. | | | RUSSIA. | | | ITALY. | | | GERMANY. | | | UNITED STATES. | | | JAPAN. | | |
|----------------------|----------------|----------------|--------|---------|----------------|--------|---------|----------------|--------|--------|----------------|--------|----------|----------------|--------|----------------|----------------|--------|--------|----------------|--------|
| | Built. | Build- ing. | Total. | Built. | Build- ing. | Total. | Built. | Build- ing. | Total. | Built. | Build- ing. | Total. | Built. | Build- ing. | Total. | Built. | Build- ing. | Total. | Built. | Build- ing. | Total. |
| | | | | | | | | | | | | | | | | | | | | | |
| BATTLESHIPS— | | | | | | | | | | | | | | | | | | | | | |
| 1st-Class | 24 | 14 | 38 | 10 | 3 | 13 | 6 | 8 | 14 | 3 | 6 | 9 | 7 | 9 | 16 | 9 | 8 | 17 | 5 | 1 | 6 |
| 2nd-Class | 11 | .. | 11 | 9 | 1 | 10 | 10 | .. | 10 | 5 | .. | 5 | .. | .. | .. | .. | .. | .. | .. | .. | .. |
| 3rd-Class | 10 | .. | 10 | 11 | .. | 11 | 1 | .. | 1 | 2 | .. | 2 | 7 | .. | 7 | 1 | .. | 1 | 1 | .. | 1 |
| TOTAL BATTLESHIPS | 45 | 14 | 59 | 30 | 4 | 34 | 17 | 8 | 25 | 10 | 6 | 16 | 14 | 9 | 23 | 10 | 8 | 18 | 6 | 1 | 7 |
| CRUISERS— | | | | | | | | | | | | | | | | | | | | | |
| 1st-Class | 25 | 18 | 43 | 5 | 14 | 19 | 5 | 8 | 13 | 4 | 1 | 5 | 2 | 3 | 5 | 4 | 9 | 13 | 6 | .. | 6 |
| 2nd-Class | 60 | 2 | 62 | 22 | 1 | 23 | 7 | .. | 7 | 5 | .. | 5 | 8 | .. | 8 | 10 | 6 | 16 | 9 | 1 | 10 |
| 3rd-Class | 44 | .. | 44 | 13 | .. | 13 | 2 | 3 | 5 | 11 | .. | 11 | 13 | 5 | 18 | 5 | .. | 5 | 5 | 1 | 6 |
| TOTAL CRUISERS | 129 | 20 | 149 | 40 | 15 | 55 | 14 | 11 | 25 | 20 | 1 | 21 | 23 | 8 | 31 | 19 | 15 | 34 | 20 | 2 | 22 |
| COAST-DEFENCE SHIPS. | 17 | .. | 17 | 14 | .. | 14 | 15 | 1 | 16 | 3 | .. | 3 | 19 | .. | 19 | 6 | 4 | 10 | 1 | .. | 1 |
| TORPEDO-GUNBOATS | 34 | .. | 34 | 21 | .. | 21 | 9 | .. | 9 | 17 | .. | 17 | 4 | .. | 4 | .. | .. | .. | 1 | 1 | 2 |

CHAPTER V.

BRITISH NAVAL MANŒUVRES.

Pro-
gramme.

The following was the programme of the manœuvres of 1900 :—

OBJECT.

The principal object of the Manœuvres is to obtain information relative to the working of a fleet, which is composed of vessels of all classes and is fighting for the command of the sea.

The most suitable distance at which to establish a temporary base for a squadron watching a hostile fortified port is a subsidiary question.

The power which cruisers may or may not possess of hunting down and driving torpedo craft into port is another important point.

GENERAL IDEA.

A fleet (B) is divided into two squadrons :—

B1 at Milford.

B2 at Lamlash.

A hostile fleet (A) inferior in battleships to (B) is also divided into two squadrons :—

A1 at Berehaven.

A2 at Lough Swilly.

A hostile reinforcement (A3) which will make $A1 + A2 + A3$ nearly equal to $B1 + B2$ in battleships, is expected from the Mediterranean.

The whole of Ireland is hostile territory, and belongs to (A). The whole of Great Britain, from Cape Wrath to the Land's End, the Isle of Man, and the Scilly Islands belong to (B).

The fleet (B) has destroyers.

The hostile fleet (A) has torpedo boats, supported by fast small craft.

The following ports are fortified, and will be placed in a state of defence :—

In Great Britain :—

Milford Haven.

In Ireland :—

Berehaven.

Queenstown.

Lough Swilly.

All other ports including Lamlash are unfortified.

Each fleet will try to obtain command of the sea, that is to say, will endeavour to defeat the other, to shut him up in his ports, and especially to clear the sea of his torpedo craft.

Comments
thereon.

Two or three features in this programme invite special comment. It represents a struggle for the command of the sea between two hostile fleets, approximately equal in members and composed of units conventionally equal in fighting strength, so far as battleships are concerned. The British fleet B is slightly the stronger, and the opposing fleet A is at the outset completely overmatched, though it may expect to receive in the course of the operations a reinforcement which will make it nearly equal to B. B has destroyers, A has only torpedo boats. A has three fortified ports, Berehaven, Lough Swilly, and Queenstown, B has only one, Milford Haven. But these fortified ports have no conventional defensive value. They "are fortified and will be placed in a state of defence." In other words, such defences as they actually have will be mobilised and placed under military authority to be defended up to the limit of their actual defensive capacity, but not beyond. If the enemy on either side chooses to

assail them he must take the consequences. His success or failure will be determined, not by any arbitrary assumption of impregnability, but by a decision of the umpires, taking all the circumstances into account and judging them solely on the basis of what would be probable in war. Thus, for the first time in the history of naval manœuvres, the naval and military arms were brought into active co-operation. The sequel will show that the results of this co-operation left a good deal to be desired. It appears to be impossible for soldiers to think and act as sailors do. It is not perhaps to be desired that sailors should think and act as soldiers.

The two fleets were composed as follows:—

Composition of the fleets.

FLEET "A."

A 1.

MAJESTIC (flag).
REPULSE.
DREADNOUGHT.
SULTAN.

A 2.

JUPITER.
RESOLUTION.
EDINBURGH.
CONQUEROR.

A 3.

MAGNIFICENT (flag).
PRINCE GEORGE.
HANNIBAL.
MARS.

CRUISERS.

DIADEM.
BLAKE.
EDGAR.
GIBRALTAR.
IMMORTALITÉ.

GLADIATOR.
TALBOT.
FURIOUS.
NAIAD.
SIRIUS.
APOLLO.
RETRIBUTION.
PHOEBE.

FLOTILLAS.

| | | |
|-----------|---|---------|
| PACULUS | } | 42, 49, |
| PERSEUS | | 50, 59, |
| PIONEER | | 66, 71, |
| SPANKER | | 76, 77, |
| SHELDRAKE | | 81, 82, |
| SEAGULL | | 83, 84, |
| SKIPJACK | | 63, 64, |
| JASON | | 68, 74. |
| HECLA | | |

| | | |
|--------------|---|---------|
| MERSEY | } | 51, 52, |
| PROMETHEUS | | 53, 55, |
| SPEEDWELL | | 57, 58, |
| SHARPSHOOTER | | 85, 86. |

FLEET "B."

B 1.

Alexandra (flag).
Colossus.
Rodney.
Howe.
Collingwood.
Camperdown.
Hero.
Thunderer.
Superb.

B 2.

Sans Pareil (flag).
Nile.
Trafalgar.
Benbow.

CRUISERS.

Ariadne.
Blenheim.
Hawke.
St. George.
Galatea.

Vindictive.
Minerva.
Cambrian.
Rainbow.
Melampus.
Andromache.
Medea.
Medusa.

FLOTILLAS.

| | | |
|-----------|---|----------------------------|
| Brilliant | } | Fawn, Flirt, Flying Fish, |
| Alarm | | Kestrel, Spiteful, Star, |
| Renard | | Sylvia, Violet (Portsmouth |
| Leda | | Division); Angler, Ariel, |
| Circe | | Acon, Bittern, Cheerful, |
| Jaseur | | Cynthia, Mallard, Mermaid |
| | | (Chatham Division). |
| | | |

| | | |
|----------|---|---------------------------|
| Severn | } | Leopard, Leven, Locust, |
| Antelope | | Panther, Seal, Shark, |
| Gleaner | | Thrasher, Wolf (Devonport |
| | | Division). |

Orders.

The following are the more important of the "General Orders and Instructions" issued for the occasion:—

GENERAL ORDERS AND INSTRUCTIONS.

A partial mobilisation of the Fleet for Manœuvres will take place this year. The vessels mobilised will be attached to the Channel and Reserve Squadrons. They will assemble as soon as ready under the orders of the Flag Officers in command, at Portland and Torbay respectively, and will be formed into two fleets, to be known as Fleet A and Fleet B respectively.

At the time appointed the main fleets will proceed to sea for the usual preliminary cruise, during which the ships will be exercised and anchored at the discretion of the Admiral in command.

Two flotillas composed of cruisers, torpedo gunboats, and destroyers will be attached to B fleet.

The vessels belonging to these two flotillas will assemble at Torbay, and will be organised thus:—

Severn, 2 torpedo gunboats, Devonport division of destroyers.

Brilliant, 5 torpedo gunboats, Portsmouth and Chatham divisions of destroyers.

They will then proceed as follows:—

Severn and flotilla to Lamlash.

Brilliant and flotilla to Milford Haven;

where they will be exercised and will coal, care being taken that all are complete with coal before the commencement of hostilities.

Two flotillas composed of cruisers, torpedo gunboats, and torpedo boats will be attached to A Fleet.

The vessels belonging to these two flotillas will assemble at Devonport, and will be organised thus:—

Pactolus, *Perseus*, *Pioneer*, *Hecla*, 5 torpedo gunboats, Portsmouth and Chatham divisions of torpedo boats.

Mersey, *Prometheus*, 2 torpedo gunboats, Devonport division of torpedo boats.

They will then proceed as follows:—

Pactolus and flotilla to Berehaven;

Mersey and flotilla to Lough Swilly;

where they will be exercised and will coal, care being taken that all are complete with coal before the commencement of hostilities.

Any portion of the Berehaven flotilla can be sent thence to Queenstown, provided that it arrives there and is completed with coal before the commencement of hostilities.

At the termination of the preliminary cruise, the ships forming Fleet A will be formed into three divisions, and those forming Fleet B into two divisions. They will then be detached to the following base ports:—

A1 to Berehaven.

A2 to Lough Swilly.

A3 to a Rendezvous.

B1 to Pembroke.

B2 to Lamlash.

The order to commence hostilities will be sent on the day on which the ships arrive at their base ports.

The period of active operations will last 10 days.

Vice-Admiral Sir Harry Rawson was in command of the A fleet, with Rear-Admiral Albert B. Jenkins as his second in command, the A 2 fleet, when detached from the flag, being placed under the orders of Captain John Durnford, senior officer in the *JUPITER*. Rear-Admiral Sir Gerard Noel was in command of the B fleet, with Rear-Admiral J. L. Hammet as second in command. A detached squadron of cruisers belonging to the B fleet was placed under the orders of Commodore E. S. Poë in the *St. George*.

The following were the principal "Rules and Regulations" to be Rules observed during the manœuvres :—

RULES AND REGULATIONS TO BE OBSERVED DURING THE
MANŒUVRES.

The Manœuvre field is bounded—

- on the west by the 20th meridian ;
- on the north by the 60th parallel ;
- on the east by the 5th meridian as far as Cape Wrath, by the west coast of Great Britain, and by the meridian of the Lizard Head from that point to the southward ;
- on the south by the 45th parallel.

As soon as the whole of the ships and vessels composing the two fleets, together with the destroyers and torpedo boats, have arrived in port, a telegram will be sent from the Admiralty naming the hour when hostilities are to commence.

No vessel of any class is to put to sea before the hour named for the commencement of hostilities.

Battleships are to complete with coal on arrival at their base ports before again putting to sea.

All battleships are to be considered equal in fighting power to the *Majestic*.

No rules setting forth the conditions under which ships will be put out of action will be issued. Each case must be decided by the umpires on its merits on the basis of what would be probable in war.

When two or more ships come into action the commencement of the engagement is to be marked by the firing of a gun by one of the ships engaged. During the engagement single guns are to be fired at five-minute intervals by one ship on each side.

When either side considers that he has beaten the other, he should signal "Propose reference to umpires." If the other agrees to the reference the action is to cease. If the other does not agree the action may continue, but not for more than a reasonable time, which is to be determined by the senior officer present. A reasonable time under ordinary conditions would be one hour in the case of battleships, cruisers, and torpedo gunboats, and half an hour in that of destroyers and torpedo boats.

When reference to the umpires has been settled, the senior officer present is to determine what ships on either side are to proceed into port to await their decision, pending which the ships detached are to be considered out of action. The senior officer present must take care to select as far as possible equally from both sides.

If a ship is undoubtedly torpedoed, or manifestly overpowered by a much superior force, the senior officer present may take the responsibility of temporarily putting such ship out of action and ordering her into port for the decision of the umpires. In this case it will not be obligatory to order into port a ship from the opposite side.

Ships put out of action can take no further part in the Manœuvres, but must return to one of their base ports—Milford, Lamlash, Berehaven, or Lough Swilly—flying the Blue Peter at the fore. They are to select a route as far as possible clear of the scene of operation, and are strictly enjoined not to communicate any information to the ships on either side which they may meet on the way.

Colliers, after reaching Milford, Lamlash, Lough Swilly, Berehaven, or Queens-town, are open to capture; the captors can use the coal in them.

Colliers are not to be interfered with after they have discharged their cargoes.

Signal stations are not open to attack by landing parties.

As the 18-inch torpedo cannot be fired at a ship in a peace exercise, a destroyer is to fire a blue light by night or blow her whistle by day at the moment when the torpedo would be discharged, the tube being trained and all adjustments made as if actually firing.

Torpedoes fitted with collapsible heads may be fired at battleships and cruisers, but not at torpedo gunboats, destroyers, or torpedo boats.

Torpedo boats are not to paint out their numbers.

As it is assumed that the command of the sea is disputed care, should be taken not to expose vessels needlessly to fire from forts.

Vice-Admiral Sir Compton Domville and Rear-Admirals C. C. Umpires. Penrose Fitzgerald and A. D. Fanshawe were nominated to act as umpires. Their instructions were of the usual character, except that Lieut.-General J. F. Owen, R.A., was "nominated by the War Office to act as Military umpire to decide, jointly with the Naval umpires,

claims arising between the land defences and the ships." Very few such claims appear to have been preferred, but the report of the military umpire and of his naval colleagues on such claims as they were empowered to decide conjointly with him would probably furnish some very instructive reading.

Criticism
of the
rules, etc.

There is one glaring inconsistency in the foregoing rules and instructions. All battleships were to be considered equal in fighting power to the MAJESTIC, and yet the umpires were required to decide each case referred to them "on the basis of what would be probable in war." If the term "fighting power" be taken as equivalent to the aggregate of qualities which make for success in battle—whether of speed, coal endurance, tactical mobility, armament, or protection—there was no single ship in the B fleet which could be regarded as equal to the MAJESTIC, and there were four ships in the A fleet which could not by any possibility be regarded as equal to the MAJESTIC "on the basis of what would be probable in war." This was at once made apparent during the preliminary cruise of the A fleet. The Channel Squadron proper includes eight battleships, all practically homogeneous in respect of speed, coal endurance, and tactical mobility, and all assiduously trained to a common standard of proficiency in evolutionary exercises suited to their common capacities. They can maintain a continuous sea-speed of 14 knots, they can manœuvre at 12, and are habitually manœuvred at 10 knots. For the purposes of the manœuvres they were reinforced by four additional ships, different in speed, different in coal endurance, different in tactical mobility—all factors of capital moment in the consideration of "what would be probable in war"—and not less different in armament, armour, and protection, though as no ship could fire her guns these latter factors did not count. The effect of this so-called reinforcement was to reduce the extreme speed of the combined fleet to 12 knots at the outside, to reduce its manœuvring speed to 8 knots, and very materially to impair its tactical mobility. Many things would be possible in war to a squadron composed of eight real MAJESTICS which would be quite impossible to a squadron composed of eight real MAJESTICS combined with four putative and only nominal MAJESTICS. It is at least conceivable that a fleet of eight real MAJESTICS might, by taking advantage of their speed and tactical mobility, and in the last resort of their coal endurance, be adjudged on the basis of "what would be probable in war" to have got the better of the whole of the B fleet combined, assuming the latter to be as it actually was; nor is it less conceivable that the reduction of speed, tactical mobility, and capacity to keep the sea involved in the addition of four inferior and heterogeneous ships might on the same

basis have neutralised entirely the supposed advantage to be derived from the increase of numbers. This is a very serious consideration, but the argument seems irrefragable. The more homogeneous a squadron is, the more perfectly it is trained in the qualities and aptitudes which belong to its homogeneous character, the more inexpedient is it to dilute it with a sudden and improvised reinforcement of inferior and heterogeneous ships. Such a policy reduces the whole theory and practice of tactical training to an absurdity. It assumes, in the first place, that the fighting fleets we keep at sea are not strong enough to fight until they are reinforced; in the second place, that such reinforcements may consist of quite inferior ships, newly commissioned, untrained in fleet evolutions, and manned by crews unaccustomed to work together; in the third place, that such reinforcements so organised afford an access of numerical strength which more than compensates for the loss of tactical mobility and the change of tactical method imposed on the fleet so reinforced. If these assumptions are sound, it follows that tactical training at sea as pursued by our fighting fleets is little better than an elaborate and costly method of marking time. If our fighting fleets are not strong enough to fight without being reinforced, they ought to be reinforced at once up to their full fighting strength, even if the reinforcements must consist of inferior and heterogeneous ships. Then, at any rate, they can be trained from the outset in a system of tactics adapted to their composite and heterogeneous character. But to train a heterogeneous fleet in tactics which it can never pursue in war because it will be rendered heterogeneous by reinforcements the moment war is imminent, is practically to declare either that tactical training is worthless, or that newly organised fleets can learn all that is worth knowing about it in the very short interval which, in future wars, is likely to precede the actual outbreak of hostilities. The only sound and logical policy is permanently to maintain our fighting fleets in all respects on a footing of instant readiness for war. This is, perhaps, the chief lesson of the manœuvres of 1900, and it was learnt before the manœuvres began. In its ulterior implications it is probably the most impressive lesson we have had since the manœuvres of 1888.

Hostilities were ordered to begin at 2 a.m. on July 24, and to cease at 2 a.m. on August 3. The telegram from the Admiralty conveying this order was despatched simultaneously to all the fleets in British ports in time to reach them before the hour appointed. But the B1 fleet, at Milford, was much hampered by fog, which delayed its return to port after the preliminary cruise, and retarded its reception of the telegram. It could not, therefore, leave at the

Hostilities
began.

earliest moment permitted, as some of its battleships, owing to the delay, had not completed coaling, nor had the telegram been received at that time. In spite of the fog, however, it got to sea in the forenoon of the 24th. The other fleets in British ports put to sea at the appointed hour. The A 3 fleet had on July 20 been despatched from Berehaven to a southern rendezvous fixed by the Admiralty outside the manœuvre area with sealed orders determining the time and the direction of its subsequent advance.

Disadvan-
tages of a
fixed
period.

It has usually been the practice of the Admiralty to fix a period for the duration of hostilities, and this practice was pursued on the present occasion. The practice, though obviously a convenient one for many reasons, is nevertheless open to serious criticism. Manœuvres are too costly, especially in the matter of coal consumption, to be allowed to last for more than a very limited period, nor is it expedient to encourage admirals to dawdle over them. But the topic of "coal strategy," discussed by Captain Bacon in another chapter of this volume, suggests problems which have never yet been adequately or systematically studied, though they will assume immense importance in any future naval war. A fixed period of hostilities eliminates them altogether from the range of instruction to be derived from manœuvres. If an admiral knows that his coal will last as long as the manœuvres will last, he may keep the sea and "put on a brag countenance," as Howard of Effingham said with only just coal enough to take him back to his nearest port at the close of the fixed period. But this is not war—indeed, it is diametrically opposed to "what would be probable in war." In war the relation of coal endurance to the nearest source of supply would govern all dispositions, and this is why fleet-colliers are such indispensable auxiliaries to a mobile fighting fleet. In a fixed period of hostilities, on the other hand, this relation may be practically neglected, as indeed it was. At the close of the period the MAJESTIC had over 1,000 tons of coal in her bunkers, the *Alexandra* little more than 100. But this essential difference in "fighting power" had little or no effect on the dispositions of either side. It is impossible to doubt that in actual war it would have a very material, perhaps even a decisive, effect. The sufficiency and accessibility of his coal supply must ever be the paramount consideration of an admiral who seeks to command the sea. It is impossible to command the sea with ships which for lack of coal are little better than derelicts. The possession of coal and speed is, in fact, the modern equivalent of the weather-gauge. It enables an admiral to force or decline an action at his discretion. Even if speed be no more than equal, the admiral who has the larger coal supply

enjoys an immense advantage. It would for these reasons seem to be the better course to fix no definite period for hostilities, but to allow them to run their natural course until either a decisive issue has been reached or the Admiralty think that they have lasted long enough. Their average duration would probably not be increased by such a policy. In 1894, as recorded in the *Naval Annual* for 1895, the manœuvres were "the shortest and most decisive on record." They lasted little more than 36 hours. In 1900 the operations had not been brought to a decisive issue at the end of 10 days. Yet the period of hostilities fixed beforehand on both occasions was the same—namely, 10 days. Taking the manœuvres of 1894 as the *minimum* and a possible duration of some 15 days as the *maximum*, the average duration would probably be found to be less than the 10 days which seem to be regarded by the Admiralty as a reasonable and normal period. But the gain in actuality and in experience really profitable for war would be incontestable.

The situation as it stood at the outbreak of hostilities naturally pointed to the concentration of the detached battle squadrons engaged on both sides. Cruiser and torpedo operations may be considered later. They are essentially subsidiary to a struggle for the command of the sea, which will always be determined by the conflict of battleships, so long as battleships exist. Each side knew that A might expect a strong reinforcement from Gibraltar at a later stage of the proceedings, but neither knew at the outset when it might be expected to enter the manœuvre field. It would seem that Admiral Noel expected that this information would reach him before he left Milford, but it did not, and apparently it was not intended by the Admiralty to do so. It was despatched by the Admiralty simultaneously to both sides early in the morning of July 25, more than twenty-four hours after hostilities had begun. It reached Admiral Rawson at sea off the west coast of Ireland before midnight on the same day, he having the advantage of being at the time in cruiser contact with his signal stations. But as Admiral Noel's dispositions involved the surrender of that advantage, the information did not reach him until the afternoon of July 26. It was to the effect that A 3 fleet had passed Gibraltar at 5 a.m. on July 25, at a speed of 10 knots. As the position of the rendezvous to which A 3 fleet had actually been sent was known to both sides, and was only a few miles to the southward of the southern limit of the manœuvre field, it was thus easy to calculate approximately the time at which A 3 would actually come within the sphere of operations, and with similar approximation the point at which it would enter it. But its course after entering it would naturally be determined by the orders it had

Position
of A 3
unknown
at the out-
set to both
sides.

received from Admiral Rawson. These dispositions would seem to be not unfairly adjusted to the probabilities of real war. The movements of an enemy coming from the Mediterranean might quite conceivably elude observation until Gibraltar was reached. But if the Straits were properly patrolled, such a fleet could hardly escape observation in that neighbourhood. It was assumed to have been observed, and to have been immediately reported to headquarters at home. From headquarters it was simultaneously reported to both sides, but, as was natural in the conditions assumed, it reached one side earlier than it did the other. It was stated by correspondents attached to his fleet that Admiral Noel, expecting to be informed before he left Milford of the whereabouts of the hostile fleet "expected from the Mediterranean," had made his dispositions accordingly. It is hard to reconcile this expectation with the wording of the "General Idea" or with the probabilities of the case, as set forth above.

Admiral
Noel's
plan.

Be this as it may, Admiral Noel, assuming that A 3 was probably well to the northward of Gibraltar when hostilities began, resolved to concentrate his whole force as soon as possible in such a position as might best enable him to prevent or interfere with the anticipated junction of A 3 with A 1 and A 2 combined. The position selected was well chosen on this assumption. A series of rendezvous had been preconcerted skirting the west coast of Ireland, but out of sight of land, and on this line the B 1 and B 2 fleets effected their junction unmolested in the afternoon of July 25, in lat. $52^{\circ} 9' N.$, long. $11^{\circ} 28' W.$ They then proceeded to cruise on the same parallel to beyond the fifteenth meridian, scouting widely in search of the enemy. B 2 had left Lamlash as soon as hostilities began, and, though not unobserved from the Irish coast, had encountered no hostile force.

Its as-
sumptions
and their
conse-
quences.

Having assumed that A 3 fleet was well to the northward of Gibraltar at the time that he himself left Milford, Admiral Noel seems very naturally to have inferred that Admiral Rawson would probably endeavour to concentrate his three divisions as soon as possible at some point not very far to the westward of the fifteenth meridian nor very far north or south of the fifty-second parallel. Such a point would be conveniently situated as regards both Berehaven and Lough Swilly, and could be reached by A 1 and A 2 without the possibility of being molested or overtaken by B 1 or B 2 at the outset. In point of fact, Admiral Rawson had originally ordered A 3 to advance along the meridian of 15° , and would have met him on that line of advance if his original plan had been carried out. On this assumption Admiral Noel's dispositions would seem to have been well conceived. But it is never safe to make a picture of this

kind. The weak point in it was the unfounded, perhaps unwarranted, assumption as to the position of A 3 when hostilities began. On any other assumption the dispositions adopted were extremely hazardous. It was certain that by starting at the earliest moment and steaming towards each other off the west coast of Ireland A 1 and A 2 could effect a junction before B 2, starting from Lamlash, could reach any point of the parallel on which the junction was effected. A 1 and A 2 combined would then be between B 1 and B 2, in a position much nearer to the latter and in force greatly superior to it. Indeed, until it could get to the southward of A 1 and A 2, B 2 would be altogether in the air, and would run grave risk of destruction. In point of fact, as we shall shortly see, it escaped destruction literally by a hair's breadth.

Admiral Rawson left Berehaven as soon as hostilities began with all the A 1 battleships, and with the BLAKE, SIRIUS, PERSEUS, and SKIP-JACK also in company. He had not received any information as to the whereabouts of A 3 at the time of leaving, nor does he seem to have expected any, thus reading the "General Idea" in a sense different from that which Admiral Noel attached to it. In these circumstances he deemed it inexpedient to sever his communications with his signal stations until he had received this all-important information. He accordingly proceeded to the northward towards a rendezvous off Black Sod Bay which had been given to the senior officer of A 2. Here at 7 p.m. he was joined by the JUPITER, RESOLUTION, APOLLO, PHEBE, RETRIBUTION, and PROMETHEUS belonging to A 2, and the combined squadron proceeded to the northward, giving the land a wider berth for the night. The EDINBURGH and the CONQUEROR had been ordered to remain at Lough Swilly for the present to save coal, and because they were not required for the immediate purpose which Admiral Rawson had in hand. This was to make a raid on the enemy's northern territory in force greater than the enemy was likely to be able to meet. This raid never came off. It was not perhaps a very hopeful project in any case, nor strategically very discreet as an opening move in a struggle for the command of the sea. It involved a hasty descent on Lamlash, starting from a safe distance at early dawn, with such further naval forays in the estuary of the Clyde as time and circumstances might permit, the intention being to get back into the open again before dark with Lough Swilly as a safe retreat, and a possibility of falling back on the line of advance of A 3 if the enemy were found to have concentrated in the neighbourhood of the North Channel. It might in certain contingencies have effected a useful diversion, but in no probable circumstances could it materially have affected the larger

Admiral
Rawson's
move-
ments.

issues of the campaign. As it never came off, it need not be further discussed. Perhaps it may best be regarded as a rather adventurous way of marking time until the movements of A 3 had been ascertained.

Narrow
escape of
B 2.

Shortly after the junction of A 1 and A 2 had been effected on the evening of July 25, a cruiser, sent into Black Sod Bay for intelligence, rejoined with the information that four of the enemy's battleships, presumably the B 2 fleet, had been observed in the forenoon from Malin Head at a distance of about 15 miles steering north-west. The course steered indicated nothing beyond an intent to deceive, and this intent appeared to be emphasised by the enemy's showing himself within sight of a hostile signal station without any obvious necessity. Anyhow the ruse, which was perhaps an oversight, was curiously successful. Admiral Rawson did not dispose his fleet during the night in any such formation as, while keeping his forces in hand, might present a wide front to the enemy's possible advance towards the southward; though if he had, with six battleships and eight cruisers in company, an advance in line abreast at moderate intervals so as to cover a front of from ten to twelve miles must have intercepted the enemy and brought him to action at a great disadvantage. About midnight the two fleets passed each other at a distance of some three miles, though neither appears to have observed the slightest trace of the other.

Remarks
thereon.

The history of naval manœuvres records no incident more illustrative than this of the inherent chances and accidents of naval warfare. It would be incredible that two considerable fleets could pass unobserved within three miles of each other even at midnight in ordinary weather, if the thing had not actually happened. It is true that the A fleet was not on the look-out for B 2 nor expecting to encounter it, while B 2 had every reason to avoid observation. Still, war is war, and the unexpected is of the essence of war. There is an absent-minded touch about the proceedings of A which it is not quite easy to understand. At midnight on the first day of the operations Admiral Rawson was within three miles of a decisive advantage if he had only known it. He might have known it, and, since he might have known it, it is hard not to think that he ought to have known it. Captain Bacon pointed out in the *Naval Annual* of last year that the most advantageous formation for one fleet which desires to discover another is the line abreast with cruisers disposed on either beam. Had this formation been adopted by A, with intervals suitable to the weather, on the night of July 24, 1900, the B 2 fleet could not have passed unobserved, and the whole course of the operations would have been altered. In all probability ten days would have

more than sufficed to bring them to a decisive conclusion. Here again is a lesson of capital moment to be derived from the manœuvres of 1900—the lesson that nothing must be taken for granted in naval war, and that opportunities missed seldom return.

The appearance of several of the enemy's cruisers in the early morning of the 25th soon led Admiral Rawson to the conclusion that the B 2 fleet must have passed him during the night. The cruisers observed had all been originally attached to the fleet. Some of them got near enough to make out the identity of A, but all were chased away, and all as they retreated made off eventually to the southward. Some time was lost in altering course to deceive them, and the projected raid on the estuary of the Clyde was thereby frustrated, since it required the whole of the daylight between dawn and dusk for its safe and successful execution. It might have been carried out on the following day with a prospect of as much success as is ever likely to attend such operations—a success which in war is moral rather than material, and in manœuvres is apt to be little more than theatrical. But before night information received from the shore, and described as “most important” by the cruiser which brought it—as indeed it was—induced Admiral Rawson entirely to alter his plans. It was to the effect that the DIADEM—which, with a strong contingent of cruisers, had been despatched to Queenstown at the outbreak of hostilities, under orders which will be detailed hereafter—had observed the whole of the B 1 fleet on the morning of July 25 off Brow Head, but out of sight of land, and apparently making for the northward. Brow Head is a signal station in the neighbourhood of the Fastnet. It was thus clear, from these and other indications, that B 1 and B 2 had effected their junction not very far from Berehaven, as they actually did in the position already indicated. This was held by Admiral Rawson to be a very strong position for them to take up, and he anticipated that they would move, as they did, towards some position to the westward of it, intermediate between the coast of Ireland and the western limit of the manœuvre field, in long. 20° W. He thought that, having reached this second position, there were three courses open to them—namely, (1) to steam in full force towards the rendezvous assigned by the Admiralty outside the manœuvre field, in lat. 44° N., long. 14° W., to the A 3 fleet, and endeavour either to bring it to action or to drive it off its preconceived line of advance; (2) to cruise in the neighbourhood of the position they had reached, scouting widely in all directions so as, if possible, to get touch either of A 1 and A 2 combined or of A 3 advancing to meet them, and to bring one or other to action before they could effect a junction; or (3) to spread their forces as far as they would

Further
proceed-
ings of A.

go without breach of contract on a line stretching from the Irish coast towards the western limit of the manœuvre field, and scout as actively as possible over the remaining interval. In any one of these contingencies, or indeed in any contingency based on the assumption that Admiral Noel would hold on to the position he had occupied, it was fatal to allow A 3 to advance to the northward along the line originally preconcerted—namely, the fifteenth meridian—and equally fatal for Admiral Rawson himself to move to the southward along the same line. Thus, the first thing now to be done was to endeavour to convey to A 3 fresh instructions adapted to the altered situation and to adapt the movements of A 1 and A 2 to the same situation and to the new instructions sent to A 3. The same cruiser which brought Admiral Rawson intelligence of Admiral Noel's dispositions also brought a telegram from the Admiralty to the effect that A 3 was to be considered to have passed Gibraltar at 5 a.m. on July 25, steaming at 10 knots. At this speed the point where the 15th meridian cuts the southern limit of the manœuvre field could not be reached until some 70 hours after the time named in the Admiralty telegram, and, as Admiral Rawson had received the intelligence within 18 hours of the same time, there was still time if all went well to warn A 3 away from the trap which had apparently been laid for it. Admiral Rawson proceeded forthwith to Lough Swilly, reaching it early in the morning of July 26. Orders had previously been sent to the EDINBURGH and CONQUEROR to get up steam, so as to be ready to join him on his arrival, and, having despatched the orders necessary for the execution of his altered plan, he left the anchorage with his whole force to carry out his own share of the new plan of campaign. Shortly after leaving Lough Swilly he made the following general signal in explanation of his proceedings and intentions: "I consider that B 1 and B 2 must have combined by this time, and that they are some distance from Brow Head. I am now going to try and effect a junction with A 3, an effort which will probably end in a fight. DIADEM'S division of cruisers had been ordered to proceed to lat. $47^{\circ} 35'$, long. 15° , and then run south along the 15th meridian to meet A 3 and direct the Rear-Admiral to meet me at a rendezvous in lat. $47^{\circ} 35'$, long. 20° , about 5 p.m. on Sunday (July 29). A 3 leaves Admiralty rendezvous in lat. 44° , long. 14° at midnight on Friday (July 27), and comes north along the 15th meridian at 12 knots." These dispositions were carried out in the main, and were brought to a successful issue. The A 3 fleet was met early in the afternoon of July 29 in lat. $47^{\circ} 53'$, long. $19^{\circ} 40'$. The DIADEM was not at Queenstown when Admiral Rawson's orders were received there, but the PIONEER was despatched in her stead to convey them. She

encountered the A fleet between 6 and 7 p.m. on July 28 in lat. $47^{\circ} 50'$, long. 15° , and, having delivered her orders, returned direct to Queenstown. The A 3 fleet at once turned to the westward, and joined Admiral Rawson's flag on the following day at the time and place mentioned above. Anticipating that the DIADEM might be unable to carry out her orders Admiral Rawson had on the 27th despatched the BLAKE ahead with similar orders to be carried out with due regard to the position assumed to be occupied by Admiral Noel, and early on the 29th the APOLLO was sent ahead to look out for A 3, now supposed to be nearing the new rendezvous assigned. They both rejoined the flag shortly after the junction was effected, but they do not seem to have accomplished their respective missions, which, in the case of the BLAKE, had been anticipated by the proceedings of the PIONEER, and in the case of the APOLLO by the appearance of A 3 to the north of the appointed rendezvous. The only other change in the plan adopted at Lough Swilly was that the CONQUEROR, which had experienced some difficulty in maintaining the speed of the fleet—10 knots—and was burning her coal at a disquieting rate, was detached on July 28, when the squadron was well past the point at which it was thought that Admiral Noel or some of his cruisers might be encountered, and ordered to steam at easy speed to a rendezvous on the course which Admiral Rawson intended to take on his return, and there wait until she was rejoined by the main body of the squadron. Having now in hand his full force of battle-ships, Admiral Rawson shaped a course for a rendezvous south of Queenstown, detaching the ARROGANT and the FURIOUS to Berehaven with orders to the DIADEM and her division to rejoin him at the rendezvous, and for the Berehaven flotilla of torpedo boats and torpedo gunboats to concentrate with all despatch at Queenstown. But as this final concentration could not be effected for more than two days, it is time to return to the proceedings of Admiral Noel.

On receiving the intelligence, which reached him on the evening of July 25, Admiral Rawson had made to himself a picture. He assumed that Admiral Noel had concentrated the whole of the B fleet in a position which he himself regarded as the most advantageous for his adversary to occupy in the whole range of the manœuvre field. The assumption was correct as regards the facts, for Admiral Noel had concentrated his whole sea-going force in the position assigned to him by Admiral Rawson. But it was not correct in regard to Admiral Noel's motives, nor in regard to his estimate of the advantages of the position he had occupied. Reading the "General Idea" in a rather non-natural sense, Admiral Noel had assumed that the A 3 fleet was much nearer the scene of operations

Further
proceed-
ings of B.

than it actually was when hostilities began. On that hypothesis he had further assumed, legitimately enough if the original hypothesis had only been correct, that the rendezvous of concentration of A 1, A 2, and A 3 would be found somewhere in the neighbourhood of lat. 52°, long. 15°, and that he could reach the position in time to anticipate, and possibly prevent, the concentration he expected. With this picture in his mind he took the very hazardous course of ordering the B 2 fleet to the southward in the teeth of a possible combination of A 1 and A 2 in front of it, and though B 2 escaped by a hair's breadth it is almost impossible to exaggerate the risks it ran or the disastrous consequences that might have ensued from the adventure. But Admiral Noel found no trace of his adversary in the position he had occupied. The picture he had made proved to be a false one, and either his imagination failed to show him, or his judgment refused to acknowledge, that the position he had occupied might be turned to account in another way. Finding no enemy where he had expected to find him, he determined to look for him elsewhere. He did not receive the telegram relating to the position of A 3 until the afternoon of July 26, by which time he had returned from his extreme western point some 100 miles in a south-easterly direction. He knew, therefore, that A 3 could not reach the neighbourhood of Ireland for two days at least. He might endeavour to intercept it, but owing to its superior speed he could hardly hope to bring it to a decisive action. He knew from his cruisers that A 1 and A 2 were combined in the north. Having all his battleships with him, he might well feel anxious for the safety of his northern base, which was devoid of all but such defence as could be extemporised from its own resources. As a matter of fact, he had virtually abandoned it for another, equally undefended, which he hoped might escape the observation of the enemy. This may be regarded in some quarters as showing that undefended bases are untenable. The truer inference is perhaps that they can generally, if not always, be extemporised, and that to select and advertise them beforehand is to direct the enemy's attention to them. As matters turned out, Lamlash was of no more use to Admiral Noel than any convenient anchorage in that region would have been. He did not keep his colliers there, but placed them where they were less likely to be found and captured by the enemy. Admiral Rawson partially followed the same policy, although he had three defended bases, when he placed a collier in the Shannon. Such a policy will undoubtedly be pursued in war whenever circumstances permit, as they nearly always will. Almost any secluded anchorage, even in the enemy's territory, will serve the purpose, if it is not covered by guns of position nor occupied in force by troops provided

with field artillery. Neutral territory no doubt presents greater difficulties. But it is probable that even the rights of neutrals will only be respected so far as neutrals are able to enforce them. This is the answer of naval history and war experience, now confirmed by the experience of the manœuvres, to one of the questions propounded as subsidiary objects of the manœuvres—namely, to ascertain “the most suitable distance at which to establish a temporary base for a squadron watching a hostile fortified port.” The most suitable distance is one which best serves the purpose of one belligerent and best conceals the purpose from the other. It can only be determined by circumstances when and as they arise. If Wei-hai-wei was contemplated when this problem was propounded the solution was little in its favour. Lamlash was not found so suitable a base for any purpose of the manœuvres as another unknown to the enemy. It was never occupied by a squadron watching a hostile fortified port, and the only hostile fortified port which such a squadron could have watched never had anything in it worth watching. A fleet which seeks to command the sea will rarely be found skulking in its ports.

Anyhow, Admiral Noel, knowing on the afternoon of July 26 that A 1 and A 2 were combined in the north, and that A 3 was too far to the south to count for the next two days, seems to have thought that the best thing he could do was to follow up Admiral Rawson and try to catch him in case he had entangled himself in an attack on Lamlash and a raid on the estuary of the Clyde. Accordingly he went north, and found—nothing. It was now too late to prevent the junction of A 1 and A 2 with A 3. Where it might take place was still unknown to Admiral Noel. But that it must take place was certain, nor was it less certain that Admiral Rawson having effected it would be able to choose his own time and place for reappearing. His object in reappearing, however, must be to seek the enemy or to compel the enemy to seek him, as might seem to be the most advantageous course. Both combatants being engaged in a struggle for the command of the sea, they must seek each other as soon as they were in a position to offer battle. Whenever that is the case they are certain to find each other sooner or later, and very generally without much delay. The object of scouting is seldom that of finding an enemy who wants to fight: its main purpose is to find an enemy who wants to elude observation, and if possible to bring him to action at a disadvantage. This purpose was no longer open to Admiral Noel. Until Admiral Rawson reappeared he could only place himself in a position to defend the points which he thought his adversary most likely to assail, and there mark time while awaiting further developments.

B goes
north-
ward.

Still apparently clinging to the belief that the final rendezvous of the A fleets would be to the westward of Ireland, and not to the southward of it, he patrolled the northern part of the Irish Channel between Holyhead and its northern exit, until on August 1 he received off Port Patrick the information from two of his cruisers scouting off the south of Ireland that Admiral Rawson had reappeared in full force off Queenstown.

Comments
on the
foregoing
proceed-
ings.

Thus from July 24 to August 1 two great fleets had, as often happens and must happen in naval war, been playing at cross-purposes, acting, as naval commanders in war often must act, on very insufficient information, misinterpreting each other's motives and movements, taking immense pains to avoid contingencies which never arose, and to avert evils which never even threatened them—it must be added, as regards one, running risks with a light heart which all but proved fatal, and as regards the other missing a splendid opportunity by what at least looks like a piece of sheer inadvertence. It may be thought that Admiral Noel did not fully appreciate the advantage of the position he assumed at the outset. Certainly he did not rate it as highly as Admiral Rawson did, for the latter made certain that, having occupied it, Admiral Noel would stick to it. The final judgment on this issue must depend on the question whether, with the resources at his command, Admiral Noel could have occupied a line some 340 miles in length in such a manner as to make it impossible for a hostile force to pass in either direction without being detected and brought to action. Admiral Noel evidently never dreamt of such a thing. Admiral Rawson, on the other hand, quite as evidently thought it not only feasible but probable. Experiment, perhaps, alone could decide between them. But experimental and systematic scouting is apparently not in favour with the Admiralty, which seems to consider that the art of scouting comes by nature. It certainly does not on land, as we have lately learnt to our cost. Why are we to assume that it does at sea? We take immense pains to exercise our battleships in tactics suitable to their functions, and we prepare an evolutionary signal book from which every captain of a battleship may learn exactly what he has to do, though he can only learn how to do it at sea and on the bridge. But of cruiser tactics, which are much less geometrical, or rather diagrammatic, in character, and depend much more on individual experience and intelligence, we have not even a manual. What is worse, our fighting fleets can seldom study them at all, and can never study them systematically and exhaustively, so short, and latterly so precarious, is the supply of cruisers which the Admiralty in its wisdom allows them. So long as this is the case, the possi-

bilities and limitations of scouting can never be brought to an experimental test, and scientifically determined once for all; and we shall be confronted with the disquieting paradox that one distinguished Admiral thought his adversary certain to do that which the adversary himself, not less distinguished, never seems to have dreamt of doing.

It may also be thought, perhaps, that a more efficient system of scouting might have enabled Admiral Rawson to get some more definite intelligence of his adversary's movements and apparent intentions before making his wide sweep to the westward. But a fleet which seeks to elude the observation of an enemy superior in force and not inferior in speed must scout with great caution and circumspection. Nevertheless, a more scientific study of the art and practice of scouting than the British Navy is allowed by its rulers to undertake might have enabled the required intelligence to be obtained without compromising Admiral Rawson's safety. Admiral Noel advanced northwards at a mean distance of some thirty or forty miles from the Irish coast. Could he have been observed by one or more of Admiral Rawson's cruisers soon after his intention to go northwards had been disclosed by his movements—that is, before dark on the 26th—the information might have reached Lough Swilly through the signal stations the next morning. Had Admiral Rawson been either there or in the neighbourhood at that time, he would have seen that there was no occasion for him to alter his original plan, that he would probably be able to throw Admiral Noel off his scent and go off to meet A 3 advancing along the 15th meridian as originally arranged. In any case, had he known that Admiral Noel had once abandoned the position which he himself regarded as the most advantageous to occupy, Admiral Rawson might have inferred that he was not very likely to return to it, that he did not perceive its advantages, or did not rate them as highly as Admiral Rawson himself did. There were some risks in taking this course, notably the risk that if the chain of communication failed Admiral Rawson might have been caught in inferior force, or might even have been blockaded in Lough Swilly, as well as the certainty that, after loitering for twenty-four hours off Lough Swilly, it might be too late to take the wide circuit he did, and to warn A 3 in time should Admiral Noel, after all, be found to have occupied a line between the two portions of the divided A fleet. But there were plenty of risks involved in taking the course Admiral Rawson did take. "It is by no means certain," wrote the correspondent of the *Times* on board the *MAJESTIC* on July 28, "that Admiral Noel has occupied the position attributed to him. It is not certain, though it is highly probable, that B 1 and B 2 had combined at the time that Admiral

Comment
continued.

Rawson assumed that they had. It is not certain that if combined they have not gone off to intercept A 3 on the southern boundary of the manœuvre field. It is not certain that the DIADEM was in a position to execute the orders sent to her from Lough Swilly; and for this reason Admiral Rawson, yesterday, detached the BLAKE on the same errand. . . . But, again, it is not certain that the BLAKE would be able to elude or evade the cruisers of B. She might escape capture by taking to her heels, but in that case she might be driven so far out of her course as to be unable to reach A 3 in time to prevent the latter running into danger, or to make certain that A 3 will be informed of the new rendezvous before it is too late. In either of the latter alternatives, A 3 will still be in the air, and Admiral Rawson will probably be deprived of the only chance he ever had of obtaining the command of the sea."

The
neglect of
scouting.

On the whole, then, it must be acknowledged that both sides were, or may have been, hampered by the ignorance which the policy of the Admiralty imposes on the whole service of the possibilities and limitations of scouting and cruiser tactics in general. What Admiral Rawson thought it possible and most advantageous for his adversary to do will not be pronounced by any competent critic to be altogether foolish and impracticable. What is here suggested as possible for Admiral Rawson to have done probably no officer in the service will pronounce offhand to be impracticable and inexpedient. Until the art of scouting can be scientifically and systematically studied at sea, opinions the most diverse will prevail and dispositions the most meticulous will be the order of the day. This is not to say, however, that Admiral Rawson's dispositions were meticulous. He took the safest course, but not the most adventurous course. The safest course served his purpose, but it brought him into final contact with his adversary too late for the issue to be fought out. The more adventurous course might have undone him, but it might have given him a better, because an earlier, prospect of success. This, however, is a consideration which arises directly out of the fixed period assigned to the operations, and does not, therefore, apply with equal force to the conditions of real war. There is no fixed period in real war. Time is of importance in war—in some cases it is all-important—but no time is wasted which enables an admiral to avoid a superior enemy and to go into action on the best terms he can with all his available force and at a time and place chosen by himself. Villeneuve did not waste time in going to the West Indies, where reinforcements awaited him. He was worsted in the Trafalgar campaign, not so much because the plan was bad—it was Napoleon's—but because it was feebly executed, and especially because Villeneuve's nerve and

judgment failed him at the critical moment. We may press the parallel even further, though with no reflection on either admiral concerned. We shall see presently that when the two fleets at last met Admiral Noel failed, as Calder did, to carry the fight to a finish, not because he was a man, like Calder, to be content with what Nelson contemptuously called a "Lord Howe's victory," but because he had no alternative. The manœuvres were coming to an end, and his coal was running short. On the other hand, Admiral Rawson, who found himself for the moment at a disadvantage, withdrew, as Villeneuve did, as though to wait for a better opportunity. The better opportunity was denied him by the close of the manœuvres; but no one will suppose that had it been offered him he would have failed, like Villeneuve, to take advantage of it.

Nevertheless, if details be discarded, it is impossible not to be struck with the confirmation afforded by the general course of the operations to the teaching of naval history. On this point there is little to be added to the remarks of the correspondent above quoted. Writing on July 30, he said: "We were attempting a combination of great, perhaps of unprecedented, magnitude. The historic principles of naval warfare were reasserting themselves in a most significant fashion. Admiral Noel seemed to have shown that the best way to protect the Irish Channel from naval attack was not to occupy it in force, but to move all his force to any position from which he thought he could best frustrate the designs of his enemy. I commend this fact to the earnest attention of those who hold—there are far too many, I fear, and among them are some of our leading statesmen—that in time of war England would be in danger if our 'great ships' were not to be found in the Channel. As soon as Admiral Rawson became aware of his opponent's movements, did he at once make a descent on the defenceless coasts of England, as some of our amateur strategists, and not a few of our professional strategists of the 'brick-laying school,' would have had him do? Nothing of the kind. He had contemplated a movement into the Irish Channel when he thought the enemy's fleets were there, and hoped to surprise one of them in inferior force. But the moment Admiral Rawson found that the enemy had given him the slip, and had become aware, through the reports of his cruisers, of his own movements and position, the Irish Channel and all it contained was for the moment wiped out of his calculations. . . . He resolved at once to play the great game, to concentrate all his force, and to make the best bid he could for the command of the sea. . . . He himself was at Lough Swilly, his reinforcements were practically only a few hours from Gibraltar, and between the two he held that his adversary had

Further
lessons of
the
operations.

occupied the most advantageous position to be found in the whole of the manœuvre field—a position approximately equidistant from his own base ports, adjacent to the principal base port of his opponent, and intermediate between the two fleets of the latter, which were practically separated—in time, that is, though not in actual distance—by 1,200 miles of sea.” Such are the dimensions which a struggle for the command of the sea may take in an area, large indeed in itself—no less than 425,000 square miles—but insignificant as compared with the area involved in a conflict between two naval Powers of the first rank. And yet there are some who think that the naval wars of the future will be decided in a few days, and conducted mainly in narrow waters by “vessels which do not love the open ocean!”

Proceed-
ings off
Queens-
town.

Admiral Rawson's return to Irish waters on July 31 was forthwith observed by some of the B cruisers, scouting in the neighbourhood, which after an insignificant skirmish made off, to report proceedings to their own side. The *DIADEM*, *IMMORTALITÉ*, *TALBOT*, *EDGAR*, *NAIAD*, *FURIOUS*, and *GLADIATOR* had rejoined the flag on the same day. The *FURIOUS* reported that the B fleet had been observed off Belfast, and this intelligence was confirmed by later intelligence from Queenstown. On August 1 the southern torpedo-boat flotillas which had been concentrated at Queenstown were ordered to join the flag, and Admiral Rawson, having thus gathered all his available forces together, shaped a course for the *Tuskar*, as though he intended to enter the Irish Channel and go to meet Admiral Noel, who was certain to come south as soon as he heard that the A fleet had reappeared. But this intention, if it existed, was not carried out. The weather had broken, the sea was rising fast, and soon became too rough for torpedo boats to operate with effect, or even to cruise without risk during the night. They were sent in to Waterford for the night, there to await orders. The torpedo gunboats which accompanied them rejoined in the morning, but the sea was still too rough for the torpedo boats, and the torpedo gunboats also were soon ordered to return. Moreover, as the wind and sea rose, the *EDINBURGH* and the *CONQUEROR*, which were already nearing the limit of their coal supply, began to labour heavily, and to lose their speed rapidly, the former carrying away her topmast, and the latter burying her bows so deeply that she could not possibly have fought the only powerful and well-protected armament she possesses. She was designed as a coast-defence vessel, with a specially powerful bow-fire. She could not keep the sea twenty miles from the coast in a summer gale, nor, if she could have kept the sea, could she have fought her guns. In other words, she is quite useless for the only purposes she was ever meant to fulfil—sorry purposes at the best—and for all other purposes she is worse

than useless. In company with the EDINBURGH she was ordered to remain at a rendezvous for the night, and to rejoin in the morning. When the morning came the enemy appeared, and then both ships were ordered to proceed forthwith to Queenstown, in order to avoid possible capture.

Thus the great Armada, collected and marshalled with such infinite pains to fight for and, if possible, to secure the command of the sea, was gradually dwindling away. When he reached the Tuskar towards evening Admiral Rawson deemed it prudent to go no farther. He was two ships short, destroyers were about, and he must wait for the chance of the weather so far improving as to enable him to put the EDINBURGH and the CONQUEROR again into the line in the morning. Accordingly he steered a south-westerly course during the night, returning towards Waterford in the morning, intending, if the enemy did not appear, to proceed towards Milford and there await him. It is not quite easy to understand the purpose of these movements and proceedings on August 1. The position of the enemy was known, and when Admiral Rawson was off Queenstown it showed that he could not possibly reach the southern entrance of the Irish Channel for at least twenty-four hours. Two courses would then appear to have been open to Admiral Rawson—either to go and meet the enemy with his whole force, or to wait where he was until the enemy appeared. The former was disallowed by the short and failing coal supply of two of his ships; but the latter would have enabled him to coal those two ships at Queenstown, and thereby to recover his full freedom of action so far as coal strategy was concerned. If he could not trust those two ships to take and keep their place in the line, he should, it would seem, have made up his mind to do without them. He would then have had ten ships, eight of which were real MAJESTICS, against thirteen on the other side, not one of which was a real MAJESTIC. The victory was to be won, if at all, not by numbers—for the A fleet all told was inferior in numbers to the B—but by tactics. If it could not be won by tactics it could not be won at all. Is it certain that eight MAJESTICS, together with the SULTAN and the DREADNOUGHT, could not have gained such a tactical advantage over the thirteen ships of the B fleet as would have induced the umpires to award the command of the sea to A? Moreover, the EDINBURGH and the CONQUEROR could probably have obtained at Queenstown coal enough to last them until the end of the manœuvres in a very few hours. That would have enabled Admiral Rawson to have gained a good offing during the night with all his force, and to have rounded the Tuskar before coming into contact with the enemy in the morning, and by keeping as near the Irish

Comments
thereon.

Coast as he could he might have found water smooth enough to enable his less seaworthy ships to manœuvre with effect. He would have encountered destroyers, no doubt. But a fleet which will not face destroyers in the day-time, and even risk encountering them at night, will never win the command of the sea. In any case the great game was to fight for the command of the sea with all his force if he could, with less than all his force if he must. If he was beaten he had done his best. If he was victorious he had done more than could well be expected of him. There can be no real struggle for the command of the sea unless both sides are prepared to fight for it when the time comes. The time could never come again. The manœuvres were to end the next day. In such circumstances a "fleet in being" is a beaten fleet. It had had an opportunity of fighting, and had declined it.

The final stage.

On the morning of August 2 Admiral Rawson, having despatched the EDINBURGH and CONQUEROR to Queenstown, was proceeding with his remaining battleships on his way towards Milford, when his cruisers thrown out ahead announced the approach of the enemy. Admiral Noel had received information of Admiral Rawson's reappearance in Irish waters from Port Patrick shortly before noon on August 1, and at once set forth with all his battleships to engage him, gathering on his way as many of his cruisers, destroyers, and other craft as were within call. The encounter at once took the form of a retreat on the part of A and a general chase on the part of B, which was sustained for hours with unexpected vigour on the part of the latter, regard being had to the legend speed of some of his ships. Admiral Rawson steered a south-westerly course against a strong head wind and heavy sea, and this obliged him to detach the DREADNOUGHT and send her to Queenstown. Being still pressed at a speed of thirteen knots, the SULTAN, which could hardly keep station at that speed, was ordered to make direct for Berehaven, and the remainder of the A fleet, now reduced to eight battleships of the MAJESTIC and ROYAL SOVEREIGN classes, quickened to 14 knots. This was more than B could attain, and about 3 p.m. Admiral Noel gave up the chase, having sustained it with great tenacity for over four hours, and withdrew towards Milford, leaving some of his cruisers to follow A for an hour or two longer. Thus the manœuvres ended, rather ignominiously for A and not very decisively for B. Neither could claim the command of the sea, but B could certainly claim that he was ready to fight for it when A was not. A might claim that if he could have lived to fight another day his "fleet in being" might have become a fleet in action, and possibly a victorious fleet. But as both fleets ceased to exist as opposing forces at 2 a.m. on the

following day, his "fleet in being" really ended its days as a fleet in retreat.

The fast craft operations associated with the operations were of the usual active and varied character. They included the operations of scouts and look-outs attached to the main fleets, of single cruisers engaged both as scouts and messengers, of detached bodies of cruisers, and of torpedo craft. The torpedo boats attached to A were, for reasons which will be considered presently, not actively employed by Admiral Rawson at the outset of the operations, and at their close they were prevented by the weather from fulfilling the purpose for which they had been reserved. The destroyers attached to B were much more active, much more effective, for that reason, and perhaps a little too adventurous. They proved singularly useful as scouts for certain purposes, such as the examination of the enemy's anchorages and possible shelter places, and as fast messengers—"gallopers," as they might be called—but they suffered heavily, and were not very successful in offence, nor always quite trustworthy in observation. On one occasion a destroyer was said to have passed, at night, six friendly battleships steaming without lights, and to have mistaken them for hostile torpedo-boats. On another, a destroyer was literally caught napping by a portion of the A fleet off Lough Swilly, and appeared to be quite unconscious of an enemy's presence until fire was opened on her. Six destroyers in all were put out of action by the umpires as having been captured, sunk, or otherwise destroyed. But twenty-six other claims were made, several being duplicates, all of which were disallowed by umpires. On the other hand, the claims made by destroyers were not numerous, nor was any ship adjudged to have been torpedoed. The *Les Reaulx*, a so-called distilling ship, of pitiful speed and contemptible condensing capacity, was claimed as a prize by the *Leopard* off Lough Swilly on the morning of the first day of hostilities. This claim was allowed by the umpires, as was inevitable, but the *Les Reaulx* was no great loss to the A fleet. Her storage capacity was 853 tons, but she could only distill some twenty-seven tons daily, which is not much more than half as much as a MAJESTIC could accomplish for herself, and she could only pump about ten tons an hour. She had left Berehaven on the morning of July 22, with orders to proceed to Lough Swilly, which, with very moderate speed, she ought to have reached before hostilities began at 2 a.m. on July 24. As she failed to do this, she naturally fell an easy prey to the first destroyer which arrived off Lough Swilly. The incident proves—not that properly equipped fleet-auxiliaries are a mistake—but that inadequate fleet-auxiliaries are more than useless. For the rest, the *Seal*, *Wolf*, and *Locust* were adjudged to have dis-

Fast craft
opera-
tions.
Des-
troyers.

abled the *SPEEDWELL* off Lough Swilly, though whether by torpedo or gunfire is not clear, but the claims of the *Kestrel* to have torpedoed the *GIBRALTAR*, and of the *Wolf* to have torpedoed the *PROMETHEUS*, were disallowed. These, with a disallowed claim of the *Cheerful* to have destroyed some searchlights at Queenstown, were all the claims presented by destroyers. They contrast significantly with the claims allowed against them, and still more with the claims presented against them but not allowed, especially when it is considered that for many days during the period of hostilities the whole of the battleships of the A fleet and many of its cruisers were altogether out of the range of destroyer operations. As a menace the destroyer is exceedingly formidable—indeed, against torpedo boats its menace is little short of a positive deterrent; as a messenger, and for certain purposes as a scout, it is within certain limits almost invaluable. But its offensive power against large ships well handled and keeping a sharp look-out would seem to be still in some measure undetermined. The power sometimes imputed to it in this respect is perhaps exaggerated. If it is not, if destroyers can deny access to narrow seas to powerful and well-equipped fleets, it is clear that we shall soon have to revise the current estimates of the relative value of different elements of naval force. If the destroyer is to this extent master of the battleship, either singly or as flotilla against fleet, then the battleship at once becomes not only a ship that loves the open ocean, but a ship that must fight there if at all. Yet the experience of the manœuvres, as far as it goes, seems to make against this view of the matter. The *DIADEM* and her division of cruisers were in the Irish Channel from the morning of July 27 to the evening of July 28, being about midway between Holyhead and the Isle of Man at midnight, and yet they were never attacked by destroyers, though they must have encountered several, as more than one was claimed by them. On the other hand, the temerity too freely displayed by destroyers during the manœuvres in remaining in daylight within reach of the guns of larger ships, even at very long range, might tend in actual warfare to their rapid disablement and extinction.

Torpedo
boats.

It has already been said that Admiral Rawson kept his torpedo boats in hand, intending to use them, if he could, in his final onslaught on his adversary. His action in this respect is perhaps open to criticism, and it certainly diminished his chance of finding the numbers of the B fleet when he did encounter it reduced to an equality with his own, if not to a position of inferiority. But the question is quite open to argument, as was shown at the time by the correspondent already quoted: "He thought he could better employ his torpedo boats in wearing out the enemy's destroyers in a prolonged and fruit-

less search for a prey which persistently refused to show itself, than in exposing them to a conflict in which they were so heavily handicapped. For such a policy there is not a little to be said. Torpedo boats, not being an independent and self-sufficient element of naval force, are perhaps little adapted to take an active part in a struggle which can only be decided by the conflict of sea-going ships at sea. Their effective range of action is very limited; they can do little or nothing within that range unless they know exactly when and where to find the enemy they are seeking, and even within that range they are no match for destroyers. It is not much use to send torpedo boats to sea on a roving search for enemies who may possibly come within their very narrow range of action, and who, if they do so come, will almost certainly be accompanied by destroyers. Naval warfare in all its initial stages is at all times very much like looking for a needle in a bundle of hay, but a torpedo boat, which can only work at night—it is a nocturnal animal, small, indeed, and very venomous, but with very indifferent nocturnal vision—is a very poor agency for the prosecution of such a search; and it is the special prey of other nocturnal animals, larger and more agile, endowed with a keener vision and a much more deadly sting. Hence the policy of keeping torpedo boats in hand until the struggle for the command of the sea is decided—or, at least, until issue is finally joined—is by no means so pusillanimous or so ill advised as it might at first sight appear to be.” Acting on these views, Admiral Rawson kept his torpedo boats in reserve until the last moment, when he hoped for an opportunity to employ them with effect; but, as we have seen, the weather entirely frustrated his design. One singular incident may, however, be mentioned as tending to show that the torpedo boat still shares with the destroyer the power of operating on occasion by means of menace. The *Minerva*, scouting off the west coast of Ireland, got amongst a fleet of fishing boats off the Skelligs, on the night of July 27. Mistaking them for torpedo boats, and remaining among them apparently for some hours, she persuaded herself that she must have been torpedoed, and, loyally hoisting the “Blue Peter”—the signal for being out of action—she proceeded quietly to Milford, there to await the decision of the umpires. As no torpedo boats were nor, under Admiral Rawson’s orders, could have been engaged, the decision was naturally given in her favour. But the action of the *Minerva* was remarkable, not to say quixotic. Such an incident could not, of course, happen in war, but, even in war, cruisers which mistake fishing boats for torpedo boats are likely to meet with strange adventures, and to play the enemy’s game rather than their own.

Cruisers.

It is impossible here to follow the cruiser operations in all their details. But one important and very instructive engagement between two opposing divisions of cruisers is entitled to special notice. At the outset of hostilities, Admiral Rawson had organised a very powerful division of swift cruisers, consisting of the *DIADEM*, *IMMORTALITÉ*, *TALBOT*, *EDGAR*, *GIBRALTAR*, and *NAIAD*, and instructed it first to get touch, if possible, with the enemy's fleet, and to report its strength and presumed movements to himself, and afterwards to act as a flying squadron preying upon the enemy's commerce, harrying his torpedo craft, and generally doing as much mischief as it could. The first object was, as we have seen, speedily accomplished, and the information obtained proved of great importance to Admiral Rawson, and determined the whole course of his proceedings. In obtaining it the *DIADEM* and her consorts ran some risk of a serious encounter with the B 1 fleet at an early stage of the proceedings, but Admiral Noel's claim was disallowed by the umpires. Subsequently an incursion was made into the Irish Channel, and here, the *TALBOT* being temporarily detached, the division came into conflict on July 28 with a similar division organised by Admiral Noel under Commodore Poë, consisting of the *St. George*, *Ariadne*, *Vindictive*, and *Hawke*. On observing the enemy, the *DIADEM* and her consorts at once gave chase, altering course eight points to port together so as to come into line abreast astern of the enemy. The *IMMORTALITÉ* was ordered to take the starboard position, and gradually to edge away to starboard, so as to prevent the enemy making off in that direction, though it is not easy to see how a single ship could have that effect, or could avoid weakening her own force by taking up a more or less isolated position. It gave her, however, the opportunity of raking the enemy's whole line as he advanced. Commodore Poë, seeing that an action could not be avoided, inasmuch as the *Vindictive* was temporarily disabled in one engine, and could maintain no higher speed than some twelve or thirteen knots, decided to take his chance, and, being in line ahead, he altered course sixteen points to starboard in succession so as to engage four of his enemy's cruisers before the *IMMORTALITÉ* could support them. As he neared them he altered course to starboard again, so as to pass across their front, and, seeing this movement, the *DIADEM* and her three followers altered course in succession to starboard, so as to take up a position parallel to Commodore Poë's line, the *IMMORTALITÉ* ultimately falling in astern. By this movement the *NAIAD*, the rear ship of the *DIADEM*'s line, was brought under the fire, at close range, of each of Commodore Poë's four ships in succession, and was subsequently adjudged by the umpires to have been sunk. As the evolution adopted by the *DIADEM*'s


division was adjudged by the umpires to have produced this result, it must clearly have been a faulty one, though how that result could have been avoided must be left to professional tacticians to decide. The incident is instructive as showing that superior strength may often be neutralised by the superior tactics of a weaker force, and it may perhaps be added that no theoretical study of tactics is likely to enforce this lesson so cogently as actual experience at sea.

It only remains to say a few words about the proceedings of the military authorities at the ports where the military defences in their charge were brought into co-operation with the naval forces engaged. As the instructions on which they acted have not been made public, it is only possible to judge by results. Of the state of preparation in which the military defences were found, and of their adequate adaptation to the requirements of the case, it must suffice to say that the correspondents afloat gave no very reassuring account, though no doubt the officers in charge spared no pains, and did their best with the materials and resources available. But, to judge by the reports from both sides, they showed a very imperfect grasp of the requirements and conditions of naval warfare. "Their zeal is unimpeachable," wrote the correspondent already quoted, "but it is not always according to knowledge, certainly not according to naval knowledge. When they get hold of a searchlight and play it over a minefield entrusted to their charge they . . . work it in season and out of season, more especially when friendly ships are navigating an intricate and difficult passage—as actually happened when the A1 fleet left Berehaven at the outbreak of hostilities, and . . . when the B fleet returned to Berehaven at their close. It never seems to have occurred to them that a navigator cannot see his leading marks with a searchlight blazing into his eyes. . . . I have already mentioned how the *FURIOUS*, returning in urgent haste to Berehaven, failed altogether to attract the attention of the military authorities until she was preparing to anchor, when they incontinently fired on her, and how Admiral Rawson was kept waiting for nearly an hour off Dunaff Head, in Lough Swilly, before he could get permission from the military authorities to go any farther. I have now to mention that the *SULTAN* experienced exactly the same treatment as the *FURIOUS* when she returned to Berehaven at the close of the hostilities, and I dare say the same thing would have happened to the whole of the A fleet if the war had not been over for some hours before it put in an appearance. All this is amusing enough, and I have not attempted to treat it too seriously. But it has its serious side. It is at least serious enough to show that military officers are not to be trusted with the land defences of a

Military
co-operation.

naval port unless they possess some rudimentary knowledge of the conditions and requirements of naval warfare. The moral seems to be that inasmuch as naval and military forces must co-operate on many occasions in war, the conditions which make for their effective and intelligent co-operation should be systematically studied beforehand, so that military officers may learn to understand what they can do and what they cannot, what they must do and what they must not, when engaged in the local defence of a naval port. For lack of this knowledge they are apt to do many very foolish things, and to try to do many quite impossible things. But systematic study and intelligent forethought are not in fashion in this country. Our faith is rather in the makeshift and the make-believe, in the improvised and the ill-co-ordinated. It is a very costly faith, and withal a very dangerous one. We squander millions where pence would be thrown away, and even the pence we wisely spend are often wasted for lack of knowledge.

JAMES R. THURSFIELD.



"IDZUMO,"
JAPANESE FIRST-CLASS ARMoured CRUISER.

CHAPTER VI.

MARINE ENGINEERING.

DURING the past year the chief event of interest in the field of naval engineering has been the appointment by the late First Lord of the Admiralty of a committee to inquire into the working of the Belleville boiler in the Royal Navy. This alone would be sufficient to again bring forward the boiler question to a position of first importance, for the marine engine, as applied to warships, has undergone no change of any magnitude during the last twelve months, if we except the Parsons steam turbine. Another boiler event of considerable importance to naval engineers was the issuing last summer of an Admiralty "Memorandum respecting Water-Tube Boilers in H.M. Ships" (C.D. 250). This report chiefly dealt with the extensive trials of the Highflyer and the Minerva. As the data embodied in it are among the most important that have yet been published in connection with the performance of water-tube boilers of the large tube type, it is necessary to refer to it here at some length.

Admiralty
Boiler
Com-
mittee.

The memorandum points out that "the use of small tube boilers has hitherto been confined in the Royal Navy to third-class cruisers and smaller vessels, where the importance of securing high speed on small dimensions justifies the acceptance of boilers which have a shorter life than is desirable for large ships." So far as the British Navy is concerned, that is perfectly true, but other countries have been somewhat more progressive. For instance, Armstrong, Whitworth & Co. have now in hand for a foreign Power two small ironclad ships which are to have all boilers of the Yarrow type. As the same firm completed some time ago a cruiser of 12,500 horse-power also with the same description of boilers, it may perhaps be safely concluded that the type gave satisfaction. The Dutch Navy authorities have had considerable experience with this boiler. In a former issue of the *Naval Annual* particulars were given of three cruisers of 10,000 horse-power that were built in Holland. In each of these three-fourths of the power was supplied by Yarrow boilers, and one-fourth by boilers of the ordinary cylindrical type. The experiment appears to have been also satisfactory, as since then three cruisers, each of 10,000 horse-power, have been completed for this Government, and three armoured vessels

Admiralty
Memo-
randum
on water-
tube
boilers.

Foreign
war vessels
with small
tube
boilers.

are now in hand. The Swedish Government have also built, or are about to build, seven cruisers and armoured vessels, the most powerful being of 12,000 horse-power. The Austrian Government have three cruisers built and one building, the latter of 13,000 horse-power, besides an ironclad in progress of 14,000 horse-power, and I understand two more armour-clad vessels are being designed. This would give a total of twenty-six vessels having small tube boilers of the Yarrow type, excepting the three mentioned which have one-quarter of their steam-generating plant in ordinary boilers.

The Thornycroft type of small tube boiler has also been placed in foreign war vessels, some of them being of the largest and most powerful type. They include two German battleships and five cruisers, two first-class battleships (the Missouri and the Ohio) of 16,000 horse-power each for the United States Navy, and two coast-defence ships for Denmark.

The list of vessels above-named does not include torpedo craft, although destroyers are always very high-powered, some far more so than much bigger vessels. It need hardly be said that all torpedo craft are now fitted with water-tube boilers of the small tube type. Probably other small tube boilers of other patterns, or of other names, have been placed in large vessels, but one need not go beyond the two pioneer types of British small tube boilers to show that confidence is being gained in their use.

Tubes.

Returning to the Admiralty memorandum, we find detailed reasons given why the small tube class has not hitherto been favoured for large vessels. The first is that "the tubes of small tube boilers are much thinner than those of the large tube types, and the maximum power of the boilers is obtained by forcing, which also tends to shorten their life." Of course both these statements are incontrovertible, but, in regard to the first, it may be said that the smaller diameter tubes have purposely been made of thinner metal in order to attain special ends (chiefly lightness), for which it is worth sacrificing other qualities in exceptionally high-speed vessels. It is to craft of this description that the Admiralty experience of small tube boilers has been almost entirely confined. The small tube boiler is, however, so very much lighter, power for power (as was shown in last year's *Naval Annual*), than any other type that something in regard to the quality of lightness might easily be sacrificed to durability; the metal of the tube might, therefore, be materially thickened up, and yet leave the advantage in weight on the side of the small tubes. No doubt the gauge of metal in small tubes cannot be brought up to an equality with that of the large tubes in Belleville and kindred types, but there are other things

besides thickness of metal which are conducive to the longevity of a boiler—circulation being one of the most important.

In regard to the second objection above mentioned—that the maximum power is obtained by forcing—that is true of all boilers capable of being forced. One of the greatest merits of the small diameter, direct-tube type is that it can be forced without damage. This is a most valuable property in a warship boiler, and might easily decide the fate of an action. It is something that the naval commander would always have in hand for an emergency, when the shortening of the life of the boiler would be the merest bagatelle.

“The Admiralty policy has been,” the report continues, “to consider the Belleville boiler, in which they have had more experience than with any other type of water-tube boiler, as the approved type for large ships, treating other types as experimental until they have shown that they possess some distinct superiority.” When the water-tube boiler, in some form, was forced on the Admiralty authorities, the Belleville boiler was the only one with which extensive sea-going experience had been gained, and the engineering advisers of the Board could hardly have done otherwise than recommend its adoption. Other types of large tube boilers have since been tried. “Two long series of trials have been carried out,” the report states, “in the Sheldrake and the Seagull with the Babcock and Wilcox and the Niclausse boilers respectively, for comparison with those previously carried out on Belleville boilers in the Sharpshooter.” We are told that: “Each of these boilers has its advantages and drawbacks, but the trials showed no decided advantage of either over the Belleville boiler. The experiments were, however, considered to justify further trials of both on a larger scale, and it has been decided to fit the Babcock and Wilcox boiler in one of the new sloops, and possibly in one of the two new second-class cruisers, and the Niclausse boiler in a new sloop and in a first-class cruiser of the Monmouth type.”*

The Admiralty authorities deserve great credit for their open mind in this matter, and the step completely refutes the accusation, very unfairly brought against them, that they are “wedded” to the Belleville boiler. The Niclausse type has tubes large in diameter and approximately horizontal; and in this respect it resembles the Belleville boiler. The tubes in the Babcock and Wilcox boiler are at a standard inclination of 15 degrees from horizontal. In some

* It has since been stated in the House of Commons that, “The Challenger, the sister ship to the Encounter, is being fitted with Babcock and Wilcox boilers for comparison with the Belleville boilers in the latter ship. Babcock and Wilcox boilers are also being fitted in the Espiegle and Odin, and Niclausse boilers in the Suffolk, sister ship to the Cornwall, and in the Merlin for comparison with other ships of the same classes fitted with Belleville boilers.”

other important points, however, both boilers differ materially from the Belleville type, and as they are about to be tried in His Majesty's Navy, it is well perhaps these differences should be here explained.

Belleville.

In the issues of the *Naval Annual* for 1897 and 1898, sectional views of the Belleville boiler were published, and the principle on which it operated was set forth. It is hardly necessary to go over




FIG. 1.

the whole ground again, but for convenience of reference a few words may be said about the circulation of water and steam in order to compare the Belleville with the two other boilers mentioned. Fig. 1, on this page, is a sectional view of a Belleville boiler of the economiser type, but the economiser has been left out, as it does not affect our present description. In the view only one element of the boiler is

shown, this being a side elevation; but it will, of course, be understood that the whole boiler consists of a number of elements placed side by side. The feed water is pumped into the drum at the top left hand corner, and from thence it descends by a vertical pipe, not shown in the engraving, to the bottom end of the zig-zag of tubes which form the steam-generating element. From thence the water ascends through the element—which is in the course of the flame and heated gases—and is more or less evaporated during its progress, the steam and evaporated water being discharged into the drum. The steam is taken to the engine, and the surplus water mixes with the fresh feed water and falls through the vertical pipe to be again passed through the element.

It is as well to repeat here that the success of a water-tube boiler depends largely on the vigour of the circulation of steam and water in the generating tubes; and in the Belleville boiler this circulation is a good deal checked by the length of tube in the element, and by the numerous sudden bends at the junctions of the various lengths. So much is this the case that non-return valves are placed near the bottom end of each element to prevent a reversal of the circulation.

The Babcock and Wilcox boiler is shown diagrammatically in Fig. 2, on page 124, and an engraving of a complete boiler is given in Fig. 3, on page 125. Water is pumped into the drum at the top and falls by gravity through the short length of pipe, shown in Fig. 2, and passes to the header, into which the tubes are fixed at one end. The other ends of the tubes lead into the back header. It will, of course, be understood, that the whole boiler is composed of a number of vertical rows of tubes, placed side by side, each one corresponding to the element of the Belleville boiler. The headers are rectangular in cross section—square tubes they might roughly be called—each vertical row of generating tubes having its own back and front header. It will be seen, therefore, that the water and steam have not to pass through a long, tortuous passage exposed to the heat of the furnace, as in the Belleville boiler. For instance, a given quantity of water may pass from the drum into the front header, fall right to the bottom, and then enter the lowest tube, through which it would flow to the back header, and then ascend, as water and steam, to pass back into the drum by the two top tubes. Other water may pass through the top row of tubes, and other quantities again through the intermediate tubes. It will be noticed that above the two bottom tubes a space is left where two other tubes might have been placed. This is done in order to provide a combustion chamber, where unconsumed gases may be burnt before they are cooled below the temperature of combustion. This is a detail of

Babcock
and
Wilcox.

practice that need not be considered in studying the general principle of the boiler. In Fig. 2 the course of the products of combustion is shown by feathered arrows. It will be seen that baffle plates of fire tiles are placed among the tubes to prevent the gases from passing too directly to the chimney. In this way they are made to distribute their heat more evenly over the whole of the tube surface. The direction of water and steam circulation is shown by dotted arrows.




FIG. 2.

Circulation.

In this boiler circulation is maintained by the difference between the specific gravity of a column of solid water in the drum and the front header, and the specific gravity of a column of mixed water and steam in the inclined generating tubes and the back header. In the Belleville boiler, any water entering at the bottom of an element must necessarily pass through the whole length of the tubes forming

that element, for there is no other road open to it; though it is possible any one element might refuse to take water—from some untoward cause,—because the feed distributing pipe is common to all elements. The Babcock and Wilcox boiler stands on a different footing. Thus, if the feed were limited, all the water might descend




FIG. 3.

by gravity to the bottom of the element, and pass only through the lower tubes, leaving the upper ones bare. On the other hand, it has been objected in regard to this boiler that if the circulation were very rapid, it is conceivable that the water would take the shortest course and switch off from the header into the first opening it came to, which would be the upper rows of pipe. What actually

occurs is a matter of conjecture, though the conditions might be laid down theoretically by mathematical calculation. Probably the lower tubes would always have the advantage owing to the increased head, due to their position, available for circulation. This would be felt to the fullest extent if feed were restricted, and the ratio of water to steam in the column in the back header were lowest. Naturally it is desirable that the bottom tubes should be best protected by water, as they are nearest the fire.*

Niclausse. We now pass to the Niclausse boiler, of which Fig. 4, page 127 (taken from *Engineering*), shows diagrammatically the steam-generating portion. Here also the horizontal tubes are arranged in vertical rows or elements, much as in the Babcock and Wilcox boiler, but the circulation is provided in quite a different way. There is but one header common to each vertical row of tubes, and this is placed in front, there being no back headers at all. The tubes are closed at the back end, being therefore free to expand and contract at will. This is an advantage that the Niclausse boiler possesses. Its value is variously estimated; but it may be stated that in the Belleville boiler tubes have been pulled out of the junction boxes into which they are screwed. This is attributed to defective threads; and no doubt it is better to use expanded joints rather than threaded tube ends. The front header—the somewhat complicated structure of which is very much simplified in the diagram—is divided vertically into two parts by a diaphragm, thus forming an inner and an outer chamber. The inner chamber communicates with the generating tubes exposed to the action of the flame and hot gases. These larger tubes, closed at the ends, have inside them smaller open-ended tubes, which pass right through the inner chamber and also through the diaphragm so as to communicate with the outer chamber.

The circulation here is due to the difference in specific gravity of the column of water in the outer chamber and the specific gravity of the column of mixed steam and water in the inner chamber. The cycle, which is easily followed by means of the arrows in the diagram, is as follows:—Water from the drum falls into the outer chamber, and from thence passes along the inner tubes. Out of these it flows, coming back along the annular space formed between the walls of the inner and outer tubes. Here the steam is generated, and the mixture of water and steam passes into the inner chamber, and from thence back into the drum. The steam is taken to the engine, and the unevaporated water falls again, to pass once more through the

* Since the above was written I have been informed that model experiments show that the harder the boiler is driven, with such steam pressures as could safely be carried in glass tubes, the more brisk the circulation in bottom tubes becomes.

tubes along with the new feed-water. All horizontal tube boilers possess the defect of their type in regard to circulation. With vertical tubes the steam as generated can pass upwards to the steam drum at once; in horizontal tubes it ascends to the top of the tube, where it is inclined to stop.

Mr. Thornycroft, in conjunction with Mr. Marshall, of Newcastle, has recently introduced a new description of water-tube boiler, which is illustrated in Fig. 5, p. 129. It will be seen that there is here a single header or flat chamber into which a number of pairs of tubes are expanded at one end. These pairs are joined at their opposite ends by junction boxes. There is the usual drum into which the feed water is pumped, and from thence descends from the two pipes shown

The
Thorny-
croft-
Marshall
boiler.




FIG. 4.

into the header, from whence it is distributed to the tubes. The inclination of these being upward, the tendency of the steam is to pass to the flat chamber, and having there risen to the top, it will flow into the drum by way of the pipe which enters the drum above water level. The tubes in this boiler are 3 inches in diameter, and the steam drum is of large capacity, the proportion adopted being about .04 cubic feet per I.H.P. The flat chamber or header is also of fair proportions, being about 9 inches deep.

The design of the boiler is ingenious, but it will not take the place of the older Thornycroft type. It would hardly be suitable for forcing, as the head available for circulation is small. The tubes, though bent, are open to inspection throughout. At the back end they are expanded through the inner wall of the flat chamber, on the outer wall of which are placed—opposite each tube end—covers or

inspection doors, of which two only are shown in Fig. 5. At the front end the junction boxes are also fitted with covers as shown. The curve of the tubes is such that, when the covers or doors at each end are removed, it is possible to see halfway down the tube from either end, so that the whole tube is open to inspection. It is worth noting that it is easier to establish the position of a flaw on the interior of a curved tube than it is to do so with a perfectly straight tube. The large number of made joints in this boiler is an undesirable feature.

The High-
flyer—
Minerva
trials.

The Highflyer and Minerva trials, already mentioned, were of an extended nature. These two cruisers are identical in form and external dimensions, but there are differences between their machinery. The former ship has eighteen Belleville, and the latter eight cylindrical boilers. The Highflyer has four cylinder triple-expansion engines of 10,000 horse-power and the steam-pressure is 300 lbs. in the boilers, reduced to 250 lbs. at the engines. The Minerva's engines are three cylinder triple-expansion of 9,600 horse-power, the steam-pressure being 155 lbs. in the boilers and 150 lbs. at the engines. The weight of the Highflyer's main and auxiliary machinery is 373·8 tons, and of her boilers 461·5 tons. The weight of the Minerva's main and auxiliary machinery is 380·1 tons, and of her boilers 557·8 tons. The advantage on the side of lightness was therefore 102·6 tons in favour of the Highflyer.

The era of competition between the shell-boiler and water-tube boiler for navy work is past. We are never likely to go back to tank boilers for warships, and the practical question now to be answered is what type of water-tube boiler shall be adopted. The competition between the Highflyer and the Minerva is so instructive, however, that the trials will be noticed at some length, and later on two tables are given showing the observed results of evaporation tests. A circumstance that lessens the value of the trials, especially the early trials, for comparative purposes, although it strengthens the moral to be drawn from them, is that "the Highflyer," to quote the Admiralty report, "had been only recently commissioned for the first time, and, with few exceptions, the crew had had no previous experience with Belleville boilers."

Results of
untrained
crews.

The result was what might have been expected. To get good results, especially in regard to fuel consumption, with a Belleville boiler skilled stoking is undoubtedly needed, in order to keep the large grate area completely covered with a fire not too thick. On the first trials at the moderate speed of about 10 knots the Minerva's cylindrical boiler burnt 2·88 lbs. of coal per I.H.P. developed; whilst the corresponding figure for the Highflyer was 3·46 lbs. of coal. The

Coal con-
sumption.

difference, of course, is very large and sufficient to counterbalance the gain in lightness on the side of the Highflyer. The matter is accounted for. Whilst the Minerva made her run without mishap, in the Highflyer there were, to quote the report, "two generator door




FIG. 5.

joints and seven economiser door joints leaky, and two fusible plugs were renewed."

These defects also made themselves manifest in the quantity of "make-up" water that had to be put into the boilers to replace that wasted. In the Minerva it was 5 tons for the 60 hours, but in the

Lost
water.

Highflyer it was no less than 42 tons. On two other trials of 60 hours each much the same results were recorded: boiler joints leaking, and both coal and make-up water largely in excess. Undoubtedly the Belleville boiler came out very badly on the three runs.

These results were so inferior to those recorded on the contractor's trials of the Highflyer that it was determined to have another run of 60 hours at low power. Previously to this being made, however, an inspector of machinery, experienced in the management of Belleville boilers, was sent on board, and the ship was sent to sea purposely for training the stokers. A marked improvement was the result. The coal consumption was brought down to 3·16 lbs. per I.H.P. per hour and the water consumption to 16 tons. Before the stokers had been trained the excess of coal burnt on the Highflyer over that of the Minerva was 16·5 per cent.; and this was reduced to 6·7 per cent. by the short period of instruction. At higher powers the coal consumption improved still further, the best figure for the Highflyer being at 9,132 I.H.P., when the fuel burnt was 2·36 lbs. per I.H.P. per hour; a result which indicates how wastefully the engines were working at the low powers, and also showing the misleading nature of trial data which include both engine and boiler performance. The Minerva's best record was 2·11 lbs. of coal per I.H.P. per hour.

Comparison,
Highflyer and
Minerva.

It will thus be seen that even at her best the Highflyer was beaten by the Minerva in regard to fuel consumption; and in the important matter of water wasted the advantage was enormously in favour of the tank-boilered ship. That is a point to which reference will be made later. At her best, however, the results of the Highflyer's trials were so much less satisfactory, in regard to coal consumption, than those obtained on the official contractor's trials, that the naval authorities concluded there was something wrong with the machinery, and on opening up at Devonport it was found that the low pressure valves and faces were much worn and not bearing satisfactorily, a circumstance that would account for considerable loss.

Speed.

In the matter of speed the Highflyer showed a distinct superiority, as she excelled the Minerva by nearly a knot (·94), comparing the best performances of both ships. In trials made to test the time taken in raising steam, the Belleville boiler naturally showed a very great superiority.

If it should be thought that the trials of the Highflyer and Minerva are here given more in detail than the instruction to be gained from them warrants, I would point out that so much has been said in the press and elsewhere about the preference shown to the Belleville boiler, that I have been, perhaps, over-anxious to put this chapter beyond such a reproach. In spite of the extra

speed of the Highflyer, her extra coal consumption on the early trials and the additional water consumed show the Belleville-boilered ship to disadvantage. For these reasons the results are given in detail. It can only be said that these trials are neither typical nor crucial. This view is borne out by subsequent performances, but more especially by water evaporation tests made later on with the Hermes and Diana.

The Hermes—a second-class cruiser that later became notorious through her misfortunes—has Belleville boilers, her machinery being identical with that of the Highflyer. The Diana has cylindrical boilers. Both these ships were fitted with tanks for measuring the feed water, and trials were made. Unfortunately, the quantity of feed evaporated by the two descriptions of boilers respectively is not given in the reports, although the coal burnt per I.H.P. per hour and the weight of water used per I.H.P. per hour for all purposes are recorded. If the mean power developed be known, the water evaporated can be deduced. The figures as to horse-power are, however, so roundly stated in the case of the Hermes that some hesitation may be excusable in using them for the purpose; and again the auxiliary engines come in as a disturbing factor. The trials, on this more crucial test, are distinctly in favour of the Belleville boiler as the figures stand. “At the higher powers,” to quote the official report of the trials, “the quantity of water passing through the engines, and the coal consumption, were both less in the Hermes than in the Diana; whereas, at the lower powers, although the coal consumption was still slightly less in the Hermes than in the Diana the water used by the former was more, showing that the boiler was more economical, but more steam was used in the engines.”

The
Hermes—
Diana
trials.

The results of these trials are so instructive, outside their bearing on the question of cylindrical *v.* water-tube boilers, that the tables from the report are given in full on the two following pages.

There is a good deal in these tables worthy of note. For instance, when the Hermes was running at 2,000 I.H.P., about one-fifth of her full power, more coal was burnt in terms of the power developed than when she was fully pressed. If coal per I.H.P. were alone taken as a measure of efficiency of the boilers, as is so often done, it might be concluded that a higher boiler-efficiency was obtained on the high-speed run. This, however, is against common experience, for, within reason, the more easily a boiler is worked, the more economical it becomes; and therefore if different ships had run these two trials—say, ship A with shell boilers for the high-speed trial, and ship B with Belleville boilers for the low-speed trial—we should have been apt to say, “How much more economical

Engine
and boiler
efficiencies.

H.M.S. DIANA.—RESULTS OF WATER CONSUMPTION TRIALS.

| Description of Trial. | Percentage of Full Power. | Steam Pressure. | | | Lbs. of Water per I.H.P. per Hour. | | | Lbs. of Coal per I.H.P. per Hour. | REMARKS. |
|--------------------------|---------------------------|-----------------|---------------------|----------------|------------------------------------|------------|---------------|-----------------------------------|--|
| | | Boilers. | Engines, Starboard. | Engines, Port. | Main Engines. | Auxiliary. | All Purposes. | | |
| 30 hours at 800 I.H.P. | 8·3 | 101 | 96 | 97 | 20·59 | 5·68 | 26·27 | 2·82 | |
| 12 hours at 1,600 I.H.P. | 16·6 | 124 | 120 | 121 | 18·94 | 4·21 | 23·15 | 2·52 | Cut-off in horse-power cylinder 38 per cent. |
| 30 hours at 1,600 I.H.P. | 16·6 | 117 | 113 | 113 | 18·26 | 3·29 | 21·55 | 2·52 | Cut-off in horse-power cylinder 44·5 per cent. |
| 30 hours at 4,800 I.H.P. | 50·0 | 133 | 128 | 128 | 17·09 | 2·14 | 19·23 | 2·02 | |
| 30 hours at 6,400 I.H.P. | 66·6 | 138 | 129 | 129 | 17·9 | 2·56 | 20·46 | 2·38 | |
| 8 hours at 8,000 I.H.P. | 83·3 | 150 | 144 | 144 | 17·75 | 1·94 | 19·69 | 2·39 | |

H.M.S. HERMES.—RESULTS OF WATER CONSUMPTION TRIALS.

| Description of Trial. | Percentage of Full Power. | Steam Pressure. | | | Lbs. of Water per I.H.P. per Hour. | | | Lbs. of Coal per I.H.P. per Hour. | REMARKS. |
|---|---------------------------|-----------------|---------------------|----------------|------------------------------------|------------|---------------|-----------------------------------|--|
| | | Boilers. | Engines, Starboard. | Engines, Port. | Main Engines. | Auxiliary. | All Purposes. | | |
| 12 hours at 1,000 I.H.P. | 10.0 | 241 | 169 | 176 | 21.9 | 5.2 | 27.1 | 2.5 | Main links linked up as far as practicable—cut-off in horse-power cylinder 13.5 per cent. |
| 12 hours at 1,000 I.H.P. | 10.0 | 163 | 124 | 123 | 20.1 | 6.67 | 26.8 | 2.3 | Main links in full gear—interdependent links run in. |
| 30 hours at 2,000 I.H.P. | 20.0 | 196 | 126 | 127 | 17.06 | 4.22 | 21.28 | 1.76 | Cut-off in horse-power cylinders 47.8 per cent. |
| 30 hours at 7,500 I.H.P. | 75.0 | 263 | 223 | 222 | 15.3 | 2.1 | 17.4 | 1.57 | |
| 12 hours at 7,500 I.H.P. (Closed exhaust system in use.) | 75.0 | 264 | 228 | 219 | — | — | 16.84 | 1.5 | Auxiliary exhaust at 26 lbs. pressure in use on evaporators and surplus to L.P. receivers. |
| 8 hours at 9,000 I.H.P. (Closed exhaust system in use.) | 90.0 | 270 | 249 | 244 | — | — | 17.13 | 1.54 | Auxiliary exhaust at 29 lbs. pressure in use on L.P. receivers only. |
| 8 hours at 10,000 I.H.P. | 100.0 | 240 | 231 | 228 | 15.64 | 2.05 | 17.69 | 1.58 | |

the tank boiler is than the water-tube boiler, as it can beat the latter even when it is pressed." An examination of the engine records, which the measurement of feed-water enables us to make, shows that the comparatively poor economy at low speeds does not rest with the boiler, but with the engine. At the high-speed trial the main engines needed but 15.64 lbs. of water evaporated to develop one horsepower for an hour, but at the lower speed nearly $1\frac{1}{2}$ lbs. more were needed, and on one run at the lowest speed no less than $6\frac{1}{4}$ lbs. more.

Defects of
low-power
working.

At low-running speeds, with a high range of expansion of steam in the cylinders, excessive liquefaction takes place, with all its consequent evils; and there is also the higher ratio of power absorbed by friction. Very much the same conclusions may be reached by a comparison of the Diana experiments, although with them the difference is not so marked.

Priming.

These figures, therefore, emphasize strongly the misconceptions that may arise through judging boiler performance from records of coal per I.H.P., a practice the undesirability of which has been more than once commented upon in the *Naval Annual*. At the same time, it is but fair to state, evaporative tests of boilers with measured feed-water may in themselves be misleading. In the first place they are very difficult to make, and need the greatest care in measurement and supervision. With every desire to be honest on the part of the staff, a little carelessness may upset the truth of the records. That, however, is common to nearly all machinery trials, but boiler tests are beset with a danger of their own. A boiler may prime or may supply steam so wet that a great deal of unevaporated water may be carried over with the steam. Such a boiler would be likely to show high evaporative efficiency, but it would be supplying steam that would effectually prevent the engine appearing to advantage, however good it might be if fairly treated. There are certain methods known to engineers by which the amount of unevaporated water mixed with steam is estimated; but it may be said that a good method for practical work has yet to be introduced.

The
engine
as a calori-
meter.

An engine, the performance of which is well known, forms in itself a very fair instrument for testing the quality of steam. For example, it may be that the steam used by a given engine is 15 lbs. per I.H.P. per hour when driven by a boiler at moderately low rates of combustion, while the measured water evaporated per hour per lb. of coal is 9 lbs. If now the fires be forced, and we find that the water evaporated rises to 11 lbs. per lb. of coal, whilst the engine needs 22 lbs. of steam, we may fairly suspect the boiler of adulterating its steam pretty heavily with hot water, supposing of course the steam is used at proper grades of expansion.

In examining the two tables of performances of these ships, the much higher steam pressure in the Belleville boilers will be noticed. It need hardly be said that theoretically the higher the steam pressure, the greater the economy, and no doubt the superior efficiency of the *Hermes* is largely to be attributed simply to increased pressure of steam. It is assumed, of course, that the *Diana's* boilers were clean and free, not only from scale, but any deposit due to grease. I believe the ship had recently returned from a commission abroad, but no doubt her boilers were well overhauled before the trials.

But although high steam pressure is a most desirable thing for economy's sake, it has its drawbacks and dangers, due not only to excess of pressure, but also to its increased heat. If we consider its advantages, we ought also to refer to its disadvantages. During the trials of the *Highflyer*, we hear of generator door joints and economiser door joints leaking badly, and of joints in main steam pipes leaking. As the report very justly states, "higher pressures necessarily require greater perfection in all such parts as slide valves, piston-rings, and stuffing-boxes, as well as in all joints. The higher the pressure, the more steam will pass through any leak without doing useful work. The waste of steam from stuffing-boxes and joints is generally visible, but that which passes through any defective piston rings and slide valves, in either the main or auxiliary machinery, can generally only be discovered by taking the machinery to pieces." These passages are well worth bearing in mind by all who have charge of marine machinery, and, indeed, by all who are engaged in its manufacture also. In fact, higher pressures demand higher work, not only from the maker, but also from the operator. There must be a levelling up all round. In regard to the escape of steam from cylinders through stuffing-boxes, one engineer, at least, has essayed to meet the difficulty by greater accuracy of workmanship: Mr. Yarrow, the well-known torpedo-boat builder, having recently stated at a meeting of a technical institution that he proposed grinding piston rods smooth and truly cylindrical, in place of leaving them as turned by the lathe. This plan, I believe, has been followed out at the Poplar works, and possibly other makers of engines in this country have adopted the practice. A true fit of the cylinder rod in the packing is also a great advantage, as it tends to keep oil from being carried up into the cylinder, and from thence to the boiler, where its presence is sure to cause trouble. While speaking on this subject, I would like to call the attention of British engineers to the extended use abroad of the emery-wheel grinder. Both in the United States and Germany I have lately seen this machine-tool used with the greatest advantage in connection with a system of

Leaky
doors and
joints.

Loss of
steam
through
stuffing-
boxes.

special gauges, surface and fit being obtained at a cost that would not be possible to attain by the older systems. Of course emery-grinding has long been known in this country, but the practice appears to be more extensively adopted in the United States shops, and the Germans are fast following the Americans in this and other branches of engineering practice.

Conden-
sers.

A good deal of trouble has been caused in ships of the Royal Navy by leaky condensers, and here not only is fresh water lost, but salt water is liable to be introduced into the boiler. In some of the later ships the condensers are so arranged that one half can be shut off for examination and repairs whilst the other half is in operation. Condenser troubles generally arise, we are told by an Admiralty return, through the splitting of tubes; although pitting is also a fruitful source of trouble. Where condenser tubes are held between tube plates, it has been thought that vibration is largely accountable for splitting, but whether this be so or not, it would doubtless be safer if these delicate tubes were so arranged that the steam passed inside them and the refrigerating water outside. In that case the vacuum would be formed in the tubes, and they would thus be subjected to compression, so that incipient cracks, in place of opening, would be closed up. If surface condensers could also be arranged on the principle of the Niclausse boiler, practically as a series of Field tubes, so as to be free to expand and contract in place of being rigidly held between two tube plates, there would be less likelihood of leaky joints, and consequent contamination of the feed water by salt. Whilst speaking of the different effect of having pressure inside or on the outside of tubes, it may here be pointed out that in this respect the water-tube boiler is at a distinct disadvantage as compared to a fire-tube boiler, much trouble having arisen, not only through splitting, but also through lamination of tubes in water-tube boilers.

Pitting of condensers may be met by tinning. Mr. Yarrow, from whom we all gain so much instruction on these questions in the present day, has stated, during a discussion on the subject, that he has by actual experiment traced pitting to the action set up by different alloys in the metal of which the tubes are formed. The refrigerating water pumped through the condenser of course sets up a galvanic couple, which, intensified by the heat of the steam, leads to the well-known result. The defect is overcome by tinning the tubes, so long as the tin lasts. The period may be prolonged by the presence of zinc, but the remedy must be freely applied, and the slabs of zinc so distributed that no part of the condenser is beyond their influence.

That higher steam pressures lead to increased liability to leakage has been pointed out, but there is one advantage accruing from the same source which does much to counterbalance the defect. It will be noticed that in the full-power trial of the *Hermes* the steam pressure was reduced between the boiler and the engine by about 110 lbs. to the square inch. This is effected, as is usual in the Belleville system, by means of a reducing valve. Now it will be evident that in this case, if the full boiler pressure be maintained in the steam pipes, they can be made of smaller diameter than they would have to be if only the initial pressure in the engine were in them, and therefore they would be more flexible. With a water-tube boiler, more especially of course a small tube boiler, extra pressure is not a serious matter, so far as the strength of the boiler is concerned; and additional pressure can be reduced at the engine to that suitable for working. But, on the other hand again, the throttling of steam, or allowing it to expand without doing work, leads to superheating, and this in turn makes lubrication difficult, and the cutting of valves and valve faces or of cylinder walls more likely to occur. The scoring of valve faces has been already a serious source of trouble in engines supplied with steam by Belleville boilers, and it is worth considering whether throttling may not have been conducive to this end.

Smaller
steam
pipes.

Taking all points into consideration, however, the most prevalent; and from one point of view the most serious, cause of leakage and loss of fresh water probably arises in those water-tube boilers that have large numbers of doors, hand-holes, and screwed joints. The danger is serious because it is insidious; leakage may go on from a defective boiler joint without being discovered. The steam that escapes is invisible, and is quickly absorbed by the hot and dry gases. An analysis of chimney gases will generally reveal the defect, but such analyses are not often made in practical work. With the vast number of joints that there are in many descriptions of water-tube boilers, very small leaks in a moderate proportion will account for a very serious loss of water. Whether the great excess of make-up water needed for the *Hermes* on her trials is to be accounted for in this way or not we have no information; but it is on record that she afterwards broke down at sea, was disabled for three days, and had to be towed to port, "the cause of failure being the great leakage of water combined with persistent failure of the feed pumps"; the latter probably the result of over-work. The boilers were seriously damaged, and a large number of tubes had to be replaced.

Loss of
feed
water.

During the manœuvres of 1899 the Belleville boilers of the

Experi-
ence
during
the
man-
œuvres.

Argonaut developed serious leaks from their doors, and from the joints in steam pipes; the Europa also suffered from a similar cause. A more recent mishap has been the giving way of a tube in the Belleville boilers of the sloop Mutine, unhappily attended by loss of life. The latter accident appears to have been due to failure of circulation, but as pieces of wood, and a steel bar 6 inches long and $\frac{1}{2}$ inch in diameter, were found in the boiler after the accident, it would be unfair to attribute this mishap to defects in the design.

All these mishaps to the Belleville boiler have been seized upon by those who have made a business of opposing the introduction of the water-tube boiler into the Navy. These persons have taken little notice of the advantages offered by that type of steam generator, and they have been careful to forget the still more serious defects that were developed by the adoption of higher pressures in cylindrical boilers. For instance, during the manœuvres four Belleville boiler ships were included in those told off for the task of picking up the convoy, whilst a cylindrical boiler ship had to return, as she could not maintain the speed. A cylindrical boiler ship had also to go back to port, being short of water. It is stated that 20 battle-ships, 22 armoured cruisers, 10 protected first-class cruisers, and 9 second-class cruisers, or 61 ships in all, now fitted with Belleville boilers, would have had each a knot less speed had return-tube boilers been used. Such facts as these are all conveniently forgotten when an attack has to be made on Admiralty engineers, who, it must be remembered, are debarred by official regulations from making any reply, however much they may be vilified, and however strong a case they may have.

Wasteful-
ness of
over large
engines.

The tables on pp. 132 and 133, giving the results of the evaporative trials of the Diana and the Hermes, afford some useful illustrations of the working of high pressure steam as used in the engines. Reference having been so often made to the advantages of high pressure steam, it is right that an instance on the other side should be given. It will be noticed that the first two runs of the Hermes were made at the same power, but the results as to economy came out very differently. In the first run the boiler pressure was 78 lbs. higher than during the second trial, whilst in the engines also it was about 45 to 50 lbs. higher in the first trial. With the higher pressure of steam on the first trial, however, the coal consumption was one-fifth of a pound per I.H.P. per hour higher than on the run when the pressure was lower. Naturally, in order to get a like terminal pressure in the engines, the higher pressure steam would have to be worked at a greater number of expansions, and that it was so worked is shown by the fact referred to in the "Remarks" column, that on the first

trial steam was cut off in the high pressure cylinder so early as 13·5 of the stroke. In the second trial, the lower pressure steam was admitted to not far from half stroke, and naturally worked less expansively. The result of working with too much expansion and too little steam in a big engine is well shown in the column giving pounds of water per I.H.P. per hour. The results would have been far more favourable had the engines been a tenth of their actual size. It will be seen also in the Minerva's trials that with equal power developed, as on the second and third runs, the economy of the engines was improved by lengthening the period of steam admission and reducing the expansions; although here the difference was not great, the cut-off being 38 and 44½ per cent. of the stroke for the two trials respectively. The boilers did better, apparently, on the first of the two runs, as the coal per I.H.P. comes out the same in each case.

It will be seen from the details here given how difficult it is to design a warship to give satisfactory economy. The average merchant vessel has boilers and engines proportioned for giving the best results at the one speed she always runs at. Her engines need not be too big, and her boilers may be big enough. The fighting ship must have very big engines for high fighting speed, and these are wasteful at lower or ordinary speeds. But to give this fighting speed the boilers must be light, that is small, and they are wasteful at high speeds. In other words, when the engines are doing well the boilers are not, and *vice versa*.

Whilst dealing with the use of high pressure steam, there is another point to which reference may be made. The heat of saturated steam necessarily increases with the pressure, and the sensible heat of the water in contact with the steam also increases. The readiness with which heat is taken up by water, in a given boiler, depends on the extent to which the furnace and the furnace gases exceed the water in temperature. In other words, heating surface in a low pressure boiler should be more effective than if the steam were at higher tension. Naturally this would make the chimney gases colder, and therefore less heat would be thrown away in the funnel. The greater advances in coal economy effected during the last thirty years or so have been made in the engine and not in the boiler. There is, however, another reason why modern cylindrical boilers are not as economical as the old rectangular flue boilers, for the latter afforded more space for combustion. The big-tube boilers of the water-tube type have not taken advantage of the opportunity for improvement offered them in this respect. In the Belleville boiler, as explained in a previous issue of the *Naval Annual*, an effort has

Efficiency
of heating
surface.

been made to get over this defect by air jets above the fire, but the device has not been altogether successful to judge by the reports one hears as to "black smoke." The design of small-tube boilers is more satisfactory in this respect.

Exhaust
steam of
auxili-
aries.

There is one more point to which attention may be drawn before leaving the *Hermes* trials. The question of auxiliary machinery was discussed at some length in last year's *Naval Annual*. In the tables on pp. 132 and 133 it will be seen that the trials at 7,500 horse-power and at 9,000 horse-power were those at which the best economy was obtained, not only in fuel burnt, but also in water consumed by the engines. On these two runs it will be further noticed that the exhaust steam from the auxiliary engines was carried to the evaporators or to the low pressure stage of the main engines. On the other trials it may be presumed the auxiliary exhaust was taken to the auxiliary condensers direct—a deplorable thing to do with steam at 26 lbs. and 29 lbs. pressure. There is, it will be seen, a distinction between these two trials. On the first, 7,500 horse-power, the evaporator received part of the steam, the surplus only being taken to the main engine. This gives the best result. The water used is over $\frac{1}{2}$ lb. less (0.56) per I.H.P. per hour than on the previous trial at the same power and approximately the same pressure. There are drawbacks, on a war-ship—where it is desirable everything should be independent—in passing auxiliary exhaust steam to main engines, and for this reason one notes with satisfaction that the evaporators appear to be the better vehicles for using up this otherwise waste heat. The figures in the table bring this out very clearly.

Mechani-
cal stok-
ing.

The possibility of feeding the furnaces of marine boilers mechanically is a thing that is being constantly suggested, and a good deal of surprise that such a scheme has not been carried out is sometimes expressed by those who are not marine engineers. There is no doubt that a practical power-driven device that would take the place of the stoker's shovel would be a great blessing on board ship, and therefore any serious efforts in this direction are worth attention. Some time ago an enterprising firm of marine engineers in the North made experiments in this direction, but, so far apparently, not with any prominent success. The difficulties are considerable in marine boilers, far more so than in the case of land boilers. One of the chief is the lack of space. In the first place, for a mechanical or automatic stoker to be worked to full advantage the coal must descend to the first receptacle or hopper in front of the furnace by gravity. It needs a very slight knowledge of the bunker arrangements on board ship to see how serious an obstacle to success this is. The movement of the ship adds a disturbing feature, and the limited height of furnaces is

Difficult-
ies in using
afloat.

also a drawback. Moreover a good deal of the success of mechanical stokers on land is due to the fact that they enable a common description of smoky coal to be burnt with advantage; whilst at sea, with good Welsh coal, the less the fire is disturbed the better. It is not easy to find space in the boiler room for the mechanism of an automatic stoker, but this difficulty could be overcome if the bunker arrangements could be brought into line.

On the other side of the account, an automatic stoker that would proceed mechanically with its work during periods of great excitement, that would cover a fire grate evenly to an adjusted depth under given circumstances, that would do away with the frequent opening of the furnace doors, and that would relieve a ship's crew of about the most arduous and trying work civilised men have to perform; such an apparatus would indeed be a blessing to humanity. The even covering of the grate would permit of nice adjustment of air supply, because the feed of coal being constant and regular, the air needed for combustion would be the same at all times.

Advantages of automatic firing.

There are several descriptions of mechanical stoker. In one of them small coal falls on to a shovel, or sprinkler, in the mouth of the furnace. By means of springs and suitable mechanism the fuel is jerked over the fire in small quantities at regular and frequent intervals, with a view to keeping the grate evenly covered. Another invention consists of an automatic ram, which has imparted to it a horizontal reciprocating motion. The coal falls from the hopper on to a dead plate in the mouth of the furnace, and the ram entering the heap, gradually pushes the fuel forward after it has been coked on the dead plate. Another class comprises what are known as underfed stokers, and one of these has been tried afloat in America on a large scale, as the following facts will show.

Coking and shovel stokers.

The Minnesota Steamship Company own a vessel trading on the big American lakes, which has a displacement of over ten thousand tons, so it will be seen she is a ship comparable to our large ocean-going vessels in size. She is not very high-powered, however, her engines working up to about 1,600 horse-power. Steam is supplied by two Babcock and Wilcox boilers, a type in extensive use in American lake steamers. The steam generating tubes are 2 in. in diameter, and each grate is 65 sq. ft. in area. To each boiler there are fitted three of the American Stoker Company's mechanical stokers, which are of the underfed type.* The arrangement consists of a hopper placed at the boiler front in the position where the furnace

American automatic stoker.

* This type of automatic stoker is to be applied to a large steamship with water-tube boilers, now being built in England, by the Underfeed Stoker Company, of 31, Walbrook, E.C.

door would ordinarily be. The bottom of the hopper opens into an almost horizontal tube, which extends beyond to beneath the grate in the form of an open-topped trough. Inside the middle of the tube and trough, running through their entire length, is a conveyer, consisting of a shaft, round which is a worm of flat spiral. This is revolved by a small independent engine securely boxed in and placed at the outer end of the shaft.

The action is as follows: The coal falls from the hopper by gravity on to the worm, and as the latter revolves it feeds the fuel forward through the tube and then into the trough beneath the grate. The top of the trough being open, the coal rises through the slotted opening and overflows on to the grate. The sides of the trough bordering the slotted opening are wide enough to form a double dead plate—one half on each side of the opening—and here the coked coal is first deposited as it overflows in the furnace. By means of a blower air is forced beneath the dead plate and passes out amongst the fuel by openings at the side. This enables combustion to take place. No air enters from the ash pit in the usual way. The slotted opening and its marginal dead plate do not occupy the whole width of the grate, there being grate bars at the side and parallel with the opening. The coal, as it passes up from the trough, is coked by the heat of the fire above; the gases, being driven off gradually and continuously, permeate the glowing coke mass, there mixing with the air and being consumed; or if any ascend into the space above the fire, they are still subject to the radiant heat of the furnace, so that they will be burnt, supposing, of course, sufficient air to be present. The expansion of the gases among the coke during combustion keeps the mass of fuel moving, and materially assists the working of the furnace. In this way, if the apparatus works as it is intended to do, there is no smoke, and the other advantages incidental to mechanical stoking are secured. Naturally the zone of combustion cannot descend through the slotted opening into the mass of fuel in the trough beneath the grate, because air is not admitted to the trough.

Fires are cleaned by slicing between the bars and raking out clinker in the usual way, there being a furnace door on each side of the hopper. Firing by hand can be carried on through these doors should the apparatus break down. In the Pennsylvania the exhaust steam from the engines that work the stoker is admitted to the ash-pit. Such an arrangement is quite permissible in a vessel running on the fresh-water lakes—indeed the main engines have jet condensers—but would be a serious matter in a sea-going ship. The steam used in working the stoker and driving the fans is said to be $1\frac{1}{2}$ per cent. of that generated for all purposes.

An extensive series of trials was made with the Pennsylvania by Lieutenants B. C. Bryan and W. W. White, U.S.N., by direction of the American Bureau of Steam Engineering. The records of these experiments are given in the *Journal of the American Society of Naval Engineers*, Vol. xi., No. 3. The weight of each stoker complete as fitted in the Pennsylvania was found to be 3,500 lbs. There was one Sturtevant blower, 60 inches in diameter. The coal was of an inferior grade, giving on test 11,790 B.T.U. per lb. dry. The cost of operating all stokers and blowers was found to be 1.68 per cent. of the steam made, allowance being made for the blower exhaust passing through the feed heater. The stokers worked satisfactorily throughout, and "the steam required at all times was generated without difficulty, and, no doubt, with greater ease and economy than if hand firing had been employed. Only an extremely light smoke was observable during the ordinary working of the stokers. Practically, it may be said the coal was burned smokelessly, except when the cleaning doors were opened." A successful trial was subsequently made, coaling being carried on through the cleaning doors, "demonstrating the feasibility of feeding the furnaces by hand." It is stated in another report that "one fireman can readily handle four stokers, shovelling his own coal. With mechanical coal carriers along the front of the boilers, one man can handle from twelve to fifteen stokers." Probably this does not refer to marine practice.

In a former issue of the *Naval Annual* reference was made to the Inchmona, a merchant steamer fitted with four-stage compound engines having five cranks. These engines were designed by the late Mr. Mudd and built at the Central Marine Engine Works, West Hartlepool. It will be remembered that by means of various devices the fuel consumption was reduced to a very low point, about 1 lb. of coal being sufficient to supply steam to give 1 I.H.P. for an hour. It was questioned at the time by some whether the additional complication and expense involved was warranted by the saving in fuel; but that question is answered by the owners, Messrs. Hamilton, Fraser & Co. of Liverpool, having three more ships built with machinery by the same makers of a like description, although certain improvements of an important nature have been made by Mr. Borrowman, who has succeeded the late Mr. Mudd. According to data observed on a run made by one of these ships, the Inchmarlo, from Hartlepool to Dover, the coal consumption has been now brought down to the remarkable figure of 0.97 lbs. of coal per I.H.P. per hour. The cylinders are, high pressure 17 inches, first intermediate pressure 24 inches, second intermediate pressure 34 inches, and two low pressure of 42 inches, the stroke being 42 inches. They are of

Trials of
Pennsyl-
vania.

The Inch-
marlo.

1,600 horse-power. The boilers are of the cylindrical return-tube type and work at no less than 267 lbs. to the square inch. As they are 13 feet in diameter, it will be understood that the shell must needs be of rather massive scantling, and the plates are $1\frac{1}{2}$ inch thick, whilst the staying is unusually strong. Service tubes are fitted, with internal longitudinal ribs to collect the heat of the gases more effectually.

Heat-catching devices.

In order to reduce loss by escape of heat, every precaution has been taken. Except the high-pressure cylinder, all cylinders are completely steam-jacketed, including the tops and bottoms, and the asbestos lagging is of a very complete nature. Superheaters are so arranged that the steam on its way from the boilers to the engine passes through a series of pipes, which are placed in the uptake through which the heated gases are carried to the base of the chimney. The feed water is also heated before entering the boiler. After leaving the hot well it is filtered, and then brought into contact with a Weir's feed heater, where its temperature is raised from about 96 to 209 degrees. It is then taken to a surface-heater and is brought up to about 370 degrees. The temperature of the water in the boiler is about 412 degrees. The steam, which leaves the boiler at 412 degrees, is heated to about 470 degrees in the superheater, but about 23 degrees of this superheat are lost on the way to the engine, so that the steam enters the high pressure steam chest at a superheat of about 35 degrees. This was found to be due to inefficient lagging of steam pipe, and was entirely obviated in later steamers. The result is well shown in the indicator diagrams, the combined area of which—in spite of some wire-drawing due to the superheater—is about 88 per cent. of the calculated area of a combined diagram. Induced draught on the Ellis and Eaves system is used, and the air supplied to the furnace is heated in the following manner. The furnace gases, before passing to the fan—which is at the base of the funnel—and after leaving the superheater, are drawn through a series of tubes contained in a casing. The air to support combustion passes among these tubes on its way to the ashpits, and its temperature can thus be raised from 53 to 299 degrees. The furnace gases leave the tubes of the boiler at about 587 degrees; they part with 44 degrees in superheating the steam, and with another 39 degrees in heating up the air for combustion. They therefore enter the fan at 404 degrees, a temperature actually below the heat of the steam and water in the boiler.

Reasons for economy.

The design of the machinery in these vessels indicates the manner in which the economy of higher steam pressures, made possible by modern boiler practice, may be secured. The uselessness of over-

expansion has been already shown by the low-power trials of the *Hermes*, but high ratios of expansion are needed to secure the economy of high pressure, and therefore expansion through four stages has been adopted. This, of course, reduces the condensation in the cylinders as compared to the triple-expansion engine—for the same reason that the ordinary two-stage compound was an improvement on the simple engine, with expansion in one cylinder; but in order to still further prevent liquefaction of steam in the cylinders, the designers of these engines have not only applied a very complete system of steam jacketing, but also superheat their already very hot steam. These are heat-saving devices which prevent the temperature imparted to the steam in the boiler being carried through to the condenser without doing work. The heat from the jacket steam has to be paid for at first hand, but doubtless it is worth its cost, for nothing is worse than water in a cylinder, as Willans proved some years ago by a very pretty experiment. The superheating however, is obtained from the temperature of the waste gases, from heat that would otherwise go up the funnel; and the same may be said of the heating of the air for combustion.

With high pressure steam, necessarily high temperature also, it is more needful to work on this regenerative system. As already stated, the ratio of temperature between the furnace, or furnace gases, and the water in the boiler is a measure of the efficiency of any given area of heating surface of a boiler. As pressures increase, a nearer equality of temperature on the two sides of the boiler heating surface is reached; for, though it is quite possible to raise the heat of the fire by forced draught, or by heated air, as in the present case the degree to which this can be done is limited. Under these circumstances, the higher the pressure at which steam is generated, the higher is likely to be the temperature at which the products of combustion escape from the boiler, and unless means are taken to catch some of this waste heat, it passes uselessly up the funnel.

These, of course, are elementary considerations well known to engineers, but they are worth repeating here, because in the machinery of these merchant vessels they have been applied in a manner that appears to be remarkably successful, to judge by reports from well accredited authorities. The working out of the various devices to a fortunate issue has involved much labour, expense and experiment, and both the constructors and owners deserve credit for the result. It has been calculated that in this ship one ton of cargo is carried one nautical mile on an expenditure of one-third of an ounce of coal, and allowing coal to be 15s. per ton, one pennyworth would carry one ton of cargo 550 miles. The designer of warship machinery

A regenerative system.

The cost of transportation.

can hardly hope to reach such figures as these, at any rate on existing lines, because a cargo vessel, such as the *Inchmarlo*, is designed throughout to the end that she may carry the greatest weight over a given distance with the smallest expenditure of fuel; a feature which is quite secondary in a war vessel. Nevertheless the *Inchmarlo* is a useful example to naval engineers.

The
steam
turbine.

The steam turbine of Mr. Parsons continues to attract attention in marine engineering circles, but there is not much that is new calling for notice here. Since last June the *Viper* has only made two trials at Portsmouth, and has reached a speed of 33·8 knots with regulation weights, and limited to 3 in. of air pressure. With 5 in. she steamed 3 knots faster—namely, 36·8 knots. The fact shows how important a point the boiler plays in the design of these high-speed craft. She has been passed and goes into commission in about six weeks from the time of writing. The *Cobra*, the other destroyer with Parsons engines, has not been run since May of last year, and is now being altered to meet Admiralty requirements. She will be delivered at Portsmouth some time in May. It is intended that both these destroyers shall take part in the autumn manœuvres this year, so that there will doubtless be a good opportunity of learning how machinery of this class will act under the conditions of actual service.

In regard to the use of the steam turbine in mercantile vessels, there will, during the coming year, also be an opportunity of gaining practical experience. Messrs. W. Denny & Bros., of Dumbarton, have now in course of construction a passenger steamer which is intended for the Fairlie and Campbeltown route in connection with the Glasgow and South Western Railway Company. She is expected to start running about the 1st of July, and will doubtless prove one of the attractions of the Exhibition year. The vessel will be 250 ft. long by 30 ft. wide, and 6 ft. 6 in. draught. The engines will exert 3,500 I.H.P., and the speed will be from 20 to 21 knots. She will have a No. 2 modified Board of Trade certificate. There will be one large double-ended return-tube boiler. The shafts will be three in number, one screw being on the centre shaft and two on each of the side shafts. The performance of this vessel will be watched with the greatest interest.

The Boiler
Com-
mittee's
Interim
Report.

Since the foregoing was written, the Interim Report of the Admiralty Boiler Committee, to which reference is made in the opening paragraph of this chapter, has appeared. The document is one of considerable importance, and has led to a good deal of discussion in the Press. It has been criticised chiefly on the score that the *personnel* of the Committee was not of a nature which

enabled a true estimate being formed of the value of the Belleville boiler, and because the members, with one exception, had not had experience in the working of water-tube boilers. In regard to this objection, it may be pointed out that the members of the Committee are all trained engineers of eminence in their profession. Their names are as follows: Mr. J. A. Smith, R.N., Inspector of Machinery; Mr. John List, R.N.R., who is the Superintending Engineer of the Castle Line; Mr. James Bain, R.N.R., Superintending Engineer of the Cunard Line; Mr. J. T. Milton, Chief Engineer-Surveyor of Lloyd's Register of Shipping; Dr. A. B. W. Kennedy, who was for many years Professor of Engineering at University College, London; Dr. J. Inglis, who was the chief partner in the firm of Messrs. A. and J. Inglis, the well-known firm of engineers and shipbuilders of Glasgow. The president of the Committee is Vice-Admiral Sir Compton Domville, K.C.B., and the secretaries are Commander Montague E. Browning, R.N., and Chief Engineer William H. Wood, R.N.

The Committee are unanimous in the Report, with the exception of Mr. J. A. Smith, who may be said to have represented the Naval element. This gentleman, however, agrees with the tenor of the Report as a whole, but explains that, in his opinion, the Belleville boiler will give satisfactory results when carefully treated, and he thinks there is no necessity for delaying the progress of ships already designed for them. A good deal has been said about Mr. Smith not subscribing to the Report of his colleagues, but it will be seen from the words he quoted that he does not express any opinion very strongly opposed to their ruling. It may be that a boiler will act admirably under favourable circumstances, as no doubt the Belleville boiler has done and will in future do. In practical work, however, both in the Navy and in the mercantile marine, favourable conditions are not always secured, and a steam generator is needed that will not only "give satisfactory results when carefully treated," but can also be depended upon not to be permanently injured or break down when the treatment is perhaps less careful than might be desired. Turning to the main body of the Interim Report, we find the Committee first stating that they are "of opinion that the advantages of water-tube boilers for naval purposes are so great, chiefly from the military point of view, that, provided a satisfactory type of water-tube boiler be adopted, it will be more suitable for use in His Majesty's Navy than the cylindrical type of boiler." This expression of opinion, coming from a body of engineers so eminently qualified to speak, should be sufficient answer to those critics who desire a return to the cylindrical boiler. It is hardly necessary to repeat here that

Mr.
Smith's
reservations.

the water-tube boiler (not necessarily the Belleville boiler) has been adopted in all navies of the world, and, should it be determined by the Admiralty to return to the shell boiler, the British Navy would be placed in a position of distinct inferiority in regard to the speed of its ships.

Recommenda-
tions in
regard to
Belleville
boilers.

The Committee next state that they do not consider that "the Belleville boiler has any such advantage over other types of water-tube boilers as to lead them to recommend them as the best adapted to the requirements of His Majesty's Navy." The statement as it stands is somewhat colourless, and must be taken in connection with the recommendations that follow it. They are as follows:—

- (a) As regards ships which are to be ordered in the future; That Belleville boilers be not fitted in any case.
- (b) As regards ships recently ordered, for which the work done on the boilers is not too far advanced: That Belleville boilers be not fitted.
- (c) As regards ships under construction, for which the work is so far advanced that any alteration of type of boiler would delay the completion of the ships: That Belleville boilers be retained.
- (d) As regards completed ships: That Belleville boilers be retained as fitted.

These recommendations cannot be taken as otherwise than a condemnation of the Belleville boiler, though not of so sweeping a nature as to lead to it being replaced where it has once been put in position. Were the latter course proposed, it would be indeed almost impossible to carry out, as the engineers engaged on the Committee must have recognised. One of the great advantages of the water-tube boilers consists in the possibility of fitting it in a ship in small parts, so that the decks need not be disturbed and the general structural arrangement of the ship disorganised. Indeed, to re-boiler the whole fleet of vessels that have been fitted with the Belleville boiler—as some who claim to speak with authority have advocated—would be to reduce Great Britain for a time to the position of a second or third-rate naval power. As a matter of fact, the Belleville boiler is a great advance upon the naval type of cylindrical boiler which it replaced; and, though its merits are not so great as those of other types of water-tube boilers, largely owing to defective circulation, yet it can and has performed excellently for long periods of time under favourable circumstances.

The Committee have had under consideration four types of large

straight-tube boilers which have been tried in war vessels and are now being adopted on an extended scale in foreign navies. These are as follows: the Babcock and Wilcox boiler, the Niclausse boiler, the Dürr boiler, the Yarrow large-tube boiler. The two former have been fitted in vessels of the Royal Navy for experimental purposes with satisfactory results. The Dürr boiler is not well known in England, but was described some years ago in a paper read by Mr. Milton before the Institution of Naval Architects. I have never seen it in work, but gather that it is somewhat similar in principle to the Niclausse boiler, though doubtless there are differences in detail. There are internal tubes for circulation, the arrangement apparently being that of a number of Field tubes placed horizontally or approximately so; perhaps the worst position in which Field tubes could be placed. In these boilers, however, some head for circulation is afforded by the division of the water-chamber. The Yarrow boiler of the Express type, as fitted in torpedo craft, is well known in this country, and has been frequently referred to in former numbers of the *Naval Annual*. It was also illustrated in the issues of 1896 and 1898. The Babcock and Wilcox boiler and the Niclausse boiler are referred to on a previous page. What is described in the Report as the large-tube type of Yarrow boiler has been placed in a number of armour-clad vessels and large cruisers in foreign navies, as already stated in this chapter. It is essentially of the same design as the ordinary Yarrow boiler, but the tubes are somewhat larger in diameter and the metal in them is thicker. There is, however, one point in connection with this subject which was not previously mentioned, but of which advantage may be taken to point out here. In the Yarrow system a certain size boiler tube may be determined upon, dependent upon the need of any navy, and that size should be adopted throughout all war-vessels in that navy. The tubes being in every case straight, interchangeability of tubes is ensured. In time of war, when speedy repair becomes absolutely necessary, this point is of vital importance. The comparison has already been made between the Yarrow boiler and the Belleville boiler in the *Naval Annual*, and it is hardly necessary to go over the whole ground again. The great advantage the Yarrow boiler possesses is that its tubes are but slightly inclined from the vertical, as compared to the Belleville boiler, in which the tubes are almost horizontal. The communication between the water vessels and the steam separator is much shorter and more direct in the Yarrow boiler. The result of these features is that the circulation in the latter type of steam generator is far more vigorous, and it can therefore be operated with safety under forced draft, but it will perform equally well under the more ordinary conditions of

Other
boilers to
be tried.

steaming. The fact that all the tubes are expanded in place of being screwed, and that there is not a multitude of small doors and hand-holes, is also a point very much in favour of the boilers of this type. As already stated, the loss of water on some of the trials of the Belleville boiler was exceedingly great, and this has been attributed to small leakages at innumerable joints.

It has already been said that the Babcock and Wilcox and Nielausse boilers are being fitted into Government vessels, and the Committee recommend that the work on these should be hurried on, so that they may make practical trial of the boilers mentioned. They also recommend that boilers of the Dürr and of the modified Yarrow type should be made and tested at the earliest possible date. These recommendations have been adopted, and the work has been commenced since the Report was issued. The following are what the Committee consider the practical and serious objections in the design of the Belleville boiler:—

Defects of
the Belle-
ville
boiler.

- (a) The circulation of water is defective and uncertain, because of the resistance offered by the great length of tube between the feed and steam collectors, the friction of the junction boxes, and the small holes in the nipples between the feed-collector and the generator-tubes which also are liable to be obstructed, and may thus become a source of danger.
- (b) The necessity of an automatic feeding apparatus of a delicate and complicated kind.
- (c) The great excess of the pressure required in the feed-pipes and pumps over the boiler pressure.
- (d) The considerable necessary excess of boiler pressure over the working pressure at the engines.
- (e) The water-gauges not indicating with certainty the amount of water in the boiler. This has led to serious accidents.
- (f) The quantity of water which the boiler contains at different rates of combustion varying, although the same level may be shown on the water-gauges.
- (g) The necessity of providing separators with automatic blow-out valves on the main steam-pipes to provide for water thrown out of the boilers when speed is suddenly increased.
- (h) The constant trouble and loss of water resulting from the nickel sleeve-joints connecting the elements to the feed collectors.

- (i) The liability of the upper generator to fail by pitting or corrosion, and, in economiser boilers, the still greater liability of the economiser-tubes to fail from the same cause.
- (k) The upkeep of the Belleville boiler has so far proved to be more costly than that of cylindrical boilers; in the opinion of the Committee this excess is likely to increase materially with the age of the boilers.
- (l) The additional evaporating plant required with Belleville boilers, and their greater coal consumption on ordinary service, as compared with cylindrical boilers, has hitherto nullified to a great extent the saving of weight effected by their adoption, and, in considering the radius of action, it is doubtful whether any real advantage has been gained. The Committee are not prepared, without further experience, to say to what extent this may not apply to other types of water-tube boilers.

The Report further states that at the time the Belleville boiler was introduced into the Navy, in the Powerful and Terrible, it was the only large-tube type of water-tube boiler that had been tried at sea on a considerable scale under ordinary working conditions. The Committee, therefore, consider that there was justification for then regarding it as the most suitable type of water-tube boiler for the Navy.

In speaking of the addition of the economiser, it is stated that, "in view of the rapid deterioration of economiser-tubes in several vessels, the Committee have specially considered whether the extra power per ton of boiler at high rates of combustion, obtained by the use of economisers, has not been too dearly purchased. The evidence before them indicates that at the lower and more usual rates of combustion, the Powerful type of boiler has given results as satisfactory as the economiser type. It is at the same time less complex and free from the special risks of tube deterioration, which have proved so serious in many cases, notably in the Europa. They therefore recommend, for ships under construction, that the non-economiser type should be reverted to where practicable, with the tubes raised higher above the firebars to increase the combustion space, and that where possible the steam collectors should be made larger and more accessible internally."

Econo-
misers.

It is recommended, however, that cylindrical boilers should be maintained for distilling and other auxillary purposes in harbour as well as at sea. The shell type of boiler is considered more suitable

and economical than any type of water-tube boiler. The statement is somewhat comprehensive, and one would like to know whether it is to be taken as applying universally. At any rate, the Report advises that all new vessels of large power should be provided with cylindrical boilers to do the auxiliary work.

The public will look forward with interest to the publication of the full Report, which, however, will doubtless not appear for some considerable time. It is proposed to carry out further trials of somewhat extended nature, including a run of the *Hyacinth* and the *Minerva*, fitted respectively with Belleville and shell boilers, from Portsmouth to Gibraltar and back.

G. R. DUNELL.

CHAPTER VII.

THE MANNING OF THE NAVY AND MERCANTILE MARINE.

THE manning of the Navy and mercantile marine is a subject, as all admit, of national importance. Under the changed conditions of this age of steam, new and grave difficulties have arisen in furnishing an adequate supply of seamen. The best seamen of the present day are worthy successors to those of the elder generation. We see with regret the rapid reduction in their numbers. Fifty years ago we had 200,000 British seamen in our mercantile marine ; we have scarcely half that number at the present time. Our British A.B.'s and firemen in the over-sea trade will soon be outnumbered by foreigners and Lascars. For the trade through the Suez Canal to India and the Far East the men of the tropics are better adapted than those of our Northern race. British seamen and firemen must suffer—it is almost inevitable that they should deteriorate—if serving continually under the rays of a vertical sun. In other branches of trade it would be well if our ships were manned more fully than at present by British subjects. The falling off in numbers is the more deplorable, because it is mainly amongst the younger men. The state of things is grave, and calls for the attention of statesmen.

Our inadequate national supply of seamen.

We may dismiss from view the difficulties with which the ship-owners have to deal. The efficient manning of their ships is a question of wages. It is not the business of the State to favour any industry, however important, by supplying labour partially paid from the public exchequer.

Viewed from another standpoint, that of those employed in the mercantile marine, the state of things leaves much to be desired. It will be admitted that those who follow the sea are insufficiently compensated in pay for the social privations of a calling in which the bread-winner must leave his home to earn his livelihood. Wages, however, cannot be fixed by legislative enactment. Whether under free trade or protection, remuneration depends on large economic causes which lie beyond the control of the Legislature. The ship-owner complains of that competition, both under the British and the

foreign flag, which often makes his hazardous business barely remunerative. Seamen are exposed to the same competition in its acutest form. The report of the Manning Committee of 1896 is very emphatic on this point. The whole world has been open as a recruiting ground to British shipowners; they have not been hampered in their selection by any restriction as to colour, language, qualification, age or strength. It is idle to propose a return to the old Navigation Laws; our shipping industry, in common with other industries, has greatly prospered under free-trade; the country will not lightly reverse a system under which great interests have been created.

The increase of the permanent naval personnel.

War strength maintained in peace time.

Reserves should be strengthened.

Officers of the mercantile marine.

There is, however, another aspect of the question before us. It has been and will continue the policy of the State to maintain such a Navy as will command the seas. In pursuance of that policy, shipbuilding for the Navy has been increased in vast proportions. For the manning of the ships which we are rapidly adding to the fleet, the Admiralty has relied mainly upon the permanent force. In round figures it has been doubled since I first entered Parliament. If the increase continues in the same *ratio* during the next decade a heavy burden will be imposed upon the taxpayer. The ports will be crowded with men for whom it will be difficult to provide sufficient training at sea. Never before in history has it been attempted by any maritime power to maintain in peace the full numbers required to man the Navy in time of war. Reliance has been placed on a force in reserve, of which the French "Inscription Maritime" is the earliest, as it is still the most perfect, example. The French maintain a reserve capable of supplying 40,000 efficient men to the Navy, and that from a mercantile marine, the tonnage of which, in comparison with our own, stands in the relation of one to ten. It seems no exaggeration to say that we require at least 50,000 men in our Naval Reserves. A deficiency in engine-room complements could rapidly be made up from the mercantile marine. To train seamen is more difficult. The fostering care of the State is needed. It is my object to urge that a great national duty should no longer be neglected.

Dealing first with the officers of the mercantile marine, the aid of the State can be justified in so far only as it may be necessary to provide for the manning of the Navy. In comparison with continental countries, little has been done by the British Government for nautical education. The Naval University at Greenwich is open to merchant officers; an efficient college has been established at Liverpool by the municipal authorities. Few have been found to avail themselves even of these limited opportunities. The reason is

obvious. There was no prospect of reward for labour bestowed on mathematical studies.

While the State has done little, private enterprise has come in to supply what was wanted. An excellent combination of theoretical and practical training for officers is afforded to the cadets of the merchant service on board those well-known school-ships, the Worcester and the Conway. While the professional education has been admirably begun in these school-ships, no adequate provision has yet been made for professional training at sea. Here again the aid of the State can only be justified in view of the necessity for an efficient reserve of officers. That some assistance should be given in providing facilities for the sea training of officers for the Reserve is a proposition, as I venture to think, not open to question. Under present conditions it is not reasonable to look to the merchant navy to supply a large reserve of officers having the comprehensive professional attainments which we find in the Royal Navy, as the result of a long and elaborate course of training. To bring a reserve fully up to the level of a permanent force is neither necessary nor feasible. Much may, however, be done to extend the very limited opportunities of training for officers at present available. Training.

Here I may perhaps permit myself to refer to an unaided effort to remedy the present unsatisfactory state of things. To meet the wishes of parents and guardians anxious to send their boys to sea, I purchased two sailing ships, the Hesperus and the Harbinger. In each twenty-four midshipmen were carried. An experienced officer of the Royal Navy conducted the school work, embracing all branches of a practical nautical education. As a scheme for the training of young officers at sea the experiment was highly successful. Our lists were always full. The cadets were of the right stamp and quality, full of ardour for a nautical career. They had the distinguished bearing and attractive manners which we admire so much in the gun-rooms of the Royal Navy. Unfortunately the vessels were of an obsolete type. Year by year increasing losses fell on their unfortunate owner. His poverty, but not his will, consenting, the ships have been sold at a loss to the omnivorous foreigner. It was some compensation to receive the grateful letters of parents and guardians, and to find that the boys, on the completion of their training, never failed to get berths in the best services. I am glad to know that in the Macquarrie and Illawara, vessels of larger tonnage, sailing under the flag of Messrs. Devitt and Moore, the work begun in those pioneer vessels is still being carried on. Private efforts.

A training ship, organised in all important particulars on the lines already described, has recently been fitted out by the North German Lloyd. To the management of great services such as that of the P. and O., the White Star, the British India, or Union Companies, it would be a small matter to equip a training-ship under their own house flag, following the lead of their German competitors. I hope they will do so.

The duty
of the
State.
Progres-
sive in-
crease of
the reserve
of officers.

As I have already said, the aid of the State can only be justified on the ground that we have not sufficient numbers in the mercantile marine with the high qualifications required in those to whom we look as a reserve of officers for the Navy. Such a reserve is indispensable. It was the only means by which an addition urgently wanted could be made quite recently to the lieutenants' list of the Royal Navy. Looking to the future, it is evident that the increase in the list of Royal Naval Reserve officers must proceed *pari passu* with the additions to the strength of the Navy in ships. If the recommendations to which I shall call attention in favour of training-ships for seamen should be carried into effect by the Government, an opportunity will be offered for carrying forward the training of officers on a scale commensurate with the requirements of the great fleet we are creating. The cost of training officers for the Reserve should be met by fees. They would be moderate in amount in comparison with the cost of education on board the Britannia.

Though not directly connected with the subject before us, I may, perhaps, interpose suggestions having for their object the improved efficiency of the officers of the Reserve. To secure the cream of the mercantile marine, the Reserves Office should be assisted in making selections for commissions by an advisory committee of shipowners at the principal ports. All Reserve officers should be probationers until they have served not less than a year in a man-of-war, and been in all respects favourably reported upon by the captain under whom they served. I need not dwell on the advantages which would result from the adoption of these suggestions. They will readily commend themselves to those who know the Reserves.

More discrimination in making first appointments, higher standards of qualification and longer service in the Navy, may involve as a necessary consequence improved pay to the Reserve officers. If such should be the case, and a larger number of desirable billets should be thrown open to the mercantile marine, it will tend to accomplish that which on other grounds is so much to be wished, namely, that advancement in the position of mercantile marine officers which the economic conditions make it impossible to achieve by more direct means.

In closing this portion of my subject, I may appropriately remark that the closer connection with the Navy, which has been brought about through the creation of the Reserve Force, has been of undoubted value to the mercantile marine by raising the status of officers, enlarging their experience, and instructing them how to maintain discipline among large bodies of men.

I pass from the officers to the seamen. From the repeal of the Navigation Laws onwards the necessity has been felt for some alternative means of furnishing that ample supply of seamen obtained under the protective system of former days. There is a general concurrence of opinion in favour of naval training-ships at the great ports. They were recommended by the Manning Commission, to which the first enrolment of the Reserve is due. The Commission proposed that school-ships should be established at the principal ports, capable of accommodating from 100 to 200 boarders on each ship, of whom 100 should be supported by the State. The schools were to be under the Board of Trade, the military part of the training under the Coastguard. It was assumed that in all 2,400 apprentices would be supplied annually by these schools, and that shipowners would be willing to take the whole number. In the altered conditions of the present day the payment of subsidies for taking apprentices has become necessary. School-ships were strongly recommended by the Royal Commission on unseaworthy ships. Seamen.

The Manning Committee of 1894, under the presidency of Sir Edward Reed, recommended that training-ships, or schools with a small vessel attached, should be established round the coast. In the opinion of the Committee, the deterioration of British seamen, as to which many witnesses had spoken, was owing in great measure to an insufficient number of boys being trained. While the Legislature had recently provided for technical education by grants from the Exchequer, there was no branch of training more directly profitable to this maritime country than the preparation of youths at the public expense for service at sea, primarily available for the Royal Navy, but available likewise for the mercantile marine. These unanimous and valuable recommendations have been too long neglected. School-ships at the ports, for apprentices to the Royal Naval Reserve, should be established without delay. The necessity of establishing school-ships.

Having established the harbour training ships, the seaman's apprenticeship at sea, no less than that of his officer, demands consideration. Hitherto we have looked to the sailing ships of the mercantile marine to supply seamen for the Reserve. A serious diminution in this source of recruitment has for some time been in progress. Not on sentimental grounds, but upon a serious view of Sea training.

the grave consequences in the impaired efficiency of our seamen, it is to be regretted that sailing ships are disappearing from under the British flag just as the types were attaining perfection. They are disappearing, not because it is of vital consequence to make a saving of twenty days in the duration of a voyage from Australia or California to Europe with a cargo of wool or wheat, but because there is a small advantage in point of economy of working in favour of a cargo steamer of the great dimensions at which we have now arrived. A very small percentage of economy is all important from a strictly commercial point of view. The offer of sufficient subsidies for carrying apprentices to the Naval Reserve may incline the scale in favour of sailing ships, in which the owners might be prepared to combine suitable arrangements for training with the carrying of cargo. The system of training for the Royal Navy, as indeed for every other Navy, is begun in sailing ships. That able and distinguished officer, Sir Gerard Noel, now Admiral in command of the Reserves, and formerly a captain in our Training Squadron, has, in a recent paper, given his opinion of the value of the discipline of masts and sails. It was emphatically advocated by the late Sir Geoffrey Hornby. It is not less strongly recommended by contemporary officers of the highest authority, such as Sir Frederick Richards, lately the First Sea Lord, and others too numerous to mention. Sir Gerard Noel holds that masts and sails must not be relinquished until an equally effective substitute is found. The only alternative in his view must be the disappearance of the naval officers and seamen as now known, their places being taken by steamship officers and harbour-drilled crews, with none of the attributes of seamen. To a seaman the fact of being at sea in a steamship means that he has rather less to do than when his ship is in harbour. How different the life in a sailing ship, where every change of weather requires unceasing attention to the setting, trimming, and reefing of sails! Such sea experience keeps all on the alert. In sailing ships the younger officers find themselves in really responsible positions, not only as to the safe conduct of their ships, but also as to the safety of the men employed in working the sails and spars.

Training
under
sails.

The
system
abroad.
Subsidies.

In this connection let us not neglect to take into view the policy which is being pursued in foreign countries, under the most vigorous and efficient administrators. As an encouragement to their employment in the mercantile marine, in which their reserves of seamen are reared, subsidies are paid to the owners of sailing ships on a liberal scale both in France and Italy. In France the bounty on construction is 65 frs. per ton. The mileage bounty is

at the rate of 1·70 frs. per ton per thousand miles sailed. As a result, construction under the French flag shows considerable progress, and that at a time when sailing ships are disappearing altogether from beneath the British flag. The finest sailing ships which visited the port of Sydney during my residence in Australia were French. The house of Bordes, of Bordeaux, has taken the lead in the revival of the fleet of sailers. The increase in the tonnage belonging to the firm is hardly exceeded in the most successful steam shipping companies of Great Britain. In the United States the duty of the State in relation to the training of seamen has not been neglected. Training ships lent by the Navy have been sent to sea by the States of New York and Pennsylvania. In these ships there is little to differentiate from the training ships maintained by boys of the War Navy. The naval authorities have lent their aid as well in the training of officers as in that of seamen. The *Enterprise* has been fitted out as a school-ship; the boys taken on board have passed a high scholastic examination, and are entered for a three years' course of training designed to fit them to be efficient officers of the mercantile marine. In the United States it has become the settled policy to give encouragement to shipping by subsidies. A Bill is now before Congress prepared by the Committee of the Senate on Commerce, authorising the payment of distance bounties to selected sailing ships, at the rate of 1 per cent. per gross ton for every one hundred miles.

The time has now come when the adoption of every practical means to prevent the disappearance of British seamen from our foreign-going ships should be considered. As a proposal for discussion, I have from time to time put forward a scheme based on the recommendations of the Manning Commission of 1860. It was proposed that the Government should train boys for the Reserves by entering them as apprentices indentured to an official of the Board of Trade and to remain under his supervision. They were to be sent to sea for four years in selected sailing ships, and afterwards join the Reserve. A subsidy was proposed, of £20 to the shipowner and £15 to the apprentice, on the satisfactory completion of the apprenticeship.

Under the conviction of the necessity for taking some action, the Imperial Government, at the close of the session of 1898, introduced a clause into the Merchant Shipping Act providing for a reduction of the light dues to owners of ships carrying apprentices. The scheme failed because the inducements were inadequate. I have endeavoured to show that the increasing requirements for the Naval Reserve can only be met by dealing with the training of boys on a comprehensive plan and with the aid of the State. Better terms

The decline of the British seaman must be checked.

Bounties
for appren-
tices.

should be offered to the shipowners and stricter conditions insisted upon. The sea training of the boys we enter for the Reserve should, as I have said, be in sailing ships only. I offer as a suggestion, thrown on the table for discussion, that the bounty for apprentices might be at the rate of £25 for the first year, £15 for the second, and £5 for the third year. No boy should be eligible who had not passed through the harbour training-ships at the ports. The number of boys to be entered in the harbour ships being determined with reference to the requirements of the Naval Reserve, this condition would limit the charge to be borne by the Exchequer. We should pay for the training of reservists and reservists alone.

Govern-
ment ap-
prentices
should
join the
Navy.

On the completion of their apprenticeship the Government apprentices should join the Navy. After serving in the fleet, they would return to the mercantile marine, where their high qualifications would secure good employment. Their pay would be supplemented by their retainers as reserve men, and by the prospect of a pension.

In conclusion, it has been my endeavour to show that a strong reserve is essential for the Navy, the number of prime seamen in the mercantile marine is diminishing, and without the aid of the State in training must continue to diminish. On every occasion when a public inquiry has been held the establishment of training-ships at the ports has been urged. In the still more important work of training at sea I have endeavoured to show that timely and effective aid is needed on the part of the State in order to provide for the requirements of the Royal Naval Reserve. Working on the lines briefly indicated, the State may be relieved of the cost of training excessive numbers for the Navy, while assisting to rear up a body of men equally useful in peace and in war. I close with the impressive words in which the Commission on Manning ended their report: "We possess in the Merchant Service elements of naval power such as no other Government in the world enjoys. Hitherto no sufficient organisation has existed for securing the immediate command of those resources for the defence of the Empire. It is in the power of the Government to draw closer to the State, at the moment of danger, the loyal enthusiasm of our noble mercantile marine. While the primary object of any scheme for training at the public charge is the protection of the country from the hazards of war, it is an advantage not lightly to be valued that the enrolment, training, and maintenance of a Reserve must improve the position and elevate the character of British seamen of both the services, and knit them together in the firm bonds of reciprocal feeling and of common interest."

BRASSEY.

CHAPTER VIII.

FLEET AUXILIARIES.

It is now generally conceded that mercantile auxiliaries are a necessity with a modern fleet; but, so far as the public are aware, no attempt has been made to formulate types or lay down any fundamental rules for tonnage, speed, or equipment. We have, it is true, a torpedo depôt repairing ship, and have acquired a military hospital steamer, but obviously our requirements embrace, in addition to these, store ships, colliers, ammunition vessels, and condensing and repairing ships. Nor can we excuse ourselves in the case of colliers by pleading inactivity in other nations, since we read in the press that both America and Russia contemplate the construction of fleet colliers, whilst the former Power has also a repairing ship in hand. It may certainly be said that, though our requirements are well defined, the details connected with the provision for them are not so clear, but this is precisely the plea urged for embarking in experimental types which should establish standards for future guidance.

Beginning with fleet colliers, it may be asked whether, at this moment, we have any that are suitable to accompany a fleet, and what should form the qualifications of the class. I should assign the first place to speed, a sufficiency of which is necessary to enable such vessels to keep pace with a battleship squadron, and this may be put at 16 knots. Then an adequate amount of coal in their bunkers to make them independent of the fleet supply should be aimed at, and this I should put at a thousand tons (to name a figure for discussion), whilst five thousand should be carried for the fleet. The Americans are said to contemplate the building of fleet colliers of 15,000 tons. It is true that the congested state of the American yards, due to the extensive building work now in hand, has not enabled the colliers yet to be laid down; but, as I said in my paper, read on December 12, 1900, at the Royal United Service Institution, if the intentions of the Americans are rightly interpreted, it would appear that our astute cousins, with a much smaller navy, were already working in the direction I had indicated. The size of these intended colliers was not made clear, but, if three of 15,000 tons each are proposed, I should consider it a mistake, as they would not be so easily handled or cleared if of that

Classes of
auxiliary
ships.

Fleet
colliers.
Essential
qualities.

size, and the more colliers you can get alongside individual ships of a fleet at the same time, the sooner will that fleet be coaled and ready for further service; hence the greater advantage of possessing a larger number of small colliers.

Then the details of equipment require to be worked out by the light of all experiences up to date, such as the size and number of hatchways required, derricks, and steam-winchcs, bags, baskets, &c. An equipment also for coaling ships at sea should be fitted and thoroughly tested for future guidance.

Coaling
in the
Channel
Squadron.

In respect to suitable fittings no difficulties should be found, as the Channel Squadron has a wide range of experience in coaling from colliers, whilst the Mediterranean Fleet has summer practice in the same direction, and in all cases the Admiralty very wisely insist on a full report after such coalings, giving all details worthy of record in connection with the general quality of the collier, her outfit of winches, derricks, &c., and the size and convenience for unloading of her hatchways. As celerity in coaling will be of great importance in war time, the healthy competition afforded by the Channel Squadron in taking in coal is of great value, and it is satisfactory to note that the following excellent results were attained on the last occasion of coaling, as given by the *Naval and Military Record* of February 14:—

The five battleships constituting the Portsmouth Division of the Channel Squadron have completed coaling for the first time since a commander, with a chief boatswain as his assistant, has been placed in control of the depôt, and the results are somewhat remarkable. It has been clearly demonstrated, that, in the winter, any ship demanding anything up to 1500 tons, or even more, can be supplied during one day's daylight. To effect this, three cranes were kept at work on the shore side, and on the water side were two Temperley vessels with two transporters in each. The question, therefore, arose whether the crew could stow the coal as rapidly as it could be shipped. It was further determined to give, as far as possible, each ship the same chance, but this condition could not be fully observed, for, while four of the vessels coaled in daylight, the Prince George had three hours of artificial light—namely, from 5.30 to 8.30 p.m. In each case, however, every detail of the operation was carried out by the ship's companies, the only outside assistance being rendered by the dockyardmen, who worked the winches on shore. The work, even to bringing the lighters alongside and the running of the coal to the cranes, was performed entirely by the crews. So keen was the competition that not only lieutenants but chaplains, surgeons, and paymasters threw themselves into the work, and wheeled their loads with the energy and rapidity of trained stokers. The following table gives the return for each ship:—

| | | | | | Tons shipped. | Average per hour. |
|------------------|----|----|----|----|------------------|----------------------|
| Hannibal .. | .. | .. | .. | .. | 943 | 170 |
| Prince George .. | .. | .. | .. | .. | 1220 | 187.7 |
| Resolution .. | .. | .. | .. | .. | 1215 | 169.5 |
| Majestic .. | .. | .. | .. | .. | 1230 | 200.3 |
| Mars .. | .. | .. | .. | .. | 1070 | 203.78 |

About an hour before coaling ceased the Mars had averaged 218 tons an hour, but at this point the fuel accumulated on deck, the men below being unable to trim it as rapidly as it was sent down; and, though this broke down her average, she for the present holds the record, so far as the Portsmouth division of the Channel Squadron is concerned. It should be mentioned that the competition was instituted without any advice or recommendation from the Admiralty, but in order that Commander Heathcote, who has relieved the dockyard staff officer of the responsibility, might obtain information for his guidance in the event of an emergency arising.

After determining the type of the future fleet collier, two should be built at once for trial and report, one being attached to the Channel Squadron, the other to the Mediterranean Fleet, and both vessels should be kept constantly running, till all debatable points are set at rest.

Next to coals, engineers' stores are probably the most vital requirement of a fleet, and these would stow in any cargo vessel, but the same amount of speed—viz., 16 knots—must be provided. Also in these vessels the facilities for rapid clearance should be a *sine quâ non*, and, if one or two are built for trial, the development in this respect shown by the mercantile marine in certain of the latest cargo and passenger ships affords a good lead, as some of them, I am informed, can discharge at the rate of 2000 tons in twenty-four hours.

Engineers
store
vessels.

Hospital ships have already been fitted by that enterprising nation, the Japanese, and it is probable that their Minister of Marine, if asked, would courteously place the drawings at the disposal of our Admiralty. We have also an example in this direction afforded by the military hospital ships sent to the Cape, and if the rumour is correct that the Admiralty have purchased the *Maine*, and intend sending her to the Mediterranean, the value of her fittings can be tested, improvements suggested, and, what is of great importance, bad fever cases given a better chance of "pulling through" when the fleet is away from the vicinity of a hospital.

Hospital
ships.

Ammunition vessels in attendance on a fleet will be of great value after an action, as even at Alexandria the want of shell made itself acutely felt after a comparatively short bombardment, in which no quick-firing or breech-loading guns were used. The fitting of such vessels requires to be carefully thought out, as all magazines should be able to be readily flooded, should be placed below the water-line, and should be well lighted electrically, with every facility for rapid supply to several ships at the same time. To keep the metacentric height right some weights would probably have to be carried above the water-line, and these might consist of repairing plates and plant, warrant officers' stores, etc. The speed of these vessels should not be less than 16 knots, and I would suggest that a typical ship be at once fitted out and attached to the Mediterranean Fleet in the summer, and the Channel Squadron in the winter, to test fittings and suggest improvements by the ships drawing upon her for all ammunition expended for quarterly practice.

Ammu-
nition
vessels.

Provision and store ships could be more readily extemporised, as any cargo steamer of sufficient speed would probably answer all requirements, but the stowage of everything must be carefully considered, as it should be possible to get at anything required

Provision
and store
ships.

quite easily and without undue disturbance of other portions of the cargo.

As has been suggested by Lord Charles Beresford, let a cold meat store ship be kept in view, as the Americans have given us a lead in this direction, and there seems no reason why fresh meat and vegetables should not assist to relieve a war strain by supplying a more generous diet than that afforded by canned or salt provisions.

Condensing ships.

Condensing ships are now also recognised as a necessity in a war squadron, and one or two have already been attached to the fleet in the annual mobilisation, but those tried were, I understand, anything but a success, which points to the desirability of providing a well-thought-out specimen for trial in the Mediterranean or Channel Fleet in order to determine an efficient type. A vessel of this kind would also at times be very useful at such places as Gibraltar and Malta, where shortage of water occasionally occurs, and might also be a great boon in certain military operations. To quote historical examples, the base in the Abyssinian campaign was kept going by distilled water, the elephants alone using some tons for their daily wash down, and this water was furnished at a great cost by the transports, some of which were kept steaming round the anchorage for condensing purposes only. Crete was another instance of the utility of distilling ships, one being attached to Candia to supply the troops with wholesome drinking water.

Repairing ships.

Repairing ships must of necessity be of a special type, and one or two should be prepared for trial and report in order to determine a pattern. These vessels might carry spare feed-pumps for boilers, as also other small spare auxiliary engines, since the constant running of the auxiliary machinery is a source of frequently recurring defects, which in many cases could be readily made good by shifting the engine or part of it in far less time than it could be repaired, and this would be of great importance in war time. And, if all the auxiliary engines could be kept to standard types and gauges as far as possible, their repair would in all cases be much facilitated. In the matter of interchangeability of parts of nearly all machinery we have much to learn from the Americans, and the chances are that their repairing ship under construction will be admirably thought out in every detail.

The extensive need for fleet auxiliaries

The foregoing is only an outline of fleet auxiliary requirements, but this should be filled in as soon as possible by a well-considered scheme in detail, in which everything conducing to their efficiency should be worked to in specimen vessels for practical trial and report. The types being settled, it will be requisite to determine the total number of each to be allotted to every fleet or station, and an officer

of high rank and wide professional knowledge in the Mediterranean puts the requirements of that station alone at upwards of thirty auxiliaries, thus affording evidence of the large demands which will have to be made on the mercantile marine to supplement what we build ourselves. Then arises the question: Can the mercantile marine furnish the number of vessels required at short notice, of sufficient speed and general adaptability to follow a pattern ship of each type when such is evolved? Personally I should doubt it, except at the cost of great disorganisation of the carrying trade, which in a war would probably become more acute by the extra demands on it, and possibly by some of the slower "tramps" dropping out, thereby throwing a greater carrying strain on the faster steamers.

Therefore it will be as well (if not already worked out) to ascertain how far we can rely on our merchant service for the balance of the fleet auxiliaries required, and supplement the deficiency by building our own auxiliaries as a component part of the Royal Navy. And if we again resort to Imperial troopers, and construct vessels capable of a dual duty as either auxiliaries or troopships, we shall save the extravagant expenditure of coal which is entailed by running our cruisers with relief crews,* as also the wear and tear of their machinery, and have ready to our hand on the outbreak of a war some well-trying steamers, which would fall naturally into their places as auxiliaries without any question as to their aptitude. Then due consideration must be given to the manning of the auxiliaries, as it is evident that their crews cannot be drawn from the fighting line, but equally evident that they must be forthcoming when required, and this points to the necessity for some reserve in this direction capable of being called upon at short notice; and where are we to look for it? Possibly the watermen and bargemen and local steamer stokers might be induced to join a reserve in which no drills are required, and probably other sources may be tapped, but the numbers required will be considerable, as one hundred auxiliaries at the modest figure of one hundred men in each crew will absorb 10,000 men, and this at a time when demands upon the naval labour market will be unprecedented.

It may be pertinently asked why this question of auxiliaries has now become a prominent one, and, if pressing, why it was not attended to long ago. We may hopefully assume that this has been the case, but we have no evidence to that effect, nor has it been alluded to by the First Lord of the Admiralty in any of the explanatory annual statements which usually precede the Naval Estimates.

The
provision
of ships
and
manning.

* The Europa burnt 20,000 tons of coal in steaming to Australia and back with relief crews.

Mr. (now Lord) Goschen certainly, in his 1900-1901 statement, touched upon fleet coaling as follows:—

Arrangements connected with the coaling of the fleet have been under the special consideration of the board. Steps have been taken to increase the reserve stocks at certain of our coaling stations, and experiments are in progress with the object of selecting a patent fuel suitable as a special reserve on the more distant stations. Arrangements are being made for the institution of a system of supply of coal to certain fleets and dockyards by colliers directly under Admiralty control, a successful experiment in this direction having been made in the course of the year. Efforts are being made to widen the area of supply as far as practicable, and to take advantage of the coal resources of the Colonies when local coal can be shown to be of suitable quality for her Majesty's ships, and can be supplied at reasonable rates. Steps have been taken to provide for a certain quantity of New Zealand coal from the West Port Collieries for use on the China station, and local Australian coal is now used on the Australian station as far as circumstances permit.

Lord Selborne, also, in the Memorandum presented with the Estimates of 1901-2, alludes to the coaling of the fleet, and states that additions have been made to the coaling craft, and that other ships will be equipped with modern appliances.

This, so far as it goes, is satisfactory, but it does not touch the question of properly constructed colliers of sufficient speed and capacity to accompany a fleet in war time, for it may be surmised without fear of being in error that the colliers named as "directly under the control of the Admiralty" have no greater speed than 10 or 11 knots, and no larger storage than 3000 tons of fleet coal.

In conclusion, it cannot be too strongly urged that the fleet auxiliary question is of paramount importance, that now is the time to thresh out its multifarious details, both personal and material, and to put the service in such a condition of organisation and efficiency that hostilities will find us fully prepared with a fleet equipment of auxiliaries for every station, capable of being mobilised and despatched on their important duties as quickly and as readily as the A Division of the Fleet Reserve.

J. O. HOPKINS.

CHAPTER IX.

THE TRANSPORT OPERATIONS TO SOUTH AFRICA.

THE transport of the troops to South Africa during the war has been by far the most considerable operation of the kind in which any nation has ever engaged, and the more one thinks of the embarkation and despatch of the troops, the more profoundly is one impressed with the significance of the great historic success. The distance at which the hostilities were waged, the vast numbers of men and animals employed, the huge aggregate of stores of every class to be conveyed, all demanded the resources of a merchant marine such as is possessed by no Power save our own. No other nation has ever put into the field an army of a quarter of a million men, with lines of communications covering 7,000 miles of sea and land, provided with horses, transport animals, field and siege guns, ammunition, waggons, vehicles, traction-engines, bridge-building, pontooning, and telegraph materials, and tents, tools, and equipments, as well as with food, forage, and hospitals, not to speak of the thousands of objects that are necessary for the efficiency and the operations of forces in the field.* These forces were to be employed in a country that may be described as almost destitute of military supplies, and where few requirements beyond waggons and draught oxen could be procured, and they were to continue on active service for a period which has not yet come to an end. From the strategic point of view the naval transport was simplified, owing to the fact that we were not at war with a sea power, and that beyond a general patrol of the route to South Africa no special precautions were called for. On the other hand, having regard to national considerations, it was necessary that the immense strain thrown upon our merchant marine should not dislocate commerce or industries, and should not disarrange the rates of freight. When we remember that this was accomplished with complete success, we recognise that the fact speaks volumes

The
conditions
of the
work.

* The siege train despatched in the Tantalion Castle in December, 1899, consisted of eight 6-in. howitzers on heavy mountings and carriages, and four 4·7-in. guns, with very cumbersome platforms, which weighed 36 cwt. each. The ship also carried twenty pontoon waggons, fourteen other waggons, 5,000 boxes of shell, 400 cases of 4·7-in. cartridges, and a great weight of other ammunition. She also conveyed 470 officers and men.

for the strength of our commercial fleet, and there need be no surprise that the achievement has aroused the admiration of the world, for it has been a revelation of resource, energy, organisation, and national spirit, for which there is perhaps no parallel, as also a triumph of good management and business-like capacity, reflecting the highest credit upon all concerned.

Its mag-
nitude.

Troops
conveyed.

The magnitude of the operations undertaken by the Transport Department of the Admiralty, under the direction of Rear-Admiral Bouverie F. Clark, can only be appreciated by the evidence of statistics, though these can but imperfectly suggest the vastness of the task. Before the war broke out, and in the period from June to September, 1899, preliminary reinforcements from Home and the Mediterranean, to the number of 8,168, reached South Africa. The following table shows the total number of officers and men landed at the various South African ports from all sources during the succeeding period, from October 1st, 1899, to October 31st, 1900:—

| | From Home and Mediterranean. | From India. | From Mauritius. | Colonial Contingents. | Totals. |
|-------------------------|------------------------------------|--------------|------------------------|--------------------------|----------------|
| 1899. | | | | | |
| October | 1,632 | 6,004 | 450 | .. | 8,086 |
| November | 42,642 | .. | .. | 1,922 | 44,564 |
| December | 23,548 | 572 | .. | 689 | 24,809 |
| 1900. | | | | | |
| January | 25,134 | 1,007 | .. | .. | 26,141 |
| February | 19,259 | 391 | .. | 2,625 | 22,275 |
| March | 37,144 | 315 | .. | 953 | 38,412 |
| April | 21,425 | 19 | .. | 2,750 | 24,194 |
| May | 11,554 | .. | .. | 1,784 | 13,288 |
| June | 9,795 | .. | .. | 918 | 10,713 |
| July | 7,675 | .. | .. | .. | 7,675 |
| August | 1,765 | .. | .. | .. | 1,765 |
| September | 4,143 | .. | .. | .. | 4,143 |
| October | 3,267 | .. | .. | .. | 3,267 |
| Totals | 208,983 | 8,308 | 450 | 11,591 | |
| | | | Grand Total . . | | 229,332 |

The subsequent reinforcements to South Africa up to January 31st, 1901, were 8,072. We thus reach a grand total of 245,572 officers and men; but this aggregate has since been very largely increased, and the despatch of transports still goes on.

It must, however, be remembered that the transport service has not merely been for the conveyance of the forces from certain places

to South Africa. It was, for example, necessary to detain certain of the transports, to the number of about twenty, on the Cape station, always in readiness to move a division from Cape Town to Durban or intermediate ports, or *vice versâ*, according to the military requirements. Moreover, provision had to be made for conveyance to England, India, and the Colonies of returning troops and invalids, sick, and wounded. The total number in the last categories up to January 31st, 1901, was returned as 58,911.*

Scarcely less important than the men were the horses and other transport animals employed in the field. The total number of horses from Home, India, Austria, America, and Australia, including those with the Colonial contingents, embarked for South Africa up to October 19th, 1900, was 124,834. The mules were conveyed from North America, Spain, Italy, India, England, Cyprus, and Australia, and the total number landed in South Africa from October, 1899, to the end of October, 1900, was 62,690.

Horses
and mules.

It is unnecessary to burden these pages with a classification of the military and other stores, vast in variety as in volume, that have been transported from various points, and chiefly from England, to South Africa. But it will illustrate the magnitude of the work if I take the month of December, 1899, premising that, in some of the early months of 1900, the aggregate was still higher. In the month selected the total bulk of stores conveyed to South Africa in transports and freight-ships may be estimated at 52,000 tons, while ships not taken up by the Admiralty conveyed, during the same period, nearly 17,000 tons of hay, about 7,000 tons of oats, over 600 tons of meat, and about 1,000 head of cattle, besides nearly 15,000 tons of coal.

Stores.

The troops were principally embarked in transports hired by the Admiralty, of which there were 102, chartered at a rate estimated on their gross tonnage—perhaps I shall not be far wrong in saying that the mean rate was 20s. per ton per mensem—and these were under their own officers, and were manned by their own men, whose wages were paid by their owners; but the vessels were completely at the disposal of the Admiralty, who coaled them, superintended the order of embarkation, fixed the dates of departure, and, in a word, had complete control of the whole operation. The freight-ships were in a different category altogether; being hired to carry so many men, horses, or tons of goods, at an agreed rate for the voyage, the management remaining in the hands of the owners. For example, the great

Trans-
ports
chartered
and
freight-
ships
employed.

* It was estimated that, up to the end of March, 1901, about 50,000 officers and men, sick and wounded, had been disembarked at Southampton, many of them requiring very special handling at the port.

majority of the boats of the Union-Castle Line were so employed, and did splendid work. I am indebted to a table prepared by Dr. Benedict William Ginsburg, showing the number of ships and the gross tonnage of each shipping company engaged in chartered transport work.*

| Ships. | Companies. | Gross Tonnage. | Ships. | Companies. | Gross Tonnage. |
|--------|---|----------------|--------|--------------------------------|----------------|
| 9 | Elder, Dempster & Co. | 52,164 | 2 | Orient Line | 10,953 |
| 6 | Cunard S.S. Co. | 38,414 | 2 | Pacific S. N. Co. | 10,355 |
| 4 | Leyland Line | 36,756 | 2 | Lamport and Holt | 10,287 |
| 5 | West India and Pacific S.S. Co. | 33,275 | 2 | Lund Line | 10,156 |
| 4 | White Star Line | 33,270 | 2 | Bibby Line | 9,969 |
| 6 | P. and O. Co. | 32,103 | 2 | Geo. Smith and Sons | 8,516 |
| 6 | B. I. S. N. Co. | 13,739 | 1 | J. Glynn | 7,359 |
| | B. I. Association | 16,959 | 2 | Union Line | 7,139 |
| 5 | Allan Line | 29,559 | 1 | Rankin, Gilmour & Co. | 6,900 |
| 4 | Dominion Line | 28,019 | 1 | Welsford & Co. | 6,215 |
| 4 | Johnston Line | 26,534 | 1 | Asiatic S. N. Co. | 5,660 |
| 5 | Castle Line | 25,831 | 1 | Federal Line | 5,464 |
| 3 | Manchester Liners | 16,682 | 2 | Plate S.S. Co. | 4,767 |
| 3 | Anchor Line | 16,559 | 1 | Atlantic Transport Co. | 4,212 |
| 2 | British Shipowners | 14,651 | 1 | Lawther, Latta & Co. | 4,009 |
| 2 | Harrison Line | 13,330 | 1 | McGregor, Gow & Co. | 3,455 |
| 2 | National Line | 13,162 | 1 | Houlder Bros. | 3,444 |
| 2 | Wilson Line | 12,382 | 1 | Houston Line | 3,261 |
| 2 | Royal Mail S. P. Co. | 11,491 | | | |
| 2 | Brocklebank Line | 11,353 | 102 | Grand Total | 598,354 |

In addition to these vessels, thirty-one ships of the British India Steam Navigation Company, with a gross tonnage of 109,730, were chartered for the transport of troops from India to South Africa. We thus arrive at a total of 133 ships, with an aggregate tonnage of 708,084. This immense fleet did not, however, represent anything like the full number of vessels engaged in transport operations. Troops were conveyed in ships engaged in the regular service to South Africa, and large numbers of vessels were employed in the transport of Colonial contingents, and others again in the conveyance of horses, mules, and stores. Indeed, a War Office return of "Embarkations in connection with the South African Campaign, 1899-1900 (up to October 19th, 1900)," which was issued on March 1st, 1901, indicates that 283 transport and freight ships had been employed in the operations, and, of course, many of these had made repeated passages to and fro.

Resources
of the
mercantile
marine
not
exhausted.

Vast as was the undertaking, the resources of the mercantile marine were by no means exhausted, in relation to which matter the following statement, based on practical experience, made by Sir Thomas Sutherland at the meeting of the Peninsular and

* "The Syren and Shipping," January 2nd, 1901.

Oriental Steam Navigation Company on June 12th, 1900, may be quoted:—

Our share in the work has not been a very large one, as none of our mail steamers have been engaged in it; but still we have transported altogether about 24,000 men, and our ships have run in connection with the service a distance of 300,000 miles. But what applies to our own service in regard to the efficiency with which this work has been carried out, applies to the mercantile marine of the country generally. And I venture to say that for the first time the country has realised, in the manner in which this expedition has been carried out, the great strength which we possess in the mercantile marine of Great Britain. Gentlemen, I assure you that its strength has not nearly been put out in this expedition, considerable as the work has been. I am satisfied that it would have been easy for the merchant shipping under our flag to have carried double the force that has been carried out to South Africa, and in the same time. And I argue that from the simple premises that the P. and O. Company, in the Crimean War, when they had, comparatively speaking, a small number of vessels, and when none of those vessels, with one exception, exceeded 1,800 tons, carried in that Crimean War 60,000 men and 15,000 horses—I say, if it were ever necessary for the great strength of the mercantile marine to be put out in the defence of the country, it would produce much greater results even than the great efficiency which has been shown in connection with the South African expedition.

It will be seen from the list of companies that Messrs. Elder, Dempster and Co. contributed very largely to the fleet of transports. They also took a great part in the work of transporting animals in freight-ships from various ports, bringing about 20,000 horses and 17,000 mules, and Strathcona's Horse crossed the Atlantic in one of their vessels. Six ships of the Cunard Line were engaged in the transport of troops, and conveyed outward 1,050 officers and 22,900 men, and homeward 465 officers and 6,800 men. This Company also conveyed to South Africa 3,972 mules and large quantities of stores.* The White Star liners made excellent troopships, and the *Afric*, *Medic*, and *Persic*, belonging to the new Australian line of the Company conveyed men, horses, and stores from Australia to the Cape. The *Cymric* was one of the finest vessels taken up by the Admiralty, and on one occasion she carried 55 officers, 1,497 men, 430 horses, 19 guns, and 43 vehicles. The total numbers carried by the line were 17,393, of whom 2,494 were from the Cape to England, while the horses numbered 3,659. In addition to the ships of the Allan Line which are shown in the list, the *Sardinian*, *Laurentian*, and *Pomeranian* were taken up by the Canadian Government, and carried very large numbers of troops. The Dominion Line contributed the *Canada*, *Majestic*, and *Umbria*, very fine Transatlantic liners; some very erroneous statements were made in regard to the *Majestic* which are alluded to below. It is unnecessary to allude here to the many other lines which were engaged in this work, but it may be said that the Peninsular and Oriental and the Union-Castle Line did very admirable work. The Manchester Liners—a new company—contributed three remarkable vessels which had been built expressly

Shipping
companies
engaged.

* These particulars are up to January, 1901.

for the Montreal cattle trade, but which were adapted for the transport of troops and horses with very great success and satisfaction both to the company and to the troops conveyed in the ships.

Transport
naval
officers at
British
ports.

The following is a list of the naval officers in principal charge of transport duties at English ports during the war:—

| PORT. | OFFICER. | PERIOD. |
|--|--|---|
| London District (Royal Albert Docks and Tilbury) | Captain Charles H. Coke . . | 30th September, 1899, to 15th March, 1900. |
| | Captain Edward E. Bradford . | 16th March to 18th June, 1900. |
| | Commander (retired) Charles W. P. Allen | 18th June, 1900, to present time. |
| Southampton District | Captain William G. White. . | 30th September, 1899, to 9th July, 1900. |
| | Commander (retired) Reginald Y. Heriz | 10th July, 1900, to present time. |
| Liverpool District | Captain Honourable Hugh Tyrwhitt | 30th September, 1899, to 18th March, 1900. |
| | Captain Charles H. Coke . . | 19th March to 8th July, 1900. |
| | Captain (retired) Francis J. J. Elliott | 9th July, 1900, to present time. |

At Queenstown the senior naval officer, Rear-Admiral A. P. M. Lake, was *ex officio* in charge of transport duties.

The
inspection
and taking
up of
vessels.

In relation to the taking up of transports by the Admiralty not much shall be said here. The operation implied a thorough inspection of the ships for selection and the conversion of them for the accommodation of troops. In the first place the inspecting officers had to investigate the suitability of the ships, and it may be said, broadly speaking, that a satisfactory transport should be capable of carrying a number of men equal to 25 per cent. of her tonnage. They had to consider questions of ballasting, speed, coal consumption, etc., and then to take account of the removal or adaptation of existing fixtures, and the allotting of space for various purposes, in strict accordance with the number of troops to be carried, including the provision of hospital accommodation. The separation between the duties of the naval officers in charge of transport duties at the ports and those of the military embarkation officers was clearly marked. The naval authorities were responsible for taking up, fitting, coaling, and otherwise preparing the vessels for sea. They had to give all orders for the movements of ships at the ports on arrival and depar-

ture, and no transport could leave without an order from the divisional naval transport officer. In this officer's charge was the provision for the safety and expedition of all embarkations of men, horses, and stores, as were all arrangements for docking and like matters. He was also responsible for the safety and disembarkation of invalids, which was very weary work. On the other hand, the military embarkation officers gave orders for the marching of men on board, and had, of course, charge of all the troops ashore; and before a transport could leave there was a final inspection by a board of naval and military officers, who framed a report on the ship and the operation.

In the early part of the war many complaints were raised against the management of the Admiralty, and it may be admitted that some few ships were taken up which proved not altogether suitable; that there was occasional failure, perhaps, to reach the very highest level of efficiency or economy, and that some ships broke down; but this is no more than to say that the stupendous work was subject to those conditions which are inseparable from the conduct of all business, and the fact that everything worked so smoothly, and that so few defects were revealed where so many were possible, is testimony enough to the splendid character of the achievement. The very fact that the mail and passenger services were not dislocated, and that the sea-borne supplies of food and raw material were not interfered with, has contributed to hide from public view the great work that was going on.

Admiralty
manage-
ment.

It was stated that preconceived ideas impeded efficiency, that unsuitable ships were taken up, that questions of loading, berthing, and feeding should have been left to other hands, and that a good deal of red tape characterised the operations. I have no hesitation in declaring that many of these statements were based upon imperfect information. It was asked why the Admiralty failed to secure the fastest transports, but the answer is because they acquired such as were most suitable for the long voyages to be undertaken. It was under the pressure of popular clamour that the *Majestic*, a fine Atlantic greyhound, was taken up. She was altogether beaten by the *Briton*, and the rumour was then circulated that she had been ordered to proceed under her proper speed. This was an entirely erroneous statement. As a matter of fact, the *Majestic* was ordered to keep enough coal on board to proceed to Durban if required—an order which was given to every transport leaving British ports for South Africa—and she could not steam at her high speed. There were complaints from time to time that sufficient transports had not been taken up for all the Yeomanry, but it should not be forgotten that

Charges
refuted.

this patriotic force began by attempting to provide its own transport, and only came to the Admiralty when the effort failed, and, of course, an unlimited number of satisfactory ships was not available. The *Times* correspondent at the Albert Docks, in relation to this matter, stated that only those who had closely followed the practical details involved in the provision of ships were aware of the labour thrown upon the Transport Department, and could realise how well the task was performed. Justice had not been done to the naval officers to whom the selection, fitting out, and despatch of transports was entrusted. It was work not much in the public eye. Another somewhat wild complaint was that the Admiralty had not taken up the whole of the White Star Line and other mercantile fleets. People who made this reproach forgot that it was an object not to dislocate the service of any company, and the White Star Line, like the Peninsular and Oriental and the Union-Castle, made a notable record. Among the ships it contributed to the transport fleet was the *Cymric*, of 22,552 gross tonnage, which was probably the finest vessel taken up. As a transport she was really three ships in one, a passenger, a trooper, and a horse-ship, with ample space and every convenience, and on one trip she carried 55 officers, 1,497 men, 430 horses, 19 guns, and 43 vehicles.

The
shipping
companies
and the
Admiralty

In relation to many statements circulated to the disparagement of the Admiralty in its management, I may say that I have the authority of several of the great shipping companies for expressing complete satisfaction with what was done. "The Admiralty arrangements were conceived on sensible and effective lines. The changes made in the ships chartered were necessary to enable the number of men to be carried whom the War Office desired to send. The work necessary to fit the vessels for service was not excessive. There was nothing excessive in the fittings; everything done was useful and necessary. The fittings already in the ships for carrying cattle were used for the transport of mules and were quite satisfactory." For the transport of men the ships were fitted in a manner thoroughly good, comfortable, sensible, and wholesome, a statement in which, I believe, many companies will concur. It is obvious that the Admiralty officials had to work upon a fixed plan, and that exceptions could not be made to accommodate some shipowners without causing grievous complaints on the part of others. The use of hammocks was made necessary by the great number of men to be carried. The ships of the Manchester Liners were fitted with the latest improvements for the conveyance of cattle, but the company recognised that they could not be employed for the transport of horses. Upon this point they were a good deal exercised, but came to the conclusion

Horse
transport.

that their fittings could not be utilised except possibly by great alterations, at a cost much exceeding that of the Admiralty fittings, which fittings in the opinion of the company's officers were most excellent for the purpose. Of course, in spite of the excellence of the fittings, and of the good accommodation provided, horses were lost, as might have been expected, considering that all sorts of animals, seasoned and unseasoned, were necessarily shipped owing to the great pressure at one period of the war. Doubtless experience of horse transport in the early part of the war contributed to better results later on. It may here be remarked that the total number of horses lost from October 1st, 1899, to October 31st, 1900, was 6,193 (117,738 landed), and of mules, 2,174 (62,690 landed).

Horses
and mules
lost.

I venture to quote the following opinion expressed by a leading shipping company in regard to the general question of Admiralty management: "We have seen from time to time various letters and comments in the daily press as to the red tapeism, etc., manifested, and as to the obstinacy, etc., of the Admiralty officials. We can only say that these letters and comments have evidently been made by people who have not had experience of the work, and who like to air their own ideas without knowledge. We think we can speak with some experience, and we can most unhesitatingly say that the consideration which has been given to any suggestions made by ourselves to the Admiralty and their officials, the courtesy which we have received from them, and the business-like way in which all matters have been conducted by these officials, call from us for the very highest expressions of satisfaction and praise."

In relation to the victualling of the troops at sea various opinions have been expressed. On the whole the troops preferred the food supplied by the companies, it being more palatable than the Government rations. These were nearly similar to those supplied to seamen in the Fleet, and, the British soldier having generally been brought up on the rations of the shore, his stomach does not relish salt beef, pork, etc. Later on, however, most of the transports were victualled by their owners, and although this method was more expensive than the scale of Government provisions, it gave much more satisfaction to the men, and the country has not grudged any extra cost involved. It was the general opinion of the shipping companies that it was a wise step to allow them to undertake the catering. The Manchester Liners were catered by the company from the very beginning, and the following bill of fare, indicating what was provided for the Regulars, will show the variety of food that was supplied. In the case of the Yeomanry, by the addition

Victual-
ling the
troops.

of a few pence from the Admiralty, the menu was very considerably extended:—

| | BREAKFAST. | DINNER. | TEA. |
|---------------------|--------------------------------------|---|------------------------------|
| SUNDAY | Irish stew, fresh bread, coffee. | Soup, fresh beef, carrots and turnips, potatoes and plum pudding. | Fresh bread, jam, tea. |
| MONDAY | Porridge, fresh bread, coffee. | Soup, boiled mutton, potatoes. | Fresh bread, marmalade, tea. |
| TUESDAY | Curry and rice, fresh bread, coffee. | Soup, salt beef, potatoes, apples and rice. | Fresh bread, jam, tea. |
| WEDNESDAY | Irish stew, fresh bread, coffee. | Soup, fresh beef, potatoes. | Fresh bread, marmalade, tea. |
| THURSDAY | Porridge, fresh bread, coffee. | Soup, boiled mutton, carrots and turnips, potatoes, plum pudding. | Fresh bread, jam, tea. |
| FRIDAY | Curry and rice, fresh bread, coffee. | Pea soup, salt pork, calavances, potatoes, sago pudding. | Fresh bread, marmalade, tea. |
| SATURDAY | Irish stew, fresh bread, coffee. | Soup, fresh beef, potatoes. | Fresh bread, jam, tea. |

Poultry to be given with pork for dinner one Sunday on passage in lieu of fresh beef.

Work at
British
ports.
Southamp-
ton.

A large number of transports left the Thames, and some the Mersey. Excellent work was done at both ports, but it is worthy of note, as a matter of future reference, that, in the early part of the war, when Captain Charles H. Coke, R.N., and Commander Christopher Cradock, R.N., had charge of the operations at the former, progress was more than once impeded by heavy fog. But the chief burden of the work fell upon Southampton, where the operations were attended with remarkable success. The very anxious, responsible and laborious work which fell first upon Captain Graham White, R.N., as Divisional Transport Officer, and afterwards upon Commander Reginald Yorke Heriz, R.N., assisted by Commander W. W. Barnard, an expert in the fitting of ships, was most admirably performed, while Lieutenant-Colonel John Stacpole, C.V.O., A.A.G. for Military Embarkation Duties, had charge from the very beginning of an operation of extraordinary difficulty, involving prodigious labour. It was certainly due to the ready co-operation of the naval and military officers that the success of the operation was largely

due. Everything worked with the utmost smoothness, and in the most satisfactory way that was possible, a remark which applies also to the conduct of the transport work at other ports. Something of the remarkable success at Southampton was doubtless due to the fact that the South Western Railway Company owns the docks, and was able to despatch troops with the utmost regularity and punctuality. On one day, October 20th, 1899, five transports left the port for South Africa, taking 167 officers, 4,756 men, some horses, 38 vehicles, and five guns; but, although this was the busiest day for the railway company and the dock officials, it did not, by any means, overtax the available resources, for double the number could have been dealt with. More than once the South Western Railway Company has received expressions of gratification from the Admiralty and War Office for the excellent work that was done. It deserves to be recorded that the troop traffic on this line from October 30th, 1899, to December 31st, 1900, was as follows: 6,160 officers, 229,097 men, over 23,000 horses, 286 guns, and over 1,000 waggons, all conveyed in 992 special trains, of which 573 were from the London and South Western Company's own system, and this number does not include 162 additional special trains for the transport of horses. These facts are cited as illustrative of the extraordinary extent of transport work, the success in dealing with which was not, however, confined to the port of Southampton.

There were, of course, some mishaps and misadventures, but I do not propose to make a full catalogue of the untoward incidents which occurred during the course of the transport operations, though some facts may be recorded. In October, 1899, the *Wardha*, with the 9th Lancers on board from Bombay, broke down, and the troops were sent on from Durban to Cape Town in the *Nevassa*. The shaft of the *Persia*, with a squadron of the 6th Dragoons on board, broke near St. Vincent in November, and the troops were transferred to the *Goth*. The *Rapidan*, leaving Liverpool in the same month, with 494 horses on board, encountered a gale in the Irish Sea, and some of the horse fittings were broken away, with the result that 156 horses were lost, and the ship had to return to port to refit. The experience was valuable, and in later horse transports the fittings were of greater strength. Shortly afterwards, the *Ismore*, with the 63rd Battery, R.F.A., on board, was wrecked in St. Helena Bay, and the battery reached Durban in the *Algeria*. In January, 1900, the *Denton Grange* went ashore at Las Palmas with about 7,000 tons of stores on board, which were sent on to Cape Town in the *Yoruba* and *Fort Salisbury*. A somewhat serious incident occurred at Southampton in February, 1900, through a fire in the *Simla*, which did considerable

Some
mishaps.

damage and caused some delay. There were various lesser mishaps, including damage to the propellers of the Manchester Corporation and the Pinemore, and to the stern of the Montrose as she left the dock at Liverpool, and the Sicilian, with remounts, was in collision at Las Palmas in May, 1900. But these and other episodes were only misfortunes such as are incidental to navigation. They did not mar the very conspicuous success that was achieved, and I shall now turn to the naval transport operations in South Africa.

The naval
transport
operations
at South
African
ports.

A thoroughly efficient organisation for dealing with the vast work of naval transport had also to be devised at the bases of the military operations in that country, and obviously many of the special conditions which attended the transport of troops, stores, and animals could only be fully revealed on the arrival of the ships at the ports of disembarkation. We cannot attach too much weight to the magnitude of the responsibilities involved, nor speak too highly of the great services rendered by Captain Sir Edward Chichester, as Principal Naval Transport Officer, and his staff in South Africa. An enormous amount of work devolved upon these officers, which demanded both organising discernment and administrative capacity, and it was conducted in a manner which reflects the highest credit upon the naval service, and of which the country may well be proud. It must be remembered that in addition to the huge business connected with the arrival, berthing, coaling, and departure of the various transports from England, India, and elsewhere, transport vessels were in constant demand for a vast amount of work of which very little is known. They were used to convey native carriers from Chinde round to Cape Coast Castle; the Australian contingents from Australia to Beira and Cape Colony; and the Boer prisoners to Ceylon and St. Helena; and later on they were detached to transport troops to China. They ran the mail service between Lourenço Marques to Beira, and conveyed naval details from Simon's Bay to coast ports, and troops to Walfisch Bay, and relieved them from time to time. They were also requisitioned to convey undesirables, ordered out of the country by the Field-Marshal Commanding-in-Chief, from coast ports to England and Flushing, as well as to return native carriers to India, besides much other service of a like character. A few transports were moreover often used for the reception of Boer prisoners and Boer sick, these being invariably anchored in Simon's Bay under the eye of the naval authorities there.

Transport
staff.

It is only right to link with the name of Sir Edward Chichester in this great work of dealing with the transport in South Africa, although it is impossible to do justice to all who were concerned in the operations, the names of his executive officer, Lieutenant S. A.

Perry-Ayscough, R.N., his coaling officer, Lieutenant A. Lingham, R.N., (retired) and his secretary, Mr. W. Beresford Whyte, R.N.

The naval transport staff in South Africa consisted of the following :—

| Cape Town. | Port Elizabeth. | East London. | Durban. |
|---|--------------------------------------|--|--|
| 1 Captain P.T.O. 1 Lieutenant. 1 Lieutenant (retired) for coaling duties. 1 Secretary. 1 Boatswain. 2 Chief Writers. 2 Signalmen. | 1 Captain. 1 Commander (retired). | 1 Commander (retired). 1 Boatswain. | 1 Captain (retired.) 1 Commander R.I.M. 1 Chief Boatswain. 1 Carpenter. 1 Lieutenant R.I.M. 1 Writer. |

The Indian Marine officers employed at Durban came over with the first of the troops from India.

The military embarkation staff at Cape Town consisted of a Deputy Assistant Adjutant-General for Embarkation Duties, and certain other officers known as embarking staff officers, and to each ship that landed troops one of these was told off, and was responsible for the receipt of all papers and returns, and for the disposal of all troops, stores, etc., on shore. At the commencement of the war, the military work was done by a lieutenant-colonel and three or four officers of the Army Service Corps, but, owing to pressure of work, Major Lascelles, Deputy Assistant Adjutant-General for Embarkation, and four subordinates undertook the duties, and after a time, when the military officers had gained experience in the nautical work, it became unnecessary for the naval executive officer to board every ship immediately on arrival.

Three or four ships might arrive on the same day, and were anchored in Table Bay, while the military officers got their exact details, told off the troops which were to be first landed in order that these might get up their baggage, and gave the commanding officers of the troops a general outline of what was expected of them when the ships were berthed. Meanwhile the general officer commanding the lines of communication at Cape Town had been informed of the arrival of the ships, and on several occasions had to telegraph to the Commander-in-chief for instructions as to whether the troops should be disembarked at Cape Town or be sent on to Port Elizabeth, East London, or Durban. As soon as an answer was received, the Principal Naval Transport Officer was informed through the Deputy Assistant Adjutant-General for Embarkation, and the coast-bound ships (if any) were immediately ordered on by the former, while the

Arrival of transports.

ships required at Cape Town Docks were berthed. All movements of ships coming into and going out of dock were ordered by the Principal Naval Transport Officer, who would telephone to the Port Captain precise instructions as to the berths to be taken up by the arriving ships—a matter which required considerable discretion. The Port Captain would then give directions to the several pilots, an excellent set of men, to carry out these directions. Sometimes a ship would arrive from England with insufficient coal to take her on to Durban, at which port her troops might be required. A berth would then be found for her, and she would be at once brought in to be completed with as much coal as would enable her to proceed with safety. These cases were, of course, most irritating to the officers and troops on board, who were eager to go to the front, and orders were therefore given that all ships coaling at St. Vincent should, if possible, complete for Durban, but in some cases this was impossible. When a regiment disembarked, it was sometimes entrained at once, or, if trucks were not available, it was sent to Green Point Camp or elsewhere until the rolling stock was ready.

Naval and
military
co-operation.

Preparatory to landing troops, stores, or animals, the Naval Executive Officer would often accompany the Military Staff Officer to give orders to the captain of the transport as to getting derricks rigged and hatches uncovered. He would inform the military authorities as to how many fatigue parties would be required, and where, but the actual ordering of the men to pass out rifles or parade on the wharf was always executed by the military officers, while the stevedores, under the orders of the naval authorities, hoisted out the stores, guns, waggons, or whatever might be to discharge from the ship. After a little experience the limits of the naval and military authorities were perfectly understood, and the naval officers, who were responsible, were well supported by their military coadjutors. The best feeling existed between them, and this was the secret of the smooth working of all the transport at Cape Town. The disembarkation of horses and mules was carried out under naval control, but the men for taking the horses out of the ships and leading them away were supplied by the Remount Depôts, working under officers of the Army Service Corps, who carried out the plan of disembarkation arranged by the naval authorities, whose authority and responsibility were fully recognised.

Requisitions
for
passages
and
freight.

In regard to requisitions for passages and freight, which latter came mainly from the Ordnance and Supply Departments, a special system was instituted. In the early part of the war, when demands were urgent, requisitions were accepted from the departments concerned, but afterwards the Principal Naval Transport Officer

declined to receive requisitions, except through the Deputy Assistant Adjutant-General for Embarkation, who thus became the medium between the naval authorities and the various military departments. This was an excellent system, because that officer was in touch with the General Officer Commanding Lines of Communications, and was usually informed as to the position of affairs at the front, and thus able to co-ordinate the work of the various departments, which might otherwise have been apt to consider only their immediate interests, and much expense appears to have been avoided in consequence. It follows from the nature of military operations that requirements may vary from day to day, and that, for example, ammunition may be running short in some particular theatre of the war, while the provision of forage may also demand great forethought. As an instance of what occurred before this direct channel for issuing orders had been instituted, the following example was cited: A ship might arrive with provisions, and being required at another port, the Director of Supplies would request the Principal Naval Transport Officer to send her on, which he would do, but after her departure it might be discovered that she had also on board large quantities of ordnance stores urgently required at the first port of arrival.

Allusion has been made above to the delay in the landing of stores. This chiefly occurred in the case of horse ships, which carried enormous quantities of stores, and always had forage for fifteen days besides a surplus stock for the voyage out. The result was that, in nearly all cases, before the troops, horses, guns, etc., had been landed, the berth was required for another transport, and ships would have to wait out in the bay until a favourable opportunity occurred of discharging the forage or other stores they had brought. At one time there were over twenty transports in Table Bay, all empty except for forage. Much of this delay was due to the inability to receive the cargoes owing to the want of stocking space and the scarcity of rolling stock for despatching forage up country. As opportunities offered, the enormous cargoes were discharged and the ships sent back to England and India respectively, but it was pointed out that if these ships had brought only troops, horses, and the necessary impedimenta, this delay, which was over three months in many cases, would never have occurred.

Causes
leading to
delay in
disem-
barkation.

Delay was also caused in several ships by only two hatches being used for the enormous quantities of stores and forage, and in some cases there was mismanagement which recalled Crimean days. Rarely in transports, but very often in freight ships, the stores for the troops were placed at the bottom of the hold, while private cargo, in the latter class of ships, and hay, etc., in the case of some

Defective
stowage.

transports, was put on the top. In many ships conveying artillery the guns and vehicles had their wheels taken off, the wheels being put in first, and the heavily packed limbers and guns on the top, and, in a number of cases where ammunition columns and batteries came together, there appeared to be no separation, and the method of stowage left very much to be desired. This is a matter that deserves to be dwelt upon. Chaos and delay to a damaging extent were caused by want of forethought, and the wharf at Cape Town was sometimes lumbered with heavy vehicles, guns and limbers, all unable to be moved, except by great exertion, because their wheels were at the bottom of the hold.

As a contrast to this confused state of things, it may be mentioned that, in the case of one ship, a battery was very urgently required, and within five hours of coming alongside the wharf the officers, men, horses, guns and vehicles were all in the train. The reason was that every wheeled conveyance had been put into the ship just as it arrived at the port of departure, and just as it was taken out at Cape Town. Another example of fine work was the embarkation of a complete battery of artillery in the space of two hours. On the other hand, an unfortunate case of mismanagement was that of the Umbria, which brought out four battalions of Militia, of which two were landed at Cape Town and the others at Port Elizabeth and East London, but, in order to get at the camp equipment for the battalions landed at the first-named port, everything had to be taken out of the ship, sorted on the wharf, and the rest put back again; and this was not an isolated case. In many of the horse ships, in which horses had to be walked from one deck to another in order to land them, the hatches in which the horse-brows had been erected had been filled with stores, etc., to be landed with the troops, which made it necessary to unrig the brows to get at the stores and to rig them up again to take out the horses. In some cases the horse-brows had been taken down altogether, and in one or two cases had been left behind in England, thus entailing unnecessary delay and labour at Cape Town. Durban was in a better situation for disembarking stores, etc., because of possessing cranes, but at the other ports derricks were absolutely necessary.

Insufficient
tackle and
means for
disem-
barkation.

Many of the transports arrived without necessary tackle and appliances for working out their own cargo, and additional work was thus thrown on the people at the port of disembarkation. The facilities for discharging lighters at Cape Town were very limited, and happily it was not often necessary to resort to that method, but, when a great number of ships were waiting to discharge, the inability to work with lighters was a serious cause of delay. Later on the

Harbour Board provided a greater number of lighters, with additional cranes, and undoubtedly the port of Cape Town gained much experience during the war, and improvements are likely to be made.

The labour for stevedoring and discharging stores from transports was provided by contractors, but was at first most unsatisfactory, the men, mostly West Indian and American blacks, being very independent, making it extremely difficult to get labour on Saturday afternoons, or on Sundays at all. The difficulty was got over by offering greater wages, but, as the men got accustomed to regular work, and picked labourers were distributed among them, the conditions greatly improved. The real need, however, was for a party of bluejackets, who would have done the work in half the time. It was impossible to impress upon the natives how much depended on getting the ships cleared and the troops away up country with despatch.

Provision
of labour.

Generally speaking, the horses and mules arrived in good order, but serious illness broke out in some cases, and ran up the total of deaths considerably. The Atlantic cattle ships gave excellent results, and their officers were quite at home with the horses. At Cape Town the animals were almost invariably walked ashore, the saving of time and labour being enormous. The horse-brows which were found most useful were of light construction, about 24 feet long by 4 feet wide, and with sides about 4 feet high, and were fitted on a pair of small wheels balanced in the middle, but other horse-brows were provided for the requirements of different sizes of ships. The big cattle ports as fitted in the cattle ships were quite the handiest for getting horses out. The horse fittings of the *Armenian* were much approved, these being a good example of the system of sacrificing a gangway in rear of the stalls to a little extra room in front, thus affording greater facilities for cleansing and far better drainage. It was pointed out, however, that in this ship, which was fitted for 750 men, there was an elaborately fitted saddle-room at the foremost end of the troop deck which would have accommodated 150 men, but was never used. One of the best horse ships that reached Cape Town was the *British Princess*, which had wide roomy decks, with gangways behind the stalls and also in front, with a perfect system of drainage.

Horse
transport
and disem-
barking
horses.

As soon as the outward bound transports were clear of troops and stores, they were at once coaled (if infantry ships), filled up with invalids, and despatched home, and, when the numbers of enteric and wounded increased, the best of the horse ships were employed in this service, and were useful in clearing the base hospitals and making room for bad cases from the front. The prompt coaling of the transports was at times very difficult, owing to the scarcity of

Coaling
trans-
ports.

native labour, which has been alluded to, and the shifting of coal from ships' holds to bunkers was often performed by the ships' crews, who got paid for this work.

The Junior Lord of the Admiralty was responsible for the supply of coal, and he was constantly kept informed by the Principal Naval Transport Officer as to the requirements for the same.* In the early part of the war some six colliers, containing between 3,000 and 4,000 tons of coal each, used to arrive at Cape Town monthly. When the rush of troops was fairly over, this number was reduced, and about the middle of 1900 the Natal Coal Company supplied the Durban transports from their colliery at thirty shillings per ton, thus effecting a great saving in the coal bill. This Natal coal was very fair, and, in fact, a shade better perhaps than our English north country coal. Some of the larger transports, notably the Cunarders, were large coal consumers, and used to arrive at Cape Town with not too much coal to spare. This was accounted for by the fact that these ships were built for the New York trade, a 3,000 miles run, and the run from St. Vincent to Cape Town, about 4,000 miles, was never anticipated when their bunker space was designed.

There were, at Table Bay harbour and docks, only four docks in which transports could be coaled in dock, though on a few occasions of emergency vessels berthed alongside the south arm were coaled from a collier on the outside, but no coaling from the jetty side was possible, owing to the whole space being required for the disembarkation of troops, horses and stores, and also to the fact that the Government coal stack on the north arm was at a distance of over a mile. During the early part of the operations a few transports were coaled in Table Bay from colliers taken alongside, but the contractors did not like the expense of sending labourers out, and the work could only take place in fine weather and in smooth water. A complaint was made at the beginning of the war that some of the coal-bags used by the contractors were very defective. The Kildonan Castle, transport No. 44, was one of the very best class of ships for all-round coaling that was dealt with at Cape Town, and the Orient, No. 24, was another very good type. The experience gained justified the conclusion that, when transports are required in time of war, they should be selected, as far as may be possible, with a view to their facilities for all-round coaling, and should be required to carry their shoots in all cases where they take coal in through the ships' sides.

Colliers.

Up to the beginning of October, 1900, fifty colliers, with an output

* The coaling of transports was afterwards in the hands of the Transport Department of the Admiralty.

of about 161,000 tons, had been discharged at Cape Town, and the Floriston was pronounced to be the best type for discharging into every kind of transport. She had an average cargo of 3,200 tons, and her deck was flush fore and aft, thus enabling coal to be carried the whole length of the ship; there were two derricks with separate winches over two holds, and the rails round the sides were nearly all removable, which enabled coal to be carried across gangways, whereas in a collier with permanent bulwarks, it is obvious that, when she rises and the transport gets low in the water, the facilities for discharging coal down shoots through narrow doors, or over the transport's rails, are reduced sooner than when there are no bulwarks at all. The advantage of having two derricks with separate winches for each hold, or for at least two holds with large hatchways and no 'tween decks, of ballast tanks, of exhaust steam pipes which do not interfere with the work, of holds without wooden partitions, and of wire runners and swivel hooks, seem to be indicated by the experience at Cape Town. In the "collier's outfit" of many of the colliers which reached Cape Town were included 200 coal sacks, each to hold 2 cwt., but the sacks were too heavy for any ordinary man to carry when full, and the natives at Cape Town refused the work altogether. These sacks were excellent when derricks were used, and when they could be wheeled on trucks, but for man-handling they should have been smaller.

From November 8, 1899, when the first transport was coaled at Cape Town, up to October 5, 1900, 102 transports, etc., had been coaled at the port, many of them several times, thus giving 234 separate coaling operations, while 50 colliers had discharged 164,959 tons, including 80,785 tons of Welsh, 79,076 of North Country, 4,997 of patent fuel, and 101 of coke. It was found that the dealing with briquettes involved considerable labour, since each one of them had to be handled from five to seven times.

Finally I may give some details of the work connected with the disembarkation of troops, animals, and stores, at Durban and other ports, directed by Captain E. B. Van Koughnet, R.N. (retired), as Divisional Transport Officer, assisted by Commander John Martin, R.N. (retired). At the outset difficulties were anticipated in getting the transports inside the harbour, but these were overcome. Troops to the number of over 100,000 were disembarked and re-embarked, with over 500,000 tons of stores, and nearly 40,000 cattle, mules, and horses. The railway company moved them up to the front according to the directions of the military authorities as rapidly as possible. The following are some details:—Landed from October, 1899, to September, 1900: officers and men, 75,359; horses, 21,150; mules,

At
Durban.

9,558; tons of stores, 350,529; tons of coal, 70,403. Re-shipped: officers and men, 31,018; horses and mules, 3,439; tons of stores, 12,000. Durban was also instrumental in providing hospital ships. The first of these, the Lismore Castle, was ordered at very short notice, and within four and a half days the vessel was selected, fitted up, and had received her first batch of patients. It was a marvellous piece of work to be done at a port 7,000 miles from England. The other hospital ships were the Nubia, Dunera, Avoca, Simla, and Orkana. To Port Elizabeth Commander F. St. Leger Luscombe, R.N., and to East London Commander Thomas Hadley, R.N. (retired), were appointed as chief naval transport officers.

JOHN LEYLAND.

CHAPTER X.

THE OPERATIONS OF OUR NAVAL FORCES ON SHORE, 1899-1901.

It has been described as a characteristic of the reign of Queen Victoria that her Navy was never called upon to perform its function of defence upon its proper element ; but, on the contrary, that there was hardly an occasion when the Army had been employed that it had not had the assistance of a naval brigade on shore. The statement is true with some qualification, for, although there have not been for many years engagements at sea in which our fleets have participated, on the other hand, the "noiseless" influence exercised by the Navy has been markedly effective at frequent intervals during the late reign. This was the case during the war with Russia in 1854-55 ; it is apparent to any student of history in many of those crises when war has threatened, but it has never been more obvious than during the recent struggle in South Africa. No better illustration, indeed, of the true significance of sea power can be desired than that afforded by the circumstances presented to us during the past year. That this fact is recognised on the Continent we have demonstrated by the speech of General Radzenhöfer, as well as in a more practical manner by the circumstance that such talk of interference as there has been remained mere talk, and did not assume concrete shape. Once more sea power has gained its purpose without the fighting of a battle or the discharge of a gun. Once again we have demonstrated the truth of Captain Mahan's dictum, that "the successes of the Army can be gained only as the result of the earlier victories of the Fleet, be these victories 'noiseless' or static, as in the case of the Crimea, or be they active and dynamic, as in the case of the victories of Nelson." Nevertheless, it would be altogether a contradiction of history if we had found that the Navy could rest content with playing this important but passive part in any struggle ; both in South Africa and in China bluejackets and marines have been landed, the guns of the Fleet have been used, and the Navy has added fresh laurels to that garland of renown which is its birthright. In the following pages I have attempted to sketch succinctly and

Static and
dynamic
influence
of the
Navy.

concisely the operations and movements in which the Navy has taken part during these campaigns.

THE NAVY IN SOUTH AFRICA.

Naval
Brigades
in South
Africa.

It is unnecessary here to describe at length either the manner in which Great Britain and the Boer Republics came to actual blows, or the strategical situation which was created in October 1899. It will satisfy all the requirements of this brief sketch if I recall the fact that, on October 9, the Boers issued an "ultimatum" to this country, calling upon us to withdraw our troops from certain positions or take the consequences. Forty-eight hours later a state of war automatically came into existence, and on October 20 the battle of Dundee took place. On the same day Rear-Admiral Sir Robert Harris had decided to land a naval force at the Cape, where, in view of the offensive operations around Mafeking and Kimberley, it was apprehended that the enemy might cross the Orange River. A detachment of guns, with bluejackets and marines, under Commander A. P. Ethelston, of the *Powerful*, was landed and despatched by train to Stormberg, where it encamped. This force was apparently intended to hold the line of railway which is in direct connection with Cape Town, Port Elizabeth, and East London, and connects the De Aar-Naauwpoort line with the Orange Free State.

Captain
Scott's
Guns.

In the meantime the *Terrible* and *Powerful*, two of the largest cruisers in the Navy, had arrived in South African waters to reinforce the squadron there. The *Powerful*—Captain the Hon. Hedworth Lambton—was on her way home from the China Station when she was intercepted at Singapore by a cablegram, and ordered to proceed, *via* Mauritius, to the Cape. The run to Mauritius was made in nine days, at an average of 370 miles a day. There a half-battalion of the King's Own Yorkshire Light Infantry was embarked and conveyed to Cape Town, where the *Powerful* was able to make a contribution to the landing party mentioned above. The *Terrible*—Captain Percy Scott—had already arrived from England on October 14, and her captain, with marvellous intuition, had divined that the most pressing want of the moment would be long-range field-guns. He set to work, therefore, to invent a travelling carriage for the long 12-pounders, which were mounted in the cruisers as broadside guns. His first design consisted of a log of wood to form a trail, mounted on an axle-tree, with a pair of ordinary Cape waggon wheels. On this was placed the ship carriage, bolted down and secured in such a manner as not to interfere with its being put back on board, should circumstances have required it. Two guns thus mounted were landed with the party under Commander Ethelston.

The next step in the naval history of the war was brought about by the situation in Natal. The British troops, after fighting the battles of Elandslaagte and Rietfontein to cover the retirement of the force at Glencoe, had concentrated at Ladysmith, where the Boers threatened their communications. On October 25, General Sir George White, finding that he had no artillery capable of keeping the Boer guns in check, telegraphed to know if it were possible for the Navy to send him some long range guns. Sir Robert Harris at once asked Captain Scott if he could design a mounting for a 4·7-in. gun and get two finished by the following afternoon. The *Powerful* was selected to take the guns to Durban; by the time stated the two guns, with their mountings and ammunition, were shipped from the arsenal at Simonstown; and at ten the same evening the ship started with them for Natal. The mountings for the 4·7-in. consisted of four pieces of timber, 14 ft. long by 12 in., placed in the form of a cross. On the centre of this was placed the ordinary ship mounting, bolted through to a plate underneath. The pedestal and timbers were thus all securely bolted together. Next the gun carriage was dropped over the spindle, and secured down by its clip plate. Subsequent experiments with a platform of this description showed that it was not even necessary to fill in round the timbers with earth; on firing, a slight jump of the platform, of course, took place, but this in itself was advantageous as it relieved the strain. At 9 A.M. on Sunday, October 29, the *Powerful* arrived at Durban, having made the voyage at the rate of 380 miles a day. During the few days at sea the mountings for the 4·7-in. guns were packed in strong cases ready for immediate landing, and field carriages on Scott's pattern were constructed for the 12-pounders. Every preparation, too, was made for disembarking a naval brigade. Immediately on arrival the landing took place, and the same evening the brigade in two trains was *en route* for Ladysmith. The force consisted of seventeen officers and 267 men. The battery comprised the guns' crews, a gun mounting party, stretcher bearers and ammunition carriers, cooks, servants, and sick berth attendants, with three armourers, a blacksmith, and a carpenter. The guns which they took with them were two 4·7-in. quick-firers, to be mounted on the wooden platform, three 12 cwt. 12-pounders on Scott's carriages, one 8 cwt. 12-pounder on naval field mounting, and four maxims, three mounted on field carriages and one on a tripod. The ammunition consisted, for the 4·7-in., of 200 rounds of common shell, 200 rounds of lyddite shell, 200 rounds of shrapnel shell. For the 12-pounders, 738 rounds of common shell, 396 rounds of shrapnel, and 24 case shot. In addition to the 150 rounds of Lee-Metford ammunition carried by each man, 39,000 rounds were taken, with 64,000 rounds for the

The
Powerful's
Column.

maxims, and 5,400 rounds for the revolvers. The journey was made without any unusual incident until within sight of Ladysmith station, when the train was greeted with several shells from a Boer 6-in. gun, the Long Tom of Pepworth Hill. The battle of Lombard's Kop or Farquhar's Farm was actually in progress, the advance of our troops having been checked, and indeed, a retirement was taking place. The Naval Brigade, therefore, was at once detrained and three 12-pounders were despatched to the scene of action. Each gun was secured by the trail to a waggon drawn by sixteen oxen, and thus advanced for two miles to a position from which they could engage the Boers. As soon as they got into the open the guns came under a heavy fire, one being overturned by a bursting shell and three of the bluejackets wounded. The remaining 12-pounders unlimbered and got into action, opening such an accurate fire that at the third shot the enemy's gun was knocked over and ceased to reply. With the silencing of this gun the enemy's attack ceased and the British force was enabled to return to camp without further fighting. To Mr. W. Sims, the gunner of the Powerful, who has since been promoted to commissioned rank, belongs the honour of laying and sighting the gun which made such splendid practice, the range being between 6,500 and 7,000 yards. In regard to this exploit, Sir George White says in his despatches, "Captain the Hon. Hedworth Lambton, commanding the Naval Brigade, reached Ladysmith in the nick of time, when it became evident that I was not strong enough to meet the enemy in the open field. He brought with him two 4·7-in. and four 12-pounder guns, which proved to be the only ordnance in my possession capable of equalling in range the enemy's heavy guns. Although the ammunition available was very limited, Captain Lambton so economised it that it lasted out to the end of the siege, and under his direction the naval guns succeeded in keeping at a distance the enemy's siege guns, a service which was of the utmost importance." The same night (Monday, October 31) an attempt was made to get one of the 4·7-in. guns to a position in which it was proposed to mount it, but owing to one of the waggons sticking in a donga the attempt was unsuccessful. The three long 12-pounders, the field piece, and the four maxims were, however, placed on the top of Gordon Hill in the centre of the northern line of defence, and later on the two 4·7-in. guns were mounted, one on Junction Hill, at the foot of which the railway lines join one another, and the other on Cove Redoubt, about a mile to the north-west of the town. This last gun remained in this position during the whole of the siege, but the others were moved several times during its progress. It is beyond the scope of this article to describe the events of the siege, but it should be mentioned that the Navy

The Ladysmith
siege.

took part in the defence of Waggon Hill when, on January 6, the enemy made a determined but fortunately unsuccessful attempt to carry Ladysmith by storm. Two naval guns were in process of transfer to the hill during the previous night. These guns were accompanied by naval detachments and a working party of Royal Engineers and Gordon Highlanders, and were consequently on the hill when the attack commenced in the morning. The bluejackets with their military comrades clung to their positions on the extreme south-west point of the hill and held the Boers in check till daylight. Gunner Sims was in charge of this party of seamen and their gallant service has been testified to by all who were present. To contribute to the water supply, condensers were constructed out of improvised materials under the direction of Engineer Sheen of the Powerful and proved most valuable. Of the general conduct of the brigade Sir George White says in his despatch that "they rivalled the best of our troops in gallantry and endurance, and their long-range guns, though hampered by a most serious want of sufficient ammunition, have played a most prominent part in the defence, and have been most successful in keeping the enemy from bringing his guns to ranges at which they would have been most efficient. On February 29, when Ladysmith was relieved, the Powerfuls returned to their ship, and that vessel returned to England. On her arrival at home in April, Captain Lambton and the officers and men who had served during the siege of Ladysmith were entertained at Portsmouth, and were afterwards ordered to Windsor, where they were inspected and thanked for their services by Queen Victoria. On May 7, the brigade marched through London to be inspected by the Admiralty on the Horse Guards Parade. The streets were decorated and the public seized the opportunity to give the bluejackets and marines an enthusiastic reception. The King, then the Prince of Wales, attended by Viscount, then Mr., Goschen, the First Lord of the Admiralty, addressed the brigade.

Reception
of the
Powerful's
contingent
in
England.

To return to the situation in Natal. With the field force shut up in Ladysmith and the Boers overrunning the country, Sir Walter Hely Hutchinson, the Governor, applied to the Admiral for a force to undertake the defence of Durban. The Terrible was despatched for this purpose and arrived on November 6, 1899. By the following day Captain Percy Scott had surveyed the position, and by the 8th had completed his arrangements for defence. Thirty guns in all were so mounted as to command all the approaches as well as the waterworks and other important positions. The guns were two 4·7-in., sixteen 12 cwt. 12-pounders, two 8 cwt. 12-pounders, one 9-pounder, one 7-pounder, two 3-pounders, two Nordenfelts, and four Maxims. Captain Scott was appointed Commandant of the town,

Defence
of Durban.

with a staff of naval and military officers to assist him; the local rifle associations volunteered for service, with a corps of mounted scouts. The ship herself was utilised in the scheme of defence and an armoured train patrolled the railway in the neighbourhood of the town. Such an event as a naval officer becoming commandant of a large town under martial law and organising its defence from naval sources is probably unique. As it turned out, the matter was never put to the test, but there can be no doubt that had the enemy appeared they would have met with a warm reception.

Natal
Field
Force.

By the end of November the Ladysmith relief column was ready to begin an advance, and a Naval Brigade under Captain E. P. Jones, of the *Forte*, and Commander A. H. Limpus, of the *Terrible*, with two 4·7-in. guns and eighteen long 12-pounders, were ordered to accompany it. These 4·7-in. guns were on a different pattern of mounting from those sent to Ladysmith, improvements having been made by Captain Scott in his design. A double trail was used to allow of great elevation, and iron wheels were supplied. A heavy axle-tree was used, on which the double trail was secured and the carriage put on it. Telescope sights were fitted to these guns. They were easily drawn by a span of oxen, and were found to be sufficiently mobile to accompany the columns on the march.

The guns were taken to Chieveley, opposite the Boer position at Colenso, on the northern bank of the Tugela, and from a position called Shooters Hill opened fire at from 5,000 to 9,000 yards, making very good practice at the enemy. The whole of the brigade took part on December 15 in the battle of Colenso, the two 4·7-in. guns and four 12-pounders being in the above-named position, from which they shelled the enemy with lyddite and silenced several guns. Six 12-pounders, under Lieutenant F. C. A. Ogilvy, with Lieutenant H. W. James, of the *Tartar*, and Lieutenant A. Deas, of the *Philomel*, were attached to the field artillery under Colonel Long. The two other 12-pounders, under Lieutenant Burne, remained in reserve. The general plan of the advance, had been for two columns to advance and cross the river covered by the fire of the long-range naval guns and supported by Colonel Long's artillery. The first shot of the day was fired at 5.20 A.M. without any reply from the Boers. The field artillery and the naval 12-pounders had then advanced to within about 1,200 yards of Fort Wyllie, when a tremendous rifle fire was opened on them from rifle pits along the river banks as well as from the rising ground on the north side of the river. Nearly all the native drivers of the naval gun teams immediately bolted, but four of the guns were able to come into action. The two centre guns, under Mr. J. Wright, the gunner of the *Terrible*, were unfortunately

jammed with their ammunition waggons in a drift they were crossing at the time. Eventually even these guns were extricated and brought into action. After half an hour's firing, however, the Royal Artillery guns were silenced and a gallant attempt to withdraw them failed. The naval guns were then ordered back and were dragged away by teams of artillery horses. Lieutenant Ogilvy speaks most highly of the officers above mentioned, and also refers favourably to the conduct of Midshipmen H. S. W. Boldero and G. L. Hodson and Mr. W. T. Hollins, clerk. With regard to the 4·7-in. guns under Captain E. P. Jones, Commander Limpus says: "There was too much for us to cope with; there was Fort Wyllie to shut up and the infernal triple row of schantzes and shelters along the neighbouring kopjes, and we wanted more long-range guns. As soon as the General realised that he had practically lost the services of the guns under Colonel Long altogether, and considering the non-success of his left attack, he ordered a general retirement to camp. This was at about 11 A.M." The naval guns, however, did not retire until every one else had gone back, as they covered the retirement, and it was nearly half-past two when they reached the camp. Two days later the 4·7-in. battery and six of the 12-pounders were moved forward again to Gun Hill, where they remained until the second week in January, and during that time worried the Boers at odd hours during the day and night. It was during this bombardment that William Bate, the captain of one of the 4·7-in. guns, cut the Colenso road bridge at 7,500 yards, putting a lyddite shell through the span close up against one of the piers, so that one end of the span dropped into the river and the bridge was useless. The naval guns were next moved to Mount Alice, a plateau near Spearman's Camp about one thousand feet above the river level, commanding a magnificent view of the Tugela Valley and of Ladysmith, where the entrenchments at Cæsar's Camp were plainly visible. The work of moving the guns to this position was exceedingly arduous. Commander Limpus, in his diary, relates:

Battle of
Colenso.

"If a waggon dared leave the road and tried to push on across the tempting-looking green veldt, down sank the wheels to their axle-trees and it had to be extricated. We, with the guns, tried it, and so we knew. But we were fortunate in having drag ropes and men to use them, and so soon got out, and, indeed, were able sometimes to give a helping hand to waggons that had not these luxuries. And then the spruits that had been dry were now rushing torrents, which had to be bridged or else crossed exactly at the right place, and the flatter ground near them had become either a lake or a swamp. In the exits from these drifts the oxen sometimes sank the whole length of their legs, and the waggons up to the axles, and one had to put in an

extra team so that the beasts at the end, on comparatively hard ground, might pull the others along. . . . Captain Scott has said that the 4·7-in. guns were mobile. They certainly were. For even under these trying circumstances we never delayed anybody else or found any difficulty in keeping our place or time. My orders, when starting for the front, were that the guns could go anywhere, but we were never driven to extreme measures. If necessary, of course, the guns could have been dismounted, packed round with wood, and hooped together like a cask, and then rolled up any place one can think of with ropes. On ordinary ground their rate of travel was practically that of the infantry. Our longest march was eighteen miles in six hours, and during that time we had two or three halts in order to give our infantry escort a spell. In fact, the guns were, even on their improvised mountings, as mobile as was necessary for all their purposes."

Vaal
Krantz.

The guns of the Naval Brigade played their part from Mount Alice, and other positions to which they were moved, in all the fighting which took place from about the middle of January, and including, of course, the fighting round Spion Kop and the capture and evacuation of Vaal Krantz, until February 8, when the force moved back again to the neighbourhood of Chieveley.

While the main body of the relief force had been thus operating the General left in command at Chieveley had applied to Captain Percy Scott for a 4·7-in. mounted on a railway truck. One of the platform mountings, similar to those sent to Ladysmith, was placed on a low truck and secured by means of chains. This gun could be fired at right angles to the direction of the railway line, and was used to shell a new position which had been made by the Boers. Three more 4·7-in. guns on platforms were also sent to the front, and for the final attack Sir Redvers Buller wired to Captain Scott asking if he could have a 6-in. gun on a field mounting. A gun was taken out of the Terrible, a design prepared, and a mounting made in less than four days. It arrived at the front in time and threw upwards of 500 lyddite and common shell into the enemy's position. The General, in his despatch to Lord Roberts, mentions this reinforcement of heavy guns. "One naval 6-in. mounted on travelling carriage by Captain Scott, R.N., and two naval 4·7-in. mounted on platform carriages." In the attack he refers to these naval guns, which, under Captain Jones, R.N., "rendered the greatest possible service." And again, in the concluding battle at Pieters Hill and Terrace Hill, Sir Redvers Buller says: "The fire of the naval guns here was particularly valuable, their shooting was admirable, and they were able to keep up fire with common shell long after the Royal Field

Relief of
Ladysmith.

Artillery were obliged to cease their shrapnel. Indeed, Lieutenant Ogilvy, of the *Terrible*, kept up fire on the largest sangars till the infantry were within fifteen yards of them. His guns must have saved us many casualties." In another despatch the General says: "Captain E. P. Jones, of the *Forte*, as senior officer of the Naval Brigade, has earned my most heartfelt thanks. The assistance the brigade have rendered to me has been invaluable, the spirit of their leader was reflected in the men, and at any time, day or night, they were always ready, and their work was excellent. Commander A. H. Limpus and Lieutenant F. C. A. Ogilvy and Lieutenant H. W. James were indefatigable. There never was a moment in the day that they were not working hard and well to advance the work in hand. Lieutenant N. W. Chiazzari, Natal Naval Volunteers, was in charge of a detachment who were associated with the Naval Brigade and took their full share of the good work done by it."

After the relief of Ladysmith the greater part of the two brigades, with their guns, returned to their ships, a small column, belonging to the *Forte*, *Philomel* and *Tartar*, with two 4·7-in. and four 12-pounders on travelling carriages, alone continuing with General Buller in his advance to the frontiers of Natal. Two smaller naval forces were employed in Natal. A few men of the *Forte* and *Philomel* were in the armoured train disaster at Estcourt, where they worked a machine-gun on the train and were taken prisoners by the Boers. Two of the *Terrible*'s 12-pounders accompanied a small force which was sent to Eshowe, in Zululand, to stop any Boer incursions in that neighbourhood.

Later
operations
in Natal.

The bluejackets were utilised in many other ways than with their guns. Nine of the *Philomels* and *Fortes* worked with the balloon, and the officer in command reported that their services were invaluable. A party of the *Terribles* worked with Captain Percy Scott's searchlight, and others fitted out an armoured train for the Royal Engineers, covering the whole with double part of 6-in. hawsers, worked like the rope traverses used between unprotected guns on board ship. They also assisted in working the pontoons, and General Lyttelton, at Potgieters, sent a message to Captain Jones to say they had been to him "worth their weight in gold."

The small force referred to above accompanied the troops over difficult country to Volksrust, where it arrived on June 13. A summary of the operations is drawn from the despatches of Captain Jones. On April 10 the Boers opened fire on the camp at Sundays River, and the naval guns were immediately brought into action, eliciting commendation from General Clery for their smartness and the way in which they kept the enemy's fire down. General Clery requested

that his letter might be read to the men, and Captain Jones remarks that it was the first time any of them, except the Tartar's, had been under fire, and they acquitted themselves very well. Lieutenant J. M. Steel, of the Forte, was slightly wounded in this action by the fragment of a shell. On May 11 the brigade accompanied the movement which took place through Helpmakaar and the Biggarsberg to Glencoe and Newcastle, a succession of wearisome daily treks, until June 5, when the brigade encamped at De Wet's Farm. Then, attached to General Coke's brigade, it took part in the flank march through Botha's Pass into the Orange Free State, assisting in the flank movement which brought about the evacuation of Laings Nek. On June 14, from Volksrust, Captain Jones wrote: "We have been trekking hard and fighting at intervals for a month without intermission." In another letter he describes how, after fighting all day, about 8 P.M. he received orders that his guns were to be got to the bottom of Van Wyk, a hill near Botha's Pass, during the night. There was a dense fog and it was bitterly cold, but by putting every man on the drag ropes the waggons containing the guns were eased one by one down the hill, a most arduous piece of work, as the men had to climb the hill again after each. They worked splendidly, and everything was got down to the drift at the bottom by 4 A.M. "I consider," says Captain Jones, "that this is the best night's work our men have done during the whole campaign." On June 24, Captain Jones and the officers and men of the Forte returned to their ship. Lieutenant A. Halsey, with two 12-pounders, accompanied the flying column, under General Coke, in the advance to Standerton, where they arrived on August 28. Lieutenant C. R. N. Burne, commanding the Tartar's detachment, and Mr. W. R. Ledgard, midshipman of the Philomel, also remained until this portion of the Naval Brigade was finally withdrawn in October.

Work of
the ships.

Although the officers and men who were landed naturally loom largest in the story of the naval participation in the war, the arduous labour that fell upon those who remained on board the ships at sea should not be forgotten. The duties that devolved upon these ships was varied and yet monotonous. They were required to patrol the coast, especially to watch Lourenço Marques, and to arrest such vessels as might attempt to carry on a contraband trade. Some vessels they did actually arrest; but, unfortunately, for political reasons, most of these were released. The fact that this was so should not make less ready public recognition of the zealous work done in this direction. "When everything is taken into consideration," as Captain J. E. Bearcroft said at a banquet given to the Philomel's naval brigade, "the absence of prize money, and the danger

and wear and tear of being always at sea, which they all knew, because they had had to do it, those at the front had, at all times, certainly the best of it." The Philomel herself was, it appears, thirty-four out of thirty-six days at sea, and the odd two days coaling, and this should be a fair specimen of the kind of operations which fell upon those who remained on board the ships, and who, of course, had to work short-handed.

The landing of a brigade at Cape Town, and its despatch to Stormberg, has been already mentioned. When it was decided that Lord Methuen should make an attempt to relieve Kimberley this force was withdrawn through East London, and returned to its ship at Simonstown. There it was reorganised, and when re-landed was commanded by Captain R. S. Prothero, the flag captain to Sir Robert Harris.

The force left Simons Bay on Sunday, November 19, and arrived at Lord Methuen's headquarters at Wittiputs on the 22nd. That afternoon the brigade advanced towards Belmont, and next day took part in the battle called by that name. The guns only participated, and at 1,700 yards made excellent practice until the Boers retreated. On the afternoon of the 24th the brigade moved on, marching at the head of the column to the next bivouac, the guns and ammunition being left in the trains under command of Lieutenant F. W. Dean. That night orders were issued by General Methuen that the Naval Brigade would lead the attack on the following morning on the enemy's position, supported by the Yorkshire Light Infantry, the attacking force being under the command of Brigadier-General Money. The brigade paraded at 3 A.M. on the 25th, and fought the battle which is known both as Graspán and Enslin. The brigade deployed in line, single rank, four paces interval, and advanced on the enemy, Major J. H. Plumbe, R.M.L.I., in command on the left, Commander Ethelston, R.N., in command on the right, and Captain Prothero in the centre. The enemy opened fire at about 600 yards, the brigade advancing with great courage and cool determination by rushes. After losing heavily, both in officers and men, the position was carried by the bluejackets, marines, and Yorkshires. Out of the total of deaths and wounds suffered by the attacking forces in this battle about a third fell on the Naval Brigade. Fifty-seven per cent. of the rank-and-file of the marines were hit and fifteen bluejackets, and of the nine officers killed four belonged to the Naval Brigade. The total number of casualties in the brigade was 105. Commander Ethelston, R.N., Major Plumbe, R.M.L.I., Captain Guy Senior, R.M.A., and Midshipman C. A. E. Huddart were killed; Captain Prothero and Lieutenant W. T. C. Jones, R.M.L.I., were wounded, the last named with a

In the
Cape
Colony.

Battle of
Graspán.

bullet in his hip while charging to the top of the hill. The Yorkshires lost forty-five killed and wounded. After Commander Ethelston and Major Plumbe had been killed their men were led by Lieutenant the Hon. E. S. H. Boyle and Captain A. E. Marchant, R.M.L.I., respectively, the latter officer taking command of the whole brigade when Captain Prothero was wounded. The officers, petty officers, and non-commissioned officers and men of the brigade behaved, says Captain Marchant in his report, with conspicuous gallantry, and Captain Prothero remarks that, in spite of the murderous fire, the behaviour of officers and men was beyond all praise. In addition to the officers, whose names have been already mentioned, reference is specially made to the services of Lieutenant F. J. Saunders, R.M.L.I., Gunner E. E. Lowe, R.N., and Midshipman W. W. Sillem. Lieutenant F. W. Dean, Lieutenant G. W. Campbell, Sub-Lieutenant R. F. White, and Midshipman T. C. Armstrong, who were with the guns, behaved with great gallantry in a very exposed position commanded by the enemy's guns. Lieutenant Dean, referring to the part played by the naval artillery, says: "I continued to fire as briskly as possible at the Boer guns with such effect that we continually put them out of action for as much as fifteen or twenty minutes at a time. Their shells burst with utmost accuracy, and both our guns and ammunition trolley were spattered all over with shrapnel balls; but, owing to my system of making all hands lie down when we saw their guns flash and remaining till the shell burst and the balls flew by, we had only six men wounded when, at 9.30 A.M., the Boers finally ceased and abandoned their position." The invaluable aid rendered to the wounded in the action by Fleet-Surgeon J. Porter and Surgeon C. M. Beadnell is also referred to in the despatches. By direction of her Majesty Queen Victoria the following telegram was sent to the Naval Commander-in-Chief at the Cape of Good Hope: "The Queen desires that you will convey to the Naval Brigade who were present at the action at Graspan her Majesty's congratulations on their gallant conduct, and at the same time express the Queen's regret at the losses sustained by the Brigade."

Comment
on the em-
ployment
of the
brigade.

The employment of bluejackets and marines as infantry in this action has been much commented on and criticised. Seeing that Lord Methuen commanded a force of some 8,000 men the use of the Naval Brigade for the purpose is certainly open to question; but, although it has not been so stated officially, it seems probable that, in this instance, the Navy asked for the position of honour, and possibly claimed it as a right. The result was, in any case, most lamentable, except in so far as the opportunity was given to the seamen and marines to prove that under most adverse conditions

they would behave in a manner worthy of the best traditions of the noble service to which they belonged. Henceforward the naval detachments simply acted as gunners. The remnant of the brigade, under the command of Captain Bearcroft, of the *Philomel*, with Commander S. V. Y. de Horsey, R.N., Captain Morgan, R.M.L.I., and Lieutenant L. O. Wilson, R.M.L.I., accompanied Lord Methuen in his advance, and the guns took part in the battles of the Modder River and Magersfontein. After the last named battle they were almost daily employed in shelling the Boer lines up to the date of the general advance into the Orange Free State.

Lord Roberts, who had been appointed Commander-in-Chief of the Army in South Africa, landed at Cape Town on January 10, 1900, and a few days later applied to the Admiral for two more naval 4.7-in. guns on travelling carriages. The crews for these guns were made up of fifty-nine men from the *Doris* and *Barrosa*, under the following officers: Commander W. L. Grant, *Doris*; Lieutenant J. A. Fergusson, *Barrosa*; Surgeon T. T. Jeans, *Monarch*; Gunner J. Cannon, of the same ship; and Midshipmen G. H. Lang and James Menzies, both of the *Doris*. These guns were originally intended to operate with General French, at Rensburg, and were landed at Port Elizabeth on January 31, 1900, and sent up by train to Naauwpoort for that purpose. They were afterwards ordered to join Captain Bearcroft's Brigade, but throughout the operations formed a complete naval unit by themselves, and were again detached later on, and are generally spoken of in the telegrams from South Africa as "Grant's guns." To these two guns transport was attached consisting of thirteen large waggons, two small ones for water carts, and 280 oxen, with forty-two native drivers and four Colonial conductors. The mountings of the guns were on the Scott principle, but that which belonged to the flagship had a trail made of steel and weighed about five and a half tons, or somewhat lighter than the mountings which had wooden trails. Each gun was drawn muzzle first by a long steel chain attached to the framework of the mounting, the trail being hung to a limber which formed the steering-gear of the gun. Thirty-two oxen were allotted to each gun, sixteen to each wagon, and six to a water-cart. A span of sixteen oxen covers about fifty yards. The distance taken up by a number of guns was thus very great. Much difficulty was experienced with the chains used for trekking, as these, when broken, had to be mended with steel wire. As in Natal, when it was necessary to cross a drift, drag-ropes were hooked to the wheels and the men assisted in getting the guns over. During the march from the Modder onwards soldiers were frequently told off for this work. Grant's guns marched

Later
operations
in Cape
Colony.

into Jacobsdal on February 16, escorted by half a battalion of Royal Canadians, singing "We'll rant and we'll roar, like true British sailors," and other nautical songs.

Advance
into the
Orange
State.

Paarde-
berg.

The remainder of the Naval Brigade, which had been for the past three months at Magersfontein, marched into Jacobsdal on February 18, with two 4·7-in. guns and two 12-pounders. These guns were dragged trail first, being fastened to ox-waggons. On the following day the whole brigade, with its six guns and escort of marines, started on the march to Johannesburg. In the endeavour to get up in time to participate in the blockade of Cronje's laager at Paardeberg, the brigade on one occasion, in twenty-two hours, covered twenty-seven miles, probably a record for guns of this size and weight. On their arrival at Paardeberg three of the 4·7-in. and one 12-pounder were sent to the north of the Modder River, where two other 12-pounders had already been placed in position. The remaining guns remained on the south side, and all took part in the bombardment at ranges varying from 1,300 on the south side to 2,500 on the north. In these positions the naval guns remained until the capitulation. Surgeon C. M. Beadnell accompanied the Royal Canadians in the final advance, and was the first doctor to enter the laager and attend to the Boer wounded. The three guns from the north of the river now rejoined the main body, the other two 12-pounders being sent, under Lieutenant Colquhoun, of the Victorian Navy, to Kimberley, for repairs. These two guns had accompanied General Kelly-Kenny in his chase of Cronje, and on one occasion, when it had been found impossible to get them to the top of a kopje in the usual way, the guns were dismounted, lashed to poles, and carried to the top by their crews, with the help of some of the soldiers. Then they opened fire upon their retreating enemy. These two guns rejoined headquarters before the brigade left Paardeberg.

Poplar
Grove.

Bloem-
fontein.

The brigade next took part in the battle of Poplar Grove, and on March 10 began its march of seventy miles to Bloemfontein, with the central division, where it arrived without any particular incident. By some mistake it missed the promised honour of taking part in the entry into the capital of the Orange Free State, but a few days later, on March 21, was inspected by the Field-Marshal, who thanked the seamen and marines for their services, and wished good-bye to those officers and men who had been ordered to rejoin their ship, the *Powerful*. It was at Bloemfontein that the brigade was fully clothed in khaki serge and felt hats of the same pattern as worn by the Army, the only difference being that on the turned-up brims of the hats the bluejackets wore the Admiralty badge of a foul anchor,

and the marines a bugle. For seven weeks the brigade remained at Bloemfontein, and owing to the depletion of the ranks from sickness, was there reorganised, the bluejackets being formed into crews sufficient to man three of the 4·7-in. and the 12-pounders, while the fourth 4·7-in. was allotted to the marines. On April 23 Grant's guns were attached to the Highland Brigade and left for the waterworks, and on May 1 the rest of the brigade, under Captain Bearcroft, left for the north with Lord Roberts. Two 12-pounders were left behind in Bloemfontein. The strength of the brigade after the Powerfuls had left was 400, and out of this number ninety went into hospital suffering from typhoid, dysentery, or fever.

After leaving Bloemfontein the brigade, under the command of Captain Bearcroft, was a good deal split up; the main body remained with the Field-Marshal Commander-in-Chief until his arrival at Pretoria, taking part, among other occasions, at the engagements on the Wet River, the Zand River, and that which occurred on June 4, where Commander Spencer de Horsey, whose calmness, ability, and energy are commended by the Captain, was wounded. The movements of this portion of the brigade had been to Brandfort, where it arrived on May 4, from thence to Smaldeel, distance twenty-one miles, which was reached on May 6, from thence to Kroonstadt, where the brigade arrived on May 12. Kroonstadt was not left until May 22, the Rhenoster River was crossed two days later, the Vaal River at Viljoen's Drift on May 27, and Johannesburg on May 31. Here the portion of the Naval Brigade present marched past the Field-Marshal Commanding-in-Chief, and camped out about seven miles on the Pretoria road. The next action was that already mentioned, on June 4, and on the following day the entry was made into Pretoria, the brigade during this latter portion of the march having been attached to the 11th Division, with which it marched on to Christenin, about eight miles east of Pretoria on the Middleburg road, where it encamped. Four men of the Tartar, who had been taken prisoners in the armoured train disaster of November 15, here rejoined the brigade, having escaped from the Boers. In spite of the long forced march the officers and men had stood the strain well, and so had the guns and their mountings, though part of these had to be renewed. The general conduct of the men, says Captain Bearcroft, was very good indeed.

Advance
into the
Transvaal.

Throughout the months of August and September the four guns under Captain Bearcroft were continually at work in the advance to the eastward, sometimes together and sometimes in divisions. Major Marchant, R.M.L.I., went as far as Belfast with a 4·7-in., while Lieutenant Back carried his two 12-pounders right to Koomati

East of
Pretoria.

Poort, the Headquarters, proceeding to Barberton. During this time the guns were frequently in action, and the casualties, although few, included Lieutenant L. O. Wilson, R.M.L.I., on August 26, when the heavier guns were in position on Monument Hill, covering the advance of the Cavalry Division and the Guards' Brigade. The journey from Belfast to Barberton was over exceptionally heavy country, with bad roads, steep pitches both up and down, and many drifts, causing a heavy strain on the gun wheels; indeed, on this and other occasions breakdowns occurred, but the men worked indefatigably day and night, and the ingenuity and resourcefulness of the artificers and handicraftsmen attached to the brigade enabled matters to be put right with hardly any delay. The march of the 12-pounder battery with the force under General Pole-Carew was a most remarkable piece of work, among much which is remarkable. From September 6, when the guns were encamped at Waterval Onder, to September 23, when they arrived at Koomati Poort, the distance covered was 144 miles, and much of it over mountainous and rough country. These guns were returning by train to Pretoria when they ran into another one which was being shunted. Two trucks of the latter were completely smashed, but by the aid of drag-ropes and hydraulic jacks the wreckage was most expeditiously cleared away by the bluejackets, and the line reported "clear" to headquarters in less than two hours. In this work, says Lieutenant Back, who was in command, the armourer and three stokers were of great service.

Return to
Simons-
town.

On October 7 the three divisions of Captain Bearcroft's command reassembled at Pretoria, where the brigade was inspected by the Field-Marshal Commanding-in-Chief, when Lord Roberts expressed his high appreciation of the services rendered by the bluejackets and marines. It was on this occasion that the Field-Marshal sent the following telegram home: "I wished Captain Bearcroft and the Naval Brigade good-bye to-day. They leave for Capetown to-night, carrying with them the thanks and good wishes of the army in South Africa for the able assistance they have afforded throughout the war."

Services
of the
brigade.

The brigade arrived at Simonstown on October 12, and Captain Bearcroft, on relinquishing the command, makes the following observations in a despatch to the Admiral: "The work of the brigade has been of a novel and more or less arduous nature throughout, the guns having travelled upwards of eight hundred miles after leaving Modder River, over country of all sorts. The marching powers and endurance of the men have exceeded my expectations, while the energy, zeal, and cheerfulness of officers and men under all circumstances have been most satisfactory and encouraging. The general

conduct of the men has been most exemplary, in spite of the many temptations placed in their way during enforced periods of inactivity at Modder River, Bloemfontein, Pretoria, and Barberton."

It has already been noted that Commander Grant was detached by Captain Bearcroft at Bloemfontein on April 23 and placed under the orders of General Colvile, with two guns. He did not again rejoin, but, under different military commanders, took part in a number of fights, and was for days at a time under fire. In his final report on the operations, Commander Grant gives the following table and information respecting the work done by his two guns.

Grant's
Guns.

The summary of work done is as follows :—

| | Days Marching. | Miles. | Miles average March |
|---|-------------------|--------|---------------------------|
| Enslin to Bloemfontein | 14 | 169 | 12·1 |
| Bloemfontein to Winburg | 8 | 95½ | 11·94 |
| Winburn to Heilbron | 8 | | |
| Eight days consecutive marching, with fighting on five of them | — | 127 | 15·9 |
| Chasing De Wet | 17 | 265 | 15·6 |
| Potchefstroom Column | 20 | 310 | 15·5 |
| Total | 67 | 966½ | 14·43 |
| Marching to positions and fights, etc., and returning to camp— about 70 miles. | | | |
| Total | | 1,036 | |

On August 1 Grant's guns were attached to General Hart's Brigade and took part in the chase of De Wet, during which 250 miles were covered in fifteen consecutive days, giving an average of 16·7 miles. The longest marches were thirty-seven miles in thirteen and a quarter hours, and thirty-seven miles in twenty-five hours. Fourteen of the day's marches included in the above table were from two to six miles and nine more ten miles and under. Deducting these, 816 miles were marched in forty-four days, with an average of 18·5 miles. On the twenty-five different occasions on which the guns fired in action, counting the eight or ten days' bombardment of Paardeberg as one, 520 rounds were fired, the longest range being 9,000 to 10,000 yards and the shortest 1,900 yards. Commander Grant says in his despatch: "I have much pleasure in reporting that the spirit, endurance, and behaviour of officers and men throughout the campaign has been beyond praise. Work, often under conditions of great hardship, requiring endurance and spirit to a very high degree, has been met throughout with the greatest spirit and cheeriness, and the smartness, discipline, and soldierly qualities they

have displayed will, I am sure, ever be remembered to their credit and that of the Naval Service. In no single instance has Lieutenant Ferguson ever had to bring a man before me for any crime, neglect of duty, slackness, or any other offence whatsoever, and this for a period of nearly nine months. The marching powers displayed by the men have been to me quite a revelation, and by no troops in South Africa have I seen them excelled."

In South Africa then, the Navy did well; naval officers occupied important posts; naval officers introduced a revolution as regards all former ideas of the mobility of heavy siege guns, and in all the brigades the seamen and marines earned the praise of the naval and military chiefs alike. The Admiralty expressed their opinion in the following words: "The Navy upheld the traditions of the service and added to its reputation for resourcefulness, courage, and devotion."

THE NAVY IN CHINA.

The origin of what it is the custom to call the crisis in China, or any investigation of the causes which led to the events at Peking last year, would be foreign to our purpose here. The story of the work of the Navy may be said to begin with the despatch of a Legation Guard consisting of three officers and seventy-two men to the Chinese capital at the request of our Minister. This guard arrived in Peking with similar representatives of the American, French, Russian, Japanese, Italian, and other forces despatched to protect their Legations. What happened in Peking will be told in its place, but an account of the work of the Navy in this connection naturally divides itself under four heads:—the Seymour Expedition, the capture of the Taku Forts, the defence of Tientsin, the siege and relief of the foreign legations in Peking; and in this order I propose to deal with them.

Four days after the arrival of the Legation Guards, railway communication with Peking was finally interrupted, and this, following upon the massacre of British missionaries by the turbulent Boxers, was sufficiently alarming to point to the fact that it was no mere temporary wave of local excitement which had to be met. A large number of ships of the different Powers had assembled off the mouth of the Peiho, and Sir Edward Seymour, as the senior naval officer, suggested a conference at which all the senior officers of the naval forces were present, and it was agreed to take such measures as might become necessary in conjunction. The fact that the Legations were also seriously imperilled necessitated a military step almost immediately. Telegraphing from Tongku on June 10 to the Admiralty, Sir Edward Seymour reported the following telegram from the Minister at Peking: "Situation extremely grave, unless

arrangements are made for an immediate advance to Peking it will be too late." In these circumstances there was only one thing to do. All the available men from the squadrons were landed to the number of about 2,000, and the British Admiral, placing himself at the head of this force, attempted to reach Peking in order to effect the relief of the besieged Legations. When the Admiral thus started in his gallant attempt to relieve the women and children, whose position appeared to have become desperate, everything pointed to the success of a bold and determined display of force. As the Japanese Admiral reported, up to the moment when the expedition started on June 10 there was no reason to doubt the friendly disposition of the Chinese authorities. After passing Yangtsun, where it was found that the Boxers had made attempts to destroy the bridges and had torn up the sleepers of the railway, the workmen and materials for the repair of the track were furnished by the Viceroy of Chi-li. It was not indeed until seven days later, when the column was less than half way to Peking, that the Chinese troops made a hostile demonstration. The changed attitude on the part of the Chinese authorities appears to have been directly connected with the bombardment of the Taku Forts, which were stormed and captured at dawn on the 17th, the morning before Admiral Seymour's expedition was attacked at Lang Fang by General Tung's foreign-trained troops equipped with modern arms. The radical alteration in the situation brought about by the introduction of this new factor was at once appreciated by the Admiral. He thereupon decided to abandon his advance by the railway and to return by the river to Tientsin, carrying his wounded in boats. It is unnecessary to find an excuse for the brave and gallant attempt made by Sir Edward Seymour and his colleagues. Although the undertaking was made impossible of achievement, its glory remains. As the Admiral has himself said, "I am aware, was aware, of its risks; but to my mind no other course was open to me in view of the urgent appeal from Peking. I could not with honour have held back. I went myself as the best and only possible way to put all under one head. When the Imperial Chinese troops, in numbers unknown, took arms against us, the project became impossible and retreat difficult. Two or three times our prospects were very dark and disaster seemed not improbable; yet I never regretted that I had started, as I could not have respected myself if I had not done so." The immediate purpose of the expedition failed, it is true, but the failure was of a kind which marks in glowing colours some of the brightest pages in our history.

The accounts of what befel the expedition, both public and private, are numerous. They paint a vivid picture of the hardships and perils.

Battle of
Lang
Fang.

The re-
tirement.

experienced by the column, and bear ample testimony not only to the pluck and endurance shown by all who took part in the expedition, but also to the healthy spirit of combined emulation and mutual helpfulness which united in a common effort the seaman and marines of eight different nationalities. The principal battle appears to have been that which was fought at Lang Fang on June 18, the battle which decided the Admiral to turn back. The allied force here consisted only of about one-third of the expedition, the British detachment being supplied by the *Endymion*, *Aurora*, and *Orlando*. The enemy numbered about 5,000, and it was not until after between two and three hours' hard fighting that the attack was repulsed. The enemy sustained a loss of between 400 and 500, while the loss on our side was 58 killed and wounded. Two days previously the Admiral had discovered that his communications with Tientsin had also been cut, that the bridge at Yangtsun was destroyed, and that the trains were useless. The task before him was to secure a retreat, and by the skill, courage, and discipline of those with him, and the ability, gallantry, and tact of the Admiral himself, and the loyalty of the foreign officers who accepted his wishes as orders, this task was successfully achieved and without disaster. The narratives of those engaged relate how day by day they had to fight their way with the ammunition supply running short, and encumbered by the wounded who could not be abandoned because the Chinese beheaded all who fell into their hands. Admiral Seymour himself testifies to the hard straits they were put to, "drinking Peiho water, which is like red pea soup, plus the most awful things thrown into it." And again, "at one time we shot a horse and its rider in action in the morning and ate the former in the evening." It was not until June 22, when the column seized the Hsiku Arsenal and found therein a store of rice, that the danger of starvation passed, for all the stores and provisions save a very trifling amount were necessarily abandoned with the trains. Relief came on Monday, the 25th, when a force from Tientsin cleared the line of communication and enabled the expedition to make good its withdrawal from the Arsenal.

Harmony
among the
Allies.

Not the least among the pleasing features of the despatches from the different commanders are those which bear testimony to the perfect harmony which prevailed among the units of the allied force. From first to last there never was a breath of dissension; the foreign officers speak in the most enthusiastic terms of Sir Edward Seymour, and he bears testimony to the valour and whole-souled assistance given to him when in a trying and unexampled position. This singularly daring and dangerous march is one which will always be remembered as among the most stirring and adventurous of our time.

In an order issued to the squadron the Admiral pays the following tribute to the services of those with him: "The officers and men landed from Her Majesty's ships and present with me acted throughout, as regards energy, courage, and cheerfulness, in a manner well worthy of the high traditions of Her Majesty's Navy."

We now return to the squadrons which were lying off Taku when the Admiral landed, and to Tientsin, where a naval brigade, under the command of Captain E. H. Bayly, of the *Aurora*, had been left. On June 15 it was discovered that the Chinese were laying torpedoes in the river Peiho and concentrating regular troops in the neighbourhood of Tientsin as well as in the Taku Forts. The senior officers of the foreign ships then met on board the Russian flagship and addressed an ultimatum to the Chinese commander of the Taku Forts, requiring him to withdraw his troops by two o'clock on the afternoon of June 17. A naval brigade, made up of English, Russians, Italians, Austrians, Germans, Japanese, and French, had been prepared for landing on the previous night and were in readiness to support the demands of the foreigners. At one o'clock on the morning of June 17 the Taku Forts opened fire on the foreign, gunboats in the river. An artillery action ensued which lasted seven hours, when the forts were stormed by the foreign forces.

Capture of
the Taku
Forts

At the time when these events occurred the vessels lying in the Peiho were (British) the *Algerine*, Commander R. H. J. Stewart, a steel sloop, 1,050 tons displacement, mounting six 4-in., one 25-pounder, and four 3-pounders, and two torpedo-boat destroyers, the *Whiting* and *Fame*; (German) *Iltis*, gunboat, 894 tons displacement, eight 3·4-in., six 1·4-in.; (French) *Lion*, wooden gunboat, 503 tons, two 5·5-in. guns; (Russian) *Bobr*, gunvessel, 950 tons, one 9-in., one 6-in., nine machine-guns, *Koreets*, gunvessel, 1,213 tons, and *Gilyak*, gunboat, 963 tons, one 4·7-in., five 3-in., two 2·6-in., and four 1·8-in. guns. The United States steamer *Monocacy*, and the Japanese vessel *Atago* were present, but took no part in the action. On the east side of the river, near Tongku, a large force of Japanese and Russians, with some bluejackets from the *Orlando* and other ships, were encamped, the remainder of the British Naval Brigade being in a tug alongside the *Algerine*. The larger foreign men of war, to the number of twenty-five, of seven different nationalities, and including the following British ships, *Centurion*, *Barfleur*, *Orlando*, *Aurora*, and *Endymion*, were anchored ten miles off the forts outside the Taku bar.

The forts at the entrance to the river were of a very formidable nature. On the north side of the bend which the river makes from the bar there are two forts. The outer fort is casemated with earthworks

throughout, mounting about fifty guns. About a third of a mile up the river is a strong but smaller fort, sometimes called the North-West Fort, mounting about thirty guns. These two defences are connected by a curtain and covered way, with small guns on the parapets. The forts on the south bank stretch along the seashore for about a mile, these batteries mounting about one hundred and twenty guns in all. About a mile inland there is another fort on the south side, built for the protection of the main magazines. All these fortifications had been modernised, and consisted of earthworks with concrete galleries and powerful redoubts, surmounted by lofty cavaliers armed with quick-firing guns. The armament generally, although of a very varied nature, comprised specimens of nearly every description of modern British and German artillery. The garrison of the forts probably consisted of about three thousand regular Chinese soldiers, but no large number of trained gunners.

The
attack.

It was a little after midnight when the inner fort on the north side opened fire on the Algerine, and the British vessel replied, the Russian gunboats shortly afterwards joining in the bombardment. Then the German gunboat, which had been moored to one of the railway wharves, cast off and, steaming down the river, came into action, followed by the French gunboat, which had been at anchor higher up the river. These two vessels were cheered by the British and Russians as they took up their stations and replied to the forts, which had now all joined in the fight. The *Iltis*, Algerine, and *Lion* dealt principally with the north forts, while the Russians fired on those on the south side. As soon as the battle commenced the *Fame* and the *Whiting* attacked four German built destroyers, which were lying alongside the naval yard. The Chinese crews, after the first round, bolted, and these vessels were captured and carried up out of the fire of the forts. The bombardment went on intermittently through the darkness until between four and five o'clock, when the day broke and the Chinese gunners redoubled their exertions. The Russian *Gilyak* was badly hit and her fore magazine blew up. The men-of-war now got under way, and almost immediately the German *Iltis* was badly hit and had to be beached. A little later a shell from the Algerine blew up one of the southern magazines and the Naval Brigades began, at about the same time, their advance. The bombardment went on, however, and it was not until half-past seven that all the forts were silenced and their garrisons were flying before the storming parties. The storming of the forts was a very quick business, the brigades charging right into them, capturing the north-west fort first, where the Japanese lost several men, including their commander, and the British had one or two wounded. The second north fort was captured

unopposed, and the Germans turned its guns, which were similar to those in their ships, upon the forts on the south bank. Then the brigades crossed the river and captured the south forts without opposition. The losses on the side of the Allies in the bombardment were:—British, one officer wounded, three men killed; German, six men killed, fifteen wounded; France, one officer killed, one man wounded; Russians, three officers wounded, sixteen men killed, and forty-two men wounded. Commander R. H. J. Stewart, of the *Algerine*, well and ably handled his ship in this action, and Rear-Admiral Bruce, in reporting the matter, mentions that the manner in which he manœuvred his vessel largely contributed to the success achieved, which at one time was extremely doubtful. He adds that the way in which the *Algerine* was taken close under the forts, so that most of their shot went over her, accounts for her small loss. “He (Stewart) and the Captain of the *Iltis*, were always contending for the post of danger, and the German officer is, I regret to say, severely wounded in several places.” The British landing party was under the command of Commander C. G. F. M. Cradock, whose conduct, with that of the officers and men under him, was mentioned in the Admiral’s despatch as worthy of the highest praise.

At this time the communication with Tientsin had been severed, and the Seymour Expedition had not been heard from for more than a week, and was generally believed to have been destroyed. The problem therefore which presented itself to Admiral J. A. T. Bruce and his foreign colleagues was to reopen the line to Tientsin and to discover the whereabouts of the Vice-Admiral and his force, if still in existence. With this purpose in view a force of Russians and Americans advanced towards Tientsin, but were repulsed about twelve miles from the city. On June 21 an Englishman, with three Cossacks, brought the news, having pluckily ridden through the Chinese lines, that the garrison was still holding the foreign settlement, but was incessantly bombarded from the Chinese arsenal and forts. A larger relief expedition was then organised, a brigade of 200 bluejackets, under Captain Cradock, forming part of it. This force left Taku on June 22, and after two days’ fighting arrived at Tientsin, reopening the communications. The garrison of Tientsin was now strong enough to attempt to succour the force under the Commander-in-Chief, which was known to be only eight miles distant to the north. On June 25, therefore, a relief force was despatched to the Hsiku Arsenal, and the whole body returned on the following day.

The defence of Tientsin covers the whole period from June 10, when Sir Edward Seymour passed through to the north, until

Tientsin.

Defence of
Tientsin.

July 13-14, when the native city was carried by the allied forces, and the road thereby opened to Peking, although it was not until August 5 that the relief force marched out and defeated the Chinese entrenched at Peitang, and not until August 15 that Peking was entered by the Allies, after a stubborn resistance. The brunt of the earlier portion of the defence fell upon the British and the Russians; indeed, if the latter, who formed the larger part of the garrison, had not held the bridge of boats, there might not have been any foreigners left alive in the place. A constant battle raged round the railway station, the French settlement was completely burnt down, and scarcely a day passed without increased activity on the part of the enemy. Sir Edward Seymour, in his despatches, divides the above period into three stages—the fortnight between June 10 and June 26, when he himself arrived on the scene, then from June 26 to July 11, when he returned to his flagship, and from the last-named date to the date of the capture of Tientsin City—with the result already referred to.

Dealing with the first stage, we find that immediately after Sir Edward Seymour had left the Chinese began to obstruct the work of sending forward reinforcements, and trains were with difficulty sent through until the 14th, when the line was completely destroyed. On June 11 Captain Bayly's brigade was reinforced by 150 seamen and marines, under Commander D. Beatty, of the *Barfleur*, and on the 13th about 1600 Russians, with cavalry and field-guns, arrived. The settlement was attacked on June 16, but the Russians drove the attacking party away after they had set fire to several stores and houses. The Chinese also made attempts now to cut the line communicating with Tongku, but were driven off by a naval force under Lieutenant G. B. Powell, of the *Aurora*. The same day the Military College across the river, which commanded the British concession, was taken by a party of the allied forces, under Major E. V. Luke, of the marines, and the building, with the guns found in it, destroyed. On June 18 an engagement took place round the railway station, in which two British companies, under Commander Beatty and Lieutenant P. N. Wright, of the *Orlando*, did good service. On the next day an unsuccessful attempt was made by the British seamen and marines to capture some Chinese guns near the railway embankment. In this action Commander Beatty, Lieutenants F. Powell and A. J. B. Stirling, Mr. A. P. Donaldson, midshipman, and eleven men were wounded. Mr. Donaldson died of his wounds on July 3. The same day a shell from one of the Chinese guns struck Lieutenant Wright, who was on the roof of the Consulate, inflicting most dangerous wounds on his head and arms. Throughout the remainder of the period under consideration small attacks and skirmishes took place daily,

while the Concession was almost unceasingly bombarded from the native city. Sir Edward Seymour, referring to these operations, which he considers to have reflected great credit on all concerned, remarks that Captain Bayly, whose duties were most constant, harassing and onerous, displayed throughout great calmness, energy, and good judgment, and a tact and temper quite remarkable.

In the second period the principal actions occurred on June 27 and July 4. On the first occasion a naval force, under the command of Captain Burke, of the *Orlando*, supported a Russian attack on the Arsenal. They had to push forward on a flat plain for a considerable distance under a flanking fire, and when they were advancing were subjected to a harassing shrapnel fire from a field gun. At about 250 yards from the Arsenal our men fixed bayonets and charged, driving out the enemy. The British casualties were seven killed and twenty-one wounded, including two officers. On July 4 a British battalion, under Captain C. D. Granville of the flag-ship, was sent out to reinforce the French and Japanese, who were repelling an attack made by the Chinese on the railway station. For three hours the bluejackets remained in a pouring rain under a heavy shell fire, when eventually the Chinese were repulsed. We had several men wounded and one killed. Two additional 12-pounder guns on Scott's mountings were received in Tientsin this day—making three in all, the other guns with the Naval Brigade being two 9-pounder muzzle loading guns, and three 6-pounder hotchkiss. The movement which was to result eventually in the capture of the native city began virtually on July 6, when a bombardment intended to keep down the fire of the Chinese guns was begun, as well as various attempts to capture their artillery. Mr. F. S. D. Esdaile, midshipman, of the *Barfleur*, was wounded in one of these engagements. In the final operations of the 13th and 14th the Naval Brigade, numbering a little over 300 bluejackets and marines under Captain Burke, of the *Orlando*, joined the left attacking column in support of the Japanese. It was on this occasion that Captain H. T. R. Lloyd of the Marines, who had been engaged in every action, both in the Seymour Expedition, and those which had taken place around Tientsin, was killed. The Naval Brigade had their full share in the fighting and were among the first to enter the native city.

In publishing the China despatches the Admiralty included a letter dated October 1, to the Commander-in-Chief, in which they expressed their high appreciation of the tact and judgment displayed by the Admiral in his gallant attempt to relieve the Legations at Peking, which they believed to have contributed so greatly to the harmonious feeling that prevailed between the various sections under his orders.

Their lordships considered that having been suddenly called upon to assume command of a mixed force comprising representatives of almost every nation, great credit was due to the Admiral for the rapidity with which this force was organised, and for the manner in which the expedition was conducted in view of the great difficulties necessarily attending it, and the overwhelming numbers of the opposing forces. Their lordships also noted that they had read with great pleasure the Admiral's testimony to the courage shown and the hardships cheerfully endured by the officers and men in the expedition, and they wished to express to all concerned their unqualified satisfaction at receiving this high commendation of their conduct.

Pekin
Relief
Force.

The Naval Brigade, formed for the advance on and the relief of Peking, in company with H.M.'s military forces under Lt.-Gen. Sir Alfred Gaselee, K.C.B., commanding the China Expeditionary Force, was commanded by Capt. George A. Callaghan, R.N., of the *Endymion*, with Commander R. S. Fraser, of the *Phoenix*, as second in command, and comprised 21 officers, and 500 seamen and marines, with two 4-in. quick-firing guns and four 12-pounder quick-firing guns.

The Naval Brigade was formed at Tientsin on July 30, the four 12-pounder quick-firing guns being mounted on temporary field-carriages. The field mountings for the two 4-in. quick-firing guns were constructed at the factory at Taku, under the superintendence of Mr. A. Dupen, engineer of H.M.S. *Phoenix*, by the artificers of the *Endymion* and *Phoenix*. On August 3 the Naval Brigade moved out from Tientsin and marched to Hsiku (about 8 miles) and camped there, the 12-pounder quick-firing guns being conveyed there by junks and disembarked. The two 4-in. quick-firing gun mountings not being completed, Commander Fraser and 50 men were left behind at Tientsin to bring them on when ready.

Fight at
Peitsang.

On the morning of August 5 at 4 A.M. the Naval Brigade advanced with the allied forces and attacked the enemy's position at Peitsang. Three of the 12-pounder quick-firers were brought into action to support the Russian attack on the extreme right on the left bank of the Peiho. The guns opened fire at a range of 5,500 yards, and continued the attack on the bridge, and after drawing shell fire of considerable accuracy from the enemy, drove them from their position, and later shelled the enemy, who formed up in retreat on open ground (at a range of 8,800 yards), and dispersed them to the northward. The naval guns were supported in this action by the Royal Marine Battalion under Major E. V. Luke. At about 11 A.M. the guns advanced on Peitsang, which was occupied without further resistance, the allied forces camping there for the night.

On the morning of the 6th the 12-pounder guns were placed in

the gun junks, and the forces advanced at 6 A.M., the Naval Brigade following the bank of the river with the guns in the junks. Owing to the delay in cutting the Japanese boat bridge at Peitsang, the guns did not reach Yangtsun until after that place was in the hands of the Allies. Yangtsun was reached at 7 P.M. that day. At 8 A.M. on August 8 a fresh advance was made, the naval guns advancing in the junks, with the gun crews marching along the river bank. The marine battalion was now brigaded with the troops of the 1st Brigade under Brig.-Gen. Sir N. Stewart. At 4.30 P.M. on August 9 the junks arrived at Hosiwu, which place only offered a very slight resistance. Capt. Mullins, R.M.L.I., was left here as post commandant with 200 allied troops, including 50 marines.

On August 10 the guns advanced at 7.30 A.M. by the river (three hours in advance of the troops), and, stopping at 9 P.M., continued to advance at 4 A.M. on the 11th, arriving at Matao at 3 P.M. the same day. The heat was intense, many casualties occurred among the cavalry and artillery horses, and a large number of troops, including marines, fell out. It was remarkable that no seamen were affected much by the sun, although wearing only straw hats, while British troops in helmets and American troops in "slouch" hats suffered considerably. After a rest of two hours at Matao, the naval guns continued their advance. Considerable difficulty was now experienced in the navigation, the river being very low in some places, and the most ordinary precautions on the part of the enemy—such as blocking the channel—would have entirely prevented the passage by the junks. Tung Chow was reached at 2 A.M. on August 13, and three 12-pounder quick-firing guns disembarked, the junk carrying the fourth gun having grounded some miles down the river. The Royal Marine Battalion again joined the Naval Brigade. At 4.30 P.M. on the same day the naval guns, accompanied by the Royal Marine Battalion, commenced the advance from Tung Chow to Peking, a distance of 13 miles. The road by which the advance was ordered was that south of the Uliangho, and was in very bad condition. In many places the gun wheels were almost below the level of the mud through which they had to be drawn. The Japanese ponies, which had been provided to assist to drag the guns, were practically useless, never having been trained for draught, and the work of drawing the guns devolved almost entirely upon the gun crews, and it was found necessary to reduce the marine battalion to a small advance guard, and use the remainder on the drag ropes. The march was a very trying one. During the evening of August 13 rain fell in torrents and filled the roads. A halt was made at 10 P.M., and the Naval Brigade bivouacked for the night just beyond the Palikoo

Advance
of the
column.

Relief of
Pekin.

Bridge. At 3.30 A.M. on August 14 a fresh start was made, progress being difficult owing to the muddy road and the sun becoming intensely hot. A midday halt was made about 5 miles from Pekin, and finally the naval guns reached a position under the walls at about 5 P.M., and camped there for the night, the British troops having entered the city about 3 P.M., and the other nationalities shortly after. At 4 A.M. the Naval Brigade entered the city and proceeded to the "Temple of Heaven," and later were sent to guard the east gate of the Chinese city, the Royal Marine Battalion going to the British Legation, and being again temporarily brigaded with the 1st Brigade. At daylight on August 16 the Royal Marine Battalion co-operated with the French troops in the relief of Peitsang, and returned and garrisoned Coal Hill, Imperial City. The seamen and marines remained in Pekin sixteen days, sending out foraging parties, and the seamen patrolling the south-east quarter of the Chinese city.

On Tuesday, August 28, a detachment of seamen and marines (thirty of each) took part in the triumphal march through the Forbidden City. On August 31 the whole of the Naval Brigade, including the marines who had formed the Legation Guards during the siege, left Pekin and marched to Tung Chau, arriving that evening, and embarked and proceeded down the river, picking up the detachment at Hosiwu, and arriving at Tientsin on September 3, returning to their ships at Taku on September 5. One of the two 4-in. quick-firing guns under Commander Fraser left Tientsin on August 9 by junk, and reached Tung Chau on the 18th, and returned to Tientsin four days later.

The
defence of
Pekin.

It has already been explained that, in response to a request from the Minister in Pekin, a Legation Guard was ordered to that place. The Guard arrived in Pekin on the night of May 31, and consisted of 3 officers, 75 non-commissioned officers and men, 1 bugler, 1 armourer, 1 signaller, and 1 sick berth steward. The officers were Captain B. M. Strouts, who was in command, Captain L. S. T. Halliday, of the Orlando, which ship contributed 27 of the marines, the signaller, the armourer, and the sick berth steward, and Captain Edmund Wray. Ordinary guard duties were performed by the marines until June 13, on which date a party of Boxers entered the Tartar City near the Legation settlement, and from this date onwards the detachment was continuously on the alert and at the posts in the defence. The active siege continued until July 17, when there was a practical cessation of firing until August 5. The siege was raised on the afternoon of August 14 by the Allies.

The following account is compiled in the main from a diary kept by Captain Wray who succeeded to the command after Captain

Strouts and Captain Halliday had been wounded. On June 14 the picket of an officer and 12 men on the north bridge was attacked by some hundred Boxers, who were repulsed, losing four killed and two wounded. On the following day Captain Halliday, with a combined force of British and German marines, rescued several hundred Chinese Christians who were being massacred by Boxers. On June 17 the Chinese Imperial troops attacked the picket on the north bridge, and two days later the Chinese Government issued an ultimatum demanding that all the ministers should leave Peking within twenty-four hours. It was decided to remain and defend the Legations. On June 20 the picket on the north bridge was withdrawn, and our sentries at the front gate opened fire for the first time on Imperial troops. The following day Sir Claude MacDonald took supreme command of the Legations Settlement, and on June 22 an unsuccessful attempt was made by Boxers to burn the Legations at the south-west corner. Captain Poole, with 15 marines, reconnoitred the Hanlin, which, on the 23rd, was set on fire by the Chinese with the object of burning the Legation from the north. Captain Halliday, later, with 30 marines was sent by Captain Strouts to drive the enemy from the houses behind the First Chinese Secretary's house. He was attacked by the Chinese and wounded, but killed four or five of his assailants with his revolver, and subsequently returned to the Legation. Captain Strouts then took charge, and succeeded in driving the enemy back and capturing some arms and ammunition. On June 29 Captain Wray made a sortie for the purpose of capturing the Krupp gun which the Chinese had used against the Legation with some effect. He was assisted by a mixed force of British, German, and Russian marines, but it was finally discovered that the gun had been withdrawn. July 8 was notable as being the day on which an old smooth bore gun was found and mounted by an American gunner, assisted by Armourer Thomas, R.N., who also manufactured the ammunition, the projectiles being the shells of a modern Russian field gun.

From July 11 onwards British marines were constantly sent to reinforce the Japanese and Italian posts in the Suan Fu, where the heaviest attacks of the Chinese were directed, and on the 12th Captain Wray himself took command of the Italians at their post, as the Italian officer commanding had been killed. On July 16, while returning from a visit to Captain Wray's post, Captain Strouts was mortally wounded, and died three hours later. Captain Halliday was the next in seniority, but being still unfit for duty Captain Wray took command. From July 17 until August 4 there was a cessation of hostilities, except for a little sniping on both sides,

but chiefly on the part of the Chinese, and on August 13 the Chinese Government issued orders to the effect that any Chinese soldier firing on the Legations would be court-martialled. Naturally, numbers of men distinguished themselves during the siege, and Captain Wray makes special mention of Lance-Sergeant Preston of the Orlando. It appears that on July 14 the enemy had been driven down from their barricade on the Imperial Carriage Park wall near the West Hanlin by shell fire, and this N.C.O. seeing a banner left by the enemy climbed on to the wall, some 12 ft. high, to capture it. Finding that he could not reach it, he called for his rifle to be given to him, and pushing down part of the barricade he kept the enemy, some fifty in number, at bay, while an American gunner laid hold of the flag, which was eventually brought into the Legation. Mention is made of others who distinguished themselves by an officer writing to the *Times*. He says the odd men did excellent work. Harry Swannell, leading signalman of the Orlando, was erecting a staff on the wall when he observed the relief force approaching, and at once signalled for them to enter by the Water Gate. The force was on the point of turning back, but when the signal was read out pushed on and soon relieved the besieged Legations. J. Thomas, armourer of the Orlando, was the only skilled workman in that line with the international guard, and displayed great ingenuity in manufacturing ammunition of all kinds. R. Fuller, sick-berth attendant, also of the Orlando, was the only qualified nurse present in the Legations, and rendered invaluable services to the sick and wounded of nine nationalities till he himself was knocked over by dysentery. In a letter to Admiral Sir Edward Seymour, the then British Minister at Peking, Sir Claude MacDonald, said he could not speak in any other terms but those of the highest praise of the behaviour of the officers. They were exposed, day and night, for two months to the most arduous, irksome, and responsible duties, which they fulfilled with a cheerful alacrity, and with a courage and endurance which excited the admiration of everybody. The general good conduct, soldierly bearing, and steadiness under fire of the men of the detachment were worthy of the highest traditions of the British Army, and of the corps to which they belong. This high state of excellence was undoubtedly in a great measure due to the officers and non-commissioned officers. "Captain Strouts was an excellent soldier and a gallant gentleman," says Sir Claude, "and his loss to me and to the defence generally was irreparable. Had he lived I should certainly have recommended him to the Lords of the Admiralty through your Excellency, for promotion, or for the Distinguished Service Order."

An Honours List in connection with the naval operations in South Africa was published in *The London Gazette* of October 3, and one in connection with the operations in China in *The London Gazette* of October 5. In the latter it was notified, among other rewards and promotions, that the Queen had been graciously pleased to approve of the Victoria Cross being conferred upon Mr. Basil J. D. Guy, midshipman, for gallantry and endeavouring to save the life of a bluejacket while under fire, during the attack on Tientsin City on July 13. In *The London Gazette* of January 2 it was announced that the Queen had been pleased to signify her intention to confer the Victoria Cross upon Captain (now Brevet-Major) Lewis S. T. Halliday, R.M.L.I., for an act of gallantry performed on June 24, 1900, during the siege of the Pekin Legations.

CHAS. N. ROBINSON.

CHAPTER XI.

WAR AND ITS CHIEF LESSON.

(For Study at the beginning of a New Century.)

War
know-
ledge and
peace
training.

HAD the expression "real war" been introduced into the title of this chapter, its introduction would be justifiable. What may be, grammatically, a pleonasm is not necessarily one practically when distinction of meanings and precision are of urgent importance. The sources—if not of our knowledge of combat, at least of the views which are sure to prevail when we come to actual fighting—are to be found in two well-defined, dissimilar, and widely separated areas. Within one are included the records of war; within the other, remembrance of the exercises and manœuvres of a time of peace. The future belligerent will almost of a certainty have taken a practical part in the latter, whilst it is probable that he will have had no personal experience of the former. The longer the time elapsed since hostilities were in progress, the more probable and more general does this absence of experience become. The fighting man—that is to say, the man set apart, paid, and trained so as to be ready to fight when called upon—is of the same nature as the rest of his species. This is a truism; but it is necessary to insist upon it, because professional, and especially professorial, strategists and tacticians almost invariably ignore it. That which we have seen and know has not only more, but very much more, influence upon the minds of nearly all of us than that of which we have only heard, and, most likely, heard but imperfectly. The result is that, when peace is interrupted and the fighting man—on both sea and land—is confronted with the problems of practical belligerency, he brings to his attempts at their solution an intellectual equipment drawn—not from knowledge of real war, but—from the less trustworthy arsenal of the recollections of his peace training.

When peace, especially a long peace, ends, the methods which it has introduced are the first enemies whom the organised defenders of a country have to overcome. There is plenty of evidence to prove that—except, of course, in unequal conflicts between highly organised civilised States and savage or semi-barbarian tribes—success in war

is directly proportionate to the extent of the preliminary victory over the predominance of impressions derived from the habits and exercises of an armed force during peace. That the cogency of this evidence is not invariably recognised is to be attributed to insufficient attention to history and to disinclination to apply its lessons properly. A primary object of the *Naval Annual*—indeed, the chief reason for its publication—being to assist in advancing the efficiency of the British Navy, its pages are eminently the place for a review of the historical examples of the often-recurring inability of systems established in peace to stand the test of war. Hostilities on land being more frequent, and much more frequently written about, than those by sea, the history of the former as well as of the latter must be examined. The two classes of warfare have much in common. The principles of their strategy are identical; and, as regards their main features, so are those of the tactics followed in each. Consequently the history of land warfare has its lessons for those who desire to achieve success in warfare on the sea.

That this has often been lost sight of is largely due to a misapprehension of the meaning of terms. The two words "military" and "army" have been given, in English, a narrower signification than they ought, and than they used, to have. Both terms have been restricted in their use, and made to apply only to the land service. This has been unfortunate; because records of occurrences and discussions, capable of imparting much valuable instruction to naval officers, have been passed over by them as inapplicable to their own calling. It may have been noticed that Captain Mahan uses the word "military" in its right sense as indicating the members, and the most important class of operations, of both land and sea forces. The French, through whom the word has come to us from the Latin, use it in the same sense as Mahan. *Un militaire* is a member of either a land army or a navy. The "Naval and Military Intelligence" of the English press is given under the heading "*Nouvelles Militaires*" in the French. Our word "army" also came to us direct from the French, who still apply it equally to both services—*armée de terre*, *armée de mer*. It is a participle, and means "armed"; the word "force" being understood. The kindred words *armada* in Spanish and Portuguese, and *armata* in Italian—equally derived from the Latin—are used to indicate a fleet or navy, another name being given to a land army. The word "army" was generally applied to a fleet in former days by the English, as will be seen on reference to the *Navy Records Society's* volumes on the defeat of the Spanish Armada.

Lessons
of land
warfare.

This short etymological discussion is not inappropriate here, for

it shows why we should not neglect authorities on the history and conduct of war merely because they do not state specially that they are dealing with the naval branch of it.

The effect
of peace
training
on belli-
gerent
efficiency.

A very slight knowledge of history is quite enough to make us acquainted with the frequent recurrence of defeats and disasters inflicted on armed forces by antagonists whose power to do so had not been previously suspected. It has been the same on the sea as on the land, though—owing to more copious records—we may have a larger list of events on the latter. It will not be denied that it is of immense importance to us to inquire how this happened, and ascertain how—for the future—it may be rendered highly improbable in our own case. A brief enumeration of the more striking instances will make it plain that the events in question have been confined to no particular age and to no particular country.

Its dis-
appoint-
ments.

It may be said that the more elaborately organised and trained in peace time an armed force happened to be, the more unexpected always, and generally the more disastrous, was its downfall. Examples of this are to be found in the earliest campaigns of which we have anything like detailed accounts, and they continue to reappear down to very recent times. In the elaborate nature of its organisation and training there probably never has been an army surpassing that led by Xerxes into Greece twenty-four centuries ago. Something like eight years had been devoted to its preparation. The minute account of its review by Xerxes on the shores of the Hellespont proves that—however inefficient the semi-civilised contingents accompanying it may have been—the regular Persian army appeared, in discipline, equipment, and drill, to have come up to the highest standard of the most intense “pipeclay” epoch. In numbers alone its superiority was considerable till the last, and down to the very eve of Plataea its commander openly displayed his contempt for his enemy. Yet no defeat could be more complete than that suffered by the Persians at the hands of their despised antagonists.

Persian
defeat at
Plataea.

Athenian
failure at
Syracuse.

As if to establish beyond dispute the identity of governing conditions in both land and maritime wars, the next very conspicuous disappointment of an elaborately organised force was that of the Athenian fleet at Syracuse. At the time Athens, without question stood at the head of the naval world: her empire was in the truest sense the product of sea power. Her navy, whilst unequalled in size, might claim, without excessive exaggeration, to be invincible. The great armament which the Athenians despatched to Sicily seemed, in numbers alone, capable of triumphing over all resistance. If the Athenian navy had already met with some explainable mishaps, it looked back with complacent confidence on the glorious achievements

of more than half a century previously. It had enjoyed many years of what was so nearly a maritime peace that its principal exploits had been the subjection of states weak to insignificance on the sea as compared with imperial Athens. Profuse expenditure on its maintenance; the "continued practice" of which Pericles boasted, the peace manœuvres of a remote past; skilfully designed equipment; and the memory of past glories—all these did not avail to save it from defeat at the hands of an enemy who only began to organise a fleet when the Athenians had invaded his coast waters.

Ideal perfection as a regular army has never been so nearly reached as by that of Sparta. The Spartan spent his life in the barrack and the mess-room; his amusements were the exercises of the parade ground. For many generations a Spartan force had never been defeated in a pitched battle. We have had, in modern times, some instances of a hectoring soldiery arrogantly prancing amongst populations whose official defenders it had defeated in battle; but none such could vie with the Spartans in the sublimity of their military self-esteem. Overweening confidence in the prowess of her army led Sparta to trample with ruthless disdain on the rights of others. The iniquitous attack on Thebes, a State thought incapable of effectual resentment, was avenged by the defeat of Leuctra, which announced the end of the political supremacy and the military predominance of Sparta.

Fall of
Sparta.

In the series of struggles with Carthage which resulted in putting Rome in a position enabling her eventually to win the dominion of the ancient world, the issue was to be decided on the water. Carthage was essentially a maritime State. The foundation of the city was effected by a maritime expedition; its dominions lay on the neighbouring coast or in regions to which the Carthaginians could penetrate only by traversing the sea. To Carthage her fleet was "all in all": her navy, supported by large revenues and continuously maintained, was more of a "regular" force than any modern navy before the second half of the seventeenth century. The Romans were almost without a fleet, and when they formed one the undertaking was ridiculed by the Carthaginians with an un concealed assumption of superiority. The defeat of the latter off Mylæ, the first of several, came as a great surprise to them, and, as we can see now, indicated the eventual ruin of their city.

Ruin of
Carthage.

We are so familiar with stories of the luxury and corruption of the Romans during the decline of the empire that we are likely to forget that the decline went on for centuries, and that their armed forces, however recruited, presented over and over again abundant

signs of physical courage and vigour. The victory of Stilicho over Alaric at Pollentia has been aptly paralleled with that of Marius over the Cimbri. This was by no means the only achievement of the Roman army of the decadence. A century and a quarter later—when the Empire of the West had fallen and the general decline had made further progress—Belisarius conducted successful campaigns in Persia, in North Africa, in Sicily, and in Italy. The mere list of countries shows that the mobility and endurance of the Roman forces during a period in which little creditable is generally looked for were not inferior to their discipline and courage. Yet they met with disastrous defeat after all, and at the hands of races which they had more than once proved themselves capable of withstanding. It could not have been because the later Roman equipment was inferior, the organisation less elaborate, or the training less careful than those of their barbarian enemies.

Defeat
of the
Romans.

Lessons
of the
Armada.

Though it is held by some in these days that the naval power of Spain in the latter part of the sixteenth century was not really formidable, that does not appear to have been the opinion of contemporaries, whether Spaniards or others. Some English seamen of the time did, indeed, declare their conviction that Philip the Second's navy was not so much to be feared as many of their fellow-countrymen thought; but, in the public opinion of the age, Spain was the greatest, or indeed the one great, naval State. She possessed a more systematically organised navy than any other country having the ocean for a field of action had then, or till long afterwards. Even Genoa and Venice, whose operations, moreover, were restricted to Mediterranean waters, could not have been served by more finished specimens of the naval officer and the man-of-war's-man of the time than a large proportion of the military *personnel* of the regular Spanish fleet. As Basques, Castilians, Catalans, or Aragonese, or all combined, the crews of Spanish fighting ships could look back upon a glorious past. It was no wonder that, by common consent of those who manned it, the title of "Invincible" was informally conferred upon the Armada which, in 1588, sailed for the English Channel. How it fared is a matter of common knowledge. No one could have been more surprised at the result than the gallant officers who led its squadrons.

Other
instances.

Spain furnishes another instance of the unexpected overthrow of a military body to which long cohesion and precise organisation were believed to have secured invincibility. The Spanish was considered the "most redoubtable infantry in Europe" till its unexpected defeat at Rocroi. The effects of this defeat were far-reaching. Notwithstanding the bravery of her sons, which has never been open to

question, and, in fact, has always been conspicuous, the military superiority of Spain was broken beyond repair.

In the history of other countries are to be found examples equally instructive. The defeats of Almansa, Brihuega, and Villa-viciosa were nearly contemporary with the victories of Blenheim and Ramillies; and the thousands of British troops compelled to lay down their arms at the first-named belonged to the same service as their fellow-countrymen who so often marched to victory under Marlborough. A striking example of the disappointment which lies in wait for military self-satisfaction was furnished by the defeat of Soubise at Rossbach by Frederick the Great. Before the action the French had not concealed their contempt for their opponent.

The service which gloried in the exploits of Anson and of Hawke discerned the approach of the Seven Years' War without misgiving; and the ferocity shown in the treatment of Byng enables us now to measure the surprise caused by the result of the action off Minorca. There were further surprises in store for the English Navy. At the end of the Seven Years' War its reputation for invincibility was generally established. Few, perhaps none, ventured to doubt that, if there were anything like equality between the opposing forces, a meeting between the French and the British fleet could have but one result—viz., the decisive victory of the latter. Experience in the English Channel, on the other side of the Atlantic, and in the Bay of Bengal—during the War of American Independence—roughly upset this flattering anticipation. Yet, in the end, the British Navy came out the unquestioned victor in the struggle: which proves the excellence of its quality. After every allowance is made for the incapacity of the Government, we must suspect that there was something else which so often frustrated the efforts of such a formidable force as the British Navy of the day must essentially have been. On land the surprises were even more mortifying; and it is no exaggeration to say that, a year before it occurred, such an event as the surrender of Burgoyne's army to an imperfectly organised and trained body of provincials would have seemed impossible.

British
failures.

The army which Frederick the Great bequeathed to Prussia was universally regarded as the model of efficiency. Its methods were copied in other countries, and foreign officers desiring to excel in their profession made pilgrimages to Berlin and Potsdam to drink of the stream of military knowledge at its source. When it came in contact with the tumultuous array of revolutionary France, the performances of the force that preserved the tradition of the great Frederick were disappointingly wanting in brilliancy. A few years

The
Prussians
at Jena.

later it suffered an overwhelming disaster. The Prussian defeat at Jena was serious as a military event; its political effects were of the utmost importance. Yet many who were involved in that disaster took, later on, an effective part in the expulsion of the conquerors from their country, and in settling the history of Europe for nearly half a century at Waterloo.

The
French
in the
Peninsula.

The brilliancy of the exploits of Wellington and the British army in Portugal and Spain has thrown into comparative obscurity that part of the Peninsular War which was waged for years by the French against the Spaniards. Spain, distracted by palace intrigues and political faction, with the flower of her troops in a distant corner of Europe, and several of her most important fortresses in the hands of her assailant, seemed destined to fall an easy and a speedy prey to the foremost military power in the world. The attitude of the invaders made it evident that they believed themselves to be marching to certain victory. Even the British soldiers—of whom there were never many more than 50,000 in the Peninsula, and for some years not half that number—were disdained until they had been encountered. The French arms met with disappointment after disappointment. On one occasion a whole French army, over 18,000 strong, surrendered to a Spanish force, and became prisoners of war. Before the struggle closed there were six marshals of France with nearly 400,000 troops in the Peninsula. The great efforts which these figures indicate were unsuccessful, and the intruders were driven from the country. Yet they were the comrades of the victors of Austerlitz, of Jena, and of Wagram, and part of that mighty organisation which had planted its victorious standards in Berlin and Vienna, held down Prussia like a conquered province, and shattered into fragments the Holy Roman Empire.

Lessons of
1812.

In 1812 the British Navy was at the zenith of its glory. It had not only defeated all its opponents; it had also swept the seas of the fleets of the historic maritime Powers—of Spain, of France, which had absorbed the Italian maritime States, of the Netherlands, of Denmark. Warfare, nearly continuous for eighteen, and uninterrupted for nine years, had transformed the British Navy into an organisation more nearly resembling a permanently maintained force than it had been throughout its previous history. Its long employment in serious hostilities had saved it from some of the failings which the narrow spirit inherent in a close profession is only too sure to foster. It had, however, a confidence—not unjustified by its previous exploits—in its own invincibility. This confidence did not diminish, and was not less ostentatiously exhibited, as its great achievements receded more and more into the past. The new enemy

who now appeared on the farther side of the Atlantic was not considered formidable. In the British Navy there were 145,000 men. In the United States Navy the number of officers, seamen, and marines available for ocean service was less than 4,500—an insignificant numerical addition to the enemies with whom we were already contending. The subsequent increase in the American *personnel* to 18,000 shows the small extent to which it could be considered a “regular” force, its permanent nucleus being overwhelmingly outnumbered by the hastily enrolled additions. Our defeats in the war of 1812 have been greatly exaggerated; but, all the same, they did constitute rebuffs to our naval self-esteem which were highly significant in themselves, and deserve deep attention. Rebuffs of the kind were not confined to the sea service, and at New Orleans our army, which numbered in its ranks soldiers of Busaco, Fuentes de Onoro, and Salamanca, met with a serious defeat.

When the Austro-Prussian war broke out in 1866, the Austrian Commander-in-Chief, General Benedek, published an order, probably still in the remembrance of many, which officially declared the contempt for the enemy felt in the Imperial army. Even those who perceived that the Prussian forces were not fit subjects of contempt counted with confidence on the victory of the Austrians. Yet the latter never gained a considerable success in their combats with the Prussians; and within a few weeks from the beginning of hostilities the general who had assumed such a lofty tone of superiority in speaking of his foes had to implore his sovereign to make peace to avoid further disasters.

Defeat
of the
Austrians,
1866.

At the beginning of the Franco-German war of 1870, the widespread anticipation of French victories was clearly shown by the unanimity with which the journalists of various nationalities illustrated their papers with maps giving the country between the French frontier and Berlin, and omitting the part of France extending to Paris. In less than five weeks from the opening of hostilities events had made it certain that a map of the country to the eastward of Lorraine would be practically useless to a student of the campaign, unless it were to follow the route of the hundreds of thousands of French soldiers who were conveyed to Germany as prisoners of war.

The
French in
1870.

It is to be specially noted that in the above enumeration only contests in which the result was unexpected—unexpected not only by the beaten side, but also by impartial observers—have been specified. In all wars one side or the other is defeated; and it has not been attempted to give a general *résumé* of the history of war. The object has been to show the frequency—in all ages and in all

circumstances of systematic, as distinguished from savage, warfare—of the defeat of the force which by general consent was regarded as certain to win. Now it is obvious that a result so frequently reappearing must have a distinct cause, which is well worth trying to find out. Discovery of the cause may enable us to remove it in the future, and thus prevent results which are likely to be all the more disastrous because they have not been foreseen.

Causes of failure.

Professional military writers—an expression which, as before explained, includes naval—do not help us much in the prosecution of the search which is so eminently desirable. As a rule, they have contrived rather to hide than to bring to light the object sought for. It would be doing them injustice to assume that this has been done with deliberate intention. It is much more likely due to professional bias, which exercises over the minds of members of definitely limited professions incessant and potent domination. When alluding to occurrences included in the enumeration given above, they exhibit signs of a resolve to defend their profession against possible imputations of inefficiency, much more than a desire to get to the root of the matter. This explains the unremitting eagerness of military writers to extol the special qualities developed by long-continued service habits and methods. They are unsleepingly apprehensive of the possibility of credit being given to fighting bodies more loosely organised and less precisely trained in peace time than the body to which they themselves belong.

The danger of "irregulars."

This sensitiveness as to the merits of their particular profession, and impatience of even indirect criticism, are unnecessary. There is nothing in the history of war to show that an untrained force is better than a trained force. On the contrary, all historical evidence is on the other side. In quite as many instances as are presented by the opposite, the forces which put an unexpected end to the military supremacy long possessed by their antagonists were themselves, in the strictest sense of the word, "regulars." The Thebans whom Epaminondas led to victory over the Spartans at Leuctra no more resembled a hasty levy of armed peasants or men imperfectly trained as soldiers than did Napoleon's army which overthrew the Prussians at Jena, or the Germans who defeated the French at Gravelotte and Sedan. Nothing could have been less like an "irregular" force than the fleet with which La Galissonnière beat Byng off Minorca, or the French fleets which, in the War of American Independence, so often disappointed the hopes of the British. The records of war on land and by sea—especially the extracts from them included in the enumeration already given—lend no support to the silly suggestion that efficient defence can be provided for a country by "an untrained

man with a rifle behind a hedge." The truth is that it was not the absence of organisation or training on one side which enabled it to defeat the other. If the beaten side had been elaborately organised and carefully trained, there must have been something bad in its organisation or its methods.

Now this "something bad," this defect—wherever it has disclosed itself—has been enough to neutralise the most splendid courage and the most unselfish devotion. It has been seen that armies and navies the valour of which has never been questioned have been defeated by antagonists sometimes as highly organised as they were, and sometimes much less so. This ought to put us on the track of the cause which has produced an effect so little anticipated. A "regular" permanently embodied or maintained service of fighting men is always likely to develop a spirit of intense professional self-satisfaction. The more highly organised and the more sharply its official frontiers are defined, the more intense is this spirit likely to become. A "close" service of the kind grows restive at outside criticism, and yields more and more to the conviction that no advance in efficiency is possible unless it be the result of suggestions emanating from its own ranks. Its view of things becomes narrower and narrower, whereas efficiency in war demands the very widest view. Ignorant critics call the spirit thus engendered "professional conservatism"; the fact being that change is not objected to—is even welcomed, however frequent it may be, provided only that it is suggested from inside. An immediate result is "unreality and formalism of peace training"—to quote a recent thoughtful military critic.

Professional self-satisfaction.

As the formalism becomes more pronounced, so the unreality increases. The proposer or introducer of a system of organisation of training, or of exercises is often, perhaps usually, capable of distinguishing between the true and the false, the real and the unreal. His successors, the men who continue the execution of his plans, can hardly bring to their work the open mind possessed by the originator; they cannot escape the influence of the methods which have been provided for them ready made, and which they are incessantly engaged in practising. This is not a peculiarity of the military profession in either branch—it extends to nearly every calling; but in the profession specified, which is a service rather than a freely exercised profession, it is more prominent. Human thought always has a tendency to run in grooves, and in military institutions the grooves are purposely made deep, and departure from them rigorously forbidden. All exercises, even those designed to have the widest scope, tend to become mere drill. Each performance produces,

Formalism.

and bequeaths for use on the next occasion, a set of customary methods of execution which are readily adopted by the subsequent performers. There grows up in time a kind of body of customary law governing the execution of peace operations—the principles being peace-operation principles wholly and solely—which law few dare to disobey, and which eventually obtains the sanction of official written regulations. As Scharnhorst, quoted by Baron von der Goltz, said, “We have begun to place the art of war higher than military virtues.” The eminent authority who thus expressed himself wrote the words before the great catastrophe of Jena; and, with prophetic insight sharpened by his fear of the menacing tendency of peace-training formalism and unreality, added his conviction that “this has been the ruin of nations from time immemorial.”

The
fettters of
specialism.

Independently of the evidence of history already adduced, it would be reasonable to conclude that the tendency is strengthened and made more menacing when the service in which it prevails becomes more highly specialised. If custom and regulation leave little freedom of action to the individual members of an armed force, the difficulty—sure to be experienced by them—of shaking themselves clear of their fetters when the need for doing so arises is increased. To realise—when peace is broken—the practical conditions of war demands an effort of which the unfettered intelligence alone seems capable. The great majority of successful leaders in war on both elements have not been considerably, or at all, superior in intellectual acuteness to numbers of their fellows; but they have had strength of character, and their minds were not squeezed in a mould into a commonplace and uniform pattern.

—Pedantry.

The “canker of a long peace,” during recent years at any rate, is not manifested in disuse of arms, but in mistaken methods. For a quarter of a century the civilised world has tended more and more to become a drill-ground, but the spirit dominating it has been that of the pedant. There has been more exercise and less reality. The training, especially of officers, becomes increasingly scholastic. This, and the deterioration consequent on it, are not merely modern phenomena. They appear in all ages. “The Sword of the Saracens,” says Gibbon, “became less formidable when their youth was drawn from the camp to the college.” The essence of pedantry is want of originality. It is nourished on imitation. For the pedant to imitate is enough of itself; the suitability of the model is immaterial. Thus military bodies have been ruined by mimicry of foreign arrangements quite inapplicable to the conditions of the mimics’ country. Fifteen years ago Sir Henry Maine, speaking of the War of American Independence, said, “Next to their stubborn valour, the chief secret

of the colonists' success was the incapacity of the English generals, trained in the stiff Prussian system soon to perish at Jena, to adapt themselves to new conditions of warfare." He pointed out that the effect of this uncritical imitation of what was foreign was again experienced by men "full of admiration of a newer German system." We may not be able to explain what it is, but, all the same, there does exist something which we call national characteristics. The aim of all training should be to utilise these to the full, not to ignore them. The naval methods of a Continental State with relatively small oceanic interests, or with but a brief experience of securing these, cannot be very applicable to a great maritime State whose chief interests have been on the seas for many years.

How is all this applicable to the ultimate efficiency of the British Navy? It may be allowed that there is a good deal of truth in what has been written above; but it may be said that considerations sententiously presented cannot claim to have much practical value so long as they are absolute and unapplied. The statement cannot be disputed. It is unquestionably necessary to make the application. The changes in naval *matériel*, so often spoken of, introduced within the last fifty years have been rivalled by the changes in the composition of the British Navy. The human element remains in original individual character exactly the same as it always was; but there has been a great change in the opportunities and facilities offered for the development of the faculties most desired in men-of-war's men. All reform—using the word in its true sense of alteration, and not in its strained sense of improvement—has been in the direction of securing perfect uniformity. If we take the particular directly suggested by the word just used, we may remember, almost with astonishment, that there was no British naval uniform for any one below the rank of officer till after 1860. Now, at every inspection, much time is taken up in ascertaining if the narrow tape embroidery on a frock collar is of the regulation width, and if the rows of tape are the proper distance apart. The diameter of a cloth cap is officially defined; and any departure from the regulation number of inches (and fractions of an inch) is as sure of involving punishment as insubordination.

The
British
Navy.

It is the same in greater things. Till 1853—in which year the change came into force—there was no permanent British naval service except the commissioned and warrant officers. Not till several years later did the new "continuous service" men equal half of the bluejacket aggregate. Now, every bluejacket proper serves continuously, and has been in the navy since boyhood. The training of the boys is made uniform; and the training ships are

The spirit
of uni-
formity

grouped together under an officer whose duty it is to see that the uniformity is preserved. No member of the ship's company—except a domestic—is now allowed to set foot on board a sea-going ship till he has been put through a training course which is exactly like that through which every other member of his class passes. Even during the comparatively brief period in which young officers entered the Navy by joining the college at Portsmouth, it was only the minority who received the special academic training. Till the establishment of the *Illustrious* training school in 1855, the great majority of officers joined their first ship as individuals from a variety of different and quite independent quarters. Now, every one of them has, as a preliminary condition, to spend a certain time—the same for all—in one single school. Till a much later period, every engineer entered separately. Now, passing through a single training school is obligatory for engineers also.

Within the service there has been repeated formation of distinct branches or "schools," such as the further specialised specialist gunnery and torpedo sections. It was not till 1860 that uniform watch bills, quarter bills, and station bills were introduced, and not till later that their general adoption was made compulsory. Up to that time the internal organisation and discipline of a ship depended on her own officers, it being supposed that capacity to command a ship implied, at least, capacity to distribute and train her crew. The result was a larger scope than is now thought permissible for individual capability. However short-lived some particular drill or exercise may be, however soon it is superseded by another, as long as it lasts the strictest conformity to it is rigorously enforced. Even the number of times that an exercise has to be performed, difference in class of ship or in the nature of the service on which she is employed notwithstanding, is authoritatively laid down. Still more noteworthy, though much less often spoken of than the change in *matériel*, has been the progress of the Navy towards centralisation. Naval duties are now formulated at a desk on shore, and the mode of carrying them out notified to the service in print. All this would have been quite as astonishing to the contemporaries of Nelson or of Exmouth and Codrington as the aspect of a battleship or of a 12-ton breech-loading gun.

Changes
not only in
matériel.

Let it be clearly understood that none of these things has been mentioned with the intention of criticising them either favourably or unfavourably. This is, perhaps, not the place, the present is certainly not the time, for submitting them to criticism. They have been cited in order that it may be seen that the change in naval affairs is by no means one in *matériel* only, and that the transformation in other matters has been stupendous and revolu-

tionary beyond all previous experience. It follows inevitably from this that we shall wage war in future under conditions dissimilar from any hitherto known. In this very fact there lies the making of a great surprise. It will have appeared from the historical statement given above how serious a surprise sometimes turns out to be. Its consequences, always significant, are not unfrequently far-reaching. The question of practical moment is: How are we to guard ourselves against such a surprise? To this a satisfactory answer can be given, though it may be a long one. It might be summarised in the admonitions: abolish over-centralisation; give proper scope to individual capacity and initiative; eschew professional self-sufficiency.

When closely looked at, it is one of the strangest manifestations of the spirit of modern navies that, though the issues of land warfare are rarely thought instructive, the peace methods of land forces are extensively and eagerly copied by the sea service. The exercises of the parade ground and the barrack square are taken over readily, and so are the parade ground and the barrack square themselves. This may be right. The point is that it is novel, and that a navy into the training of which the innovation has entered must differ considerably from one that was without it and found no need of it during a long course of serious wars. At any rate, no one will deny that parade-ground evolutions and barrack-square drill expressly aim at the elimination of individuality, or just the quality to the possession of which we owe the phenomenon called, in vulgar speech, the "handy man." Habits and sentiments based on a great tradition, and the faculties developed by them are not killed all at once; but innovation in the end annihilates them, and their not having yet entirely disappeared gives no ground for doubting their eventual, and even near, extinction. The aptitudes still universally most prized in the seaman were produced and nourished by practices and under conditions no longer allowed to prevail. Should we lose those aptitudes, are we likely to reach the position in war gained by our predecessors?

Elimi-
nation
of indi-
viduality.

For the British Empire the matter is vital: success in maritime war, decisive and overwhelming, is indispensable to our existence. The first year of a century does not differ from any other year, but its arrival does suggest the propriety of reflection. It prompts us to consider the desirability of "taking stock" of our moral, as well as of our material, naval equipment: to ascertain where the accumulated effect of repeated innovations has carried us. The mere fact of completing the investigation will help us to rate at their true value the changes which have been introduced; will show us what to retain, what to reject, and what to substitute. There is no essential

Desira-
bility of
"taking
stock."

vagueness in these allusions. If they seem vague, it is because the moment for particularising has not yet come. The public opinion of the Navy must first be turned in the right direction. It must be led to question the soundness of the basis on which many present methods rest. Having once begun to do this, we shall find no difficulty in settling, in detail and with precision, what the true elements of naval efficiency are.

CYPRIAN A. G. BRIDGE.

CHAPTER XII.

SOME NOTES ON NAVAL STRATEGY.

THE younger student of naval strategy meets with many difficulties, but one of the greatest, and certainly the most disheartening, is the apparent intangibility of the history of the old wars. Everywhere he is counselled to read naval history, which he does, merely to find that to him its study discloses no strategic laws, that the conduct of our old sea campaigns seems merely the outcome of chance, and the lessons they contain led to no strategic deductions. Then, turning to any military text-book, he finds every campaign elaborated, every move of a general discussed from a strategic standpoint, and judged by laws acknowledged to be unchanging. He therefore is led to the reflection, Why should military operations be so favoured—why should their strategic conduct be so clear, while that of the navy is so hazy and ill defined? With a little consideration we can find three distinct causes for this difficulty—*first*, a confusion of strategy with strategic principles; *secondly*, a want of accurate record of the details of those wars; and, *thirdly*, the enormous difficulties attending the movements of ships in the old sailing days. Every one can appreciate strategic principles—they are few and patent to every layman, but they are not strategy: strategy is the assessment of the existing conditions, and the application of principles to them; the focussing of the military state, the relegation of all events and conditions to their proper perspective, and then the application of principles to movements quantitatively assessed and co-ordinated. And this is where naval history fails to teach the lessons of strategy. We read the pages bereft of the pervading spirit of the times: we do not find there the reasoning of those old salt-besprayed heroes whose sea life and conditions differ so much from ours of to-day. What do we now care strategically for the fresh breeze dying with the sun, with an ebb tide on the make, or the tale of a fleet seen ten days past by a coaster? Strategic principles were then, as now, to destroy the enemy's fleet in the quickest time, and with the least damage to your ships; but their strategy had to forecast the weather and backcast the enemy's

Strategy
and
strategic
principles.

Intangi-
bility of
naval
strategy.

movements. Principles remain the same, but strategy differs. How could history of wars record the hundred and one apparently trivial considerations of wind, weather, and expected gales, strong tides, cranky masts, and rotten canvas?—details which appeared so large and which dictated the strategy adopted: all important to the seaman of those times, but unappreciated to-day. History chiefly records the pruned fact, which looks so simple, though the reason perhaps seems incomprehensible, but not the conflicting interests and evidences of the occasion. It is the absence of these details that robs the history of naval operations of half their value. Had we verbatim accounts of every council of war, how the master mind would shine, and, while teaching us the bold illumination of world-famed principles, would show us the limiting factors which necessitated the resulting actions! Without the smell of the salt and the mist of the night, without the every detail of the particular undertaking, the spirit of the body is absent, and we must be content to discuss historical naval strategy more from the point of view of the dissection of a corpse than the examination of a living body, and we must be content with the rattle of dry bones where we would seek the secrets of the brain. Hence the intangibility of the history of old naval wars to the student of naval strategy. No rules were made or followed, nothing but example handed from generation to generation; and the strategic conduct of the naval combinations and movements by Nelson even appears rather to have been an accurately assessed commonsense view of the existing political naval and military conditions, and of the resources of his own country and of those of the enemy, which his genius guided into the right line of action, than any formulated rules or definite deductions which would form the axioms of naval strategy. The reason for this is not difficult to find: it lay in the helplessness of the sailor to move from place to place with any regularity as regards time of passage. He was powerless to do more than beat to windward, or perhaps “lay to,” when his consuming anxiety was to be two hundred miles to windward—every disposition, every plan, lay at the mercy of wind and weather.

This utter unreliability of locomotion prevented any of the niceties of combinations which ashore military leaders were employing and studying. Now this has all changed: we find ourselves capable of moving ships or fleets for hundreds of miles with absolute accuracy. We have outstripped military movements both in speed and certainty. Our enemies on the sea are able to change position with bewildering rapidity, and if we turn in vain to our only handbook, the History of the Old Wars, for guidance in details, we are disappointed. True it

is that the main principles of control of the sea, the value of sea-power, the sacrifice of the individual to the furthering of the whole campaign—true it is that main principles like these run like a steel stay through naval history, from the trireme to the battleship, but the remainder of the structure has altered. Undoubtedly it will be found a great help to study military history and strategy, adapting and assimilating their teaching to sea conditions; in them we have centuries of experience and principles that have stood the test of a hundred campaigns. For this reason the study of naval and military history and of the standard works of military strategy should be the groundwork of the study of naval strategy.

The art of war has two broad divisions—strategy and tactics. All operations come under one or the other of these two heads. Strategy is the science of conducting the war, forming combinations, and disposing them when not in contact with the enemy's forces, whereas the science of tactics governs the actual disposition of the units of the combinations, both as regards each other and the enemy. The problem of strategy is to form and place the best combinations, having regard to the numbers and distribution of the enemy, and the probable outcome of the ensuing engagement. The problem of tactics is how best to use the units of the combinations in the face of the enemy. Strategy therefore must be dependent on the probable result of the equipment, material and moral, of the units, and also on the tactics of the battlefield.

Strategy
and
tactics.

Strategy and tactics are therefore dependent one on the other. The disposal of force should take into account, as far as possible, the tactical capacity of the admiral or general, so as if possible to compensate the poorer tactician by the larger force. In the naval wars of the early part of the century superiority in training and discipline allowed our fleets to engage others of considerably superior numbers. There is no apparent reason why this should be the case now. But that a good tactician, opposed to an inferior one, is capable of engaging with fewer ships is still an axiom of warfare.

Their
inter-
depend-
ence.

Strategy has two broad divisions—the strategy of peace time, and the strategy of war. The strategy of peace time aims at preparedness for war; the preparedness of ships and keeping them and their armament up to date; instruction and employment of officers and men to keep them in a state of efficiency; diplomatic action, whereby the best strategic points are secured and suitably fortified, and the least wanted bartered for other more useful rights; the cultivation of friendly ties with nations whose ports would be of use in war time, and whose shores flank our trade routes; the collection of intelligence respecting foreign countries, their changes in war material,

and the fortification of their bases; the position, and change of position, of their ships; the selection of the ships to serve on each station, having regard to the capabilities of that station to maintain and refit them, and their tactical value compared with that of those of other countries on, or available for, the same station; the formation of reserves to fill vacancies caused by losses or disablement in the fleets; the maturing of plans of campaign in the event of all possible foreign combinations.

THE STRATEGY OF WAR.

Condition
of a
victorious
fleet after
an action.

The main object of a naval war is the destruction of the opposing fleet: all other operations are of secondary importance. Until the enemy's fleet has been disposed of, other operations cannot be undertaken with safety. The object of strategy is to do this with the least possible loss to your own fleet—but at all events to do it. The conditions underlying this consideration are very important, and in some respects differ radically from those of former naval wars, and of present military undertakings. If a naval engagement takes place, damage must be done to both sides, to the stronger as well as to the weaker fleet. And the important strategic question arises as to the extent of the damage a strong fleet will receive when fighting one considerably inferior. Supposing the weaker fleet annihilated—that is, sunk or useless scrap iron, in what condition will the surviving fleet be left? Will it be able immediately to fight again? or will its secondary armament, as well as the more or less exposed adjuncts of control and communication, be so damaged as practically to necessitate immediate and lengthy repairs? It is on this question that the whole conduct of offensive and defensive strategy hinges—whether it is advantageous to fight an enemy in detail or after concentration, whether an enemy should be engaged with equal or fewer numbers, and the balance of ships kept as a reserve for future use, or whether the whole should be employed in the attempt to crush the enemy. In olden times the question never could arise: concentration and larger numbers were the keynote of success. But we must remember that then repairs after an action were easily effected—a few holes to stop, jury masts to rig, sails to repair, and the ship was again ready for the fray. Also the tactics of those days were mere bow and arrow play compared with the possibilities of the present. The possible tactics were mere crudities of using existing wind: the forces now available are immense, and the absolute control of direction and speed only requires the master mind, transmission of orders, and practised manœuvring to make it perfect. True it is, in this day as in olden times, that a ship can be looked

on, not as capable of doing a certain amount of damage, but a certain decreasing amount per minute, and therefore the greater the gunfire directed against her the fewer the minutes and the higher the rate of decrease of that damaging power. But balancing against this the unwieldiness of a large fleet, its want of coherence if composed of different nationalities, together with the numerous tactical considerations which are out of the scope of these notes, and which, moreover, it is highly undesirable to discuss, we are faced by the question whether superiority in numbers has a similar bearing on strategy now as in olden days, whether, in fact, leaving out, of course, crushing superiority, a fleet superior before an action is after it "a fleet in being."

The control of the fleets strategically is in the hands of the central body in the home Government, by whom the general plans and original dispositions are communicated to the admirals. This control would always be kept as long as communication could be maintained with them: when communication is severed, the control devolves on the admirals commanding. Communication between the central authorities and the fleet is maintained by telegraph cables and despatches. The telegraph cables are the most rapid, but are open to attempts to destroy them, and are unsuited to lengthy communications involving much detail. Hence written communications may often have to be sent by vessels. These vessels proceed to rendezvous from whence communication is kept up with the fleet. When communication with the central body is disturbed, or when immediate action is necessary, the admiral acts on his own initiative, informing if possible all officers in command of other fleets whose actions his movements may affect.

The strategy of war is broadly divided into two classes—offensive and defensive. *Offensive strategy* has for its aim the command of the sea, and has as a main objective the destruction of the opposing fleet. *Defensive strategy* aims at preventing the opposing fleet obtaining the command of the sea by preserving a sufficient sea force intact and capable of movement and concentration, keeping the enemy's forces intent on its possible employment, and therefore limiting their offensive and military actions. Offensive strategy includes three series of operations.

Offensive
strategy.

First.—Keeping fleets of sufficient strength always opposed to those of the enemy, and seeking out and fighting the enemy wherever possible: this necessitates the observation of all bases or other positions where the enemy's ships may be found, communicating to the fleet all information respecting their movements, and concentrating the battle squadrons at positions on interior lines, so as to

be superior to the squadrons attempting a junction. *Secondly*.—A blockade of the enemy's commercial ports, the capture of his merchant shipping and of the enemy's property on the high seas, and the seizure of all contraband of war. *Lastly*.—Offensive expeditions against such of his possessions as are open to military invasion. This last can only be done when his fleets are so crippled or contained as to make it impossible for him to disturb the lines of communication.

Defini-
tions.
Bases.

It will be as well here to discuss exactly what we mean by the various names strategically applied to geographical positions—bases, lines of communications, theatre of operations, and strategic positions. The sole use of naval bases is for the assistance and maintenance of the fleet, and therefore any classification should deal with their usefulness in this capacity, while their fortification or garrisoning by military forces should be dependent solely on this function. Consequently we will divide them into three classes:—

Primary bases are those largely independent of the fleet—that is, situated in a territory to a great extent capable of self-support. To this class belong large naval arsenals in the home ports, with wide tracts of friendly country in their rear, and a large coast line to gather supplies that have to be imported, and naval arsenals or defended harbours in colonies not themselves dependent on imports for mere existence or the supply of the fleet. This class is in no way directly dependent on the fleet for existence. The fleet opposed to the enemy, perhaps many hundreds of miles away, occupies the enemy's attention, absorbs his energy and strength, and leaves the base safe from invasion, while its own fortifications are sufficient to drive off spasmodic raiders who might attempt to shell the arsenal and damage the permanent works. Indirectly, therefore, they are defended by the fleet, but not directly so.

Secondary bases are those which, while affording supplies and facilities for docking and repairs, are dependent on sea transport for the replenishment of stores and repairing material, as well as for provisions for the population. These again require fortifications to repel a raid; the fleet is their insurance against invasion, but they rely directly on the fleet to keep up their line of communication with a main base, so as fully to perform their duty towards the fleet. Malta is an example of such a base.

Tertiary or temporary bases are geographical localities used by ships to effect repairs or replenish stores, but in themselves are not large depôts, and do not provide docks or factories for repairs. They therefore require no permanent fortifications, or only those of the most elementary nature. They may equally well be a latitude or

longitude at sea, when their use is considerably reduced by conditions of swell or weather, or harbours where ships may anchor independent of such uncertainties, where, with the light defences of the place and their own appliances, they can, if necessary, guard against torpedo attack. Wei-hai-wei is an example of such a base.

Coaling bases must be included under this head. They should be situated in long lines of communication, and have sufficient fortification to withstand such minor sea operations as are likely to be directed against them.

Lines of communication of a naval Power are the high seas. These normally belong to both belligerents. Their possession by one belligerent may be obtained in the following ways:—

Lines of
communi-
cation.

1. The destruction of the enemy's battle fleets, or containing those fleets by superior or equal squadrons.
2. Similar action as regards his cruisers accompanied by destruction of his bases, so as largely to reduce their radius of action.

The destruction of the enemy's battle fleet leaves the oceans free for any operations, the transport of any troops, or the occupation and creation of any base covered by the victorious battle fleet; while it leaves the enemy powerless to act against or in the neighbourhood of such a fleet, or in waters covered by it.

When the enemy's fleets are contained by careful watch off a harbour in communication with a largely superior fleet, the enemy is deterred from undertaking any offensive action by the knowledge of the close proximity of the containing fleet, which can pursue his fleet at once should it manage to escape, and which is ready, should any other operations be conducted, to turn and destroy any transports or vessels that may be employed on such an undertaking.

But should the containing power have sufficient surplus battle-ships to cover additional operations that may be desirable, such as the destruction, siege, and capture of his secondary, and occupation of any temporary, bases, the destruction of such bases would largely constrict the sphere of the enemy's cruisers' action, and curtail their power of raiding his commerce, as well as subsequently reduce the risk to his military sea transport.

If, therefore, a belligerent loses the power of using his lines of communication the results are fourfold.

1. His outlying fleets are cut off from their main supplies of ammunition, stores, and men. They may exist from supplies that are indigenous to or are stored in secondary bases, with which communication may still be kept up, but the main supply is lost.

2. His secondary bases are thrown on their own resources, and have to become self-supporting as regards supplies of men and material, their imports being *ipso facto* intercepted.

3. His secondary bases are open to military attack and reduction: this also applies to all his foreign possessions.

4. His own imports and exports are cut off from sea transport.

Theatres
of
operations.

The larger theatres of operations will probably be those seas on whose shores either belligerent has territory, since most probably the sea communications of any territory will be guarded by the ships of war of the possessors, and the adjoining seas held to prevent armed forces being transported to attempt military occupation. The different theatres of operations will vary in the extent of their interest to the belligerents, and the number of ships engaged. They may be summarised as follows in the order of their value:—

1. The seas adjoining the coasts of the two belligerents.

2. The seas where either belligerent has territory open to invasion by small forces and incapable of prolonged self-support.

3. The trade routes of the belligerents.

4. The seas adjoining territory belonging to either belligerent, this territory being capable of self-support.

5. The seas where either belligerent has interests but no territory.

Each theatre of operations must have bases, of which at least one should afford shelter and protection to the fleet.

Strategic
positions.

Strategic positions are any localities that form suitable places for ships to cover the possible action of an enemy: they need not be harbours, but are often merely a latitude and longitude. Calder's position one hundred miles west of Finisterre, Nelson's cruising ground covering Cadiz and the Straits of Gibraltar, are two excellent examples of such positions.

Defensive
strategy.

The defensive strategy of a navy may best be defined as the policy of delay; its object being to prevent the adversary obtaining command of the sea, while itself too weak to obtain it. It would constantly be undertaken by a weaker fleet while waiting to effect a junction or to receive reinforcements, or while using its small craft to reduce the numbers of the enemy's fleet. It, if anything, necessitates more activity on the part of the cruisers, and smaller vessels, than an offensive strategy. Its aims are to force the enemy to divide his fleets, to contain several different points, and at the same time to keep him in constant fear of offensive action against his battleships; to use fast craft to reduce the numbers of his battle fleet, to fight chiefly against battleships and reduce their number, at the same time never engaging any large ships unless they can crush their opponents with but small damage to themselves. It is the combination of a guerilla

and predatory warfare against battleships with the art of maintaining and using the potent threat of a fleet in being.

A defensive strategy, like all evasive movements, is bad for the morale of the fleet; also, from frequent lengthy stays in harbour, it is bad for the sea-going efficiency and practice of the battleships. On the other hand, it stimulates the action of smaller vessels.

Although offensive and defensive strategy are more generally considered as applying to the dispositions of the whole of the forces of a country, yet it may often happen that ships of the same country may temporarily be conducting a defensive strategy in one theatre of operations, and an offensive in another. Also that the arrival of reinforcements, or the accidents of war, may cause the admiral in any particular theatre of operations to assume a different strategy. It is therefore necessary attentively to consider the principles of both classes of operations, and not neglect the study of the defensive, because our navy as a whole is stronger at present than any other.

For a largely inferior belligerent, who is compelled to take the defensive against his superior, the chances are slight of preventing his opponent commanding the sea, and therefore his trade and foreign possessions. But to a force temporarily inferior the defensive well conducted is of enormous value; to strike quickly with his force concentrated against the enemy's smaller squadrons; to force the opponent to divide his forces and then to concentrate and attack them in detail; to raid his fleets by every fast vessel available, using every means to destroy any large vessel of the enemy, at whatever cost to the small craft; in fact, to fix his whole energy on the destruction of ships in detail, and attempt to reduce the enemy's fleet to such numbers as to render uncertain his control of the sea, or to reduce his fleet power to an equality; to be always moving, or attempting to move, always trying the unexpected, striking everywhere with energy, and forcing the enemy's attention on the action of your ships, and distracting it from ulterior objects; never attempting any other operations than the destruction of the enemy's ships; never risking damaging the fleet to such an extent as to destroy its attribute of being "in being." These are the most obvious principles of a defensive strategy.

Having now considered the principal terms and operations, we will turn our attention to the comparison of the main points of strategic operations as affecting the army and navy. At first the nature of the arms employed, the physical differences of the theatres of war, the enormous difference in the transport, and of time of movement of the units—all seem to point to great variations in both the strategy and tactics of the two sister services. The power

Local
potency
of the
defensive.

Identity of
naval and
military
strategical
principles.

possessed by a fleet of being self-contained and able to traverse long distances without lines of communication, and also of such a fleet having nothing apparently analogous to the flank of an army, seem at first sight to necessitate a great departure from strategy as practised ashore. On closer examination, although the comparison of tactics must fail, the principles of strategy will be found the same—in fact, identical. So much so is this the case that a fleet, besides being able to fight a fleet, can fight and has fought, both in conjunction with and strategically against, armies ashore. It is only necessary to recall Napoleon's Continental system, when armed Europe, obeying his every command, fought strategically against our fleet, and our fleet only, in our adoption of what might be called in contradistinction the Oceanic system. For months the war continued purely strategic, no actions, no collision, but each with a grip on the vitals of the other, till exhaustion pronounced in favour of the British. This is, perhaps, the most conclusive example of the identity of naval and military strategy, and of the only ground on which the two arms can meet and, by endurance, fight to the bitter end.

A comparison.

Now, to examine more minutely the similarity in strategy of the two forces, let us follow the broad outlines of the course of a war as conducted by an army and a fleet. An army, according to circumstances, acts either on the offensive or on the defensive. Having in view the object of the operations, the general will select an objective. When near the enemy's forces he will, if possible, attack them, but if the enemy refuses action they must retreat. If there is a battle, and the invading army is victorious, the other must retire towards its base to reinforce. If the enemy is unable to offer further resistance before the objective is reached, the advancing army will seize the objective or, if fortified, lay siege to it. If unable to advance while the siege is proceeding, it will take up a strategic position covering the siege. Similar operations will continue till the armies have met and a decisive engagement or engagements have taken place which render the enemy unable to collect a sufficient force to oppose the victorious army. The head centres of administration and government can then be seized, and social and legislative disorganisation must ensue, stifling reorganisation and resistance.

In a naval war, having undertaken offensive action, the Admiral seeks the enemy's fleet: this must engage him, or retire into fortified harbours and take up a purely defensive strategy. If the enemy fights and is worsted, he must do the same, to repair his damages and wait reinforcements, until once more he is in a position to undertake offensive action, or attempt a junction with his relieving force. During the time of his remaining in port his sea commerce, exports

and imports, fall into the enemy's hands, and complete intercourse with possessions separated by sea is cut off. If the inferior power is unable to assert an equality or superiority on the sea, then the country must make peace to avoid the annihilation of certain industries and loss of capital to the nation, as well as to save any colonies which are not self-supporting and able to resist occupation. These bald outlines of the general course of a naval and military war are very incomplete, but the factors mentioned are the same, and lead to the same result in each case. To amplify the above we will consider the case of each country possessing territory in different seas. Then the theatre of war becomes the ocean, and each sea in which the countries have possessions becomes a theatre of operations. Again, the ultimate objective is the same: the control of the highways of the sea by destruction of the main fleets of the enemy, or forcing them to assume a defensive rôle and to quit active operations on the sea. Battles may go on perhaps with varying success to the two sides in the minor theatres of operations, but ultimately success must lie with the fleet whose main communications for despatch of relief ships, warlike stores, and troops are rendered safe by the practical effacement of the opposing vessels. To this scattered warfare over the remote corners of the ocean we have a complete analogy in the Napoleonic wars of the opening years of last century. The allies scattered round the frontiers of France engaged the troops of Napoleon in two or three quarters at once. So long as his line of communication was safe he could conquer and hold all these; but eventually, owing to the exhaustion of France, his line of communications to wealth and to his reserves became longer; became of necessity the paths of the sea, for his trade to pass to other countries, and to his lost colonies; for him to receive the gold for his industries and those stores he so much needed. These the British fleet held. Napoleonic Europe became an island, bordered by the sea and the deserts of Russia. Cut off from supplies and with his industries crippled, the death-grip of the English fleets on his communications slowly starved him to his doom.

Offensive strategy for the army and navy is therefore, as we have seen, broadly governed by the same principles, but with defensive strategy a different condition arises in the navy distinguished by the term "fleet in being." This term, taken from Lord Torrington's despatch after the battle of Beachy Head, has lately come into general use. It may seem strange that a term so conveniently expressing a condition of power of a fleet should have had no counterpart for over two hundred years. It must, however, be remembered that it is only of late years that naval strategy has received scientific treatment, and

The
defensive
and the
"fleet in
being."

has had terms and definitions applied to its operations. With the growth of careful analysis this happy, lucid, and graphic expression "fleet in being" has been applied to conditions which require many sentences thoroughly to explain. It will now be well to compare the state implied by this term with corresponding military conditions. This is, however, not easy, since military operations do not usually cover ulterior objectives, not themselves of a military nature, in the way that naval supremacy is a prelude to military operations across the sea. In fact, the whole object of military action is to seize and hold the enemy's country and force him to terms; while naval offence can never of itself accomplish this, it requires entirely separate assistance and operations. If ashore an army refuses to fight, the enemy's territory is invaded and he is forced to terms, while at sea the most direct injury supremacy of itself can immediately accomplish, is the capture of his sea-borne property and the taking of such distant possessions as are incapable of resistance. In the ordinary defensive strategy on shore the army acting on the defensive is not an "army in being": it is an army continually fighting, and resisting the progress of the invader, making use of physical advantages offered by the country for effectively doing so. If it remained passively inactive it could be surrounded and starved, and with a superior army across its communications would, if unable to prevent the occupation and absorption of its territory, have no potential worth. But at sea a fleet unable to undertake the dispute of actual supremacy cannot be surrounded by its adversary, if it retires into a well-defended harbour on the coast of a country from which it can draw supplies: it is in a position analogous to an army in a fortified sea-port who can draw supplies from sea traffic. Since, therefore, the fleet cannot be surrounded and starved into surrender, but on the other hand is always ready to put to sea if required, it remains a threat to the subsequent secondary operations of invasion, although its inactivity may meanwhile lose the nation its sea commerce. An uncontained enemy appearing on the flank of the lines of communication of a superior army would temporarily exert the same control over the strategy of that army that a fleet in being possesses in a naval campaign. To select one special instance. Sir John Moore's famous march from Lisbon to Corunna is an excellent example of the strategic effect of armed force "in being." His army was so inferior that if compelled to fight he would have risked annihilation, and therefore have laid the territory he defended at the mercy of the enemy. By his brilliant march his army became an "army in being," threatened the communications of Napoleon, and by strategy rather than by fighting saved Portugal by compelling the whole of the opposed

army deliberately to discard its objective and retrace its steps. The comparison is all the more complete since he had a base to retreat to, to which Napoleon could not follow him, and which he reached with the aid of a successful action. His object had been attained, Napoleon returned to France, and Portugal was saved. Let us note that it is entirely the combination of land and water that permits of a force, either naval or military, being "in being." Guerilla warfare, again, is a degenerate form of vessels "in being," and has its counterpart in the raids of small craft on a superior fleet. Ashore, without concentration and organisation, such warfare can have little final control over military operations; since the damage done is slight and not lasting, and it may often happen, as lately in South Africa, that prisoners of war taken cannot be retained. But at sea the conditions are different: every battleship torpedoed is a battleship lost, and, therefore, such warfare is of great importance. Again, ashore such warfare is carried on by parties, composed of the same fighting units that form main armies, but which, if combined, would not form an army comparable in numbers with the enemy's forces. This condition is therefore usually met with after main bodies have been beaten and reduced. Afloat it is entirely different. No combination of small craft can produce the tactical qualities of a battleship; nor is a battleship capable of subdivision—this warfare is carried on by a distinct type of vessel. The result is, that at sea guerilla warfare will precede the larger engagements, and will be a means of accomplishing the equality of the fleets before their actual encounter. In these days, therefore, such warfare increases the chances of final success of the passive strategy of a "fleet in being."

So far the broad outlines of strategic operations have been the same for each service. But when we leave mere principles, and come to consider the strategic operations due to the physical features of a geographical area, we must necessarily find considerable modification necessary, chiefly owing to the enormously increased rate of travel of ships compared with armies; and the sameness of the sea providing no physical advantages or disadvantages to either force. A battleship squadron has no line of communications when proceeding from base to base. It is analogous to a flying column ashore—it is self-contained. When on the warpath its movements are unhampered by communications; but the intercommunication of its bases must, within limits, be assured. Again, there is no such thing as fatigue, nor is rest from motion required to a fleet, within the limits of its coal endurance. For these two reasons a naval force is extremely mobile, and strategic alterations in disposition can be made with far greater rapidity and secrecy than is possible ashore. The extent of

The
factor of
naval
mobility.

Coal
strategy.

Its im-
portance.

such alterations, again, is immense. A fleet disappearing in China might turn up with equal ease in Australia, or the Pacific coast of America, or in the East Indies. The force from one theatre of operations might change its position to another, and effect a junction with a fleet there, with astounding secrecy and rapidity. The limitations to such movements ashore are physical obstructions, muscular weariness, and transport; afloat, the limitation is coal consideration. This gives rise to principles which, for want of a better name, must be called *coal strategy*. If ashore a soldier be given four days' rations to consume in one he will probably go half as fast that day; at sea, ships go twice the speed. We have, at sea, command of very high speeds, but we pay a ruinous price for the luxury. Provided we have the choice of speed we can steam long distances, but if we are hustled, if desire of evasion or other dire necessity increases our rate of travel, we draw heavily on the distance we can steam. A fleet with many coal bases can, therefore, hustle another into inability to proceed to other than certain destinations—without overtaking or forcing a general action we can, to use an "Irishism," head off the fleet from astern. This limitation of distance capacity, this invisible control over the destination of an enemy, is a point worthy of great consideration, since it gives a new meaning to the word blockade, it confers new powers on a superior fleet in touch with, but out of sight of, an enemy. Nor is it in strategy only that the question of coal and its supply have place; tactics, at times, may largely be dictated by coal considerations, but this is beyond the present question. It may be suggested that supplies of coal should always be carried with a fleet. Food for the soldiers is carried by the commissariat: why not carry food for the ships, in suitable vessels, so as to replenish their bunkers when required? That coal can be carried with a fleet and distributed under certain conditions is obvious, but to count upon such a supply as being generally possible, and to place reliance on such replenishment being always available, is quite out of the question. That ships will, on occasions, have their bunkers filled at sea is probable, and even at times a necessity, but the possibility of such replenishment must not be looked on as a general operation of war time. To appreciate this fully, let us compare the feeding of bunkers with the feeding of troops, and consider the transport required, and the subsequent disposal of that transport, as well as the time available for distributing the coal, and the localities where such distribution is possible. On all these points we shall find greater difficulties attending the supply of coal than that of provisions ashore. First of all, the rate of transport must be equal to the speed of the fleet;

consequently the coal consumption of the colliers will be comparable with that of a man-of-war of equal tonnage. To make her own coal consumption negligible compared with her carrying capacity the collier must be very large; but a very large collier is inconvenient to coal from, even in close harbours. The difficulty, again, of the disposal of colliers after use has to be considered: either they must steam under convoy, or at a high speed, to some base, which necessitates the use of coal, or they must remain with the fleet and keep coal equal to that possessed by a ship of the fleet. Both these difficulties are analogous to the portorage of water with a column in a country where none is available, when the carriers themselves have to drink of the actual loads they are carrying, and as each man's load is finished he becomes useless and wasteful to the column. Then, either the range of action of the column is limited, or they must be sent back to the base. All who have had to deal with this class of self-wasting portorage know that its employment is only practicable under dire necessity, and is always a matter of difficulty and of incipient danger. In addition to these two conditions, we have two others to take into consideration—namely, the waste of time in distributing the coal, and the difficulty of finding a suitable place when it may be required to effect the coaling. These have no counterpart in land operations, where the daily bivouac supplies both; but at sea, to coal a large fleet from colliers of requisite size to be averagely economical would either entail a very large number of such vessels, or occupy a great time, and, moreover, a time entirely lost to the operations in view, and perhaps not incurred by the opposing fleet. The difficulty of suitable position for the operation precludes the attempt in certain waters, while in others convenient places may be relied on; this condition is entirely meteorological and geographical. The separate difficulties of each of the above considerations apply to special and different conditions: it is therefore impossible to integrate and say generally that coaling at sea is possible or impossible, but it is quite safe to predict that there are occasions when coaling at sea will be systematically carried out, and that as assuredly others exist under which it will be extremely rash to put any reliance in the possibility of such an undertaking. Maintenance of coal supply, either by economy or replenishment, is as strategically important to the navy as commissariat is to an army in the field; the difficulties of maintaining the supply and the dangers in case of failure are equally grave. Moreover, let us remember that, although hundreds of years of experience have ground this danger into military thought and disposition, with the navy it is the mushroom growth of yesterday, and no experience in past wars exists to warn us of risking failure

Strategic
incidence
of coal
supply.

from this cause. Careful thought, and analogy soundly applied, are our only helps. The lessons to be learned from the failure of competent forecast lie in the naval wars of the future.

Advantages and disadvantages of physical conditions.

Dealing with the absence of physical advantage and disadvantages, we find the sea one vast tract; no limitation due to width of roads, no bridges exist, and exceedingly few passes, and these mostly of such a size as to render it possible for a fleet to traverse them unobserved by night or in thick weather. The result is that all strategico-tactical operations, such as scouting, reconnaissance, or rearguard actions, are rendered extremely difficult. We have only, in place of these physical obstructions, the alternations of light and darkness. These diurnal changes are of great importance, for, although not directly reducing the travelling power of a fleet, they absolutely limit visibility, and therefore efficiency of scouting. Also, the fact that the destructive value of certain vessels depends solely on the screen afforded by such darkness, and that they rely on nightfall for the full exercise of their function, renders this period one of danger, and imposes the utmost caution on the movements of a fleet. The rearguards of a fleet do not, like those of an army ashore, look for help from ranges of hills, passes, or natural barriers on which to rest and gain an advantage of position, but from the covering cloak of darkness fully developing the offensive value of the small craft, by, in like ratio, reducing the defensive powers of the larger vessels. But the effect of alternations of light and darkness on strategic-tactics is far too large a subject to do more than mention in these notes. Its effect is marked on every page of naval history, but of late years its potency has increased in direct proportion with the facilities and improvements of the age.

Regarding the strategico-tactical portion of a campaign, a naval theatre of war would compare with a military one consisting of a huge irregularly shaped plain bounded by water, with fortresses on the shore—this plain traversed by flying columns able to move to their visible horizon in half an hour. Fog, rain, and long hours of darkness are the principal varying factors, and when associated with great speed of movement are paralysing obstacles to scouting and observation.

Lessons of the defence of Natal.

Probably the most interesting lesson that the war in South Africa has afforded to the student of naval strategy is the defensive strategy of the troops under Sir George White in Natal; and it will perhaps not be without interest to examine the naval analogy to the military operations. The problem consisted of a force preventing an enemy of three times its number overrunning a geographical area and attacking and holding its sea base. Briefly

this was effected by intrenching the defending force in a position on the direct route of the enemy, and forcing him to one of two operations—either investing and reducing the intrenchments, or containing the garrison by investment with a sufficient force and advancing to further offensive operations with the remainder. The naval comparison would be that of a temporarily inferior fleet attempting to hold the seas of a station in the presence of a superior force of greater speed and mobility than itself. In both cases the inferior force must seek the protection of a fortified base, and become a threat to the communications, unless thoroughly invested and contained. The offensive admiral is bound to invest the fortified base with a superior number of ships before proceeding, should he think it advisable, with the reduction of the main objective by combined naval and military attack. An analogous operation would be for a temporarily weak Mediterranean fleet to attempt to prevent an invasion of Egypt from the westward. By seeking refuge in Malta on the line of communications the fleet becomes a threat, and awaits a relieving squadron. The superior fleet is bound to invest the island, and could with the remainder of his ships escort troops to the objective. The main consideration is the same in each case—namely, absolute power to control the line of communication and therefore a safe line of retreat, together with thorough ability to intercept reinforcements for the contained force. In the case of Ladysmith the contained force absolutely broke the railroad communication, so that transport was required other than by train for at least four miles. In the case of Malta, that island lies in the main road of the traffic. The power of the blockaded fleet to raid the containing force both by ships and small craft, if it remains in the vicinity of the island at night time, might lead to such a diminution of the blockaders' numbers, especially after a successful night action, that the two fleets might be reduced to equal strength, and the whole line of communications and retreat placed at the mercy of the blockaded fleet. At all events, fast cruisers escaping during suitable weather should work havoc on the lines of communications. With all these factors against the stronger fleet it is doubtful if any admiral would, under the condition, attempt offensive action, unless the number of his ships was overwhelming; and even then he has the factor of reinforcements to provide against. In fact, the whole question of the outcome of the struggle would be in the possibility of the reinforcement and relief of the contained fleet. The potential threat of the fleet, accentuated by the knowledge of reinforcements about to start to attempt its relief, would paralyse useful offensive operations on the enemy's part. It appears, therefore, that in broad

Malta and
Egypt—
an
analogy.

principle the strategy of a fleet under the conditions supposed—namely, in an island harbour fortified and provisioned beforehand, is not only merely similar, but identical with that of our gallant troops in Ladysmith. But now that we have arrived at the question of the relief of such a force, it is less easy to draw any further parallel. That the strategy ashore must be for the containing force to concentrate and defeat the reinforcements, and then try conclusions with the contained, is evident; but from the naval side the result, even if the reinforcements are beaten, is open to grave doubt. The crucial question is, How far can a fleet, after a successful engagement with an inferior one, be fit to engage another arriving fresh for the fray? We are now not merely dealing with bodies of men who, exhilarated by a victory, are ready to gain another. We pass from pluck to prosaic matter, steel and iron, guns and engines. Leaving out all questions of actual damage to guns and communication, dirty fires, unswept tubes, joints leaky from concussion of shell, must place them at a disadvantage; and it is a question of some gravity whether the majority of ships, after an action, could engage a fresh squadron. Ashore companies can be filled up and other combinations of troops readjusted; but a ship is an entirety, incapable of subdivision or agglomeration.

Strategic
alter-
natives.

The question of when a fleet should engage another and when it should refuse to fight is one of the strategy of the whole campaign. An admiral should be no more afraid to refuse to fight, should strategy demand such a course, than he should be afraid to engage the enemy. The only sure guide is for him to leave his own inclinations entirely out of the question, to remember that his force is only a portion of the whole and the sole object he should have in view is the furtherance of the whole campaign. Cases may often arise when an inferior squadron should attack and fight a superior, doing all the damage it can, though itself suffering defeat, should the urgency of the case demand the practical disablement of the enemy's ships. But, on the other hand, many conditions may exist when an inferior squadron should use every endeavour to avoid an action. Nor is it always the duty of a superior squadron to engage an inferior, if in so doing, even though achieving a temporary gain, it incurs ultimate strategic loss. Villeneuve's avoidance of Nelson in the attempted concentration in the West Indies must not be viewed in the same light as Byng's failure thoroughly to engage off Minorca. Nor should the strategic principles governing Sir John Jervis's action off Cape St. Vincent be confused with those determining Lord Torrington's inaction at Beachy Head. Each case requires the special consideration of the principles involved, and it may happen that the engagement of a stronger squadron with

an inferior may be as strategically unsound as, under certain conditions, the refusal of an inferior to engage a superior. Personal and public sentiment are factors which make, in exceptional cases, a sound strategy hard to pursue.

Although the discussion of tactics is quite outside the scope of these few notes on strategy, still it may not be out of place to remark that with strategic-tactics comparison between naval and military operations ends. Between naval and military tactics there is no similarity; the fighting units and arms employed are too different for analogy to exist. If ever the day arrives when armoured traction engines may transport and shield troops, then the disposition of brigades of tractions in echelon may resemble columns in quarter line disposed abeam. But by that day it is quite possible that the enormous warships of the present day may have undergone subdivision into crowds of small fast craft, which, in turn, would have to assume organisation resembling that of present-day battalions.

We have briefly sketched the similarity of strategic principles in their application to both navy and army, and also similarity in some of the strategic operations, but there still remains one great lesson running through history from the time of Goliath of Gath to the present century, and that is that change of arms and change of facilities, in fact changes in any of the data of warfare, necessitate corresponding changes in strategy. This broad lesson is one on which too much stress cannot be laid. In our early military wars, when armies fed on the produce of the invaded countries, and lines of communication were unknown, strategy included none of its finest problems, which deal with the threatening or maintenance of these all-important sinews of the army. With the growth of the science of maintaining an army in the field has grown the science of attack and defence of the channels of life of the force, independent perhaps of actual trials of military strength. These successive changes are very similar to our development from self-contained sailing fleets to fleets of battleships dependent on coal. Are our ideas thoroughly resonant to the change? Again, rapidity of movement by the use of military railroads prevents the conditions which gave rise to the strategic moves of dealing the right-and-left blows which made Napoleon's early campaigns of such momentous and historic value. To us a far greater change in speed has arrived. Have we so thoroughly sifted the operations of the past that we are mentally able, with comfort, to discard historical ideas that are now out of date, and apply merely those which deal with the new conditions? Perfection in modern weapons has upset the relative equilibrium of the various factors of an army, and totally changed the disposition of the forces in front of the enemy. Naval

Changes
in
strategy.

The im-
portance
of
realising
them.

arms and fighting units have also changed, and new ones of unknown possibility arisen. In the history of Goliath and David we have foreshadowed the surprise of the battleship at the success of the torpedo-boat. Have our giants of battle perfectly learned the lesson not to expose themselves to the light and active striplings whom, in the glory of their own magnificent strength, they are so apt to despise? Should we not apply to strategy the old rule in navigation of when in doubt as to the ship's position to place her on the chart in the worst possible situation, and study future action from that point? In our strategic forecast we should give to every opposing arm its highest value, and attempt to forestall success by our preparedness, not by our dicta.

Genius in strategy lies in the forecast of the effect that alterations in details should have on the dispositions for war. If we study naval and military history from the point of view of change necessitating change, and note the frequency of the failure of forecast to appreciate this, we shall have equipped our minds, not only with many lessons that in the hour of necessity may be the germs of most valuable suggestions, but we shall perhaps be more inclined to broaden our views, and, being more expectant of the unexpected, be more prepared at the outset to forestall those surprises which lie hidden in the future.

R. H. S. BACON.

CHAPTER XIII.

THE PAST FIVE YEARS' WARSHIP-BUILDING.

THE period of five years during which the late First Lord of the Admiralty presided over the administration of the Navy was notable on account of the many wise reforms which were instituted, but it will stand out in the history of the sea service of the Empire as a *régime* marked by efforts of unexampled magnitude to strengthen the Fleet, and by an unfortunate failure, from various causes, to realise fully the hopes to which year by year Lord Goschen gave expression. He succeeded to office at a time when the Navy was beginning to recover its old position of supremacy, thanks to the Naval Defence Act and the programmes introduced by his predecessor, Lord Spencer. Many ships were already in course of construction, yet in his First Statement in March, 1896, Lord Goschen indicated that he was determined to press on the work of placing the Navy in a position of unrivalled superiority. It is apparent that the task that claimed his attention after the General Election of 1895 was to survey the naval position and arrive at an estimate of the real needs of the British Fleet in view of the activity of other Powers. Eight battleships, six first-class cruisers, thirteen of the second class, and one of the third class, besides twenty torpedo-boat destroyers, were under construction. He asked the House of Commons to authorise the laying down, in the financial year 1896-7, of five battleships and four first-class cruisers, besides three second- and six third-class cruising ships, and twenty-eight torpedo-boat destroyers. In the Statement accompanying the Navy Estimates Lord Goschen promised that this programme should be prosecuted with the utmost energy. "The policy of acceleration will be pursued vigorously in the year 1896-7," he wrote. "A considerable proportion of the increase in the Shipbuilding Vote is due, not only to the number of new ships which it is proposed to build, but to the rapidity with which the contractors will be called upon to complete the third-class cruisers and torpedo-boat destroyers."

Magni-
tude of
the work
under-
taken.

for which they may obtain orders." The administration was to be characterised by rapid construction; at the end of the five years its feature is seen to have been continuous delays in the dockyards and on the part of the private firms, in supplying armour, guns, and machinery, and consequent under-expenditure of the moneys provided by Parliament. The building records established first by the Royal Sovereign, which was in commission within thirty-two months of her laying down, and greatly improved by the Magnificent and Majestic, which were ready for sea in every respect in twenty-four and twenty-two months respectively, have been lost. It is proverbial that quick building is cheap building, and in the past five years it has been shown that slow construction is dear construction. The cost per ton of armoured ships has risen from £60 10s. in 1895 to £75 1s. per ton in 1899. To some extent this appreciation has been due to increased outlay on material, labour, and machinery, but the retardation cannot have failed to influence the rise.

It will be seen that the First Lord of the Admiralty and his colleagues, in spite of the legacy that they inherited from their predecessors, lacked neither courage nor an understanding of the great charge that had been committed into their hands, of maintaining the strength of the British Fleet on an equality of numbers with and superiority of power to that of the next two strongest nations; but it has been suggested that they have failed to execute fully the programmes that have been undertaken.

Pro-
grammes
for 11
years.

Without entering fully into the thorny controversy of relative strength, it can be shown that the five years just ended have witnessed the commencement of more men-of-war of various types than any preceding quinquennial period. On the next page is a statement of the programmes authorised in the past eleven years.

In this statement is set forth the number of ships authorised from year to year since the passing of the Naval Defence Act. During these eleven years 40 battleships, 20 armoured cruisers, 19 first, 47 second, and 15 third class cruisers have been laid down, in addition to 18 torpedo gunboats, 113 torpedo-boat destroyers, 14 torpedo-boats, 6 gunboats, and 14 sloops. Of this fleet—for it is, in fact, the main force upon which the defence of the Empire would depend in case of hostilities—half the battleships, all the twenty armoured cruisers, eighteen of the cruisers, and fifty-one of the destroyers, not to mention ten sloops and six gunboats for river work, belong to the programmes introduced during Lord Goschen's *régime*. If we group all the armoured ships together, it will be seen that to the credit of the late Board at Whitehall during the last five years stand just twice as many vessels

as were authorised in the preceding six years of great activity; but whereas Lord Spencer laid down only as many ships as could be pressed forward to completion, Lord Goschen put on the stocks a large number of vessels which, from one cause or another, have not been pushed forward to completion with the celerity which was promised and desired, with the result that arrears have accumulated.

| Year. | Battle-ships. | Armoured. | Cruisers. | | | Sloops. | T.B.D.'s | T.B.G.'s | Torpedo boats. | Gun-boats. |
|-------------------------------------|---------------|-----------|-----------|------|------|---------|----------|----------|----------------|------------|
| | | | 1st. | 2nd. | 3rd. | | | | | |
| Naval Defence Act 1889-1894 .. | 10 | .. | 9 | 29 | 4 | .. | .. | 18 | .. | .. |
| Additions, 1892-1893 .. | 1 | .. | .. | .. | .. | .. | .. | .. | 10 | .. |
| „ 1893-1894 .. | 2 | .. | 2 | 3 | .. | 2 | 20 | .. | .. | .. |
| Total for five years, 1889-1894 .. | 13 | .. | 11 | 32 | 4 | 2 | 20 | 18 | 10 | .. |
| 1894-1895 | 7 | .. | .. | 6 | .. | 2 | 42 | .. | .. | .. |
| 1895-1896 | .. | .. | 4 | 4 | 2 | .. | .. | .. | .. | .. |
| 1896-1897 | 5 | .. | 4 | 3 | 6 | .. | 28 | .. | .. | .. |
| 1897-1898 | 4 | .. | .. | .. | 3 | 2 | 2 | .. | .. | 4 |
| Supplementary Programme, 1897 .. | .. | 4 | .. | .. | .. | .. | 4 | .. | .. | .. |
| 1898-9 | 3 | 4 | .. | .. | .. | 4 | .. | .. | .. | .. |
| Supplementary Programme, 1898 .. | 4 | 4 | .. | .. | .. | .. | 12 | .. | .. | .. |
| Totals for five years, 1894-1899 .. | 23 | 12 | 8 | 13 | 11 | 8 | 88 | .. | .. | 4 |
| 1899-1900 | 2 | 2 | .. | 1 | .. | 2 | .. | .. | 2 | .. |
| 1900-1901 | 2 | 6 | .. | 1 | .. | 2 | 5* | .. | 2 | 2 |
| Totals for three previous years .. | 16 | 12 | 4 | 3 | 9 | 6 | 46 | .. | .. | 4 |
| Totals for five years, 1896-1901 .. | 20 | 20 | 4 | 5 | 9 | 10 | 51 | .. | 4 | 6 |
| Total for 11 years, 1889-1901 .. | 40 | 20 | 19 | 47 | 15 | 14 | 113 | 18 | 14 | 6 |

306

* Supplementary Estimate, 1900.

Bearing in mind the opinions expressed by the late Admiral Sir Geoffrey Hornby, and other officers, and the number of cruisers laid down by foreign Powers, it is apparent that the Admiralty have not lately attempted to meet, or at least have not succeeded in meeting, the maximum requirements in the matter of fast cruising ships, having in the years under review begun the construction of only nine first and second class vessels. It is no doubt true that armoured ships, such as the Cressy and Essex classes, are intended in some measure to do the work that five or six years ago would have fallen to merely protected ships, and the success of wireless telegraphy may have affected the official calculations. Nevertheless the recent

Cruiser
pro-
grammes.

manœuvres, as well as previous Fleet movements, have clearly demonstrated the immense value of the protected scouting ships that we obtained under the Naval Defence Act, while our commerce will necessarily require the service of many cruisers, protected or otherwise. Owing to the policy of the late administration of the Navy we are in a worse relative position as to cruisers than we were in 1896. But, after all deductions have been made on account of the practical cessation of the construction of scouts in latter years, the period has been remarkable for the unparalleled efforts which have been put forward to strengthen the Fleet. On two occasions, in response to challenges by rivals, supplementary programmes were introduced.

Sums
under-
spent.

Unfortunately very soon after actual work on the ships authorised in 1896 had been begun, the engineering dispute of 1897 occurred; and when Lord Goschen presented his Estimates in the spring of 1898, he had to deplore the complete disorganisation of the previous year's work, and the under-expenditure of the money voted twelve months before to the extent of £2,109,654. It was recognised that the situation was most serious, and the Admiralty promised that everything possible should be done to retrieve the position. Official anticipations, as is now well known, were not realised. The following figures indicate the under-expenditure of the five years, 1896-1901, so far as they are at present known, the statements being founded on the Auditor-General's reports:—

| | Estimate. | Expenditure. | Spent less than Estimate. |
|-----------|------------|--------------|---------------------------|
| | £ | £ | £ |
| 1896-7 | 7,384,874 | 7,327,166 | — |
| 1897-8 | 7,161,043 | 5,051,389 | 2,109,654 |
| 1898-9 | 7,688,697 | 6,732,925 | 955,772 |
| 1899-1900 | 8,855,481 | 7,518,456 | 1,337,025 |
| 1900-1 | 8,460,146 | — | — |
| | 39,550,241 | | 4,402,451 |

Causes of
under-
expendi-
ture.

Such is the apparent deficiency on the past five years' ship-building operations, but the late First Lord protested against this view, and claimed that in the Estimates subsequent to the engineering strike provision was made for overtaking the leeway unfortunately lost. It is certainly true that in March, 1898, it was stated that in the succeeding twelve months it was hoped to clear off the sum of £1,400,000. If this amount is deducted from the total, it being actually re-voted money, we get the approximate total of just over three millions sterling as the sum below the Estimates spent in these years.

It has been urged on more than one occasion that this disorganisation has been entirely due to the results of the great labour trouble. The examination of this excuse leads to interesting conclusions. There is reason to fear that if due enquiry were made two ominous facts might be disclosed. First, it has been inferred that, possibly in the anxiety to obtain the very latest improvements in machinery and armament, the construction of ships *urgently required* was unduly and, in the circumstances of the time, dangerously delayed, and, again, that in some cases the needs of many vessels were overlooked until there was insufficient time available for the execution of orders for the delivery of material. The shipbuilding of the past three or four years particularly has been characterised by a series of delays that have had most injurious results. Again, there is the often discussed question of the penalty clause. Although many contractors have been behindhand in the delivery of material, in no case save one, and then under peculiar conditions, has the clause that was intended to meet such an emergency been put into operation.

The suggestion is that work for the Admiralty is undertaken with such a low margin of profit that the infliction of fines would lead to a revolt of the contractors. Certain it is that one firm after another, which has devoted itself to work for the British Navy, has become involved in financial difficulties. It is very questionable whether the authorities would not do well to take the stand of an ordinary business house, give out contracts, as they are distributed every day in the large centres of trade, with a clear understanding that the prices agreed upon are such as to permit of the work being carried out in a specified time, and that any default will result in the imposition of penalties. Moreover—and this is a point of much importance—after a contract has been signed and the work begun there should be no interference with the designs. If all plans, as under the Naval Defence Act, were considered by a body of experts, including officers of long sea experience, as a rule there would be no need for amendments, no afterthoughts would lead to the delay of work. A warship is the most complicated structure of the brain and hand of man, a combination of compromises, and only when it is studied by the many rather than the few can all the problems receive a satisfactory solution.

Seeing that we invariably build in classes, there should be little difficulty in abiding by a regulation that only in a matter of real importance shall any official, with the consent of the Board, have the power to vary the details of a ship already under construction. If this rule were adopted, and an experienced official under the Con-

Con-
tractors'
com-
plaints.

troller of the Navy were made responsible for the even progress of all contract work, it is probable that we should soon have heard the last of ships waiting for armour, guns and machinery, provided that labour disputes did not recur. Not until some such arrangement is made by which all branches of contract work are under the hand of one responsible official, who will see that the work on ships proceeds *pari passu*, every want being anticipated in time by the requisite order, can a fully satisfactory system be arrived at.

Increased
cost of
ships.

A glance at the latest dockyard expenses accounts indicates that the estimated cost of ships has had a marked tendency to exceed the estimate, and this although, as already remarked, they belong to classes; while in spite of the under-expenditure in actual shipbuilding, there has been no corresponding reduction in the "establishment charges." In fact, there is evidence to show that the past five years' construction because slow has also been most expensive. Eleven years since, when he introduced the Naval Defence Act, Lord George Hamilton deplored this tendency in British shipbuilding at that date, and made it the excuse for the financial arrangements by which this legislation was characterised. Experience has amply supported his conclusions. "Rapidity of construction," he said, "means economy, because delay occasions two-fold waste—not only does a ship cost more in construction, but the longer it is on the stocks, the less time is it alive as an effective ship, and therefore the less use you get out of it." Those who will carry their memories back a few years and call to mind how short is the existence, as a first-class weapon, of ships that in their day have been regarded as well-nigh perfect, will appreciate the importance of working out all designs carefully, embodying every possible improvement, and then going ahead with the work with all dispatch.

Majestic
class
delayed.

One of the earliest effects of the engineering dispute was the delay in the completion of the remaining vessels of the Majestic class. The *Cæsar*, *Illustrious*, and *Hannibal* were to have been ready to hoist the pennant in 1897. Early in the following year the first-named was completed, and the others were not commissioned until the summer of 1898, while the delays with the contract-built *Jupiter* and *Mars* were even worse. Each of these five ships occupied over three years in building, the *Hannibal* making a new modern record in dilatory construction. Laid down on May 1, 1894, she was not ready to be passed into the fleet reserve until May 9, 1898, a period of just over four years. Against the name of *Hannibal* the Accountant-General in his report makes the following note: "Excess of total cost principally due to approved alterations and additions,"

and in another place practically the same comment is appended to the Jupiter and Mars to account for the excess expenditure. The tenders in these two cases were received and the keel plate laid long before there was a whisper of the labour trouble, and if they had progressed as well as did the Majestic and Magnificent, they should have been ready for service before the storm burst. The fact is that our shipbuilding had begun to fall in arrears in 1896, and the labour dispute merely accentuated the disorganisation.

As soon as Lord Goschen returned to the Admiralty, after a quarter of a century's absence, he announced that it had been decided to lay down five battleships of moderate dimensions, improved Renowns, with a displacement of 12,950 tons. For twelve months, in accordance with recent custom, this programme remained a paper one merely, and then the Albion and Glory were laid down at Blackwall and Birkenhead respectively in December, followed by the Canopus and Goliath at Portsmouth and Chatham in January, and the Ocean at Devonport on February 15, 1897. A great quantity of material at the three Royal dockyards had been already temporarily fitted together beforehand, thus discounting the value of these dates as a guide to the actual time occupied in building. In the Estimates of 1897-8 was included another vessel of the same class, the Vengeance, which was commenced on August 23, 1897. The history of these six ships has been one of shattered hopes. The Canopus and Goliath were quickly got off the slip—in nine and thirteen months respectively; while the Ocean was in hand at Devonport sixteen and a half months. It was after these ships and their sisters were in the water that the worst delays occurred, owing to the non-delivery of armour, machinery, and other material, and the result is that in comparison with the performances in connection with the Majestic and Magnificent, the time occupied in their completion for sea is most deplorable. The naked outline of their careers may be summarised thus:—

The
Canopus
class.

| | Laid Down. | Completed. | Time Building. |
|------------------|---------------|---------------|----------------|
| Canopus | Jan. 4, 1897 | Dec. 5, 1899 | 35 months. |
| Goliath | Jan. 4, 1897 | April 1, 1900 | 39 " |
| Ocean | Feb. 15, 1897 | Feb. 20, 1900 | 36 " |
| Albion | Dec. 3, 1896 | Delivered | 51 " |
| Glory | Dec. 1, 1896 | Nov. 1900 | 47 " |
| Vengeance | Aug. 23, 1897 | Not delivered | 43 " |

When the Canopus was laid down, it was intended that she should be flying the pennant within twenty months, whereas thirty-

five months, nearly three years, was the period occupied, and it will be seen that her sisters have fared considerably worse. The Albion had the misfortune at the end of last year to develop defects during her gun tests, which hindered the carrying out of her steam trials. Over five years will have elapsed since Parliament voted the money for the commencement of this ship before she will be ready to take her place in the Fleet. The Vengeance was delayed at her contractors' until certain dock alterations could be made at Barrow. Five years will also probably be her record.

Armoured
ships of
1897-1901
pro-
grammes.

None of the armoured ships of the 1897 and later programmes has yet been completed. The appended statement indicates the dates of authorization and laying down of the following vessels:—

| Authorised. | | Laid Down. | Time under Construction. |
|-------------|------------------------------|----------------|--------------------------|
| 1897 | Vengeance, Barrow ... | Aug. 23, 1897 | 3 years 7 months. |
| " | Formidable, Portsmouth ... | March 21, 1898 | 3 years. |
| " | Irresistible, Chatham ... | April 11, 1898 | 2 years 11 months. |
| " | Implacable, Devonport ... | July 13, 1898 | 2 years 8 months. |
| 1898 | London, Portsmouth ... | Dec. 8, 1898 | 2 years 3 months. |
| " | Bulwark, Devonport ... | March 20, 1899 | 2 years. |
| " | Venerable, Chatham ... | Jan. 8, 1899 | 2 years 2 months. |
| July 1898 | Duncan, Blackwall ... | July 19, 1899 | 1 year 8 months. |
| " | Cornwallis, ... | " | " |
| " | Exmouth, Birkenhead ... | Aug. 1899 | 1 year 7 months. |
| " | Russell, Jarrow ... | March 1899 | 2 years. |
| 1899 | Albemarle, Chatham ... | Jan. 8, 1900 | 1 year 2 months. |
| " | Montague, Devonport ... | Nov. 23, 1899 | 1 year 4 months. |
| 1900 | Queen, Devonport ... | March 1901 | |
| " | Prince of Wales, Chatham ... | " | " |

Stages of
incom-
pleteness.

These figures supply facts of great import for consideration. They form a summary of the progress, or rather want of progress, of all the battleships included in the programmes of the past four years. The oldest of them is incomplete still. Seven, judged on the basis of the record established by the Majestic, should have been ready for duty this spring, and several of them many months earlier. The Implacable, which was to have been completed this year, has only just carried out her trials. The Irresistible will not be ready for commissioning before the autumn, and the same date can be assigned for the completion of the Formidable. The London and Venerable cannot begin their steam trials for many months, and are expected (officially) to be ready for service in May, 1902. The Bulwark may be completed early next year. Of the state of the later ships, on the supplementary programme of 1898 and of the ordinary programme of 1899, it is yet early to speak. The two dockyard vessels have been launched, and the ships of last year's programme have been laid down just in time for them to be included

in the retrospect of this financial year. The Russell, building by contract, was launched on February 19th of this year, and the Duncan on March 21, and the Exmouth, it is contemplated, will be floated out in May.

From time to time a great deal is made of the fact that so many battleships have been launched from certain yards, as though this fact were an accurate criterion of the progress of shipbuilding. In every Government yard, however, the construction actually begins before the keel is laid, and owing to the present policy of providing each yard with only one battleship slip, the energy of the yard is concentrated on the vessel approaching the launching stage, only for her to fall into arrears as soon as she is in the water and another ship has taken her place on the slip. The subjoined statement shows the time which elapsed between the laying down of the first and the launch of the third of the ships in each group :—

A misleading standard.

Portsmouth :—Canopus, Formidable, London, nearly 32½ months.

Devonport :—Ocean, Implacable, Bulwark, 32 months.

Chatham :—Goliath, Irresistible, Venerable, 34 months.

The above statement is an indication of the celerity with which a ship can be launched, and is in strong contrast with the subsequent fortunes of these vessels. Each ship, it will be seen, was on the slip about eleven months, and has taken two years or more to complete. Whatever may have been the cause of the later delays, no one can pretend that the mere launching of a skeleton is a satisfactory test as to the strengthening of the Navy. By an unfortunate circumstance, the passing of a ship into the water is made the occasion of an elaborate ceremony, whereas, from a naval point of view, the important date is that on which the maiden pennant is hoisted.

While referring to this subject, reference to another matter may, perhaps, be excused. In view of the present system of delaying construction for ten or eleven months after parliamentary sanction is obtained, and the practice of beginning the building in a temporary manner, the public are deceived. In all calculations it would be far better if the time occupied in the construction of a new ship dated from the March in which she is authorised to the day on which she is passed into the "A" division of the Fleet, as absolutely ready for sea.

Under construction we have twenty armoured cruisers. In the Fleet at present we can number no modern vessels of this important type, though France and Russia have added many to their navies in the past few years. When it was decided to follow in the

Armoured cruisers.

footsteps of our two rivals, Lord Goschen did not fail to confide to the House of Commons that the need for these ships was urgent, and that no effort should be spared to add as many of them as were necessary to the Fleet at the earliest possible moment. Early in the summer of 1897 the first four of the Cressy class, of 12,000 tons, were provided for in the Supplementary Estimate. Over three and a half years have elapsed, and the first of the type, the Cressy, has just carried out her trials, the Sutlej has recently been delivered by the builders, and the other two are in varying stages of incompleteness. The Euryalus, authorised in March, 1898, three years ago, has not yet been launched.

Protected
cruisers.

It is hardly necessary to refer at great length to the dilatory manner in which in the past five years cruising ships requiring little armour have been added to the Fleet. The delays have, in several cases, been most grievous, though on the whole, perhaps, less dangerous than in that of armoured ship-building. Almost all the anticipations of the year 1897 were unfulfilled. In March, 1899, of the eight first-class cruisers in hand—the Andromeda (laid down December 2, 1895), Europa (January 10, 1895), Niobe (December 16, 1895), Diadem (January 23, 1896), Argonaut (November 23, 1896), Amphitrite (December 8, 1896), Spartiate (May 10, 1897)—the last protected ships of the improved Powerful type to be authorised, the Andromeda had not completed her trials, and the Spartiate, Argonaut and Ariadne were far from ready for service. The Diadem did not hoist the pennant until July 19, 1898 (two years and six months after laying down), and the Niobe not until December 8, 1898 (three years after commencement), while the Spartiate late last year began her trials, developed defects, and will probably not be finished in all particulars until April or May, after being in hand over six years. It is a most unhappy record, but unfortunately there are other ships that have had little more fortunate careers. The second-class cruisers, Highflyer and Hermes, were about two years and a half, counting from the date of the laying of the keel only, before they could be passed into the Fleet Reserve. One particularly conspicuous straggler, the Pandora, which was laid down at Portsmouth on January 3rd, 1898, is still mentioned as “completing,” and there is no whisper as to the date when she will finish her trials. Over three years she has been in progress, and it is four years since authorisation was given by Parliament.

Torpedo-
boat
destroyers

It remains to refer to the measures which have been taken to increase the number of torpedo-boat destroyers. No better testimony on this subject can be adduced than the report of the Committee of

Public Accounts, who stated in July last :—"The Controller and Auditor-General reports upon more than one contract in respect of which non-delivery has taken place without any infliction of the penalties incurred, and eleven different destroyers are named, which on the 31st of March, 1899, were undelivered, the period of arrear varying from seventeen months to two years, in several instances. The potential penalties in all the cases taken together were £113,760 ; but on the date mentioned the balance of unpaid purchase money was only £100,098. In no case has any penalty been inflicted."

Constructors of these craft have sadly fallen from the standard that they established in earlier years. The Whiting was completed in every particular in fourteen months, and the Bat in two months more ; yet the Express, Otter, and Vulture were in hand four years, the Electra and Recruit five years, the Fervent six, and the Zephyr even longer. The last two vessels belonged to the first forty-two ordered by the Government, and were assumed to be out of date before they were completed. So rapidly are advances being made in the design of these ships that, unless they can be finished in a year or eighteen months, it would be better that the placing of contracts should be delayed until the authorities can make arrangements for the completion of orders within a reasonable period, with all the latest improvements of machinery. At most they have a life of only a little over ten years, and experience has shown that their existence is less than this official estimate, owing to the great strides that have been made in increasing their speed. While the Viper and Cobra can do their 35 knots an hour, it is bad economy to be adding to the flotillas, as we are to-day, crafts of 27 and 30 knots, delayed beyond all reason.

What is the standard period which the various types of ships should occupy in construction ? An answer to this question will enable an estimate to be formed as to the present arrears. A satisfactory reply presupposes an organisation of a businesslike character, which shall anticipate the needs of each ship in time to enable the work to be carried on without hindrance of any avoidable character. From what has already been stated, it is suggested that such an organization has not been operative in the past five years, whatever the causes may have been. As it was possible to build the Majestic and Magnificent, the first of a new class, in two years or less from the laying of the keel plates, and under three years from their authorisation by Parliament, it ought to be practicable in the case of all ships of the armoured classes to keep close to this splendid standard, on the principle that quick building is cheap building. But it may be conceded that some grace should be allowed on account of exceptional circumstances, though it is not easy to see why any difficulties should

Standard
periods
for con-
struction.

be experienced in a country where all ships are built in large classes, and where the general plans for one serve for half-a-dozen or more. For a similar reason it ought to be possible to complete a first-class cruiser well within three years from the date of the programme, or two years from the laying down. A second-class ship should be ready within a couple of years, and a torpedo-boat destroyer in eighteen months at most. These standards have been beaten time and again.

Ships in
arrears.

If we accept these bases for calculation, it will be admitted that every battleship and first-class cruiser of the 1898 and previous programmes, and every smaller cruising ship and other minor craft of 1899 or before, should be to-day in the Fleet. The following ships are in arrears, excluding the Albion and Cressy, which may be regarded as nearly complete :—

Battleships : Vengeance, Formidable, Irresistible, Implacable, London, Bulwark, Venerable.

Armoured Cruisers : Aboukir, Hogue, Sutlej, Euryalus, Bacchante, King Alfred, Drake.

First-class (protected) Cruiser : Spartiate.

Third-class Cruiser : Pandora.

Torpedo-boat Destroyers : Ten.

Official
explanations.

This is the tale of delay at the present date, as another financial year opens, and it can only be hoped that energetic steps will be taken to retrieve the past. Eleven years ago, when he was introducing the Naval Defence Act, Lord George Hamilton pointed out the two-fold evil that arises from delayed construction. This truth is supported by the Navy Estimates for the past few years. In many instances, the original estimates have been largely over-spent. The *Andromeda* exceeded the original figures by no less than ten per cent., while the sister cruisers, *Gladiator* and *Vindictive*, varied in cost by as much as £25,000. An explanation was given to the Committee on Public Accounts for this latter discrepancy in the case of ships built under the same condition as to labour and cost of material. Mr. Goddard, of the Admiralty, stated :—

“ The Admiralty consider the conditions are not precisely similar, although they are similar ships so far as the hull went, and both built in a dockyard ; but the *Gladiator* was in hand eight months longer than the *Vindictive*. We had to wait for the engines from the contractor, and therefore the ship was very much longer in hand than the sister ship. That always necessitates a certain amount of extra cost. The two ships, again, were not built under the same conditions, because the *Gladiator* was built upon a slip, and the *Vindictive* was built in a dock ; and the cost of building a ship on a slip is, for various reasons, more than if you build in a dock. It is not only

that you have launching expenses in the one case, which you have not in the other; but there is greater difficulty in getting building materials into place on the ship."

The witness explained that he was only referring to the construction of the hull. The same witness also admitted that the present practice of commencing the construction of ships at Pembroke and completing them at another yard makes these vessels "extra expensive." Yet it could be shown that the alterations now being carried out by the Admiralty to remedy this waste were urged upon them several years before any steps were taken in the matter. Probably enquiry, however, would show that the naval authorities are not to blame. The expenditure of large sums on dockyard machinery and basins is not heroic, and makes no appeal to the imagination of the taxpayer. Consequently, when it is a question between laying down a new ship and improving the facilities for building and repairing, Governments are apt to take the unheroic course, and harvest the praise that is always accorded to an Administration which begins ships, quite irrespective of the arrangements for their completion.

Slip *versus*
dock.

There can be no doubt that the operations of the workmen and officials of the Royal yards are sadly hampered by old and inefficient machinery, and that money is thereby wasted. Addressing the Institution of Naval Architects in 1895, Mr. Francis Elgar stated that "The differences between the cost of work in the various dockyards show, to some extent, the effect of inadequate appliances or arrangements for carrying on work quickly and economically. The most costly ships are those built at yards which were most backward at first in these particulars; and much might yet be done in the way of improvements." Since these remarks were made, one of the most notable features of the reports of the Auditor-General has been the difference between the original estimate of ships and the revised estimate, and, again, between the latter and the actual cost. Without going into many details, it is not easy to indicate fully the variations between these figures, but a few typical instances may serve to illustrate the point:

Variations
in cost.

| Ship. | Original Estimate. | Revised Estimate. | Actual Cost. |
|-----------------------|--------------------|-------------------|--------------|
| Jupiter | £859,393 | £876,292 | £880,811 |
| Hannibal | 809,113 | 816,282 | 846,678 |
| Illustrious. | 797,010 | 809,140 | 831,542 |
| Prince George | 813,679 | 823,127 | 818,177 |
| Mars | 860,048 | 876,337 | 879,647 |
| Renown | 626,370 | 646,399 | 650,078 |
| Powerful | 639,364 | 682,250 | 686,143 |
| Terrible | 646,641 | 686,583 | 689,357 |
| Doris | 244,571 | 246,488 | 248,755 |

These are merely incidental figures, the latest available, but they tend to show the value that attaches to the original estimates of the cost of ships, and how wide of the mark in some cases are the revisions that are made after the construction of the ships is in hand. If the "incidental charges" had been included, the contrasts would have been even more glaring. To the lay mind it would seem that there should be no great divergence between the cost of ships of the same class, and yet it is exceptional for two vessels to entail about the same expenditure. The Furious, at Devonport, cost £242,679, while the sister ship, Gladiator, at Portsmouth, cost £250,044, although both vessels were built almost simultaneously, and under the same conditions. Similarly the Cæsar, at Portsmouth, cost £794,456, and the Illustrious, at Chatham, under construction at the same time, and, therefore, when labour and material in the two yards should have absorbed about the same sums, was not completed for less than £831,542—a wide difference, even allowing for minor alterations in design. When ships are built by contract, these contrasts do not occur so frequently. The Jupiter and Mars cost the same amount within less than £2,000, and there was little difference between the Diana, Dido, Doris, Juno, Isis, and Venus, but there was considerable variation in the outlay on the Diadem class, over £14,000 separating the Europa and Niobe, though it has never been suggested that the latter is the superior, and they were built almost simultaneously. Without attempting to explain the discrepancies in the contract-built ships, some explanation should be forthcoming as to the causes which led some of the dockyard ships to eat up so much more money than their sisters, and steps should be taken to make the cost of sister ships built under identical conditions as to labour and material approximate more nearly. If the appliances of any of the yards are so seriously out of date as to account for the divergent figures, or the organisation is defective, it should be possible for the authorities to apply remedies.

Anticipa-
tions un-
fulfilled.

This retrospect of war-shipbuilding since 1896 indicates how great has been the strain on the resources of the country. Under the circumstances it was, perhaps, hardly to be wondered at that Lord Goschen should have come to the conclusion that it was impossible to embark on a larger programme last March. Ever since he went to Whitehall, he had been increasing the votes for new construction and yet unable to conquer the difficulties that hindered the completion of ships. It has been a period of proposals of unexampled magnitude, but, even admitting that the engineering dispute has been largely accountable for the retardation of work in the private establishments as well as in the Royal Dockyards, the performance

has been poor compared with the repeated promises and anticipations. Behind the labour trouble lie other causes for the *impasse*, and it is well for the future of the Navy that an attempt is being made to investigate the origin of the creeping paralysis from which the war-shipbuilding resources of this country have been suffering. It has resulted in the death of several firms, impaired the prosperity of others, and has placed back the hands of the clock by many months. Ships that should be flying the white ensign are still mere skeletons in the various yards, and the longer they remain incomplete, the less value are they to the Empire they were built to protect. The questions of the cause of the present arrears, and the means by which they can be avoided in the future, have been investigated by a Committee, consisting of Mr. H. O. Arnold-Forster, Financial Secretary to the Admiralty; Rear-Admiral A. K. Wilson, recently Controller of the Navy; Sir Thomas Sutherland, and Sir Francis Evans. Every confidence has been felt in this Committee, and it is to be hoped that on their report such reforms will be initiated as will place the relations of the Admiralty and contractors on a more satisfactory basis, and ensure that the country shall get the most efficient and prompt service from all who are entrusted with work for the fleet. The continued existence of the great private yards is an important national asset, and the public may well pause before allowing a system to be pursued which may rob the Empire of the resources, hitherto absolutely unrivalled, which have always been regarded as one of the bulwarks of our existence as a trading, colonising, and freedom-loving people. It has repeatedly been urged in the past that in the last resort these establishments could add a large number of ships to the Fleet in a year or two. It will be well for us that we should always be able to make that boast.

ARCHIBALD S. HURD.

PART II.

BRITISH AND FOREIGN
ARMOURED AND UNARMOURED SHIPS.

PART II.

ALPHABETICAL LIST OF BRITISH AND FOREIGN ARMOURED AND UNARMOURED SHIPS.

The arrangement of the lists of ships has not been changed since the important modifications made in the edition of 1896. The order of the columns corresponds in the British and Foreign Lists, except that in the former there are spaces for the makers of engines and the bulkhead protection, while the date of completion is given in the case of armoured ships instead of that of the launch. The calibre of all foreign guns is given in inches.

The maximum draught at normal displacement has been given wherever it was possible to ascertain it.

As every nation is constantly rearranging the armament of individual ships, it is only possible to publish the latest accessible information.

The vessels which in the British Official *Navy Lists* are called First-Class Gunboats, and in the French Lists are known as Aviso-Torpilleurs, are called in these lists Torpedo Gunboats. Torpedo-boats of all classes below Torpedo Gunboats are placed in a separate list.

Storeships, Harbour Service Ships, and Training Ships are not included in these lists.

The ships of those Powers whose Navies are of small importance will be found at the end of Part II.

The sketches of a larger number of ships have now been reduced to half scale, so as to enable more sketches to be given without unduly increasing the size of the book.

The following abbreviations are used throughout the Alphabetical List, occurring mainly in the first column, showing the class of ship, and in the armour column:—

| | | | |
|---------------------------|---------------------------------|---------|---|
| a.c. | Armoured cruiser. | h.s. | Harveyised or similar hard-faced steel. |
| a.g.b. | Armoured gunboat. | k.s. | Krupp steel. |
| b. | Barbette ship. | i. | Iron hull. |
| br. | Broadside ship. | shd. | Sheathed. |
| c.b. | Central-battery ship. | s. | Steel hull. |
| c.d.s. | Coast-defence ship. | 2 s. | Twin screw. |
| c. | Composite-built hull. | t. | Turret-ship. |
| comp. (in armour column). | Compound or steel-faced armour. | t. | Trial-speed and I.H.P. at trials (in speed and I.H.P. columns). |
| c.t. | Conning-tower. | to.cr. | Torpedo-cruiser. |
| corv. | Corvette. | to.g.b. | Torpedo-gunboat. |
| cr. | Cruiser. | to.r. | Torpedo-ram. |
| d.v. | Despatch vessel. | w. | Wooden hull. |
| g.b. | Gunboat. | | |
| g.v. | Gun-vessel. | | |

ARMAMENT ABBREVIATIONS.—As breech-loading rifled guns are now the most numerous in all fleets, it must be understood that all guns are of that description, unless it be otherwise indicated.

| | |
|------------------|---|
| 1. | Light guns under 15 cwt., including boats' guns. |
| M.L.R. | Muzzle-loading rifled guns. |
| q.f. | Quick or rapid-firing guns; unless otherwise indicated all guns following that first marked as q.f. in the armament column are also quick-firers. |
| f. tu. or b. tu. | Fixed or bow tube for discharging Fish Torpedoes. |
| sub. | Submerged tube for do. |
| B.L. | To 6-in. guns indicates that separate cartridges are used, but it must be observed that though this service classification is retained for the latest pattern 6-in. (Vickers) gun, which has no metal cartridge, that gun attains the full q.f. rate of fire. |

BOILERS.—It has been thought desirable to indicate particulars of the water-tube boilers adopted in the principal fleets. The following abbreviations have, therefore, been given in the column devoted to indicated horse-power. Where no reference occurs the boilers are of the cylindrical type; but the letter "C" implies that cylindrical boilers are used in conjunction with the type of water-tube boilers indicated:—

| | | | |
|---------|---|------------------|----------------------|
| W.T. | Water-tube boilers, where the type is not known or not yet decided. | L. | Laird. |
| B. | Belleville. | M. | Mumford. |
| Bl. | Blechynden. | Nic. | Niclausse. |
| B. & W. | Babcock and Wilcox. | Nor. | Normand. |
| D'A. | D'Allest. | N.S. | Normand-Sigaudy. |
| D. | Dürr. | R. | Reed. |
| E. | Earle. | T. | Thornycroft. |
| Ex. | Express. | T.S. | Thornycroft-Schultz. |
| Du T. | Du Temple. | Y ¹ . | Yarrow small tube. |
| | | Y ² . | „ large tube. |

| Class. | NAME. | Material of Hull. | Displacement. | Length. | Beam. | Draught. | Propellers. | Indicated Horse-Power. | Where Built. | Maker of Engines. | Date of Completion. | Cost † | Armour. | | | | Armament. | | Speed. | Complement. |
|----------------|---------------|-------------------|---------------|---------|---------|----------|-------------|------------------------|--------------|-------------------|---------------------|---------|------------|------------|---------------|--|---|----------------|--------|--|
| | | | tons. | ft. in. | ft. in. | ft. in. | no. | | | | Bldg. | £ | Side. | Bulk-head. | Gun Position. | Back-ing. Deck Plating. | Guns ** | Torpedo Tubes. | knots. | (Guns that can be carried in Bunkers.) |
| a.c. | Aboukir . | S. shd. | 12,000 | 440 0 | 69 6 | 26 3 | 2 | 21,000 B. | Fairfield | Fairfield | 1883 | 722,985 | in. 6 K.S. | in. 5 K.S. | in. 6 K.S. | in. 3-2 | 2 9-2-in. 12 6-in. B.L., 17 smaller Q.F. | 2 | 21.0 | 800 1600 |
| t. 2nd c. | Agamemnon . | I. | 8660 | 280 0 | 66 0 | 24 0 | 2 | 4500 | Chatham | Penn | 1883 | 504 065 | 18-15 | 16 | 16 | 18-9 3 | 4 12-5-in. M.L.R., 2 6-in. Q.F., 6 6-pr., 8 3-pr., 5 M., 21. | 2 | 12.1 | 960 410 |
| 2nd c. | Ajax . | I. | 8660 | 280 0 | 66 0 | 24 0 | 2 | 4500 | Pembroke | Penn | 1883 | 518,357 | 7 | 14 | 11-6 | 4-6 4 12-in., 12 6-in. B.L., 12 12-pr., 6 3-pr., 2 M., 21. | 4 12-in., 12 6-in. Q.F., 18 smaller (4 sub.) | 4 | 19.0 | 900 2000 |
| b. 1st cl. | Albemarle . | S. | 14,000 | 405 0 | 75 6 | 26 6 | 2 | 18,000 B. | Chatham | Thames Iron Works | Bldg. | † | 6 | 6 | 12-5 H. S. | 3-2 | 4 12-in., 12 6-in. Q.F., 18 smaller (4 sub.) | 5 | 18.25 | 800 1550 |
| b. 1st cl. | Albion . | S. | 12,950 | 390 0 | 74 0 | 26 0 | 2 | 13,500 B. | Blackwall | Maudslay | Bldg. | 802,910 | H. S. | H. S. | 8 | 12-10 8 13-1 | 10-in. M.L.R., 4 9-2-in., 6 4-7-in. Q.F., 4 6-pr. Q.F., 5 3-pr., 13 M., 21. | 4 | 14.3 | 680 700 |
| c.b. 2nd c. | Alexandra . | I. | 9490 | 325 0 | 63 8 | 26 6 | 2 | 7000 | Chatham | Humphrys | 1877 | 514,324 | 12 | 8-5 | 8 | 10-15 13-1 | 13-5-in., 6 6-in. Q.F., 12 6-pr., 10 3-pr., 7 M., 21. | 4 | 14.3 | 680 600 |
| b. 1st cl. | Anson . | S. | 10,600 | 330 0 | 68 6 | 27 3 | 2 | 11,500 | Pembroke | Humphrys | 1889 | 724,765 | 18 | 16 | 14-12 comp. | 3-2½ | 4 13-5-in., 6 6-in. Q.F., 12 6-pr., 10 3-pr., 7 M., 21. | 5 | 16.9 | 900 1200 |
| a.c. | Aurora . | S. | 5600 | 300 0 | 56 0 | 24 6 | 2 | 8500 | Pembroke | Thomson | 1889 | 284,550 | 10 | 16 | 4½ | 6 | 2 9-2-in., 10 6-in. Q.F., 6 6-pr., 10 3-pr., 6 M., 31. | 2 | 18.0 | 900 484 |
| a.c. | Australia . | S. | 5600 | 300 0 | 56 0 | 24 6 | 2 | 8500 | Glasgow | Napier | 1888 | 259,390 | comp. | comp. | comp. | 3-2 | 4 10-in., 10 4-7-in. Q.F., 8 6-pr., 12 (2 sub.) | 4 | 18.5 | 800 1600 |
| a.c. | Bacchante . | S. shd. | 12,000 | 440 0 | 69 6 | 26 3 | 2 | 21,000 B. | Glasgow | Clydebank | Bldg. | † | 6 | 5 | 6 | 3-2 | 2 9-2-in. 12 6-in. B.L., 17 smaller Q.F., 9 1. | 2 | 21.0 | 800 1600 |
| b. 1st cl. | Barfleur . | S. shd. | 10,500 | 360 0 | 70 0 | 25 6 | 2 | 13,163 | Chatham | Greenock Foundry | 1894 | 599,089 | 12 | 12 | 9 | 2½-2 | 4 10-in., 10 4-7-in. Q.F., 8 6-pr., 12 (2 sub.) | 7 | 18.5 | 1240 284 |
| a.c. | Bedford . | S. | 9800 | 440 0 | 66 0 | 24 6 | 2 | 22,000 B. | Fairfield | Fairfield | Bldg. | .. | 4 | .. | .. | .. | 3-pr., 7 M., 21. small Q.F. | .. | 23.0 | 800 .. |
| b. 3rd c. | Bellerophon . | I. | 7550 | 300 0 | 56 1 | 27 7 | 1 | 4000 | Chatham | Shipg. Co. Penn | 1865 | 322,701 | 6 | 5 | 6 | 10 | 10 8-in., 4 6-in. Q.F., 4-in., 4 6-pr. Q.F., 12 M., 41. | 2 | 12.4 | 650 572 |

| | | | | | | | | | | | | | | | | | | | | | |
|---------------|---------------|---------|--------|-------|------|-------|---|-----------|----------------------|------------------|-------|-----------|-------|-------|------|------------|---|----|-------|------|-----|
| b. | Benbow . | S. | 10,600 | 330 0 | 68 6 | 27 3 | 2 | 11,500 | Blackwall | Maudslay | 1888 | 760,820 | 18 | 16 | 14-2 | 12-15 3-2½ | 2 16-25-in., 10 6-in. Q.F., 12 6-pr., 10 3-pr., 7 M., 21. | 5 | 16.75 | 1200 | 509 |
| a.c. | Berwick . | S. | 9800 | 440 0 | 66 0 | 24 6 | 2 | 22,000 B. | Glasgow | .. | Bldg. | .. | 4-2 | 3 | 4 | 2-¾ | 14 6-in. Q.F., 10 12-pr., 3 3-pr., 9 M.G. | 2 | 23 | 1600 | ... |
| b. | Bulwark . | S. | 15,000 | 400 0 | 75 0 | 26 9 | 2 | 15,000 B. | Devonpt | Hawthorn | Bldg. | 1,018,949 | 9 | 12 | 12-5 | 3-2 | 4 12-in., 12 6-in. B.L., 2½ small | 2 | 18.0 | 900 | 750 |
| b. | Cesar . | S. | 14,900 | 390 0 | 75 0 | 27 6 | 2 | 12,000 | Portsmouth | Maudslay | 1897 | 865,538 | 9 | 14-9 | 14-6 | 4-2½ | 4 12-in., 12 6-in. Q.F., 18 12-pr., 12 3-pr., 8 M., 21. | 5 | 17.5 | 1850 | 757 |
| b. | Camperdown . | S. | 10,600 | 330 0 | 68 6 | 27 3 | 2 | 11,500 | Portsmouth | Maudslay | 1889 | 769,456 | 18 | 16 | 12 | 10-15 4 | 13-5-in., 6 6-in. Q.F., 12 6-pr., 10 3-pr., 7 M., 21. | 4 | 16.9 | 900 | 515 |
| b. | Canopus . | S. | 12,950 | 390 0 | 74 0 | 26 0 | 2 | 13,500 B. | Portsmouth | Greenock Foundry | 1900 | 869,598 | 6 | 12 | 12-5 | 3-2 | 4 12-in., 12 6-in. Q.F., 18 smaller (4 sub.) | 5 | 18.25 | 800 | 700 |
| b. | Centurion . | S. shd. | 10,500 | 360 0 | 70 0 | 25 6 | 2 | 13,214 | Portsmouth | Greenock Foundry | 1893 | 608,098 | 12 | 12 | 9 | 2½-2 | 4 10-in., 10 4-7-in. Q.F., 8 6-pr., 12 (2 sub.) | 7 | 18.25 | 1240 | 622 |
| b. | Collingwood . | S. | 9500 | 325 0 | 68 0 | 26 10 | 2 | 9500 | Pembroke | Humphrys | 1886 | 624,000 | 13 | 16 | 12 | 17-10 4 | 12-in., 6 6-in. Q.F., 12 6-pr., 8 3-pr., 6 M., 21. | 4 | 6.50 | 1200 | 480 |
| 2nd c. | Colossus . | S. | 9420 | 325 0 | 68 0 | 26 3 | 2 | 5500 | Portsmouth | Maudslay | 1886 | 646,786 | 18-14 | 16-13 | 16 | 22-10 4 | 12-in., 5 6-in. Q.F., 4 6-pr., 10 3-pr., 6 M., 41. | 2 | 4.2 | 970 | 388 |
| 2nd c. | Conqueror . | S. | 6200 | 270 0 | 58 0 | 24 0 | 2 | 6000 | Chatham | Humphrys | 1882 | 418,433 | 12-8½ | 11½ | 12 | 13 | 2 12-in., 4 6-in. Q.F., 6 6-pr., 12 M., 21. | 6 | 15.3 | 650 | 330 |
| a.c. | Cornwall . | S. | 3800 | 440 0 | 66 0 | 24 6 | 2 | 22,000 B. | Pembroke | .. | Bldg. | .. | 4-2 | 3 | 4 | 2-¾ | 14 6-in. Q.F., 10 12-pr., 3 3-pr., 9 M. | 2 | 23 | 1600 | .. |
| b. | Cornwallis . | S. | 14,000 | 405 0 | 75 6 | 26 6 | 2 | 18,000 B. | Blackwall | Thames S. Co. | Bldg. | † | 7 | .. | 11-6 | .. | 4 12-in., 12 6-in. B.L., 12 12-pr. Q.F., 6 3-pr. | 4 | 19 | 900 | 750 |
| a.c. | Cressy . | S. shd. | 12,000 | 440 0 | 69 6 | 26 3 | 2 | 21,000 B. | Fairfield | Fairfield | Bldg. | 723,012 | 6 | 5 | 6 | 3-2 | 2 9-2-in., 12 6-in. B.L., 17 smaller Q.F. | 2 | 21.0 | 800 | 615 |
| a.c. | Cumberland . | S. | 9800 | 440 0 | 66 0 | 24 6 | 2 | 22,000 B. | London & Glasgow Co. | .. | Bldg. | .. | 4-2 | 3 | 4 | 2-¾ | 14 6-in. Q.F., 10 12-pr., 3 3-pr., 9 M.G. | 2 | 23 | 1600 | .. |
| a.d.s. 2nd c. | Cyclops . | I. | 3560 | 225 0 | 45 0 | 16 4 | 2 | 1200 | Blackwall | Elder | 1871 | 154,026 | 8-6 | 9-8 | 9 | 11 4 | 10-in. M.L.R., 4 3-pr. Q.F., 5 M., 11. | .. | 9.9 | 250 | 196 |

* When two sets of figures are given the upper shows the coal capacity at load draught.
 † Includes hydraulic machinery, gun mountings, &c.

† Details of cost incomplete.

** See note relating to the new Vickers 6-in. gun on the previous page.

† Unless mentioned this does not include armament.

GREAT BRITAIN.—Armoured Ships—continued.

| Class. | NAME. | Material of Hull. | Displacement. | Length. | Beam. | Draught. | Propellers. | Indicated Horse-Power. | Where Built. | Maker of Engines. | Date of Completion. | Cost. | Armour. | | | Armament. | | Speed. | Complement. | |
|----------------------------|------------------|-------------------|---------------|-------------|---------|----------|-------------|------------------------|---------------|-------------------|---------------------|-----------|---------|------------|---------------|--------------------------|--|----------------|-------------|-------|
| | | | tons. | ft. in. ft. | in. ft. | ft. in. | no. | | | | | £ | Side. | Bulk-head. | Gun Position. | Back- ing- Deck Plating. | Guns. | Torpedo Tubes. | knots. | tons. |
| <i>t.</i> <i>2nd c.</i> | Devastation | I. | 9330 | 285 0 62 | 3 27 | 6 | 2 | 7000 | Portsmouth | Maudslay | 1873 | 353,848 | 12-10 | 12-10 | 14 | 18-16 3-2 | 4 10-in., 66-pr. Q.F., 83-pr., 5 M., 21. | 2 (3 sub.) | 14-0 | 1800 |
| <i>a.c.</i> | Donegal | S. | 9800 | 440 0 66 | 0 24 | 6 | 2 | 22,000 | Fairfield Co. | .. | Bldg. | .. | 4-2 | 3 | 4 | 2-4 | 14 6-in. Q.F., 10 12-pr., 3 3-pr., 9 M.G. | 2 | 23-0 | 1600 |
| <i>a.c.</i> | Drake | S. | 14,100 | 500 0 71 | 0 26 | 0 | 2 | 30,000 | Pembroke B. | Humphrys | Bldg. | * | 6 | 12 | 12-5 | 3-2 | 2 9-2-in., 16 6-in. B.L., 14 12-pr. Q.F., 3 3-pr. | 2 | 23-0 | 1250 |
| <i>t.</i> <i>2nd c.</i> | Dreadnought | I. | 10,820 | 320 0 63 | 10 26 | 9 | 2 | 6500 | Pembroke | Humphrys | 1875 | 592,573 | 14 | 13 | 14 | 18-15 3-2 | 4 12-5-in. M.L.R., 6 6-pr. Q.F., 12 3-pr., 7 M., 21. | 2 | 13-7 | 1200 |
| <i>b.</i> <i>1st c.</i> | Duncan | S. | 14,000 | 405 0 75 | 6 26 | 6 | 2 | 18,000 | Blackwall B. | Thames S. Co. | Bldg. | * | 7 | .. | 11-6 | .. | 4 12-in., 12 6-in. B.L., 12 12-pr. Q.F., 6 3-pr. | 4 | 19-0 | 900 |
| <i>t.</i> <i>2nd c.</i> | Edinburgh | S. | 9420 | 325 0 68 | 0 26 | 3 | 2 | 5500 | Pembroke | Humphrys | 1886 | 642,333 | 18-14 | 16-13 | 16 | 22-10 3-2 | 4 12-in., 5 6-in. Q.F., 4 6-pr., 10 3-pr., 6 M., 21. | 2 | 14-2 | 970 |
| <i>b.</i> <i>1st c.</i> | Empress of India | S. | 14,150 | 380 0 75 | 0 27 | 6 | 2 | 13,000 | Pembroke | Humphrys | 1893 | 838,087 | 18-5 | 16 | 17-6 | 3 | 4 13-5-in., 10 6-in. Q.F., 16 6-pr., 12 3-pr., 8 M., 21. | 7 (2 sub.) | 17-5 | 1800 |
| <i>a.c.</i> | Essex | S. | 9,800 | 440 0 66 | 0 24 | 6 | 2 | 22,000 | Pembroke B. | John Brown | Bldg. | * | 4 | .. | .. | .. | 14 6-in. B.L., 13 small Q.F. guns | .. | 23-0 | 800 |
| <i>a.c.</i> | Euryalus | S. | 12,000 | 440 0 69 | 6 26 | 3 | 2 | 21,000 | Barrow B. | Vickers | Bldg. | * | 6 | 5 | 6 | 4 | 2 9-2-in., 12 6-in. B.L., 14 12-pr. Q.F., 3 3-pr., 8 M. | 2 | 21-0 | 800 |
| <i>b.</i> <i>1st c.</i> | Exmouth | S. | 14,000 | 405 0 75 | 6 26 | 6 | 2 | 18,000 | Laird B. | Laird | Bldg. | * | 7 | .. | 11-6 | .. | 4 12-in., 12 6-in. B.L., 12 12-pr. Q.F., 6 3-pr. | 4 | 19-0 | 900 |
| <i>b.</i> <i>1st c.</i> | Formidable | S. | 15,000 | 400 0 75 | 0 26 | 9 | 2 | 15,000 | Portsmouth B. | Earle | Bldg. | 1,012,780 | 9 | 12 | 12-5 | 3-2 | 4 12-in., 12 6-in. B.L., 24 small Q.F., 8 M. | .. | 18-0 | 900 |
| <i>a.c.</i> | Galatea | S. | 5600 | 300 0 56 | 0 24 | 6 | 2 | 8500 | Glasgow | Napier | 1889 | 258,390 | 10 | 16 | 4-4 | 6 3-2 | 2 9-2-in., 10 6-in. Q.F., 6 6-pr., 10 3-pr., 6 M., 31. | 4 | 18-1 | 900 |
| <i>a.c.</i> | Glatton | I. | 4910 | 245 0 54 | 0 19 | 5 | 2 | 2000 | Chatham | Laird | 1872 | 219,529 | 12-10 | 12 | 14 | 20 3-1 | 2 12-in. M.L.R., 3 6-pr. Q.F., 4 M., 11. | .. | 11-0 | 540 |

| | | | | | | | | | | | | | | | | | | | | | |
|----------------------------|------------------------|----|--------|-----|------|------|----|---|--------|--------------|-----------|-------|---------|--------|-------|------|--------------|---|----|-------|-----|
| <i>b.</i> <i>1st c.</i> | Glory | S. | 12,950 | 390 | 0 74 | 0 26 | 0 | 2 | 13,500 | Laird B. | Laird | Bldg. | 844,067 | 6 | 12 | 12-5 | 3-2 | 4 12-in., 12 6-in. Q.F., 18 smaller Q.F., 21. | 5 | 18-25 | 700 |
| <i>b.</i> <i>1st c.</i> | Goliath | S. | 12,950 | 390 | 0 74 | 0 26 | 0 | 2 | 13,500 | Chatham B. | Penn | 1900 | 860,788 | 6 | 12 | 12-5 | 3-2 | 4 12-in., 12 6-in. Q.F., 21. | 2 | 23-0 | .. |
| <i>a.c.</i> | Good Hope, late Africa | S. | 14,100 | 500 | 0 71 | 0 26 | 0 | 2 | 30,000 | Fairfield B. | Fairfield | Bldg. | * | 6 | 5 | 6-5 | 3-2 | 2 9-2-in., 16 6-in. B.L., 17 small Q.F. | .. | .. | .. |
| <i>a.c.</i> | Gorgon | I. | 3560 | 225 | 0 45 | 0 16 | 4 | 2 | 1200 | Jarrow | Ravenhill | 1872 | 198,567 | 8-6 | 9-8 | 10 | 11 | 4 10-in. M.L.R., 4 3-pr. Q.F., 5 M., 21. | .. | 9-9 | 192 |
| <i>b.</i> <i>1st c.</i> | Hannibal | S. | 14,900 | 390 | 0 75 | 0 27 | 6 | 2 | 12,000 | Pembroke | Harland | 1897 | 867,403 | 9 | 14-9 | 14-6 | 4-2 | 4 12-in., 12 6-in. Q.F., 18 12-pr., 12 3-pr., 8 M., 21. | 5 | 17-5 | 757 |
| <i>a.c.</i> | Hecate | S. | 3560 | 225 | 0 45 | 0 16 | 4 | 2 | 1200 | Poplar | Ravenhill | 1872 | 140,593 | 8-6 | 9-8 | 10 | 11 | 4 10-in. M.L.R., 4 3-pr. Q.F., 5 M., 21. | .. | 9-9 | 205 |
| <i>b.</i> <i>1st c.</i> | Hercules | I. | 8680 | 325 | 0 59 | 0 26 | 6 | 1 | 8500 | Chatham | Penn | 1868 | 351,134 | 9-6 | 6-5 | 9 | 12-10 | 8 10-in. M.L.R., 2 9-in. do., 2 7-in. do., 2 6-in. Q.F., 6 4-7-in., 9 6-pr. 13 3-pr., 7 M., 21. | 4 | 14-6 | 638 |
| <i>t.</i> <i>3rd c.</i> | Hero | S. | 6200 | 270 | 0 58 | 0 24 | 0 | 2 | 6000 | Chatham | Reinie | 1888 | 397,271 | 12 | 11-1 | 12 | 13-1 | 2 12-in., 4 6-in. Q.F., 7 6-pr., 12 M., 21. | 6 | 15-2 | 339 |
| <i>a.c.</i> | Hogue | S. | 12,000 | 440 | 0 69 | 6 26 | 3 | 2 | 21,000 | Barrow B. | Vickers | Bldg. | 724,492 | 6 | 5 | 6 | 4 | 2 9-2-in., 12 6-in. B.L., 17 small Q.F. | 2 | 21-0 | 745 |
| <i>t.</i> <i>1st c.</i> | Hood | S. | 14,150 | 380 | 0 75 | 0 27 | 6 | 2 | 13,000 | Chatham | Humphrys | 1893 | 830,536 | 18 | 17 | 18-6 | .. | 4 13-5-in., 10 6-in. Q.F., 10 6-pr., 12 3-pr., 8 M., 21. | 7 | 17-5 | 730 |
| <i>a.c.</i> | Hotspur | I. | 4010 | 235 | 0 50 | 0 21 | 10 | 2 | 2500 | Glasgow | Napier | 1871 | 171,528 | 11 & 8 | 8 | 10-8 | 15-10 2-1 | 2 12-in. M.L.R., 2 6-in. Q.F., 6 12-pr., 4 3-pr. Q.F., 8 M., 21. | .. | 11-25 | 232 |
| <i>b.</i> <i>1st c.</i> | Howe | S. | 10,300 | 325 | 0 68 | 0 27 | 3 | 2 | 11,500 | Pembroke | Humphrys | 1889 | 667,022 | 18 | 16 | 11-1 | 15-12 | 4 13-5-in., 6 6-in. Q.F., 12 6-pr., 10 3-pr., 7 M., 21. | 1 | 16-8 | 515 |
| <i>b.</i> <i>1st c.</i> | Illustrious | S. | 14,900 | 390 | 0 75 | 0 27 | 6 | 2 | 12,000 | Chatham | Penn | 1893 | 885,945 | 9 | 14-9 | 14-6 | .. | 4 12-in., 12 6-in. Q.F., 18 12-pr., 12 3-pr., 8 M., 21. | 5 | 17-5 | 757 |
| <i>a.c.</i> | Immortalité | S. | 5600 | 300 | 0 56 | 0 22 | 6 | 2 | 8500 | Chatham | Earle | 1889 | 278,500 | 10 | 16 | 4-4 | 6 | 2 9-2-in., 10 6-in. Q.F., 6 6-pr., 10 3-pr., 6 M., 31. | 2 | 18-0 | 484 |
| <i>a.c.</i> | Impérieuse | S. | 8400 | 315 | 0 62 | 0 27 | 4 | 2 | 10,000 | Portsmouth | Maudslay | 1886 | 530,814 | 10 | 9 | 4-4 | 10 | 4 9-2-in., 10 6-in. Q.F., 8 6-pr., 10 3-pr., 6 M., 21. | 6 | 16-7 | 544 |
| <i>t.</i> <i>2nd c.</i> | Inflexible | I. | 11,880 | 320 | 0 75 | 0 26 | 4 | 2 | 6500 | Portsmouth | Elder | 1881 | 795,268 | 24-16 | 22-14 | 17 | 17-25 | 4 16-in. M.L.R., 8 4-in., 4 6-pr. Q.F., 2 3-pr., 15 M., 21. | 4 | 12-8 | 485 |

* Details of cost incomplete.

z Includes Hydraulic Machinery, Gun Mountings, &c.

| Class. | NAME. | Material of Hull. | Displacement. | Length. | Beam. | Draught. | Propellers. | Indicated Horse-Power. | Where Built. | Maker of Engines. | Date of Completion. | Cost. | Armour. | | | | Armament. | | Speed. | Coals that can be carried in Bunkers. | Complement. |
|------------|--------------------------------|-------------------|---------------|----------|---------|----------|-------------|------------------------|---|-------------------------------|-----------------------------------|---------|---------|------------|---------------|--------------------------|--|----------------|--------|---------------------------------------|-------------|
| | | | tons. | ft. in. | ft. in. | ft. in. | no. | | | | | £ | Side. | Bulk-head. | Gun Position. | Back- ing- Deck Plating. | Guns. | Torpedo Tubes. | knots. | tons. | |
| b. 1st cl. | Implacable Irresistible London | S. | 15,000 | 400 0 75 | 0 26 9 | 2 | 2 | 15,000 B | (D'port Chatham Maudslay Portsm'th Earle) | Laird | Bldg. 1,002,909 986,731 1,023,671 | 2 | 9 K.S. | 12 K.S. | 12-5 K.S. | .. 3-2 | 4 12-in. 12 6-in. B.L., 24 small Q.F., 8 M. | 2 | 18-0 | 900 2000 | 755 |
| a.c. | Kent. | S. | 9800 | 440 0 66 | 0 24 6 | 2 | 2 | 22,000 B. | Portsmouth Hawthorn | Hawthorn | Bldg. * | * | 4 | .. | .. | .. | 14 6-in. Q.F., 13 smaller guns. | .. | 23-0 | 800 | .. |
| a.c. | King Alfred Leviathan. | S. | 14,100 | 500 0 71 | 0 26 0 | 2 | 2 | 30,000 B | (Barrow. Vickers Clydeb'k) | Vickers | Bldg. * | * | 6 K.S. | 5 K.S. | 6-5 K.S. | 3-2 | 2 9-2-in., 16 6-in. B.L., 14 12-pr., 3 3-pr., 9 1. | 2 | 23-0 | 1250 2500 | 900 |
| a.c. | Lancaster | S. | 9800 | 440 0 66 | 0 24 6 | 2 | 2 | 22,000 B. | Elswick Hawthorn | Hawthorn | Bldg. .. | .. | 4-2 | 3 | 4 | 2-3/4 | 14 6-in. Q.F., 10 12-pr., 3 3-pr., 9 M.G. | 2 | 23 23 | 1600 800 | .. |
| b. 1st cl. | Jupiter | S. | 14,900 | 390 0 75 | 0 27 6 | 2 | 2 | 12,000 | Clydeb'nk Thomson | Thomson | 1897 901,216 | 901,216 | 9 | 14-9 H.S. | 14-6 H.S. | 4-2 1/2 | 4 12-in., 12 6-in. Q.F., 18 12-pr., 12 3-pr., 8 | 5 (4 sub.) | 17 | 1850 | 757 |
| b. 1st cl. | Magnificent | S. | 14,900 | 390 0 75 | 0 27 6 | 2 | 2 | 12,000 | Chatham Penn | Penn | 1895 912,291 | 912,291 | 9 | 14-9 H.S. | 14-6 H.S. | 4-2 1/2 | 4 12-in., 12 6-in. Q.F., 18 12-pr., 12 3-pr., 8 | 5 (4 sub.) | 17 | 1850 | 757 |
| b. 1st cl. | Majestic | S. | 14,900 | 390 0 75 | 0 27 6 | 2 | 2 | 12,000 | Portsmouth Barrow | Barrow | 1895 910,632 | 910,632 | 9 | 14-9 H.S. | 14-6 H.S. | 4-2 1/2 | 4 12-in., 12 6-in. Q.F., 18 12-pr., 12 3-pr., 8 | 5 (4 sub.) | 17 | 1850 | 757 |
| b. 1st cl. | Mars | S. | 14,900 | 390 0 75 | 0 27 6 | 2 | 2 | 12,000 | Birkenhead Laird | Laird | 1897 902,631 | 902,631 | 9 | 14-9 H.S. | 14-6 H.S. | 4-2 1/2 | 4 12-in., 12 6-in. Q.F., 18 12-pr., 12 3-pr., 8 | 5 (4 sub.) | 17 | 1850 | 757 |
| b. 1st cl. | Monarch | L. | 8930 | 330 0 57 | 6 26 7 | 1 | 1 | 8216 | Chatham Maudslay | Maudslay | 1869 354,575 | 354,575 | 7-6 | 5-4 1/2 | 8 | 12 | 4 12-in. M.L.R., 2 9-in. do., 1 7-in. do., 4 12-pr. Q.F., 10 3-pr., 6 M., 2 1. | 2 | 15 | 630 | 598 |
| a.c. | Monmouth | S. | 9800 | 440 0 66 | 0 24 6 | 2 | 2 | 22,000 B. | Glasgow | London & Glasgow Shipping Co. | Bldg. .. | .. | 4 | .. | .. | .. | 14 6-in. B.L., 13 small Q.F. | .. | 23-0 | 800 | .. |
| b. 1st cl. | Montagu. | S. | 14,000 | 405 0 75 | 6 26 6 | 2 | 2 | 18,000 B. | Devonport Laird | Laird | .. | * | 7 | 14 | 11-6 | 4-6 2-1 | 4 12-in., 12 6-in. B.L., 12 12-pr., 6 3-pr., 2 M., 2 1. | 4 | 19-0 | 900 2000 | 750 |

| | | | | | | | | | | | | | | | | | | | | |
|-------------|-----------------|----|--------|----------|--------|---|---|----------|--------------------------|-----------------|------|---------|-------------|-------------|-----------|----------|--|------------|-------|----------|
| a.c. | Narcissus | S. | 5600 | 300 0 56 | 0 24 6 | 2 | 2 | 8500 | Hull Earle | Earle | 1889 | 257,390 | 10 comp. | 16 comp. | 4½ | 3-2 | 6 2 9-2-in., 10 6-in. Q.F., 6 6-pr., 10 3-pr., 6 M., 3 1. | 4 | 18-1 | 750 900 |
| b. 1st cl. | Nile | S. | 11,940 | 345 0 73 | 0 27 6 | 2 | 2 | 12,000 | Pembroke Maudslay | Maudslay | 1890 | 819,717 | 20-16 comp. | 18-14 comp. | 18 | 3 | 4 13-5-in., 6 6-in. Q.F., 8 6-pr., 12 (2 sub.) 3-pr., 7 M., 3 1. | 6 | 16-7 | 1200 |
| b. 1st cl. | Ocean | S. | 12,350 | 390 0 74 | 0 25 5 | 2 | 2 | 13,500 B | Devonport Hawthorn | Hawthorn | 1900 | 881,248 | 6 | 12 | 12-5 H.S. | 3-2 | 4 12-in., 12 6-in. Q.F., 18 smaller (4 sub.) Q.F., 2 1. | 5 | 18-25 | 800 1850 |
| a.d.s. | Orion | L. | 4870 | 245 0 52 | 0 21 4 | 2 | 2 | 2600 | Poplar | Maudslay | 1882 | 292,229 | 12-7 | 9-5 | 8 | 16-9 3-1 | 4 12-in. M.L.R., 6 6-pr. Q.F., 6 M., 2 1. | 4 | 11-9 | 520 |
| a.c. | Orlando | S. | 5600 | 300 0 56 | 0 24 8 | 2 | 2 | 8500 | Jarrow | Palmer | 1888 | 266,812 | 10 comp. | 16 comp. | 4½ | 3-2 | 6 2 9-2-in., 10 6-in. Q.F., 6 6-pr., 10 3-pr., 7 M., 3 1. | 2 | 18-1 | 900 |
| a.d.s. c.b. | Penelope | L. | 4470 | 260 0 50 | 0 17 6 | 2 | 2 | 2700 | Pembroke Maudslay | Maudslay | 1868 | 186,848 | 6-5 | 4½ | 5 | 10-11 | 8 9-ton M.L.R., 4 3-pr. Q.F., 11 M., 4 1. | .. | 11-0 | 470 |
| b. 1st cl. | Prince George | S. | 14,900 | 390 0 75 | 0 27 6 | 2 | 2 | 12,000 | Portsm'th Humphrys | Humphrys | 1896 | 885,087 | H.S. | 14-9 | 14-6 H.S. | 4-2½ | 4 12-in., 12 6-in. Q.F., 18 12-pr., 12 3-pr., 2 1. | 5 | 17-5 | 1850 |
| b. 1st cl. | Prince of Wales | S. | 1500 | 400 0 75 | 0 26 9 | 2 | 2 | 20,000 | Chatham Greenock Foundry | Greenock | 1897 | .. | 9 | 12 | 12-6 | 2-1 | 4 12-in., 8-75-in. Q.F., 10 6-in. 16 12-pr., 2 8-owl., 6 3-pr., 8 45-in. M.G. | 4 | 19 | .. |
| b. 1st cl. | Queen | S. | 1500 | 400 0 75 | 0 26 9 | 2 | 2 | 20,000 | Dev'port Harland & Wolff | Harland & Wolff | 1897 | .. | 9 | 12 | 12-6 | 2-1 | 4 12-in., 8-75-in. Q.F., 10 6-in. 16 12-pr., 2 8-owl., 6 3-pr., 8 45-in. M.G. | 4 | 19 | .. |
| b. 1st cl. | Renown | S. | 12,350 | 380 0 72 | 0 25 5 | 2 | 2 | 12,000 | Pembroke Maudslay | Maudslay | 1896 | 696,425 | 8-6 | 10-6 | 10 | 3-2 | 4 10-in. 29-ton, 10 6-in. Q.F., 14 12-pr., 15 smaller pr., 15 smaller Q.F. and Machine Guns. | 5 | 18-0 | 1800 |
| b. 1st cl. | Ramillies | S. | 14,150 | 380 0 75 | 0 27 6 | 2 | 2 | 13,000 | Glasgow Thomson | Thomson | 1898 | 874,255 | H.S. | 10-6 | 10 | 3-2 | 4 10-in. 29-ton, 10 6-in. Q.F., 14 12-pr., 15 smaller pr., 15 smaller Q.F. and Machine Guns. | 5 (2 sub.) | 18-0 | 674 |
| b. 1st cl. | Repulse | S. | 14,150 | 380 0 75 | 0 27 6 | 2 | 2 | 13,000 | Pembroke Humphrys | Humphrys | 1894 | 841,274 | 18-5 comp. | 16 comp. | 17 | 3 | 4 13-5-in., 10 6-in. Q.F., 16 6-pr., 12 3-pr., 8 M., 2 1. | 7 (2 sub.) | 17-5 | 1800 |
| b. 1st cl. | Resolution | S. | 14,150 | 380 0 75 | 0 27 6 | 2 | 2 | 13,000 | Jarrow Palmer | Palmer | 1898 | 852,755 | 18-5 comp. | 16 comp. | 17 | 3 | 4 13-5-in., 10 6-in. Q.F., 16 6-pr., 12 3-pr., 8 M., 2 1. | 7 (2 sub.) | 17-5 | 730 |

* Details of cost incomplete

2 Includes Hydraulic Machinery, Gun Mountings, &c.

GREAT BRITAIN.—Armoured Ships — continued.

278

| Class. | NAME. | Material of Hull. | Displacement. | Length. | Beam. | draught. | Propellers. | Indicated Horse- Power. | Where Built. | Maker of Engines. | Date of Completion. | Cost. | Armour. | | | | Armament. | | Speed. | Normal Coal Supply. | Complement. |
|-------------------|-----------------|-------------------|---------------|---------|---------|----------|-------------|----------------------------|-----------------|----------------------|---------------------|------------------------|----------------|----------------|------------------|-----------------------------------|--|-------------------|--------|------------------------|-------------|
| | | | tons. | ft. in. | ft. in. | ft. in. | no. | | | | | £ | Side. | Bulk- head. | Gun Position. | Back- ing. Deck Plating. | Guns. | Torpedo Tubes. | knots. | tons. | |
| b. 1st cl. | Revenge | S. | 14,150 | 380 0 | 75 0 | 27 6 | 2 | 13,000 | Jarrow | Palmer | 1895 | 852,755 | 18-5 comp. | 16 comp. | 17 comp. | 3 | 4 13-5 in., 10 6 in. Q.F., 16 6-pr., 12 3-pr., 8 M., 2 L. | 7 (2 sub.) | 17-5 | 900 | 750 |
| b. 1st cl. | Royal Oak | S. | 14,150 | 380 0 | 75 0 | 27 6 | 2 | 13,000 | Birkenhead | Laird | 1894 | 877,378 | 18-5 comp. | 16 comp. | 17 comp. | 3 | 4 13-5 in., 10 6 in. Q.F., 16 6-pr., 12 3-pr., 8 M., 2 L. | 7 (2 sub.) | 17-5 | 1800 | 750 |
| b. 1st cl. | Royal Sovereign | S. | 14,150 | 380 0 | 75 0 | 27 6 | 2 | 13,312 | Portsmouth | Humphrys | 1892 | 824,583 | 18-5 comp. | 16 comp. | 17 comp. | 3 | 4 13-5 in., 10 6 in. Q.F., 16 6-pr., 12 3-pr., 8 M., 2 L. | 7 (2 sub.) | 17-5 | 1800 | 750 |
| b. 1st cl. | Rodney | S. | 10,300 | 325 0 | 68 0 | 27 3 | 2 | 11,500 | Chatham | Humphrys | 1888 | 639,278 | 18 comp. | 16 comp. | 11 comp. | 15-12 3-2½ | 4 13-5 in., 6 6 in. Q.F., 12 6-pr., 10 3-pr., 6 M., 2 L. | 4 | 16-75 | 1200 | 515 |
| c.d.s. 1st cl. | Rupert | I. | 5440 | 250 0 | 53 0 | 23 7 | 2 | 6000 | Chatham | Portsmouth | 1874 | 232,677 | 11-9 | 12 | 14-12 | 3-2 | 2 9-2 in., 2 6 in. Q.F., 4 6-pr., 6 3- pr., 2 M., 2 L. | 4 | 14-0 | 480 | 293 |
| b. 1st cl. | Russell | S. | 14,000 | 405 0 | 75 6 | 26 6 | 2 | 18,000 | Jarrow | Palmer | Bug. | † | 7 K.S. | 11-6 K.S. | 2-1 | 4-6 K.S. | 4 12 in., 12 6 in. B.L., 12 12-pr. Q.F., 6 3-pr. | 4 | 19 | 900 | 750 |
| b. 1st cl. | Sans Pareil | I. | 10,470 | 340 0 | 70 0 | 27 3 | 2 | 14,000 | Blackwall | Humphrys | 1889 | 719,442 | 16-18 comp. | 16 comp. | 18 comp. | 3 | 2 16-25 in., 1 10 in. Q.F., 12 6 in. Q.F., 12 6-pr., 12 3-pr., 8 M., 2 L. | 6 (2 sub.) | 17-2 | 1200 | 583 |
| a.c. | Suffolk | S. | 9800 | 440 0 | 66 0 | 24 6 | 2 | 22,000 | Portsmouth | Humphrys | Bug. | .. | 4-2 | 3 | 4 | 2-¾ | 14 6 in. Q.F., 10 12-pr., 3 3-pr., 9 M.G. | 2 | 23 | 1600 | 800 |
| c.b. 3rd c. | Sultan | I. | 9200 | 325 0 | 59 0 | 27 6 | 1 | 8000 | Chatham | Thomson | 1871 | 357,415 | 9-6 | 6-4½ | 9-8 | 12-10 | 8 10 in. M.L.R., 4 9 in. do., 4 4-7 in. Q.F., 9 6-pr., 13 3-pr., 7 M., 2 L. | 4 | 14-0 | 810 | 661 |
| c.b. 2nd c. | Superb | I. | 9170 | 332 3 | 59 0 | 26 5 | 1 | 8500 | Blackwall | Maudslay | 1880 | 443,000 (purchased) | 12-10 | 10-5 | 10 | 7-12 1½ | 12 10 in. M.L.R., 10 6 in. Q.F., 22 light Q.F. and Machine Guns. | 4 | 15-0 | 970 | 654 |
| a.c. | Sutlej | S. | 12,000 | 440 0 | 69 6 | 26 3 | 2 | 21,000 | Clydebank | Clydebank Company | Bug. | 733,625 | 6 K.S. | 5 K.S. | 6 K.S. | 3-2 | 2 9-2 in., 12 6 in. B.L., 17 small Q.F. | 2 | 21-0 | 800 | 615 |

| | | | | | | | | | | | | | | | | | | | | |
|-----------------------------|--------------------------|---------|----------------------------|-------|------|------|---|-------------------|----------|------|-----------|-------------|-------------|-------------|-------------|--|----|-------|------|-----|
| c.b. & 2nd | Temeraire | I. shd. | 8540 | 285 0 | 62 0 | 27 2 | 2 | 6500 Chatham | Humphrys | 1877 | 454,969 | 11-8 | 8-5 | 10-8 | 12-10 1 1/2 | 4 11 in. M.L.R., 4 10 in. do., 4 6-pr., 10 3-pr., 8 M., 4 L. | 2 | 13-8 | 620 | 592 |
| t. 2nd cl. | Thunderer | I. | 9330 | 285 0 | 62 3 | 27 0 | 2 | 7000 Pembroke | Maudslay | 1877 | 358,542 | 12-10 | 12-10 | 14-12 | 18-16 3-2 | 4 10 in., 6 6-pr. Q.F., 8 3-pr., 4 M., 2 L. | 2 | 14-0 | 1600 | 592 |
| t. 1st cl. | Trafalgar | S. | 11,940 | 345 0 | 73 0 | 27 6 | 2 | 12,000 Portsmouth | Humphrys | 1890 | 862,794 | 20-16 comp. | 18-14 comp. | 18 comp. | 6 3 | 4 13-5 in., 6 6 in. Q.F., 8 6-pr., 12 (2 sub.) | 6 | 16-7 | 1200 | 572 |
| a.c. | Undaunted | S. | 5600 | 300 0 | 56 0 | 22 6 | 2 | 8500 Jarrow | Palmer | 1889 | 256,055 | 10 comp. | 16 comp. | 4 1/2 comp. | 6 3-2 | 2 9-2 in., 10 6 in. Q.F., 6 6-pr., 10 3-pr., 7 M., 3 L. | 4 | 18-1 | 750 | 484 |
| b. 1st cl. | Victorious | S. | 14,900 | 380 0 | 75 0 | 27 6 | 2 | 12,000 Chatham | Hawthorn | 1897 | 868,313 | 9 H.S. | 14-9 H.S. | 14-6 H.S. | 4-2 1/2 | 4 12 in., 12 6 in. Q.F., 18 12-pr., 12 (4 sub.) | 5 | 17-5 | 1850 | 757 |
| b. 1st cl. | Venerable | S. | 15,000 | 400 0 | 75 0 | 25 9 | 2 | 15,000 Chatham | Maudslay | Bug. | 1,010,863 | 7 K.S. | 11-6 K.S. | 11-6 K.S. | 4-6 2-1 | 4 12 in., 12 6 in. B.L., 24 small Q.F., 8 M. | 2 | 18-0 | 900 | 755 |
| b. 1st cl. | Vengeance | S. | 12,950 | 390 0 | 74 0 | 26 0 | 2 | 13,500 Barrow | Vickers | Bug. | 814,619 | 6 H.N.S. | 12 H.N.S. | 12-6 H.S. | 2-1 | 4 12 in., 12 6 in. Q.F. & 18 small | 4 | 18-25 | 800 | 750 |
| a.c. | Warspite | S. | 8400 | 315 0 | 62 0 | 27 4 | 2 | 10,000 Chatham | Penn | 1888 | 529,332 | 10 comp. | 9 comp. | 8 comp. | 3-2 | 4 9-2 in., 10 6 in. Q.F., 4 6-pr. Q.F., 9 3-pr., 6 M., 2 L. | 6 | 16-7 | 1180 | 535 |
| c.d.s. 1st cl. | Wivern | I. | 2750 | 224 6 | 42 4 | 17 0 | 1 | 1000 Birkenhead | Laird | 1865 | 116,514 | 4 1/2 | .. | 8-10 | 8-10 | 4 9 in. M.L.R., 8 M., 1 L. | .. | 8-5 | 300 | 151 |
| b. 3 new ships (Programme.) | 3 new ships (Programme.) | S. | Design not settled.†† | | | | | | | | | | | | | | | | | |
| a.c. | 6 new ships (Programme.) | S. | .. " " " " " " " " " " " " | | | | | | | | | | | | | | | | | |

The following, which appear in the Official Navy List, are lent to India and Australia:—

| | | | | | | | | | | | | | | | | | | | | |
|----------------|-------------------------------|----|------|-------|------|------|---|----------------|-----------|------|---------|-----|-----|------|------------|------------------------------|----|------|-----|-----|
| c.d.s. 1st cl. | Abyssinia* (Indian Marine.) | I. | 2900 | 225 0 | 42 0 | 14 6 | 2 | 900 Poplar | Dudgeon | 1870 | 116,549 | 7-6 | 8-7 | 10-8 | 11-9 1 1/2 | 4 8 in. 14-ton, 7 M., 2 L. | .. | 9-0 | 92 | 193 |
| c.d.s. 1st cl. | Cerberus† (Victorian Marine.) | I. | 3480 | 225 0 | 45 0 | 15 3 | 2 | 1600 Jarrow | Maudslay | 1870 | 117,556 | 8-6 | 9-8 | 10-9 | 11-9 1 1/2 | 4 10 in. 18-ton M.L.R., 4 M. | .. | 9-75 | 120 | 196 |
| c.d.s. 1st cl. | Magdala* (Indian Marine.) | I. | 3340 | 225 0 | 45 0 | 15 3 | 2 | 1400 Blackwall | Ravenhill | 1870 | 132,400 | 8-6 | 9-8 | 10-9 | 11-9 1 1/2 | 4 8 in. 14-ton, 7 M., 2 L. | .. | 10-0 | 120 | 194 |

* Includes Hydraulic Machinery, Gun Mountings, &c.
†† One at Portsmouth, one at Devonport, and one by contract.

* At Bombay.
† At Melbourne.
†† One at Chatham, five by contract.

279

GREAT BRITAIN.—Cruising Ships, &c.

280

| Class. | NAME. | Material of Hull. | Displacement. | Length. | Beam. | Draught. | Propellers. | Indicated Horse-Power. | Where Built. | Maker of Engines. | Date of Launch. | Cost. | Armour. | | Armament. | | Normal Coal Supply. | Complement. |
|---------------|--------------|-------------------|-----------------|---------|-------|----------|-------------|------------------------|--------------|-------------------|-----------------|-------|---------------|---|-----------|----------------|---------------------|-------------|
| | | | | | | | | | | | | | Gun Position. | Deck. | Guns. | Torpedo Tubes. | | |
| 2nd cl. Cr. | Eolus . | S. shd. | 3600 300 0 43 | 0 17 6 | 2 | 9000 | Devonport | Hawthorn. | 1892 | 208,450 | 2 | 2-1 | in. | 2 6-in. Q.F., 6 4-7-in. 8 6-pr. 1 3-pr., 4 M., 1 l. | 4 | 19-75 | 400 | 273 |
| Dsp. Ves. | Alacrity . | S. | 1700 250 0 32 | 6 14 0 | 2 | 3000 | Jarrow | Palmer | 1885 | 77,969 | .. | .. | .. | 10 6-pr. Q.F., 2 M. | .. | 17-00 | 400 | 114 |
| T. G. B.. | Alarm . | S. | 810 230 0 27 | 0 8 9 | 2 | 3884 | Sheerness | Penn | 1892 | 59,346 | 2 | .. | .. | 2 4-7-in. Q.F., 4 3-pr. do. | 3 | 19-25 | 100 | 91 |
| 2nd cl. G. B. | Albacore . | C. | 560 135 0 26 | 0 10 6 | 1 | 500 | Birkenhead | Laird | 1883 | 28,556 | .. | .. | .. | 2 5-in., 2 4-in., 2 M. | .. | 11-0 | 85 | 59 |
| Sloop | Alert . | S. shd. | 960 180 0 32 | 6 11 6 | 1 | 1400 | Sheerness | Sheerness | 1894 | 60,309 | .. | .. | .. | 6 4-in. 25-pr. Q.F., 4 3-pr., 2 M. | .. | 13-25 | 130 | 101 |
| " | Algerine . | S. | 1050 185 0 32 | 6 11 3 | 2 | 1400 | Devonport | Devonport. | 1895 | 63,904 | .. | .. | .. | 6 4-in. 25-pr. Q.F., 4 3-pr., 3 M. | .. | 13-0 | 160 | 106 |
| 2nd cl. Cr. | Amphion . | S. | 4300 300 0 46 | 0 20 6 | 2 | 5000 | Pembroke | Maudslay. | 1883 | 160,500 | .. | 1 1/2 | .. | 10 6-in. Q.F., and 14 smaller, and M. | 4 | 16-6 | 550 | 309 |
| " | Andromache . | S. | 3400 300 0 43 | 0 16 6 | 2 | 9000 | Chatham. | Earle | 1890 | 186,280 | .. | 2 | .. | 2 6-in. Q.F., 6 4-7-in., 8 6-pr., 1 3-pr., 4 M., 1 l. | 4 | 20-0 | 400 | 273 |
| " | Apollo . | S. | 3400 300 0 43 | 0 16 6 | 2 | 9000 | Chatham. | Earle | 1891 | 186,361 | .. | .. | .. | .. | .. | .. | .. | .. |
| 1st cl. Cr. | Andromeda . | S. shd. | 11,000 435 0 69 | 0 25 3 | 2 | 16,500 | Pembroke | Hawthorn. | 1897 | 575,146 | 3 | 3-6 | .. | 16 6-in., 17 small Q.F., 2 12-pr. boat. | 3 | 20-5 | 1000 | 600 |
| T. G. B.. | Antelope . | S. | 810 230 0 27 | 0 8 9 | 2 | 3621 | Devonport | Yarrow | 1893 | 61,397 | 2 | .. | .. | 2 4-7-in. Q.F., 4 3-pr. | 3 | 19-25 | 100 | 91 |
| 3rd cl. Cr. | Archer . | S. | 1770 225 0 36 | 0 14 6 | 2 | 3500 | Glasgow | Thomson | 1885 | 287,583 | .. | .. | .. | 6 6-in. Q.F., 8 3-pr., 2 M., 1 l. | 3 | 16 5 | 475 | 172 |

| | | | | | | | | | | | | | | | | | | | |
|-------------|--------------|---------|-----------------|--------|---|--------|------------|------------|------|---------|-----|-------|----|-------|---|----|-------|-------|-----|
| 1st cl. Cr. | Argonaut . | S. shd. | 11,000 435 0 69 | 0 25 3 | 2 | 18,000 | Fairfield. | Fairfield. | 1898 | 535,557 | 3-6 | .. | .. | .. | 16 6-in. Q.F., 14 12-pr., 11 smaller Q.F., and (2 sub.) Machine Guns. | 3 | 20-75 | 1000 | 677 |
| " | Ariadne . | S. shd. | 11,000 435 0 69 | 0 25 3 | 2 | 18,000 | Clydebank | John Brown | 1898 | 543,705 | 8-6 | .. | .. | .. | .. | .. | .. | .. | .. |
| " | Amphitrite . | S. shd. | 11,000 435 0 69 | 0 25 3 | 2 | 18,000 | Barrow | Vickers | 1898 | 546,227 | .. | .. | .. | .. | .. | .. | .. | .. | .. |
| 2nd cl. Cr. | Arethusa . | S. | 4300 300 0 46 | 0 20 6 | 2 | 5000 | Glasgow | Napier | 1882 | 145,198 | .. | 1 1/2 | .. | 1 1/2 | 10 6-in. Q.F., 8 3-pr., 6 M., 2 l. | 4 | 16-6 | 1000* | 309 |
| " | Arrogant . | S. | 5900 320 0 57 | 6 21 0 | 2 | 10,000 | Devonport | Earle | 1896 | 278,878 | 3 | 1-2 | .. | 1-2 | 4 6-in. Q.F., 6 4-7-in., 9 12-pr., 3 3-pr., 1 12-pr. boat, 5 M. | 2 | 19-1 | 500 | 480 |
| " | Astræa . | S. shd. | 4300 320 0 49 | 6 19 0 | 2 | 9112 | Devonport | Devonport | 1893 | 244,831 | .. | .. | .. | .. | .. | .. | .. | .. | .. |
| 3rd cl. Cr. | Barham . | S. | 1830 280 0 35 | 0 13 3 | 2 | 4700 | Portsmouth | Hawthorn. | 1889 | 113,302 | 2 | 2-1 | .. | 2-1 | 6 4-7-in. Q.F., 4 3-pr., 2 M. | 2 | 18-6 | 140 | 169 |
| " | Bellona . | S. | 1830 280 0 35 | 0 13 3 | 2 | 4700 | Newcastle | Hawthorn. | 1890 | 94,195 | 2 | 2-1 | .. | 2-1 | 6 4-7-in. Q.F., 4 3-pr., 2 M. | 2 | 17-8 | 140 | 169 |
| " | Barracouta . | S. | 1580 220 0 35 | 0 14 0 | 2 | 3000 | Sheerness | Palmer | 1889 | 96,315 | 2 | 2-1 | .. | 2-1 | 6 4-7-in. Q.F., 4 3-pr., 2 M. | 2 | 16-5 | 160 | 159 |
| " | Barrosa . | S. | 1580 220 0 35 | 0 14 0 | 2 | 3000 | Portsmouth | Palmer | 1889 | 79,238 | 2 | 2-1 | .. | 2-1 | 6 4-7-in. Q.F., 4 3-pr., 3 M. | 2 | 16-5 | 160 | 159 |
| " | Blanche . | S. shd. | 1580 220 0 35 | 0 14 0 | 2 | 3000 | Pembroke | Laird | 1889 | 91,112 | 2 | 2-1 | .. | 2-1 | 6 4-7-in. Q.F., 4 3-pr., 2 M. | 2 | 16-5 | 160 | 159 |
| " | Blonde . | S. shd. | 1580 220 0 35 | 0 14 0 | 2 | 3000 | Pembroke | Laird | 1889 | 90,059 | 2 | 2-1 | .. | 2-1 | 6 4-7-in. Q.F., 4 3-pr., 2 M. | 2 | 16-5 | 160 | 159 |
| Sloop | Basilisk . | S. shd. | 1170 195 0 28 | 0 12 6 | 2 | 2000 | Sheerness | Rennie | 1889 | 58,013 | .. | .. | .. | .. | .. | .. | .. | .. | .. |
| " | Beagle . | S. shd. | 1170 195 0 28 | 0 12 6 | 2 | 2000 | Portsmouth | Rennie | 1889 | 56,474 | .. | .. | .. | .. | .. | .. | .. | .. | .. |
| 1st cl. Cr. | Blake . | S. | 9000 375 0 65 | 0 25 9 | 2 | 20,000 | Chatham. | Maudslay. | 1889 | 440,471 | 6 | 6-3 | .. | 6-3 | 2 9-2-in., 10 6-in. Q.F., 16 3-pr. Q.F., 7 M., 2 l. (2 sub.) | 4 | 21-5 | 1500 | 570 |
| " | Blenheim . | S. | 9000 375 0 65 | 0 25 9 | 2 | 21,411 | Blackwall | Humphrys | 1890 | 425,591 | .. | .. | .. | .. | .. | .. | .. | .. | .. |

* Includes Gun Mountings, &c.

* Bunker capacity.

281

| Class. | NAME. | Material of Hull. | Displacement. | Length. | Beam. | Draft. | Propellers. | Indicated Horse Power. | Where Built. | Maker of Engines. | Date of Launch. | Cost. | Armour. | | Armament. | | Speed. | Normal Coal Supply. | Complement. |
|---------------|-----------------------|-------------------|---------------|---------|-------|--------|-----------------------------|------------------------|--------------|-------------------|-----------------|-------|---------------|-------|---|----------------|--------|---------------------|-------------|
| | | | | | | | | | | | | | Gun Position. | Deck. | Guns. | Torpedo Tubes. | | | |
| 2nd cl. Cr. | Bonaventure | S. shd. | 4360 320 0 49 | 619 0 | 2 | 9000 | Devonport Hawthorn. | 1892 | 247,128 | 2 | 2-1 | in. | 2 | 2-1 | 2 6-in. Q.F., 8 4-7-in. 86-pr., 1 3-pr. 4 m., 1 l. | 4 | 19.5 | 400 | 312 |
| T. G. B. | Boomerang (Australia) | S. | 735 230 0 27 | 0 8 3 | 2 | 3500 | Elswick . Bellis . | 1889 | 49,962 | 2 | .. | 2 | 2 | .. | 2 4-7-in. Q.F., 4 3-pr., 1 m. | 3 | 20.0 | 100 | 91 |
| 2nd cl. Cr. | Brilliant | S. shd. | 3600 300 0 43 | 817 6 | 2 | 9164 | Sheerness Hawthorn. | 1891 | 204,228 | 2 | 2-1 | 2 | 2 | 2-1 | 2 6-in. Q.F., 6 4-7-in. 86-pr., 1 3-pr., 4 m., 1 l. | 4 | 19.7 | 400 | 273 |
| 3rd cl. Cr. | Brisk. | S. | 1770 225 0 36 | 0 14 3½ | 2 | 3500 | Glasgow Thomson . | 1886 | 87,583 | .. | .. | .. | .. | .. | 6 6-in. Q.F., 8 3-pr., 2 m., 1 l. | 3 | 16.5 | 325 | 172 |
| 1st cl. G. B. | Bramble | S. | 700 180 0 23 | 0 8 0 | 2 | 1300 | Liverpool Fawcett & Co. | 1898 | 50,461 | .. | .. | .. | .. | .. | 2 4-in., 4 12-pr. Q.F. | .. | 13.5 | 50 | 85 |
| " | Britomart | S. | 700 180 0 33 | 0 8 0 | 2 | 1300 | Liverpool Fawcett & Co. | 1898 | 50,401 | .. | .. | .. | .. | .. | 2 4-in., 4 12-pr. Q.F. | .. | 13.5 | 50 | 85 |
| Sloop | Buzzard | C. | 1140 195 0 28 | 0 11 6 | 2 | 2000 | Sheerness Barrow . | 1887 | 58,700 | .. | .. | .. | .. | .. | 8 5-in., 8 m. | 2 | 14.50 | 160 | 138 |
| 3rd cl. Cr. | Calliope | S. shd. | 2770 235 0 44 | 619 11 | 1 | 4020 | Portsmouth Rennie . | 1884 | 120,000 | .. | .. | .. | .. | .. | 4 6-in., 12 5-in. 38 cwt., 9 m., 2 l. | 2 | 14.6 | 550 | 238 |
| " | Calypso | S. shd. | 2770 235 0 44 | 619 11 | 1 | 4000 | Chatham Rennie . | 1883 | 119,500 | .. | .. | .. | .. | .. | 2 6-in. Q.F., 8 4-7-in. 86-pr., 1 3-pr., 4 m., 1 l. | 4 | 19.5 | 400 | 312 |
| 2nd cl. Cr. | Cambrian | S. shd. | 4360 320 0 49 | 619 0 | 2 | 9000 | Pembroke Hawthorn. | 1893 | 236,919 | .. | .. | .. | .. | .. | 4 6-in., 8 5-in., 4 3-pr., Q.F., 6 m., 2 l. | 2 | 12.75 | 470 | 265 |
| 2nd cl. Cr. | Challenger | S. | 5380 355 0 56 | 0 21 3 | 2 | 12,500 | Chatham Wallis & Eng'g Co. | Big. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. |
| 3rd cl. Cr. | Champion | S. shd. | 2380 225 0 44 | 619 3 | 1 | 2000 | Glasgow (Fairfield) Elder . | 1878 | 113,983 | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. |

| | | | | | | | | | | | | | | | | | | | |
|---------------|------------|---------|-----------------|---------|---|--------|--------------------------------|------|---------|------|------|------|------|------|--|----|-------|------|-----|
| 3rd cl. Cr. | Cleopatra | S. shd. | 2380 225 0 44 | 619 3 | 1 | 2000 | Glasgow (Fairfield) Humphrys | 1878 | 113,924 | .. | .. | .. | .. | .. | 4 6-in., 8 5-in., 4 3-pr., Q.F., 6 m., 2 l. | 2 | 13.0 | 470 | 265 |
| " | Comus | S. shd. | 2380 225 0 44 | 619 3 | 1 | 2000 | Glasgow (Fairfield) Elder . | 1878 | 113,974 | .. | .. | .. | .. | .. | 10 6-in., 7 m., 2 l. | 2 | 12.75 | 470 | 265 |
| " | Cordelia | S. shd. | 2380 225 0 44 | 619 3 | 1 | 2000 | Portsmouth Rennie . | 1881 | 104,500 | .. | .. | .. | .. | .. | 10 6-in., 9 m., 2 l. | 2 | 12.75 | 470 | 265 |
| Sloop | Condor | S. shd. | 980 180 0 33 | 3 11 6 | 2 | 1400 | Sheerness Thames . | 1898 | 65,185 | .. | .. | .. | .. | .. | 6 4-in. Q.F., 4 3-pr. | .. | 13.25 | 130 | 130 |
| 2nd cl. Cr. | Charybdis | S. shd. | 4360 320 0 49 | 619 0 | 2 | 9000 | Sheerness Earle . | 1893 | 237,344 | 2 | 2-1 | 2 | 2 | 2-1 | 2 6-in. Q.F., 8 4-7-in. 86-pr., 1 3-pr., 4 m., 1 l. | 4 | 19.5 | 400 | 312 |
| T. G. B. | Circe | S. | 810 230 0 27 | 0 8 9 | 2 | 3500 | Sheerness Penn . | 1892 | 61,979 | 2 | .. | .. | .. | .. | 2 4-7-in. Q.F., 4 3-pr. | 3 | 19.25 | 100 | 91 |
| 2nd cl. G. B. | Cockchafer | C. | 465 125 0 23 | 6 9 6 | 1 | 360 | Pembroke Mandslay . | 1881 | 77,000 | .. | .. | .. | .. | .. | 2 64-pr. M.L.M., 2 20-pr., 2 m. | .. | 9.8 | 40 | 61 |
| 3rd cl. Cr. | Cossack | S. | 1770 225 0 36 | 0 14 3½ | 2 | 3500 | Glasgow Thomson . | 1886 | 87,583 | .. | .. | .. | .. | .. | 6 6-in. Q.F., 8 3-pr., 2 m., 1 l. | 3 | 16.5 | 325 | 172 |
| 1st cl. Cr. | Crescent | S. shd. | 7700 360 0 60 | 0 23 9 | 2 | 12,000 | Portsmouth Penn . | 1892 | 383,068 | 6 | 5-1 | 6 | 5-1 | 5-1 | 1 9-2-in., 12 6-in. Q.F., 12 6-pr., 53-pr., 7 m., 2 l. (2 sub.) | 4 | 19.7 | 850 | 560 |
| 3rd cl. Cr. | Curacoa | S. shd. | 2380 225 0 44 | 619 3 | 1 | 2000 | Glasgow (Fairfield) Humphrys | 1878 | 112,931 | .. | .. | .. | .. | .. | 4 6-in., 8 5-in., 1 3-pr., Q.F., 9 m., 2 l. | 2 | 13.0 | 470 | 265 |
| G. V. | Curlew | S. | 950 195 0 28 | 0 10 6 | 2 | 1200 | Devonport Penn . | 1885 | 49,963 | .. | .. | .. | .. | .. | 1 6-in. 3 5-in., 7 light Q.F. and m. | 1 | 14.5 | 250 | 103 |
| Sloop | Daphne | C. | 1140 195 0 28 | 0 11 6 | 2 | 2000 | Sheerness Greenock F'ndry Co. | 1888 | 57,600 | .. | .. | .. | .. | .. | 8 5-in., 8 m. | .. | 14.0 | 160 | 138 |
| 1st cl. Cr. | Diadem | S. shd. | 11,000 435 0 39 | 0 26 0 | 2 | 16,500 | (Fairfield) Fairfield . | 1896 | 550,127 | 4½-2 | 4-2½ | 4½-2 | 4½-2 | 4-2½ | 16 6-in. Q.F., 14 12-pr., 11 light Q.F. and m. (2 sub.) | 3 | 20.5 | 1000 | 600 |
| 2nd cl. Cr. | Diana | S. shd. | 5600 350 0 54 | 0 21 0 | 2 | 9600 | (Fairfield) Fairfield . | 1895 | 249,332 | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. |
| " | Dido | S. shd. | 5600 350 0 54 | 0 21 0 | 2 | 9600 | Glasgow London and Glasgow Co. | 1896 | 252,278 | 3 | 2½ | 3 | 2½ | 2½ | 5 6-in. Q.F., 6 4-7-in., 1 12 pr., 11 smaller (2 sub.) Q.F. and m. | 3 | 19.5 | 550 | 470 |
| " | Doris | S. shd. | 5600 350 0 54 | 0 21 0 | 2 | 9600 | Barrow . | 1896 | 254,029 | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. |
| T. G. B. | Dryad | S. | 1670 250 0 30 | 6 9 0 | 2 | 3500 | Chatham Maudslay . | 1893 | 73,491 | 2 | .. | .. | .. | .. | 2 4-7-in. Q.F., 4 6-pr. | 3 | 19.0 | 100 | 120 |

a Includes Gun Mountings, &c.

GREAT BRITAIN.—Cruising Ships, &c.—continued.

284

| Class. | NAME. | Material of Hull. | Displacement. | Length. | Beam. | Draught. | Propellers. | Indicated Horse Power. | Where Built. | Maker of Engines. | Date of Launch. | Cost. | Armour. | Armament. | Speed. | Normal Coal Supply. | Complement. |
|---------------|------------|-------------------|---------------|---------|-------|----------|-------------|------------------------|--------------|-------------------|-----------------|---------|---------|--|--------|---------------------|-------------|
| 1st cl. G. B. | Dwarf | S. | 700 | 180 | 0 33 | 0 8 | 0 | 2 | 1300 | Glasgow | 1898 | 51,139 | in. | 2 4-in. Q.F., 4 12-pr. | 13.5 | 50 | 85 |
| 2nd cl. Cr. | Eclipse | S. shd. | 5600 | 350 | 0 53 | 0 20 | 3 | 2 | 9600 | Portsmouth | 1894 | 279,345 | 3 | 5 6-in. Q.F., 6 4-7-in., and 15 smaller, 4 M., 1 12-pr. boat. | 19.5 | 550 | 477 |
| 1st cl. Cr. | Edgar | S. | 7350 | 360 | 0 60 | 0 23 | 9 | 2 | 12,000 | Devonport | 1890 | 401,083 | 6 | 2 9-2-in., 10 6-in. Q.F., 12 6-pr., 5 3-pr., 7 M., 2 1. | 20.5 | 850 | 544 |
| 2nd cl. Cr. | Encounter | S. | 9800 | 355 | 0 56 | 0 21 | 3 | 2 | 12,500 | Devonport | 1891 | 350,459 | 6 | 2 9-2-in., 10 6-in. Q.F., 12 6-pr., 5 3-pr., 7 M., 2 1. | 20.5 | 850 | 544 |
| 1st cl. Cr. | Endymion | S. | 7350 | 360 | 0 60 | 0 23 | 9 | 2 | 12,000 | Hull | 1891 | 350,459 | 6 | 2 9-2-in., 10 6-in. Q.F., 12 6-pr., 5 3-pr., 7 M., 2 1. | 20.5 | 850 | 544 |
| Sloop | Egeria | C. | 940 | 160 | 0 31 | 4 14 | 3 | 1 | 700 | Pembroke | 1873 | 42,882 | .. | 4 20-pr., 2 M., 1 1. | 11.3 | 100 | 122 |
| " | Espiègle | S. shd. | 1070 | 185 | 0 33 | 0 11 | 3 | 2 | 1400 | Sheerness | 1893 | 241,819 | .. | 6 4-in. Q.F., 4 3-pr. | 13.25 | 160 | 160 |
| 1st cl. Cr. | Europa | S. shd. | 11,000 | 435 | 0 69 | 0 23 | 0 | 2 | 16,500 | Clydebank | 1897 | 561,126 | 4 1-2 | 16 6-in. Q.F., 14 12-pr., 11 light Q.F. and (2 sub.) Machine Guns. | 20.5 | 1000 | 600 |
| Sloop | Fantôme | S. shd. | 1070 | 185 | 0 33 | 0 11 | 3 | 2 | 1400 | Sheerness | 1893 | 241,819 | .. | 6 4-in. Q.F., 4 3-pr. | 13.25 | 160 | 160 |
| 3rd cl. Cr. | Fearless | S. | 1580 | 220 | 0 34 | 3 14 | 6 | 2 | 3200 | Barrow | 1886 | 87,452 | .. | 4 4-7-in. Q.F., 8 3-pr., 2 M., 1 1. | 16.7 | 450 | 147 |
| 2nd cl. G. B. | Firebrand. | C. | 455 | 125 | 0 23 | 6 10 | 0 | 1 | 360 | Glasgow | 1877 | 22,800 | .. | 2 5-in., 2 4-in., 2 M. | 10.17 | 40 | 61 |
| 2nd cl. Cr. | Flora | S. shd. | 4360 | 320 | 0 49 | 6 19 | 0 | 2 | 9000 | Pembroke | 1893 | 241,819 | 2 | 2 6-in. Q.F., 8 4-7-in., 8 6-pr., 1 3-pr., 4 M., 1 1. | 19.5 | 400 | 312 |
| " | Forté. | S. shd. | 4360 | 320 | 0 49 | 6 19 | 0 | 2 | 9000 | Chatham | 1893 | 244,078 | 2 | 2 6-in. Q.F., 8 4-7-in., 8 6-pr., 1 3-pr., 4 M., 1 1. | 19.5 | 400 | 312 |
| " | Fox | S. shd. | 4360 | 320 | 0 49 | 6 19 | 0 | 2 | 9000 | Portsmouth | 1893 | 244,078 | 2 | 2 6-in. Q.F., 8 4-7-in., 8 6-pr., 1 3-pr., 4 M., 1 1. | 19.5 | 400 | 312 |
| " | Forth | S. | 4050 | 300 | 0 46 | 0 20 | 0 | 2 | 5700 | Pembroke | 1886 | 201,952 | 2 | 2 6-in. Q.F., 8 4-7-in., 8 6-pr., 1 3-pr., 4 M., 1 1. | 16.8 | 900 | 326 |

| | | | | | | | | | | | | | | | | | | |
|---------------|-------------|---------|------|-----|------|------|-------|---|--------|------------|------|---------|----|-------|---|-------|-------|-----|
| 2nd cl. Cr. | Furious | S. shd. | 5800 | 320 | 0 57 | 6 21 | 0 | 2 | 10,000 | Devonport | 1896 | 280,772 | 3 | 1-2 | 4 6-in. Q.F., 6 4-7 in., 9 12-pr., 3 3-pr., 1 12-pr. boat, 5 M. | 19.0 | 500 | 430 |
| " | Gladiator. | S. shd. | 5750 | 320 | 0 57 | 6 21 | 0 | 2 | 10,000 | Portsmouth | 1896 | 287,642 | 6 | 5-1 | 2 9-2-in., 10 6-in. Q.F., 12 6-pr., 5 3-pr., 7 M., 2 1. | 19.7 | 850 | 544 |
| 1st cl. Cr. | Gibraltar. | S. shd. | 7700 | 360 | 0 60 | 0 23 | 9 | 2 | 12,000 | Glasgow | 1892 | 347,634 | 2 | .. | 2 4-7-in. Q.F., 4 3-pr. | 19.0 | 100 | 91 |
| T. G. B. | Gleaner | S. | 735 | 230 | 0 27 | 0 8 | 3 | 2 | 3600 | Sheerness | 1890 | 63,798 | .. | .. | 6 4-in., 2 3-pr. Q.F., 2 M. | 19.0 | 105 | 76 |
| " | Gossamer. | S. | 735 | 230 | 0 27 | 0 8 | 3 | 2 | 3600 | Sheerness | 1890 | 54,490 | 6 | 5-1 | 2 9-2-in., 10 6-in. Q.F., 12 6-pr., 5 3-pr., 7 M., 2 1. | 20.0 | 850 | 560 |
| 1st cl. G. B. | Goldfinch. | C. | 805 | 165 | 0 31 | 0 11 | 7 1/2 | 1 | 1200 | Sheerness | 1889 | 40,889 | .. | .. | 1 4-in., 6 3-pr. Q.F. | 17.0 | 80 | 67 |
| 1st cl. Cr. | Grafton | S. | 7350 | 360 | 0 60 | 0 23 | 9 | 2 | 12,000 | Blackwall | 1892 | 351,851 | 6 | 5-1 | 2 9-2-in., 10 6-in. Q.F., 12 6-pr., 5 3-pr., 7 M., 2 1. | 20.0 | 850 | 560 |
| T. G. B. | Grasshopper | S. | 525 | 200 | 0 23 | 0 8 | 9 | 2 | 2700 | Sheerness | 1887 | 34,065 | .. | .. | 1 4-in., 6 3-pr. Q.F. | 17.0 | 80 | 67 |
| " | Haleyon | S. | 1070 | 250 | 0 30 | 6 9 | 0 | 2 | 3500 | Devonport | 1894 | 75,091 | 2 | .. | 2 4-7-in. Q.F., 4 6-pr. | 19.0 | 100 | 120 |
| " | Harrier | S. | 1070 | 250 | 0 30 | 6 9 | 0 | 2 | 3500 | Devonport | 1894 | 73,428 | 6 | 5-1 | 2 9-2-in., 10 6-in. Q.F., 12 6-pr., 5 3-pr., 7 M., 2 1. | 20.0 | 850 | 544 |
| 1st cl. Cr. | Hawke | S. | 7350 | 360 | 0 60 | 0 23 | 9 | 2 | 12,000 | Chatham | 1891 | 365,491 | 2 | .. | 2 4-7-in. Q.F., 4 6-pr. | 19.0 | 100 | 120 |
| T. G. B. | Hazard | S. | 1070 | 250 | 0 30 | 6 9 | 0 | 2 | 3500 | Pembroke | 1894 | 74,076 | 2 | .. | 2 4-7-in. Q.F., 4 6-pr. | 19.0 | 100 | 120 |
| " | Hebe | S. | 810 | 230 | 0 27 | 0 8 | 9 | 2 | 3566 | Sheerness | 1892 | 73,433 | 2 | .. | 2 4-7-in. Q.F., 4 6-pr. | 19.25 | 100 | 91 |
| T. D. S. | Hecla | I. | 6400 | 391 | 7 38 | 9 24 | 3 | 1 | 2400 | Belfast | 1878 | 126,190 | .. | .. | 4 7-5-in., 14 M. | 13.0 | 2,200 | 277 |
| 2nd cl. Cr. | Hermes | S. shd. | 5600 | 350 | 0 54 | 0 20 | 6 | 2 | 10,000 | Fairfield | 1898 | 278,349 | 3 | 1 1/3 | 11 6-in. Q.F., 15 smaller Q.F. | 20.0 | 600 | 477 |
| " | Highflyer | S. shd. | 5600 | 350 | 0 54 | 0 20 | 6 | 2 | 10,000 | Fairfield | 1898 | 278,186 | 2 | 2-1 | 2 6-in. Q.F., 8 4-7-in., 8 6-pr., 1 3-pr., 4 M., 1 1. | 19.5 | 400 | 312 |
| " | Hyacinth | S. shd. | 5600 | 350 | 0 54 | 0 20 | 6 | 2 | 10,000 | Glasgow | 1898 | 282,761 | 2 | .. | .. | .. | .. | .. |
| " | Hermione | S. shd. | 4360 | 320 | 0 49 | 6 19 | 0 | 2 | 9000 | Devonport | 1893 | 223,267 | 2 | .. | .. | .. | .. | .. |

† Details not yet complete.

‡ Includes Gun Mountings, &c.

285

| Class | NAME. | Material of Hull. | Displacement. | Length. | Beam. | Draught. | Propellers. | Indicated Horse-Power. | Where Built. | Maker of Engines. | Date of Launch. | Cost. | Armour. | | Armament. | | Speed. | Normal Coal Supply. | Complement. | |
|---------------|------------------------|-------------------|---------------|---------|-------|----------|-------------|------------------------|--------------|-------------------|----------------------|-------|---------------|-------|-----------|---|--------|---------------------|-------------|-----|
| | | | | | | | | | | | | | Gun Position. | Deck. | Guns. | Torpedo Tubes. | | | | |
| 2nd cl. Cr. | Mersey | S. | 4050 | 300 | 46 | 19 | 6 | 2 | 6000 | Chatham. | Humphrys. | 1885 | 154,000 | in. 4 | in. 3-2 | 2 15-ton, 10 6-in. Q.F., 8 6-pr., 8 3-pr., 5 M., 2 L. | 4 | knots. 17·3 | 900 | 327 |
| 3rd cl. Cr. | Mildura (Australia) | S. | 2575 | 265 | 041 | 015 | 6 | 2 | 7500 | Elswick. | Hawthorn. | 1889 | 116,062 | 2 | 2-1 | 8 4·7-in. Q.F., 8 3-pr., 4 M., 1 L. | 4 | 19·0 | 300 | 217 |
| 2nd cl. Cr. | Minerva | S. shd. | 5600 | 350 | 053 | 020 | 6 | 2 | 9600 | Chatham. | Chatham. | 1895 | 244,046 | 3 | 1½-3 | 5 6-in. Q.F., 6 4·7-in., 9 12-pr., 1 L. smaller (2 sub.) Q.F., and M. | 3 | 20·3 | 550 | 437 |
| 3rd cl. Cr. | Mohawk | S. | 1770 | 225 | 036 | 014 | 6 | 2 | 3500 | Glasgow. | Thomson. | 1886 | 87,583 | .. | .. | 6 6-in. Q.F., 8 3-pr., 2 M., 1 L. | 3 | 16·5 | 475 | 172 |
| Sloop | Mutine | S. | 930 | 180 | 033 | 011 | 6 | 2 | 1400 | Laird | Laird | Bldg. | 63,204 | .. | .. | 6 4-in. Q.F., 4 3-pr. | .. | 13·25 | 130 | 130 |
| 2nd cl. Cr. | Naiad | S. | 3400 | 300 | 043 | 016 | 6 | 2 | 9000 | Barrow | Barrow | 1890 | 171,445 | 2 | 2-1 | 2 6-in. Q.F., 6 4·7-in., 8 6-pr., 1 3-pr., 4 M., 1 L. | 4 | 20·0 | 400 | 273 |
| 1st cl. Cr. | Niobe | S. shd. | 11,000 | 435 | 069 | 026 | 0 | 2 | 16,500 | Barrow | Vickers | 1897 | 552,692 | 4½-2 | 4-2½ | 16 6-in. Q.F., 14 12-pr., 1 L. light Q.F., and M. (2 sub.) | 3 | 20·5 | 1000 | 600 |
| Sloop | Nymphe | C. | 1140 | 195 | 028 | 012 | 6 | 1 | 2000 | Portsmouth | Greenock Foundry Co. | 1888 | 57,600 | .. | .. | 8 5-in., 8 M. | .. | 14·0 | 160 | 138 |
| T. G. B. | Niger | S. | 810 | 230 | 027 | 08 | 9 | 2 | 3784 | Barrow | Barrow | 1892 | 48,177 | 2 | .. | 2 4·7-in. Q.F., 4 3-pr. | 3 | 19·25 | 100 | 91 |
| Sloop | Odin | S. shd. | 1070 | 185 | 033 | 011 | 3 | 2 | 1400 | Sheerness | Devonport. | Bldg. | † | .. | .. | 6 4-in. Q.F., 4 3-pr. | .. | 13·25 | 160 | 160 |
| T. G. B. | Onyx | S. | 810 | 230 | 027 | 08 | 9 | 2 | 3548 | Birkenhead | Laird | 1892 | 53,961 | 2 | .. | 2 4·7-in. Q.F., 4 3-pr. | 3 | 19·25 | 100 | 91 |
| 3rd cl. Cr. | Pallas | S. | 2575 | 265 | 041 | 015 | 6 | 2 | 7610 | Portsmouth | Hawthorn. | 1890 | 148,828 | 2 | 2-1 | 8 4·7-in. Q.F., 8 3-pr., 4 M., 1 L. | 4 | 19·25 | 300 | 217 |
| " | Pearl | S. | 2575 | 265 | 041 | 015 | 6 | 2 | 7500 | Pembroke | Earle | 1888 | 151,693 | .. | .. | 6 4-in., 4 M. | .. | 13·25 | 105 | 76 |
| 1st cl. G. B. | Partridge | C. | 755 | 165 | 030 | 011 | 4 | 1 | 1200 | Devonport | Devonport | 1888 | 37,800 | .. | .. | 6 4-in., 4 M. | .. | 13·25 | 105 | 76 |
| " | Peacock | C. | 755 | 165 | 030 | 011 | 4 | 1 | 1200 | Pembroke | Barrow Co. | 1872 | 37,600 | .. | .. | 6 4-in., 4 M. | .. | 13·25 | 105 | 76 |

| | | | | | | | | | | | | | | | | | | |
|-------------------|------------|---------|------|---------|------|---|---|------|------------|------------|------|---------|----|----|----|----|----|----|
| 3rd cl. Cr. | Pactolus | S. | 2135 | 300 36 | 6 17 | 0 | 2 | 7000 | Elswick. | Penn. | 1897 | 139,736 | .. | .. | .. | .. | .. | .. |
| " | Pandora | S. | 2200 | 305 36 | 9 13 | 6 | 2 | 7000 | Portsmouth | Portsmouth | 1900 | 165,046 | .. | .. | .. | .. | .. | .. |
| " | Pegasus | S. | 2135 | 300 36 | 6 17 | 0 | 2 | 7000 | Jarrow. | Palmer. | 1897 | 135,071 | .. | .. | .. | .. | .. | .. |
| " | Pelorus | S. | 2135 | 300 36 | 6 17 | 0 | 2 | 7000 | Sheerness | Thomson. | 1896 | 164,840 | .. | .. | .. | .. | .. | .. |
| " | Perseus | S. | 2135 | 300 36 | 6 13 | 6 | 2 | 7000 | Hull | Earle. | 1898 | 127,992 | .. | .. | .. | .. | .. | .. |
| " | Pioneer | S. | 2200 | 305 36 | 9 13 | 6 | 2 | 7000 | Chatham. | Fairfield. | 1899 | 149,080 | .. | .. | .. | .. | .. | .. |
| " | Pomone | S. | 2135 | 300 36 | 6 13 | 6 | 2 | 7000 | Sheerness | Penn. | 1897 | 149,568 | .. | .. | .. | .. | .. | .. |
| " | Prometheus | S. | 2135 | 300 36 | 6 13 | 6 | 2 | 7000 | Hull | Earle. | 1898 | 127,975 | .. | .. | .. | .. | .. | .. |
| " | Psyche | S. | 2200 | 305 36 | 9 17 | 6 | 2 | 7000 | Devonport | Devonport | 1898 | 155,563 | .. | .. | .. | .. | .. | .. |
| " | Proserpine | S. | 2135 | 300 36 | 6 17 | 0 | 2 | 7000 | Sheerness | Devonport | 1896 | 159,136 | .. | .. | .. | .. | .. | .. |
| " | Pyramus | S. | 2135 | 300 36 | 6 13 | 6 | 2 | 7000 | Jarrow. | Palmer. | 1898 | 135,096 | .. | .. | .. | .. | .. | .. |
| Sloop (Surveying) | Penguin | C. | 1130 | 170 036 | 0 16 | 1 | 1 | 700 | Glasgow. | Hawthorn. | 1876 | 52,111 | .. | .. | .. | .. | .. | .. |
| 2nd cl. Cr. | Phaeton | S. | 4300 | 300 046 | 0 20 | 6 | 2 | 5000 | Glasgow. | Napier. | 1883 | 145,198 | .. | .. | .. | .. | .. | .. |
| 1st cl. G. B. | Pheasant | C. | 755 | 165 029 | 0 11 | 4 | 1 | 1200 | Devonport | Devonport | 1888 | 37,800 | .. | .. | .. | .. | .. | .. |
| 3rd cl. Cr. | Philomel | S. | 2575 | 265 041 | 0 15 | 6 | 2 | 7500 | Devonport | Earle. | 1890 | 156,102 | .. | .. | .. | .. | .. | .. |
| " | Phoebe | S. | 2575 | 265 041 | 0 15 | 6 | 2 | 7500 | Devonport | Devonport | 1890 | 161,154 | .. | .. | .. | .. | .. | .. |
| Sloop | Phoenix | S. shd. | 1050 | 185 032 | 6 11 | 3 | 2 | 1400 | Devonport | Devonport | 1895 | 63,930 | .. | .. | .. | .. | .. | .. |
| 1st cl. G. B. | Pigeon | C. | 755 | 165 030 | 0 11 | 4 | 1 | 1200 | Pembroke | Barrow. | 1888 | 37,800 | .. | .. | .. | .. | .. | .. |
| " | Pigny | C. | 755 | 165 030 | 0 11 | 4 | 1 | 1200 | Sheerness | Barrow. | 1888 | 37,700 | .. | .. | .. | .. | .. | .. |
| " | Plover | C. | 755 | 165 030 | 0 11 | 4 | 1 | 1200 | Pembroke | Barrow. | 1888 | 37,700 | .. | .. | .. | .. | .. | .. |
| 2nd cl. Cr. | Pique | S. shd. | 3300 | 300 043 | 8 17 | 6 | 2 | 9000 | Jarrow. | Palmer. | 1890 | 184,108 | .. | .. | .. | .. | .. | .. |
| T. Ram | Polypheus | S. | 2640 | 240 040 | 0 20 | 0 | 2 | 5500 | Chatham. | Humphrys. | 1881 | 174,450 | .. | .. | .. | .. | .. | .. |

* Includes Gun Mountings, &c.

† Details not yet complete.

| Class. | NAME. | Material of Hull. | Displacement. | Length. | Beam. | Draft. | Propellers. | Indicated Horse-Power. | Where Built. | Maker of Engines. | Date of Launch. | Cost. | Armour. | | Armament. | | Speed. | Normal Coal Supply. | Complement. |
|---|-------------|-------------------|---------------|-------------------------|-----------------------|----------------|-------------|-------------------------------|--------------|-------------------|-----------------|--------|---------------|-------|--|----------------|----------------|---------------------|-------------|
| | | | | | | | | | | | | | Gun Position. | Deck. | Guns. | Torpedo Tubes. | | | |
| 3rd cl. Cr. | Porpoise | S. | tons. 1770 | ft. in. ft. 225 0 36 | ft. in. ft. 0 14 6 | in. no. 6 2 | 2 | 3500 | Glasgow | Thomson | 1886 | 87,583 | in. | in. | 66-in. Q.F., 8 3-pr., 2 M., 1 1. | 3 | knots. 16.5 | tons. 475 | 172 |
| 1st cl. Cr. | Powerful | S. shd. | 14,200 | 500 0 71 | 0 29 0 | 2 | 25,000 | B Barrow | Barrow | 1895 | 674,879 | 6 | 6 | 3-6 | 2 9-2-in., 12 6-in. Q.F., 18 12-pr., 12 3-pr., 9 M., 2 12-pr. boat | 4 | 22.1 | 1500* | 840 |
| 3rd cl. Cr. | Pylades | C. | 1420 | 200 0 38 | 0 15 9 | 1 | 1400 | Sheerness Laird | 1884 | 62,000 | 1884 | 62,000 | .. | 1 1/4 | 14 5-in., 8 M., 1 1. | .. | 12.6 | 400 | 170 |
| 3rd cl. Cr. | Racoon | S. | 1770 | 225 0 36 | 0 13 6 | 2 | 4500 | Devonport Harland | 1887 | 91,606 | 1887 | 91,606 | .. | .. | 6 6-in. Q.F., 8 3-pr., 2 M., 1 1. | 3 | 17.5 | 475 | 176 |
| 2nd cl. Cr. | Rainbow | S. shd. | 3600 | 300 0 43 | 8 17 6 | 2 | 9681 | Jarrow | Palmer | 1891 | 184,086 | 2 | 2 | 2-1 | 2 6-in. Q.F., 6 4 7-in., 8 6-pr., 1 3-pr., 4 M., 1 1. | 4 | 19.7 | 400 | 273 |
| 2nd cl. G. Ves. (Surveying Service.) | Rambler | C. | 833 | 157 0 29 | 6 13 7 | 1 | 650 | Glasgow. Elder (Fairfield) | 1886 | 37,038 | 1886 | 37,038 | .. | .. | 2 20-pr., 1 M., 1 1. | .. | 10.66 | 40 | 160 |
| 1st cl. G. B. | Rattler | C. | 715 | 165 0 29 | 0 11 0 | 1 | 1200 | Elswick | Hawthorn | 1886 | 38,734 | .. | .. | .. | 6 4-in., 4 M. | .. | 13.6 | 105 | 76 |
| T. G. B. | Rattlesnake | S. | 550 | 200 0 23 | 0 8 0 | 2 | 2700 | Birkenhead Laird | 1886 | 35,425 | 1886 | 35,425 | .. | .. | 1 4-in., 6 3-pr. Q.F. | 4 | 18.5 | 100 | 67 |

| | | | | | | | | | | | | | | | | | | | |
|---------------|---------------------------|---------|------|----------|------------|---|--------|----------------------|----------|---------|---------|---------|----|-------|---|---------------|-------|-----|-----|
| 2nd cl. G. B. | Raven | C. | 465 | 125 0 23 | 6 10 0 | 1 | 360 | Poplar | Rennie | 1882 | 21,050 | .. | .. | .. | 2 64-pr. M.L.R., 2 20- pr., 2 M. | .. | 9.5 | 40 | 62 |
| 1st cl. G. B. | Redbreast | C. | 805 | 165 0 31 | 0 11 7 1/2 | 1 | 1200 | Pembroke Earle | 1888 | 38,700 | 1888 | 38,700 | .. | .. | 6 4-in., 4 M. | .. | 13.0 | 105 | 76 |
| " | Redpole | C. | 461 | 125 0 23 | 6 10 0 | 1 | 360 | Pembroke Maudslay | 1880 | 22,200 | 1880 | 22,200 | .. | .. | 2 20-cwt., 2 M. | .. | 9.68 | 40 | .. |
| 2nd cl. G. B. | Redwing | C. | 810 | 230 0 27 | 0 8 9 | 2 | 3500 | Birkenhead Laird | 1892 | 53,848 | 1892 | 53,848 | 2 | .. | 2 4 7 in. Q.F., 4 3-pr. | 3 | 19.25 | 100 | 91 |
| T. G. B. | Renard | S. | 3600 | 300 0 43 | 8 17 6 | 2 | 9000 | Jarrow | Palmer | 1891 | 183,975 | 2 | 2 | 2-1 | 2 6-in. Q.F., 6 4 7-in., 8 6-pr., 1 3-pr., 4 M., 1 1. | 4 | 19.75 | 400 | 275 |
| 2nd cl. Cr. | Retribution | S. shd. | 980 | 180 0 33 | 0 11 6 | 2 | 1400 | Laird | Laird | 1889 | 63,180 | .. | .. | .. | 6 4-in. Q.F., 4 3-pr. | .. | 13.25 | 180 | 180 |
| Sloop | Rinaldo | S. | 2575 | 265 0 41 | 0 15 6 | 2 | 7500 | Glasgow | Thomson | 1890 | 128,076 | 2 | 2 | 2-1 | 8 4 7-in. Q.F., 8 3-pr. Q.F., 4 M., 1 1. | 4 | 19.0 | 300 | 216 |
| 3rd cl. Cr. | Ringarooma (Australia) | S. | 805 | 165 0 31 | 5 11 7 1/2 | 1 | 1200 | Devonport Devonport | 1889 | 39,753 | 1889 | 39,753 | .. | .. | 6 4-in., 2 3-pr. Q.F., 2 M. | .. | 13.0 | 105 | 76 |
| 1st cl. G. B. | Ringdove | C. | 7700 | 360 0 60 | 0 27 9 | 2 | 12,000 | Portsmouth Maudslay | 1891 | 402,414 | 1891 | 402,414 | 6 | 5-1 | 1 9-2-in., 12 6-in. Q.F., 12 6-pr., 5 3-pr., 7 M., 2 1. | 4 (2 sub.) | 19.7 | 850 | 567 |
| 1st cl. Cr. | Royal Arthur | S. shd. | 980 | 180 0 33 | 0 11 6 | 2 | 1400 | Sheerness Government | 1898 | 77,962 | 1898 | 77,962 | .. | .. | 6 4-in., 4 3-pr. Q.F. | .. | 13.25 | 130 | 130 |
| Sloop | Rosario | S. shd. | 1420 | 200 0 38 | 0 15 9 | 1 | 1400 | Devonport Maudslay | 1883 | 68,173 | 1883 | 68,173 | .. | 1 1/2 | 2 6-in., 10 5-in., 4 M., 1 1. | .. | 12.6 | 400 | 171 |
| 3rd cl. Cr. | Royalist | C. | 7700 | 360 0 60 | 8 23 9 | 2 | 12,000 | Hull | Maudslay | 1892 | 377,204 | 6 | 6 | 5-1 | 2 9-2-in., 10 6-in. Q.F., 12 6-pr., 5 3-pr., 7 M., 2 1. | 4 (2 sub.) | 19.7 | 850 | 559 |
| 1st cl. Cr. | St. George. | S. shd. | 735 | 230 0 27 | 0 8 3 | 2 | 3500 | Chatham | Maudslay | 1889 | 57,911 | 2 | 2 | .. | 2 4 7-in. Q.F., 4 3-pr. Q.F. | 3 | 20.0 | 100 | 91 |
| T. G. B. | Salamander | S. | 525 | 200 0 23 | 0 8 9 | 2 | 2700 | Devonport Maudslay | 1887 | 36,167 | 1887 | 36,167 | .. | .. | 1 4-in., 6 3-pr. Q.F. | 4 | 19.0 | 80 | 67 |

* Includes Gun Mountings, &c.

* Banker capacity, 3000.

| Class. | NAME. | Material of Hull. | Displacement. | Length. | Beam. | Draft. | Propellers. | Indicated Horse-Power. | Where Built. | Maker of Engines. | Date of Launch. | Cost. | Armour. | | Armament. | | Speed. | Normal Coal Supply. | Complement. |
|-------------|--------------|-------------------|---------------|----------|--------|--------|-------------|------------------------|--------------|-------------------|-----------------|---------|---------------|---------|---|----------------|----------|---------------------|-------------|
| | | | | | | | | | | | | | Gun Position. | Deck. | Guns. | Torpedo Tubes. | | | |
| 2nd cl. Cr. | Sappho | S. | 3400 | 300 0 49 | 0 16 6 | 2 | 2 | 9861 | Poplar | Penn. | 1891 | 171,853 | in. 2 | in. 2-1 | 2 6-in. Q.F., 6 4-7-in., 8 6-pr., 1 3-pr., 4 M., 1 L. | 4 | 4 | 400 | 273 |
| " | Scout. | S. | 1580 | 220 0 34 | 0 14 6 | 2 | 2 | 3200 | Glasgow | Thomson | 1885 | 87,516 | .. | .. | 4 4-7-in. Q.F., 8 3-pr., 2 M., 1 L. | 3 | 3 | 450 | 147 |
| 2nd cl. Cr. | Seylla | S. | 3400 | 300 0 43 | 0 16 6 | 2 | 2 | 9280 | Poplar | Penn. | 1892 | 171,593 | 2 | 2-1 | 2 6-in. Q.F., 6 4-7-in., 8 6-pr., 1 3-pr., 4 M., 1 L. | 4 | (1 sub.) | 400 | 273 |
| T. G. B. | Seagull | S. | 735 | 230 0 27 | 0 8 3 | 2 | 2 | 3500 | Chatham. | Maudslay | 1889 | 56,922 | 2 | .. | 2 4-7-in., 4 3-pr. Q.F. | 3 | 3 | 100 | 91 |
| " | Sharpshooter | S. | 735 | 230 0 27 | 0 8 3 | 2 | 2 | 3500 | Devonp't | Bellis | 1888 | 50,029 | | | | | | | |
| Sloop | Shearwater | S. shd. | 980 | 180 0 33 | 0 11 6 | 2 | 2 | 1400 | Sheerness | Thames Co. Eng. | 1889 | 65,400 | .. | .. | 6 4-in., 4 3-pr. Q.F. | .. | .. | 130 | 130 |
| T. G. B. | Sheldrake | S. | 735 | 230 0 27 | 0 8 3 | 2 | 2 | 3500 | Chatham. | Maudslay | 1889 | 57,800 | 2 | .. | 2 4-7-in., 4 3-pr. Q.F. | 3 | 3 | 100 | 91 |
| " | Skipjack | S. | 735 | 230 0 27 | 0 8 3 | 2 | 2 | 3500 | Chatham. | Laird | 1889 | 59,531 | 2 | .. | 2 4-7-in., 4 3-pr. Q.F. | 3 | 3 | 100 | 91 |
| " | Spanker* | S. | 735 | 230 0 27 | 0 8 3 | 2 | 2 | 3500 | Devonp't | Bellis | 1889 | 50,000 | | | | | | | |
| " | Speedwell. | S. | 735 | 230 0 27 | 0 8 3 | 2 | 2 | 3500 | Devonp't | Laird | 1889 | 52,000 | | | | | | | |
| 1st cl. Cr. | Spartiate | S. shd. | 11,000 | 435 0 69 | 0 26 0 | 2 | 2 | 18,000 | Pembroke | Maudslay | 1898 | 569,841 | | | | | | | |
| 2nd cl. Cr. | Severn | S. | 4050 | 300 0 46 | 0 19 6 | 2 | 2 | 6000 | Chatham. | Humphrys | 1885 | 212,621 | 4 | 3-2 | 2 8-in., 10 6-in. Q.F., 3 6-pr., 2 3-pr., 10 M., 2 L. | .. | .. | 900 | 327 |

| | | | | | | | | | | | | | | | | | | | |
|---------------|--------------------------|---------|--------|----------|------------|---|---|--------|-----------|------------------------|------|---------|----|---------|---|----|----------|------|-----|
| 2nd cl. Cr. | Sirius | S. shd. | 3600 | 300 0 43 | 8 17 6 | 2 | 2 | 9000 | Elswick | Maudslay | 1890 | 186,649 | 2 | 2-1 | 2 6-in. Q.F., 6 4-7-in., 8 6-pr., 1 3-pr., 4 M., 1 L. | 4 | 4 | 400 | .. |
| " | Spartan | S. shd. | 3600 | 300 0 43 | 8 17 6 | 2 | 2 | 9000 | Elswick | Maudslay | 1891 | 186,351 | .. | .. | 6 4-in., 2 3-pr. Q.F., 2 M. | .. | .. | 105 | 76 |
| 1st cl. G. B. | Sparrow | C. | 805 | 165 0 31 | 0 11 7 1/2 | 1 | 1 | 1200 | Greenock | Greenock | 1889 | 39,000 | 2 | 2 | 2 4-7-in. Q.F., 4 3-pr. | 3 | 3 | 100 | 91 |
| T. G. B. | Speedy | S. | 810 | 230 0 27 | 0 8 9 | 2 | 2 | 4703 | Chiswick | Thornycroft | 1893 | 58,927 | 2 | 2 | 1 4-in., 6 3-pr. Q.F. | 4 | 4 | 80 | 67 |
| " | Spider | S. | 525 | 200 0 23 | 0 8 9 | 2 | 2 | 2700 | Devonp't | Maudslay | 1887 | 36,300 | .. | .. | 2 64-pr. M.L.R., 2 20-pr., 2 M., 2 L. | .. | .. | 40 | 61 |
| 2nd cl. G. B. | Starling | C. | 465 | 125 0 23 | 6 10 0 | 1 | 1 | 360 | Poplar | Rennie | 1882 | 21,100 | .. | .. | 1 M., 2 L. | .. | .. | 40 | .. |
| " | Stork. | C. | 465 | 125 0 23 | 6 10 0 | 1 | 1 | 360 | Poplar | Rennie | 1882 | 21,150 | .. | .. | 4 5-in., 4 6-pr. Q.F., 2 M. | .. | .. | 400 | 114 |
| D. V. | Surprise | S. | 1650 | 250 0 32 | 6 14 0 | 2 | 2 | 3000 | Jarrow | Palmer | 1885 | 278,764 | .. | .. | 8 5-in., 8 M., 1 L. | .. | .. | 280 | 135 |
| Sloop | Swallow | C. | 1130 | 195 0 28 | 0 11 6 | 2 | 2 | 1500 | Sheerness | Rennie | 1885 | 59,797 | .. | .. | 2 90-cwt. M.L.R., 4 6-pr. Q.F., 2 M. | .. | .. | 180 | 92 |
| 2nd cl. G. V. | Swift | C. | 756 | 165 0 29 | 0 10 11 | 2 | 2 | 870 | Blackwall | Rennie | 1879 | 34,670 | .. | .. | 5 6-in. Q.F., 6 4-7-in., 9 12-pr., 1 3-pr., 4 M., 1 L. | 3 | 3 | 550 | 433 |
| 2nd cl. Cr. | Talbot | S. | 5600 | 350 0 53 | 6 21 0 | 2 | 2 | 9600 | Devonp't | Devonport | 1895 | 273,856 | 3 | 1 1/2-3 | 6 6-in. Q.F., 6 4-7-in., 9 12-pr., 1 3-pr., 4 M., 1 L. | 3 | (2 sub.) | 325 | 177 |
| 3rd cl. Cr. | Tartar | S. shd. | 1770 | 225 0 36 | 0 14 3 1/2 | 2 | 2 | 3500 | Glasgow | Thomson | 1886 | 87,583 | .. | .. | 6 6-in. Q.F., 8 3-pr., 2 M., 1 L. | 3 | 3 | 300 | 212 |
| " | Tauranga. (Australia) | S. | 2575 | 265 0 41 | 0 15 6 | 2 | 2 | 7500 | Glasgow | Thomson | 1889 | 128,101 | 2 | 2-1 | 8 4-7-in. Q.F., 8 3-pr. Q.F., 4 M., 1 L. | 4 | 4 | 300 | 212 |
| 2nd cl. Cr. | Terpsichore | S. | 3400 | 300 0 43 | 0 16 6 | 2 | 2 | 9000 | Glasgow | Thomson | 1890 | 173,341 | 2 | 2-1 | 2 6-in. Q.F., 6 4-7-in., 8 6-pr., 1 3-pr., 9 M., 1 L. | 4 | 4 | 400 | 275 |
| 1st cl. Cr. | Terrible | S. shd. | 14,200 | 500 0 71 | 0 27 0 | 2 | 2 | 25,000 | Glasgow | Thomson | 1895 | 681,419 | 6 | 3-6 | 2 9-2-in., 12 6-in. Q.F., 18 12-pr., 12 3-pr., 9 M., 2 12-pr. boat. | 4 | 4 | 3000 | 810 |
| 2nd cl. Cr. | Thames | S. | 4050 | 300 0 46 | 0 19 6 | 2 | 2 | 5700 | Pembroke | Penn | 1885 | 205,452 | 4 | 3-2 | 2 8-in., 10 6-in. Q.F., 8 6-pr., 8 3-pr., 6 M., 2 L. | 2 | 2 | 900 | 326 |
| 1st cl. G. B. | Thistle | S. | 700 | 180 0 33 | 0 8 0 | 2 | 2 | 1300 | Glasgow | London and Glasgow Co. | Eng. | 51,105 | .. | .. | 2 4-in. Q.F., 4 12-pr. | .. | .. | 50 | 85 |
| 1st cl. Cr. | Theseus | S. | 7350 | 360 0 60 | 0 23 9 | 2 | 2 | 12,000 | Blackwall | Maudslay | 1892 | 347,577 | 6 | 5-1 | 2 9-2-in., 10 6-in. Q.F., 12 6-pr., 5 3-pr., 7 M., 2 L. | 4 | (2 sub.) | 850 | 544 |
| 2nd cl. Cr. | Thetis | S. | 3400 | 300 0 43 | 0 16 6 | 2 | 2 | 9000 | Glasgow | Thomson | 1890 | 173,146 | 2 | 2-1 | 2 6-in. Q.F., 6 4-7-in., 8 6-pr., 1 3-pr., 4 M., 1 L. | 4 | 4 | 400 | 2 |
| " | Tribune | S. | 3400 | 300 0 43 | 0 16 6 | 2 | 2 | 9000 | Glasgow | Thomson | 1891 | 173,006 | 2 | 2-1 | 2 6-in. Q.F., 6 4-7-in., 8 6-pr., 1 3-pr., 4 M., 1 L. | 4 | 4 | 400 | 2 |

* Includes Gun Mountings, &c.

GREAT BRITAIN.—Cruising Ships, &c.—continued.

| Class. | NAME. | Material of Hull. | Displacement. | Length. | Beam. | Draught. | Propellers. | Indicated Horse-Power. | Where Built. | Maker of Engines. | Date of Launch. | Armour. | | Armament. | | Speed. | Normal Coal Supply. | Complement. |
|---------------|----------------------|-------------------|---------------|-------------------------|---------|----------|-------------|------------------------|------------------|-------------------|-----------------|----------------|----------|---|----------------|--------|---------------------|-------------|
| | | | | | | | | | | | | Gunn Position. | Deck. | Guns. | Torpedo Tubes. | | | |
| 1st cl. G. B. | Thrush | C. | tons. 805 | ft. in. ft. in. ft. in. | 0 11 7½ | 1 | 1200 | (Greenock F'ndry Co. | Greenock | 1889 | £ 39,000 | in. | in. | 6 4-in., 2 3-pr. Q.F., 2 M. | .. | 13·0 | 105 | 76 |
| Sloop | Torch | S. shd. | 960 | 180 0 32 | 6 11 6 | 1 | 1400 | Sheerness | Sheerness. | 1894 | 60,564 | .. | .. | 6 4-in. Q.F., 4 3-pr., 2 M. | .. | 13·25 | 130 | .. |
| 2nd cl. Cr. | Venus* | S. shd. | 5600 | 350 0 54 | 0 21 2 | 2 | 9600 | Fairfield. | Fairfield. | 1895 | 249,938 | 3 | 2½ | 5 6-in. Q.F., 6 4·7-in., 9 12-pr., 7 3-pr., 4 M., 1 12-pr. boat | 3 | 19·5 | 550 | 470 |
| Sloop | Vestal | S. shd. | 980 | 180 0 33 | 0 11 6 | 2 | 1400 | Sheerness | Government Bldg. | 1896 | 94,301 | .. | .. | 6 4-in., 4 3-pr. Q.F. | .. | 13·25 | 130 | 130 |
| 2nd cl. Cr. | Vindictive | S. | 5800 | 320 0 54 | 0 20 6 | 2 | 10,000 | Chatham | Chatham | 1896 | 290,458 | 3 | 1-2 n.s. | 4 6-in. Q.F., 6 4·7-in., 9 12-pr., 3 3-pr., 1 12-pr. boat, 5 M. | 2 | 19·5 | 500 | 450 |
| T. D. S. | Vulcan | S. | 6620 | 350 0 58 | 0 23 0 | 2 | 12,032 | Portsmouth | Humphrys | 1889 | 370,447 | 2 | 5-2½ | 8 4·7-in. Q.F., 12 3-pr., 16 M., 1 L. | 6 (2 sub.) | 20·0 | 1000 | 433 |
| 3rd cl. Cr. | Wallaroo (Australia) | S. | 2575 | 265 0 41 | 0 15 6 | 2 | 7500 | Elswick | Hawthorn. | 1889 | 115,995 | 2 | 2-1 | 8 4·7-in. Q.F., 8 3-pr., 4 M., 1 L. | 4 | 19·0 | 300 | 218 |
| 1st cl. G. B. | Widgeon | C. | 805 | 165 0 30 | 0 11 7½ | 1 | 1200 | Pembroke | Rennie | 1889 | 39,315 | .. | .. | 6 4-in., 2 3-pr. Q.F., 2 M. | .. | 13·0 | 105 | 76 |

* Venus: trial, 20·1 knots.

River Gunboats.—Herald, Mosquito (1890), 82 tons; Jackdaw, Heron, Robin, Nightingale, Snipe (1897), 85 tons; Woodcock, Woodlark (1897), 122 tons, 2 6-pr., 4 Maxims; 4 recent boats in the Niger Protectorate. Recent Egyptian boats: Melik, Sultan, Sheik, 140 tons, 4 12-pr., 4 Maxims.

Royal Naval Reserved Merchant Cruisers.

| | Name. | Owners | Length. | Breadth. | Draught of Water for the Admiralty List. | Gross Tonnage. | Indicated Horse-Power. | Ocean Speed. |
|--|-------------------|------------------------------|-----------|----------|--|----------------|------------------------|--------------|
| Ships in receipt of an Annual subvention and permitted to fly the blue ensign. | Campania. | Cunard Company | Feet. 610 | Feet. 65 | Feet. 26 | Tons. 12,950 | 30,000 | Knots. 21 |
| | Lucania. | " | 610 | 65 | 26 | 12,950 | 30,000 | 21 |
| | Himalaya. | Peninsular and Oriental Co. | 465½ | 52 | 22½ | 6,898 | 10,000 | 17 |
| | Australia. | " | 465½ | 52 | 22½ | 6,901 | 10,000 | 17 |
| | Victoria. | " | 466 | 52 | 22½ | 6,091 | 7,000 | 16 |
| | Arcadia. | " | 466 | 52 | 22½ | 6,188 | 7,000 | 16 |
| | Majestic. | " | 565 | 58 | 24½ | 9,965 | 16,000 | 20 |
| | Teutonic. | White Star Company | 565 | 58 | 24½ | 9,984 | 16,000 | 20 |
| | Empress of India. | " | 440 | 51 | 24½ | 5,905 | 10,000 | 16 |
| | Empress of China. | Canadian Pacific Railway Co. | 440 | 51 | 24½ | 5,905 | 10,000 | 16 |
| Ships held at the disposition of the Admiralty without subsidy. | Empress of Japan. | " | 440 | 51 | 24½ | 5,905 | 10,000 | 16 |
| | Etruria. | Cunard Company | 501½ | 57 | 26 | 8,120 | 14,500 | 19½ |
| | Umbria. | " | 501½ | 57 | 26 | 8,128 | 14,500 | 19½ |
| | Servia. | " | 515 | 52 | 26 | 7,392 | 10,000 | 16½ |
| | Aurania. | " | 470 | 57 | 27 | 7,269 | 9,500 | 17 |
| | Britannic. | " | 455 | 45 | 25 | 5,004 | 5,200 | 16 |
| | Germanic. | White Star Company | 455 | 45 | 25 | 5,008 | 5,200 | 16 |
| | Cymric. | " | 455 | 45 | 25 | 5,008 | 5,200 | 16 |
| | Britannia. | " | 466 | 52 | 22½ | 12,551 | 6,700 | 16 |
| | Oceana. | Peninsular and Oriental Co. | 466 | 52 | 22½ | 6,525 | 7,000 | 16 |
| | Peninsular. | " | 466 | 52 | 22½ | 6,188 | 6,000 | 16 |
| | Oriental. | " | 410½ | 48 | 22½ | 5,287 | 4,972 | 15 |
| | Valetta. | " | 410½ | 48 | 22½ | 5,284 | 4,972 | 15 |
| | Massilia. | " | 420½ | 45 | 22½ | 4,904 | 5,000 | 15 |
| | Rome. | " | 420½ | 45 | 22½ | 4,902 | 5,000 | 15 |
| | Carthage. | " | 430 | 44½ | 22½ | 5,545 | 5,500 | 15 |
| | Ballarat. | " | 430 | 44½ | 22½ | 4,879 | 5,000 | 15 |
| | Parramatta. | " | 420 | 43 | 22½ | 4,778 | 4,500 | 14 |
| | | " | 420 | 43 | 22½ | 4,756 | 4,500 | 14 |

There are also numerous ships on the Admiralty List complying with Admiralty conditions as to subdivision which have no national tie. They are suitable for receiving an armament, but there is no arrangement with Owners, except the promise of preference for occasional State employment.

GREAT BRITAIN, COLONIES, &c.—Cruising Ships, Gunboats, &c.

| To what Government belonging. | Class of Ship. | Name. | Material of Construction. | Pro-pellers. | Where Built. | When Launched. | Length. | Breadth. | Draught of Water. | Displacement. | Indicated Horse-Power. | Speed. | Coal Stowage. | Armament. |
|-------------------------------|----------------|-----------|---------------------------|---------------|--------------|----------------|---------|----------|-------------------|---------------|------------------------|--------|---------------|--|
| INDIA | T. G. B. | Assaye | Steel | 2 | Elswick | 1891 | 230 0 | 27 0 | 8 3 | 735 | 3,500 | 19.0 | 100 | { 2 4.7-in. Q.F., 4 3-pr. do., 1 f. tn. & 3 l. car. |
| | D. V. | Lawrence. | Steel | Pad. B'kenh'd | | 1886 | 212 2 | 32 2 | 18 3 | 1,154 | 1,277 | 13.5 | 270 | { Four 4-in. B.L.R., 4 6-pr. Q.F., 4 M. |
| | T. G. B. | Plassy | Steel | 2 | Elswick | 1890 | 230 0 | 27 0 | 8 3 | 735 | 3,500 | 19.0 | 100 | { 2 4.7-in. Q.F., 4 3-pr. do., 1 f. tn. & 3 l. car. |
| QUEENSLAND. | Gun-vessel | Gayundah | Steel | 2 | Glasgow | 1884 | 115 0 | 25 0 | 10 0 | 450 | 400 | 10.0 | .. | { One 8-in. 11½-ton; one 6-in. 4-ton; one 3-pr. Q.F.; 2 M. |
| | Gun-vessel | Paluma | Steel | 2 | Glasgow | 1884 | 115 0 | 25 0 | 10 0 | 450 | 340 | 10.0 | .. | { One 8-in. 11½-ton; one 6-in. 4-ton; one 3-pr. Q.F.; 2 M. |
| SOUTH AUSTRALIA. | Cruiser | Protector | Steel | 2 | .. | 1884 | 188 0 | 3 0 | 12 6 | 920 | 1,640 | 14.0 | .. | { One 8-in. 11½-ton; five 6-in. 4-ton; five Gat- lings. |

The five second-class Cruisers, and the two Torpedo-Gunboats of the Australian Auxiliary Squadron, are included in the list of Ships of the Royal Navy, as well as the armour-clads Abyssinia, Cerberus, and Magdala.

ARGENTINE REPUBLIC.—Armoured Ships.

| Class. | NAME. | Material of Hull. | Displacement. | Length. | Beam. | Draught. | Propellers. | Indicated Horse-power. | Where Built. | Date of Launch. | Cost. | Armour. | | | Armament. | | Speed. | Normal Coal Supply. | Complement. |
|----------|------------------|-------------------|---------------|-------------------------|-------|----------|-------------|------------------------|----------------|-----------------|---------|-----------------|--------------------|------------------|--|----------------|----------|---------------------|-------------|
| | | | metric tons. | ft. in. ft. in. ft. in. | | | | | | | £ | Belt. | Battery or Turret. | Deck or Plating. | Guns. | Torpedo Tubes. | knots. | tons. | |
| c.b. | Almirante Brown. | S. | 4267 | 240 0 | 50 0 | 20 6 | 2 | 4500 | Poplar | 1880 | 190,000 | inches. 9 (op.) | inches. 8 (op.) | 1½ | 10 5·9-in. Q.F. (Canet), 4 4·7 in., 2 2·4 in., 2 M. | 2 | 13·75 | 650 | 350 |
| c.d.s.t. | Andes | I. | 1558 | 186 0 | 44 0 | 9 6 | 2 | 750 | Birkenhead | 1875 | 85,600 | 6 | 9 | 1 | 2 11-in., 2 4·7-in., 4 M. | .. | 9·5 | 120 | 120 |
| c.d.s.t. | Plata | I. | 1558 | 186 0 | 44 0 | 9 6 | 2 | 750 | Birkenhead | 1874 | 85,600 | | | | | | | | |
| a.c. | Garibaldi | S. | 6840 | 328 0 | 59 8 | 24 0 | 2 | 13,384 | Sestri Ponente | 1895 | 681,240 | 6 H.S. | 6 H.S. | 1½ | 2 10-in., 10 6-in. Q.F., 6 4·7 in., 10 2·2 in., 10 1·4 in., 2 M.* | .. | 19·9 (t) | 1000† | 500 |
| a.c. | General Belgrano | S. | 7182 | 328 0 | 59 8 | 24 0 | 2 | 13,000 | Leghorn | 1897 | — | 6 H.S. | 6 H.S. | 1½ | 2 10-in., 14 6-in. Q.F., 2 3-in., 10 2·2-in., 8 1·4-in., 2 L., 2 M. sub. | 4 | 20·1 | 1000 | 500 |
| c.d.s.b. | Independencia | S. | 2336 | 230 0 | 44 4 | 13 0 | 2 | 3000 | Birkenhead | 1891 | 176,600 | 8 (op.) | 8 (op.) | 2 | 2 9·4-in., 4 4·7-in. Q.F., 4 3-pr., 4 M. | 2 | 14·4 | 340 | 225 |
| c.d.s.b. | Libertad | S. | 2336 | 230 0 | 44 4 | 13 0 | 2 | 3000 | Birkenhead | 1890 | 176,600 | | | | | | | | |
| a.c. | Pueyrredon | S. | 6882 | 328 0 | 59 8 | 24 0 | 2 | 13,000 | Sestri Ponente | 1898 | — | 6 H.S. | 6 H.S. | 1½ | 2 10-in., 10 6-in. Q.F., 6 4·7 in., 10 2·2-in., 10 1·4 in., 2 M. sub. | 4 | 20·1 | 1000 | 500 |
| a.c. | San Martin | S. | 6882 | 328 0 | 59 8 | 24 0 | 2 | 13,000 | Leghorn | 1896 | 564,600 | 6 H.S. | 6 H.S. | 1½ | 4 8-in., 10 6-in. Q.F., 6 4·7 in., 12 2·2 in., & 10 1·4 in., 2 L., 2 M.* | 4 sub. | 19 | 1100 | 500 |

* Armament of Garibaldi, San Martin, General Belgrano and Pueyrredon, and Q.F. guns of Libertad and Independencia are Armstrong.

† Bunker capacity.

ARGENTINE REPUBLIC.—Cruising Ships, &c.

| Class. | NAME. | Material of Hull. | Displacement. ft. in. ft. in. ft. in. no. | Length. | Beam. | Draught. | Propellers. | Indicated Horse- power. | Where Built. | Date of Launch. | Cost. | Armour. | | Armament. | | Torpedo Tubes. | Speed. | Normal Coal Supply. | Complement. |
|----------------|--------------------|-------------------|--|--------------------|-------|----------|-------------|----------------------------|-----------------|-----------------|---------|------------------|-------------|---|----|-------------------|----------------|------------------------|-------------|
| | | | | | | | | | | | | Gun Position. | Deck. | Guns. | | | | | |
| <i>g.v.</i> | Argentina . . . | S. | metric tons. 820 | 192 0 27 0 13 0 1 | | | | 850 | Trieste | 1883 | 25,500 | inches. . . | inches. . . | 1 6-in., 6 7-cm. Krupp, 4 m. | | .. | knots. 12·0 | 220 | 120 |
| <i>cr.</i> | Buenos Aires . . | S. shd. | 4780 | 396 0 47 2 19 0 2 | | | 2 | 17,000 | Elswick | 1895 | 383,000 | 4½ | 1-5 | 28-in. Q.F. (Armstrong), 4 6-in. Q.F., 6 4·7-in. Q.F., 16 3-pr., 6 1-pr. | 5 | 23·2* | 1000† | 429 | |
| <i>to.g.b.</i> | Espora . . . | S. | 520 | 210 0 25 0 8 0 2 | | | 2 | 3500 | Birkenhead | 1890 | .. | .. | .. | 3 3-in. Q.F., 4 3-pr., 2 m. | 5 | 20·0 | 100 | 124 | |
| <i>cr.</i> | Nueva de Julio . . | S. | 3570 | 354 0 44 0 19 6 2 | | | 2 | 14,350 | Elswick | 1892 | 293,000 | 4½ | 4½ | 4 6-in. Q.F. (Armstrong), 8 4·7-in., 12 3-pr., 12 1-pr. | 5 | 22·74 | 770† | 300 | |
| <i>cr.</i> | Patagonia . . . | S. & W. | 1442 | 220 0 32 10 12 9 2 | | | 2 | 2400 | Trieste | 1885 | 100,000 | .. | 1½ | 1 10-in., 3 6-in., 6 1., 10 m. | .. | 13·0 | 350 | 210 | |
| <i>to.g.b.</i> | Patria . . . | S. | 1070 | 250 0 31 0 10 0 2 | | | 2 | 4500 | Birkenhead | 1893 | 87,000 | .. | .. | 2 4·7-in. Q.F., 4 8-pr., 2 3-pr., 2 m. | 5 | 20·75 | 288 | 159 | |
| <i>g.v.</i> | Paraná . . . | I. | 550 | 142 8 25 0 11 9 1 | | | 1 | 475 | Birkenhead | 1874 | .. | .. | .. | 2 6-in., 2 4·7-in. . . . | .. | 11·0 | .. | .. | |
| <i>cr.</i> | 25 de Mayo . . . | S. | 3200 | 325 0 43 0 16 0 2 | | | 2 | 13,800 | Elswick | 1890 | 260,000 | 4½ | 4½ | 2 8·2-in. (Armstrong) 8 4·7-in. Q.F., 12 3-pr., 12 1-pr. | 6 | 22·43 | 600† | 185 | |
| <i>g.v.</i> | Uruguay . . . | I. | 550 | 142 8 25 0 11 9 1 | | | 1 | 475 | Birkenhead | 1874 | .. | .. | .. | 2 6-in., 2 4·7-in. . . . | .. | 11·0 | .. | .. | |

Messrs. Laird have built a training-ship (cruiser), Presidente Sarmiento, 2750 tons, 2000 I.H.P. (Nicausse boilers), and 13 knots speed, with nineteen guns and three torpedo-tubes; launched 1897. There are several other small gunboats; also the torpedo-ram Maipú (1063 tons, 1750 I.H.P.), built in England in 1880. The Florio Company has sold to the Argentine Government the steamships Arno, Regina Margherita, and Sempione to be converted into cruisers; and the Spanish firm of Pinillos, Salay & Co.; the Barcelona (4020 tons register), and Cadiz (4218 tons), which have been re-named Pampa and Gaucho.

* Natural draught.

† Buikler capacity.

| Class. | NAME. | Material of Hull. | Displacement. | Length. | Beam. | Draught. | Propellers. | Indicated Horse-power. | Where Built. | Date of Launch. | Cost. | Armour. | | | Armament. | | Normal Coal Supply. | Complement. | |
|------------------|--------------------------|-------------------|---------------|-------------|-------------|----------|-------------|------------------------|--------------|-----------------|------------|---------|---------------|---------------|---|----------------|---------------------|-------------|-----|
| | | | metric tons. | ft. in. ft. | in. ft. in. | in. | | | | | £ | Belt. | Gun Position. | Deck Plating. | Guns. | Torpedo Tubes. | Speed. | | |
| b. | "A." (Ersatz Landon) | S. | 10000 | 305 | 055 | 9 | 21 | 0 | 2 | 14,000 | 1896 | 10-6 | 10-6 | 2½ | 4 9-4-in. 6 5-9-in. Q.F., 14 47-m.m. Q.F., 2 M. | 4 | 17-8 | 500 | .. |
| c.d.s. | Budapest | S. | 5550 | 305 | 055 | 9 | 21 | 0 | 2 | 9185 | 1896 | H.S. | H.S. | H.S. | 8 10-2-in. (Krupp), 11 Q.F., 8 1. 8 8-2-in. (Krupp), 11 Q.F. & M., 6 l. | 2 | (t) 14-0 | 584 | 567 |
| c.b. | Custoza | I. | 7060 | 302 | 358 | 0 | 24 | 6 | 4440 | Trieste | 1872 | 9 | 7 | 1½ | 8 8-2-in. (Krupp), 11 Q.F. & M., 6 l. | 4 | 13-0 | 380 | 440 |
| c.b. | Don Juan de Austria | I. | 3550 | 240 | 350 | 0 | 20 | 0 | 1 | 2700 | 1875 | 8 | 6 | 1 | 2 9-4-in. 10 5-9-in. Q.F., 27 smaller. | .. | 21-0 | .. | .. |
| a. c. | "E." (Ersatz Radetzky) | S. | 7400 | 383 | 1061 | 8 | 21 | 4 | 213,000 | Bdg. | .. | .. | .. | .. | 8 9-4-in. (Krupp), 11 Q.F., 8 1. 3 9-4-in. 12 5-9-in. Q.F., 24 smaller. | 2 | 13-0 | 453 | 535 |
| c.d.s. | Erzherzog Albrecht. | I. | 5940 | 285 | 256 | 3 | 22 | 0 | 1 | 3600 | 1872 | 9 | 7 | 1½ | 2 9-4-in. 8 5-9-in. Q.F., 18 | 4 | 20-0 | 800 | 450 |
| b. | Habsburg. | S. | 8340 | 354 | 365 | 8 | 23 | 4 | 211,000 | Trieste | 1900 | H.S. | H.S. | H.S. | 2 9-4-in. 8 5-9-in. Q.F., 18 1-8, 2 M. | 4 | 13-0 | 380 | 440 |
| a.c. | Kaiserin Maria Theresia | S. | 5270 | 351 | 052 | 6 | 21 | 4 | 2 | 9755 | 1893 | 4 | 4 | 2 | 2 9-4-in. 8 5-9-in. Q.F., 18 1-8, 2 M. | 4 | 19-0 | 740 | 450 |
| a.c. | Kaiser Karl VI. | S. | 6250 | 367 | 656 | 0 | 20 | 4 | 12,800 | Trieste | 1898 | 10-6 | 9-8 | 1½ | 2 9-4-in. 8 5-9-in. Q.F., 18 1-8, 2 M. | 4 | 20-0 | 800 | 450 |
| c.b. | Kaiser Max | I. | 3566 | 240 | 350 | 0 | 20 | 0 | 1 | 2700 | 1875 | 8 | 6 | 1 | 8 8-2-in. (Krupp), 11 Q.F. & M., 6 l. | 4 | 13-0 | 380 | 440 |
| Riv. Mon. b. | Körös | S. | 448 | 177 | 029 | 6 | 4 | 0 | 2 | 1250 | Buda Pesth | 2 | 3 | ¾ | 2 4-7-in. Q.F., 2 l., 1 M. | .. | 10-0 | .. | .. |
| b. | Kronprinz Rudolph | S. | 6940 | 295 | 062 | 4 | 25 | 3 | 2 | 7500 | Pola | 12 | 10 | 2½ | 3 12-in. (Krupp), 6 4-7-in. Q.F., 11 smaller & M., 2 l. | 4 | 16-0 | 600 | 492 |
| b. | Kronprinzessin Stephanie | S. | 5150 | 278 | 1055 | 9 | 21 | 6 | 2 | 8300 | Trieste | 9 | 8 | 1 | 2 12-in. (Krupp), 6 5-9-in. 11 Q.F. & M., 2 l. | 4 | 17-0 | 400 | 510 |
| Riv. Mon. c.d.s. | Leitha | I. & S. | 310 | 166 | 027 | 6 | 3 | 7 | 2 | 320 | Buda Pesth | 1-7 | 2 | 1 | 1 4-7-in. Q.F., 2 M. | .. | 8-0 | 20 | 54 |
| c.b. | Maros | S. | 5550 | 305 | 055 | 9 | 21 | 0 | 2 | 8900 | Pola | 10-6 | 10-6 | 2½ | 4 9-4-in. 6 5-9-in. Q.F., 14 47-m.m. Q.F., 2 M. | 4 | 17-4 | 500 | .. |
| c.b. | Monarch | S. | 5550 | 305 | 055 | 9 | 21 | 0 | 2 | 8900 | Pola | 10-6 | 10-6 | 2½ | 4 9-4-in. 6 5-9-in. Q.F., 14 47-m.m. Q.F., 2 M. | 4 | 17-4 | 500 | .. |
| c.b. | Prinz Eugen | I. | 3566 | 240 | 650 | 0 | 20 | 0 | 1 | 2700 | Pola | 8 | 6 | 1 | 8 8-2-in. (Krupp), 11 Q.F. & M., 6 l. | 4 | 13-0 | 380 | 440 |
| Riv. Mon. c.b. | Szamos | S. | 448 | 177 | 029 | 6 | 4 | 0 | 2 | 1250 | Buda Pesth | 2 | 3 | ¾ | 2 4-7-in. Q.F., 2 Q.F., 1 M. | .. | 10-0 | 670 | 578 |
| c.d.s. | Tegethoff | I. & S. | 7390 | 286 | 1171 | 1 | 24 | 10 | 2 | 8800 | Trieste | 14 | 14 | 9 | 6 9-4-in. (Krupp), 5 5-9-in. Q.F., 15 smaller do., 2 M. | 4 | 16-3 | 500 | .. |
| c.d.s. | Wien | S. | 5550 | 305 | 055 | 9 | 21 | 0 | 2 | 8480 | Trieste | 10-6 | 10-6 | 2½ | 4 9-4-in. 6 5-9 Q.F., 14 47-m.m. Q.F., 2 M. | 4 | 17-6 | 500 | .. |
| c.d.s.b. | Unnamed II. III. | S. | 8300 | 354 | 365 | 8 | 23 | 4 | 211,000 | Trieste | Bdg. | 8-6 | 8-2 | 2½ | 3 9-4-in. 12 5-9-in. Q.F., 24 smaller. | .. | (t) 18-0 | 840 | .. |
| c.d.s.b. | Unnamed IV. | S. | 8300 | 354 | 365 | 8 | 23 | 4 | 211,000 | Trieste | Pro. | 8-6 | 8-2 | 2½ | 3 9-4-in. 12 5-9-in. Q.F., 24 smaller. | .. | 18-0 | 840 | .. |

AUSTRIA-HUNGARY.—Cruising Ships, &c.

300

| Class. | NAME. | Material of Hull. | Displacement. | Length. | Beam. | Draught. | Propellers. | Indicated Horse-power. | Where Built. | Date of Launch. | Cost. | Armour. | | Armament. | | Speed. | Normal Coal Supply. | Complement. |
|-------------|--------------------------|-------------------|-----------------|-----------------------------------|-------|----------|---------------|------------------------|--------------|-----------------|-------|---------------|-------|--|----------------|----------------|---------------------|-------------|
| | | | | | | | | | | | | Gun Position. | Deck. | Guns. | Torpedo Tubes. | | | |
| corv. | Aurora . . . | C. | metras. 1370 | ft. in. ft. in. 190 6'32 10'16 | 1 | 1 | 1000 | Trieste | 1873 | £ | .. | in. . | in. . | 2 4·7-in. (Wahrendorf), 5 l., 2 m. or q.f. | .. | knots. 11·0 | tons. 160 | 200 |
| to. cr. | Aspern ("B.") . . | S. | 2400 | 301 10'39 6'14 | 2 | 2 | 7300 Y | Pola | 1899 | 155,000 | .. | .. | .. | 8 4·7-in. q.f., 12 l. 8-in. . | 1 | 20·0 | .. | .. |
| to. g. b. | Blitz . . . | S. | 360 | 193 6'22 4'8 | 0 | 1 | 3500 | Elbing | 1888 | .. | .. | .. | .. | 9 q.f. | .. | 21·0 | 250 | 61 |
| cr. 3rd cl. | Donau . . . | C. | 2344 | 230 0'42 8'19 | 8 | 1 | 1800 | Pola | 1893 | .. | .. | .. | .. | 10 4·7-in. (Uchatius), 4 m., 1 l. | .. | 12·0 | 320 | .. |
| cr. 3rd cl. | Erzherzog Friedrich . . | W. | 1590 | 173 10'39 5'16 | 9 | 1 | 800 | Venice | 1874 | .. | .. | .. | .. | 10 5·9-in. (Wahrendorf), 1 l. . | .. | 9·0 | 200 | 261 |
| cr. . | Frundsberg . . . | C. | 1370 | 190 6'32 10'16 | 1 | 1 | 1000 | Trieste | 1873 | .. | .. | .. | .. | 2 5·9-in. (Wahrendorf), 5 l., 2 m. or q.f. | .. | 11·0 | 160 | 209 |
| cr. 2nd cl. | Kaiserin Elizabeth . . | S. | 4064 | 321 6'47 6'18 | 7 | 2 | 9000 | Pola | 1890 | .. | .. | 3·5 | 24 | 2 9·4-in. (Krupp), 6 5·9-in. do., 11 q.f., 2 l. | 5 | 19·0 | 660 | 450 |
| cr. 2nd cl. | Kaiser Franz Joseph I. . | S. | 4030 | 321 6'47 6'18 | 7 | 2 | 9000 | Trieste | 1889 | .. | .. | 3·5 | 24 | 2 9·4-in. (Krupp), 6 5·9-in. do., 11 q.f., 2 l. | 5 | 19·0 | 660 | 450 |
| to. g. b. | Komet . . . | S. | 360 | 193 6'22 4'8 | 0 | .. | 3500 | Elbing | 1888 | .. | .. | .. | .. | 9 q.f. | .. | 21·0 | .. | 61 |
| cr. 2nd cl. | Laudon . . . | C. | 3430 | 253 0'46 0'20 | 8 | 1 | 2600 | Trieste | 1873 | .. | .. | .. | .. | 15 5·9-in. (Krupp), 7 q.f. & m., 2 l. | .. | 13·0 | 450 | 497 |
| cr. 3rd cl. | Leopard . . . | S. | 1582 | 224 0'34 0'14 | 0 | 2 | 6000 | Elswick | 1886 | 200,000 | .. | .. | .. | 2 4·7-in. q.f., 10 q.f. & m. . | 4 | 13·3 | 250 | 148 |
| to. g. b. | Lussin . . . | S. | 1011 | 200 4'26 3'12 | 2 | 2 | 1830 Darr. | Trieste | 1883 | .. | .. | .. | 1½ | 2 5·9-in. (Krupp), 7 m., 1 l. . | .. | 14·0 | 200 | 142 |

BRAZIL.—Armoured Ships.

| Class. | NAME. | Material of Hull. | Displacement. | Length. | Beam. | Draught. | Propellers. | Indicated Horse-power. | Where Built. | Date of Launch. | Cost. | Armour. | | | | Armament. | | Speed. | Normal Coal Supply. | Complement. |
|------------|---------------------------|-------------------|------------------------------------|-------------------|-----------|----------------|------------------|------------------------|--------------|-----------------|-------|------------|---------------|----------------------------------|---|----------------|----------|--------|---------------------|-------------|
| | | | | | | | | | | | | Belt. | Gun Position. | Back- ing. Deck Plating. | Guns. | Torpedo Tubes. | | | | |
| t. River | Alagoás | W. | tons. 340 ft. 120 in. 0 28 0 | ft. 4 in. 10 2 | 180 | Brazil | 1886 | £ | | | | inches. 4½ | inches. 14½ | 1 7-in. M.L.R. (Whitworth), 2 M. | .. | 7·0 | tons. 43 | | | |
| c.d.s., t. | Bahia | I. | 1000 178 0 35 0 | 8 6 2 | 1640 | Birkenhead | 1865 | .. | | | | 4½ | 5½ | 10½ | 2 7-in. M.L.R. (Whitworth), 2 M. | .. | 6·0 | 125 | | |
| t. River | Maranhao | S. | 470 137 0 34 7 | 6 5 2 | 700 | Rio de Janeiro | 1890 | .. | | | | 5 | .. | .. | 2 4·7-in. Q.F., 1 2·5-in., 5 M. | .. | 12·0 | .. | | |
| c.d.s., t. | Marshal Deodoro | S. | 3162 267 6 48 0 | 13 2 2 | 3400 D'A. | La Seyne | 1898 } 1899 } | .. | .. | .. | .. | 13¾ H.S. | 7¼-8¾ H.S. | 1½ | 2 9·4-in., 2 5·9-in. howitzers, 4 4·7-in. Q.F., 2 M., 4 6-pr. and 2 1-pr. | 2 (sub.) | 15·0 | 236 | 200 | |
| c.d.s., t. | Marshal Floriano | | | | | | | | | | | | | | | | | | | |
| t. River | Pará | S. | 470 137 0 34 7 | 6 5 2 | 700 | Rio de Janeiro | 1890 | .. | | | | 5 | .. | .. | 2 4·7-in. Q.F., 1 2·5-in., 5 M. | .. | 12·0 | .. | | |
| t. River | Piauihy | W. | 340 120 0 28 0 | 4 10 2 | 186 | Brazil | 1887 | .. | | | | 4½ | 4½ | 14½ | 1 7-in. M.L.R. (Whitworth) | .. | 7·0 | .. | 43 | |
| t. | Riachuelo | S. shd. | 5700 305 0 52 0 | 19 6 2 | 7300 | Poplar | 1883 1895 | 365,000* | | | | 11 comp. | 11 & 10 comp. | 2" | 4 9·2-in. (Whitworth), altered by Armstrong, 6 4·7-in. Q.F., 2 3-pr., 15 M. | 5 | 16·71 | 800 | 450 | |
| t. River | Rio Grande | W. | 340 120 0 28 0 | 4 10 2 | 180 | Brazil | 1888 | .. | | | | 4½ | 4½ | 14½ | 1 7-in. M.L.R. (Whitworth) | .. | 7·0 | .. | 43 | |
| t. | 24 de Maio (ex Aquidaban) | S. shd. | 4950 280 0 52 0 | 18 0 2 | 6200 | Poplar | 1885 1897 | 345,000* | | | | 11 | 11½ & 10 cp. | 2" | 4 9·4-in. (Canet), 4 5·5-in., 2 Q.F., 13 M. | 5 | 15·0 | 600 | 350 | |

* Exclusive of guns and ammunition. The ship is undergoing reconstruction at Elswick. Floating batteries, Brazil (1518 tons) and Lima-Barros (1414 tons).

BRAZIL.—Cruising Ships, &c.

| Class. | NAME. | Material of Hull. | Displacement. | Length. | Beam. | Draught. | Propellers. | Indicated Horse-power. | Where Built. | Date of Launch. | Cost. | Armour. | | Armament. | | Speed. | Normal Coal Supply. | Complement. | |
|---------|--------------------------------------|-------------------|---------------|----------|-------|----------|-------------|------------------------|--------------|-----------------|-------|---------------|--|-----------|----------------|--------|---------------------|-------------|-----|
| | | | | | | | | | | | | Gun Position. | Deck. | Guns.† | Torpedo Tubes. | | | | |
| cr. | Almirante Tamandare. | S. shd. | 4735 | 294 0 45 | 0 18 | 4 2 | 7500 | Brazil | 1890 | .. | .. | inches. 1½ | 10 6-in. Q.F., 2 4·7-in., 8 M. | 8 | .. | .. | 17·0 | 750 | 450 |
| " | Andrada (ex America) | S. shd. | 2600 | 252 8 34 | 0 18 | 0 1 | 3600 | Bergen | 1890 | .. | .. | .. | 2 4·7-in. 2 14-pr. Q.F., 6 6-pr., 6 1-pr. | 5 | .. | .. | 17·0 | .. | .. |
| " | Barroso. | S. shd. | 3600 | 330 0 43 | 9 16 | 10 2 | 7500 | Elswick | 1896 | .. | .. | 4½ | 6 6-in. Q.F., 4 4·7-in., 10 6-pr., 4 1-pr., 4 M. | 3 | .. | .. | 20·0 | 700 | .. |
| " | Benjamin Constant | S. shd. | 2750 | 236 0 46 | 0 18 | 0 1 | 2800 | La Seyne | 1892 | .. | .. | 2 | 4 6-in. Q.F., 8 4·7-in., 8 M., 4 l. | 4 | .. | .. | 14·0 | 260 | 287 |
| to.cr. | Caramuru | S. | 1080 | 249 6 30 | 9 10 | 2 2 | 6000 | Kiel | 1896 | .. | .. | .. | 23·9-in. Q.F., 6 2·2-in., 2 1·4-in. | 3 | .. | .. | 22·5 | .. | .. |
| to.g.b. | Gustavo Sampaio | S.W. | 500 | 197 0 21 | 0 7 | 9 2 | 2500 | Elswick | 1893 | .. | .. | .. | 2 20-pr. Q.F., 4 7-pr. Q.F.. | 3 | .. | .. | 18·0 | 150 | 95 |
| cr. | Parnahyba (Torpedo training.) | C. | 838 | 170 6 26 | 3 11 | 2 1 | 900 | Havre | 1878 | .. | .. | .. | 5 4·7-in., 4 M. | .. | .. | .. | 10·0 | .. | .. |
| " | Paysandu (ex Guana- bára) | W. | 1900 | 200 0 41 | 2 16 | 4 1 | 3000 | Brazil | 1877 | .. | .. | .. | 9 70-pr. M.L.R. (Whitworth), 6 M., 2 l. | .. | .. | .. | 13·0 | .. | 250 |
| cr. | Primeiro de Março | C. | 726 | 167 3 26 | 3 10 | 6 1 | 750 | Brazil | 1881 | .. | .. | .. | 7 4·5-in. M.L.R. (Whitworth), 4 M. | .. | .. | .. | 9·0 | .. | .. |
| " | Quinze de Novembro (ex Republica) | S. | 1300 | 210 0 35 | 0 13 | 0 2 | 3300 | Elswick | 1892 | .. | .. | .. | 6 4·7-in. Q.F., 4 6-pr., 6 M. | 4 | .. | .. | 17·0 | 170 | 169 |
| to.cr. | Tamoyo. | S. | 1080 | 269 0 28 | 10 9 | 10 2 | 6500 | Kiel | 1898 | .. | .. | .. | 2 3·9-in. Q.F., 6 2·2-in., 2 1·4-in., 2 M. | 3 | .. | .. | 23·0 | 293 | 110 |
| " | Timbira. | S. | 1030 | 249 6 30 | 9 10 | 2 2 | 7000 | Kiel | 1896 | .. | .. | .. | 2 3·9-in. Q.F., 6 2·2-in., 2 1·4-in., 2 M. | 3 | .. | .. | 22·5 | 250 | 110 |
| g.v. | Tiradentes | S. shd. | 800 | 165 0 30 | 0 11 | 0 2 | 1200 | Elswick | 1892 | .. | .. | .. | 4 4·7-in. Q.F., 3 6-pr., 4 M. | 2 | .. | .. | 14·5 | 110 | 107 |
| cr. | Tonelero (ex Trajano) | W. | 1414 | 200 0 30 | 0 15 | 6 2 | 2400 | Brazil | 1873 | .. | .. | .. | 7 4·7-in. Q.F., 4 M.. | .. | .. | .. | 13·0 | .. | .. |
| " | Trinidade (ex Liber- dade) | I. | 250 | 101 8 21 | 8 10 | 10 2 | 280 | Brazil | 1884 | .. | .. | .. | 2 l., 1 M. | .. | .. | .. | 10·0 | .. | .. |
| to.cr. | Tupy | S. | 1030 | 249 6 30 | 9 10 | 2 2 | 7000 | Kiel | 1896 | .. | .. | .. | 2 3·9-in. Q.F., 6 2·2-in., 2 1·4-in., 2 M. | 3 | .. | .. | 22·5 | 250 | 110 |

† All the Q.F. guns above 6-pr. in Brazilian Navy are Armstrong.

Ten screw gunboats, 200 tons to 400 tons, and eight paddle gunboats, 120 tons to 160 tons.

CHILI.—Armoured Ships.

| Class. | NAME. | Material of Hull. | Displacement. | Length. | Beam. | Draught. | Propellers. | Indicated Horse-power. | Where Built. | Date of Launch. | Cost. | Armour. | | | Armament. | | Speed. | Normal Coal Supply. | Complement. |
|--------|---------------------|-------------------|---------------|---------|---------|----------|-------------|------------------------|--------------|-----------------|---------|---------|---------------|---------------|---|----------------|--------|---------------------|-------------|
| | | | tons. | ft. in. | ft. in. | ft. in. | no. | | | | £ | Belt. | Gun Position. | Deck Plating. | Guns. | Torpedo Tubes. | knots. | tons. | |
| c.b. | Almirante Cochrane | W.I. shd. | 3500 | 210 0 | 45 9 | 19 8 | 2 | 2920 | Hull | 1874 | | 9 | 8 | 3" | 6 8-in. (Armstrong), 4 6-pr. Q.F., 4 3-pr., 7 M. | 3 | 13.0 | 350 | 242 |
| a.c. | Almirante O'Higgins | S. shd. | 8500 | 411 9 | 62 6 | 22 0 | 2 | 16,000 | Elswick | 1897 | | 7 | 6 | 2 | 4 8-in. Q.F., 10 6-in., 4 4.7-in., 10 12-pr., 10 6-pr., 4 M. | 8 | 21.5 | 1260 | .. |
| b. | Capitan Prat | S. shd. | 6900 | 328 0 | 60 8 | 21 10 | 2 | 12,000 | La Seyne | 1890 | 391,000 | 12 | 10½ 4 | 3" | 6 9.4-in. (Canet), 8 4.7-in. Q.F. (Canet), 6 2.2-in., 4 1.8-in., 10 1.4-in., 5 M. | 4 | 18.3 | 775 | 485 |
| a.c. | Esmeralda | S. shd. | 7020 | 436 0 | 53 2 | 22 3 | 2 | 16,000 | Elswick | 1896 | | 6 | H.S. | 2 | 2 8-in. Q.F., 16 6-in., 8 12-pr., 2 3-pr., 4 M. | 3 | 22.8 | 1350 | .. |

The Huascar, 1800 tons, launched at Birkenhead in 1865, is now a floating battery.

Cruising Ships, &c.

| Class. | NAME. | Material of Hull. | Displacement. | Length. | Beam. | Maximum Draught. | Propellers. | Indicated Horse-power. | Where Built. | Date of Launch. | Cost. | Armour. | | Armament. | | Speed. | Normal Coal Supply. | Complement. |
|----------------|---------------------------------|-------------------|---------------|---------|---------|------------------|-------------|------------------------|----------------|-----------------|-------|---------------|-------|--|----------------|--------|---------------------|-------------|
| | | | tons. | ft. in. | ft. in. | ft. in. | no. | | | | | Gun Position. | Deck. | Guns. | Torpedo Tubes. | knots. | tons. | |
| <i>to g.b.</i> | Almirante Condell | S | 750 | 240 | 0 27 | 6 10 | 6 | { 4500 B | Birkenhead | 1890 | .. | .. | .. | 3 14-pr. Q.F., 4 3-pr., 2 M. | 5 | 21.0 | 210 | .. |
| <i>to g.b.</i> | Almirante Lynch | S. | 812 | 240 | 0 27 | 6 10 | 6 | 4700 | Birkenhead | 1896 | .. | 4½ | .. | 2 4.7-in. Q.F., 4 3-pr. | 3 | 21.0 | 200 | .. |
| " | Almirante Simpson | S. | 4400 | 370 | 0 45 | 6 18 | 6 | Nor. 14,500 | Elswick | 1893 | .. | .. | 4-1½ | 2 8-in., 10 6-in. Q.F., 12 3-pr., 10 1-pr.* | 5 | 22.78 | 1900 | .. |
| <i>cr.</i> | Blanco Encalada | S. shd. | 2330 | 240 | 0 45 | 9 18½ | 0 | 1500 | Elswick | 1898 | .. | .. | .. | 4 4.7-in. Q.F., 2 12-pr., 2 6-pr., 2 M., 1 L. | 1 | 13.7 | 200 | 302 |
| " | General Baquedano (Training) | S. | 800 | 190 | 0 28 | 0 14 | 9 | 1230 | London | 1874 | .. | .. | .. | 2 6-in., 1 7-in. M.L.R., 6 M., 2 L. | .. | 11.0 | 300 | 100 |
| <i>gv.</i> | Magallanes | C. | 3600 | 330 | 0 34 | 3 9 | 16 | 10 | 6500 | Elswick | 1896 | .. | .. | 8 6-in. Q.F., 10 6-pr., 4 1-pr.* | 3 | 20.0 | 800 | .. |
| <i>cr.</i> | Ministro Zenteno | S. shd. | 790 | 171 | 0 27 | 4 | .. | 1 | 180 | Birkenhead | 1874 | .. | .. | 2 70-pr. B.L.R. (Armstrong), 2 40-pr., 3 M. | .. | 9.0 | 125 | 125 |
| <i>gv.</i> | Pileomayo | W. | 2080 | 268 | 0 35 | 9 19 | 6 | 2 | 5400 (nom.) | La Seyne | 1890 | .. | 3½ | 4 6-in. Q.F. (Canet), 2 5-in., 4 2-2-in., 6 M. | 3 | 19.0 | 200 | 171 |
| <i>cr.</i> | Presidente Errázuriz | S. shd. | | | | | | | | | .. | | | | | | | |
| " | Presidente Pinto | S. shd. | | | | | | | | | .. | | | | | | | |

Two Gunboats of 145 tons displacement and one of 180 tons.

* Armstrong.

† Bunker capacity.

‡ Mean draught.

CHINA.—Cruising Ships, &c.

| Class. | NAME. | Material of Hull. | Displacement. | Length. | Beam. | Draught. | Propellers. | Indicated Horse-power. | Where Built. | Date of Launch. | Cost. | Armour. | | Armament. | | Speed. | Normal Coal Supply. | Complement. |
|---------|------------|-------------------|---------------|---------|-------|----------|-------------|------------------------|--------------|-----------------|-------|---------------|------------|--|----------------|-------------|---------------------|-------------|
| | | | | | | | | | | | | Gun Position. | Deck. | Guns. | Torpedo Tubes. | | | |
| cr. | Foo-Ching | S. | 2500 | 253 | 36 | 2 | 18 0 | 2 | 2400 | 1893 | .. | inches 4½ | inches 4-2 | 3 5-in. Krupp, 4 M., 2 l. | .. | knots. 16·0 | tons. .. | .. |
| to g.b. | Fei-Ying | S. | 850 | 257 | 228 | 6 | 12 6 | 2 | 4500 | 1895 | .. | 2 | .. | 2 4-in. Q.F., 6 3·4-in., 4 smaller. | 3 | 21·8 | 75 | 90 |
| cr. | Hai-Chi. | S. | 4300 | 396 | 0 46 | 8 | 18 6 | 2 | 17000 | 1898 | .. | 6 | 5 | 2 8-in. Q.F., 10 4·7-in., 12 8-pd., 4 1·4-in., 6 M. | 5 | 24·0 | 300 | 374 |
| " | Hai-Shen | S. | 2950 | 314 | 8 41 | 0 | 16 0 | 2 | 8000 | 1898 | .. | 2 | 3 | 3 6-in. Krupp Q.F., 8 4-in., 1·4-in. Hotchkiss, 6 M. | 3 | 20·7 (Z.) | 220 (500) | 244 |
| " | Hai-Shew | S. | | | | | | | | 1897 | | | | | | | | |
| " | Hai-Yung | S. | | | | | | | | 1897 | | | | | | | | |
| " | Hai-Tien | S. | 4300 | 396 | 0 46 | 8 | 18 6 | 2 | 17000 | 1897 | .. | 6 | 5 | 2 8-in. Q.F., 10 4·7-in., 12 8-pd. | 5 | 24·1 (Z.) | 300 | 374 |
| " | Hi-Ying | S. | 2200 | 253 | 0 36 | 2 | 18 1 | 2 | 2400 | 1895 | .. | .. | .. | 2 8-in. Armstrong, 8 4·7-in. Q.F., 4 M. | 1 | 21·0 | .. | .. |
| " | Huang-Tái | C. | 2110 | 260 | 0 36 | 0 | 20 0 | 1 | 1600 | 1886 | .. | .. | .. | 3 7-in. Krupp, 7 40-pr., 6 M. | 2 | 15·0 | 360 | 300 |
| " | Kai-Chih | C. | 2110 | 260 | 0 36 | 0 | 20 0 | 1 | 1600 | 1882 | .. | .. | .. | 2 8·2-in., 6 5·9-in., 6 M., 5 l. | .. | 14·5 | 360 | 300 |
| " | Kien-Wei | C. | 2110 | 260 | 0 36 | 0 | 20 0 | 1 | 1600 | 1899 | .. | .. | .. | 2 8·2-in., 6 5·9-in., 6 M., 5 l. | .. | 14·5 | 360 | 300 |
| " | King-Ching | C. | 2100 | 250 | 0 36 | 0 | 20 0 | 1 | 2400 | 1886 | .. | .. | .. | 3 7-in. Krupp, 7 40-pr., 6 M. | 2 | 14·5 | 360 | 300 |
| to g.b. | Kwang-Ting | C. | 1000 | 235 | 0 27 | 6 | 11 4 | 2 | 3400 | 1890 | .. | .. | 1 | 3 4·7-in. Q.F., 4 M., 2 l. | 4 | 16·0 | .. | 120 |
| cr. | Nan-Schuin | S. | 2200 | 253 | 0 36 | 2 | 18 1 | 2 | 2400 | 1884 | .. | .. | .. | 2 8-in. Armstrong, 8 4·7-in. Q.F., 9 M. | 1 | 14·5 | 600 | 250 |
| " | Nan-Thin | S. | 2200 | 253 | 0 36 | 2 | 18 1 | 1 | 2400 | 1883 | .. | .. | .. | 2 8-in. Armstrong, 8 4·7-in. Q.F., 9 M. | 1 | 15·0 | 600 | 250 |
| " | Pao-Min | S. | 1480 | 213 | 0 36 | 0 | 14 0 | 1 | 2400 | 1884 | .. | .. | .. | 2 6-in. Armstrong, 6 5-in., 2 l. | .. | 9 | 300 | 200 |
| g.b. | Tien-Sing | W. | 200 | 105 | 0 20 | 4 | 7 0 | 2 | 340 | 1875 | .. | 3 | .. | 1 7-in. (Krupp) | .. | 10·0 | .. | .. |
| cr. | Unnamed | C. | 2110 | 260 | 0 36 | 0 | 20 0 | 1 | 1600 | Blg. | .. | .. | .. | 2 8·2-in., 6 5·9-in., 6 M., 5 l. | .. | 14·5 | 360 | 300 |

The displacement of German-built ships in metric tons.

Torpedo-gunboat *Pai-Ting* (349 tons), four gunboats of 411 tons, two of 300 tons, four of 215 tons (defence of Canton Roads), training vessel *Tung-Chi*, 1700 tons—all launched 1885-88.

DENMARK.—Armoured Ships.

| Class. | NAME. | Material of Hull. | Displacement. | Length. | Beam. | Draft. | Propellers. | Indicated Horse-power. | Where Built. | Date of Launch. | Cost. | Armour. | | | Armament. | | Speed. | Normal Coal Supply. | Complement. |
|-------------------|--|-------------------|--------------------------|--------------------------------------|-------|--------|-------------|------------------------|--------------|-----------------|------------|--------------|---------------|---------------|---|----------------|-----------------|---------------------|-------------|
| | | | | | | | | | | | | Belt. | Gun Position. | Deck Plating. | Guns. | Torpedo Tubes. | | | |
| <i>c.d.s., t.</i> | Gorm . . . | I. | metric tons. 2344 231 | ft. in. ft. in. no. 0 40 0 14 0 2 | | | | 1670 | Copenhagen | 1870 | £ 104,000 | inches. 7 | inches. 8 | inches. .. | 2 10-in. (Armstrong) M.L.R., 3 3 4-in. (Krupp), 4 M. | .. | knots. 12·25 | tons. 115 | 158 |
| <i>t.</i> | Helgoland . . | I. | 5347 257 | 6 59 2 18 8 2 | | | 4000 | Copenhagen | 1878 | 275,000 | 12 | 10 | 4 | 4 | 1 12-in. (Krupp), 4 10·2-in., 5 4·7-in., 10 M. | 4 | 12·0 | 230 | 350 |
| <i>c.d.s., t.</i> | Herluf Trolle . | S. | 3470 271 | 0 50 0 16 2 2 | | | 4200 T | Copenhagen | 1899 | .. | 7½ H.S. | 6 H.S. | .. | .. | 2 9·4-in., 4 5·9-in. Q.F., 10 2·2-in., 8 smaller. | 3 (sub.) | 16·0 | .. | .. |
| <i>b.</i> | Iver Hvitfeldt . | S. | 3260 242 | 0 49 6 18 0 2 | | | 5100 | Copenhagen | 1886 | 200,000 | 12 | 8 | 2 | 2 | 2 10·2-in. (Krupp), 4 4·7-in., 12 M. | 4 | 15·6 | 250 | 298 |
| <i>c.d.s., t.</i> | Lindormen . . | I. | 2076 216 | 0 39 5 13 9 2 | | | 1560 | Copenhagen | 1868 | 93,000 | 5 | 5 | .. | .. | 2 9-in. (Armstrong) M.L.R., 3 3 4-in. (Krupp), 4 M. | .. | 12·0 | 120 | 140 |
| <i>c.b.</i> | Odint . . . | I. | 3083 237 | 0 50 0 15 6 1 | | | 2260 | Copenhagen | 1872 | 147,000 | 8 | 8 | .. | .. | 4 10-in. (Armstrong) M.L.R., 4 3·4-in. (Krupp), 7 M. | .. | 12·4 | 180 | 236 |
| <i>t.</i> | Skjold . . . | S. | 2150 226 | 6 38 0 13 5 2 | | | 2200 T | Copenhagen | 1896 | .. | 9 | 8-4½ | 2 | 2 | 1 9·4-in., 3 4·7-in. (Krupp), 4 1·8-in. Q.F., 1 M. | 4 | 13·0 | .. | .. |
| T. S. | Tordenskjold † | S. | 2400 221 | 6 43 3 15 6 2 | | | 2600 | Copenhagen | 1880 | 138,900 | .. | 8 | 4-2 | 4-2 | 1 14-in. (Krupp), 4 4·7-in., 8 M. | 4 | 14·0 | 170 | 220 |
| <i>c.d.s., t.</i> | Unnamed* . . . (Herluf Trolle type) | S. | 5470 271 | 0 59 2 18 8 2 | | | 4200 | Copenhagen | Bldg. | .. | 7½ H.S. | 6 H.S. | .. | .. | 2 9·4-in., 4 5·9-in. Q.F., 10 2·2-in., 8 smaller. | 3 (sub.) | 16·0 | .. | .. |

Esbern Snare (torpedo school-ship), 530 tons, 2-in. belt.

* Estimates of 1900-1901.

† To be reconstructed.

DENMARK.—Cruising Ships, &c.

| Class. | NAME. | Material of Hull. | Displacement. | Length. | | Beam. | | Draught. | | Propellers. | Indicated Horse-power. | Where Built. | Date of Launch. | Cost. | Armour. | | Armament. | | Speed. | Normal Coal Supply. | Complement. |
|--------------------|--------------|-------------------|---------------------|---------|---------|---------|---------|----------|------------|-------------|------------------------|--------------|---|--|-------------------------|-------|-----------|----------------|--------|---------------------|-------------|
| | | | | ft. in. | ft. in. | ft. in. | ft. in. | ft. in. | ft. in. | | | | | | Gun Position. | Deck. | Guns. | Torpedo Tubes. | | | |
| <i>g. v.</i> | Absalon | I. | metric tons. 527 | 150 0 | 26 0 | 10 2 | 1 | 500 | Blackwall | 1862 | £ | 2½ | 2½ | inches. inches. | 4 3-4-in. (Krupp), 4 m. | .. | 10-0 | 65 | tons. | 70 | |
| " | Falster | I. | 356 | 111 0 | 28 10 | 7 6 | 2 | 510 | Copenhagen | 1873 | 33,000 | .. | .. | 1 10-in. (Armstrong) M.L.R., 2 3-4-in. (Krupp), 2 m. | .. | 9-8 | 20 | 35 | | | |
| <i>cr.</i> | Fyen | S. shd. | 2596 | 226 6 | 45 6 | 18 1 | 1 | 2700 | Copenhagen | 1882 | 170,000 | .. | 1½ | 18 5-9-in. (Krupp), 8 m. | .. | 13-0 | 290 | 407 | | | |
| 3rd cl. <i>cr.</i> | Geiser | S. | 1280 | 257 6 | 27 6 | 11 4 | 2 | 3000 | Copenhagen | 1892 | .. | .. | 1½ | 2 4-7-in. Q.F., 4 3-4-in., 6 m. | .. | 17-1 | .. | .. | | | |
| " | Heimdal | S. | 1280 | 257 6 | 27 6 | 11 4 | 2 | 3000 | Copenhagen | 1894 | .. | .. | 1½ | 2 4-7-in. Q.F., 4 3-pr., 6 m. | .. | 17-5 | .. | .. | | | |
| " | Hekla | S. | 1280 | 233 0 | 32 10 | 11 2 | 2 | 3000 | Copenhagen | 1890 | .. | .. | 1½ | 2 6-in. Q.F., 4 2-2-in., 6 m. | .. | 17-0 | .. | .. | | | |
| <i>g. v.</i> | Ingolf | I. | 870 | 192 0 | 28 0 | 12 6 | 1 | 600 | Copenhagen | 1876 | 44,000 | .. | .. | 2 5-9-in. (Krupp), 4 3-4-in., 2 m. | .. | 10-5 | 130 | 117 | | | |
| <i>g. v.</i> | Möen | I. | 356 | 111 0 | 28 10 | 7 6 | 1 | 523 | Copenhagen | 1875 | .. | .. | .. | 1 10-in. (Armstrong) M.L.R., 2 3-4-in. (Krupp), 2 m. | .. | 9-2 | 20 | 35 | | | |
| <i>corr.</i> | Saint Thomas | W. | 1572 | 224 0 | 33 0 | 17 0 | 1 | 1870 | Copenhagen | 1871 | .. | .. | .. | 8 4-7-in. (Krupp), 6 m. | .. | 13-0 | 190 | 182 | | | |
| <i>cr.</i> | Valkyrien | S. | 2900 | 268 0 | 43 6 | 18 0 | 2 | 5300 | Copenhagen | 1887 | .. | 2½ | 2 8-2-in. (Krupp), 6 5-9-in., 4 Q.F., 10 m. | .. | 17-0 | 450 | 300 | | | | |

Gunboats.—Five in number (*Lille Belt*, *Öresund*, *Store Belt*, *Grönsund*, *Guldborgsund*), of 150 to 240 tons, 200 to 400 I.H.P. *Dagmar* (training-ship), corvette, 1200 tons; *Hjælperen* (mining), 280 tons; *Sleipner* (ice-breaker), 1260 tons, 3000 I.H.P. The *Deslytteren*, torpedo transport, 389 tons, 600 I.H.P., 3 1-8 in. Q.F., is in hand.

| Class. | NAME. | Material of Hull. | Displacement. | Length. | Beam. | Draft. | Propellers. | Indicated Horse-power. | Where Built. | Date of Launch. | Cost. | Armour. | | | Armament. | | Speed. | Normal Coal Supply. | Complement. |
|---------------|-------------------|-------------------|---------------|-----------------|-----------------|---------|-------------|------------------------|--------------|-----------------|-----------|------------|---------------|---------------|--|----------------|--------|---------------------|-------------|
| | | | | | | | | | | | | Belt. | Gun Position. | Deck Plating. | Guns. | Torpedo Tubes. | | | |
| | | | metric tons. | ft. in. ft. in. | ft. in. ft. in. | ft. in. | no. | | | | £ | inches. | inches. | inches. | | | knots. | tons. | |
| <i>l.</i> | A 8 (République?) | S. | 14,865 | 434 10 79 | 7 27 6 3 | 17,475 | W.T. | | Brest | Bdg. | 1,421,708 | 11-8 H.S. | 12 | .. | 4 12-in., 18 6-4-in. Q.F., 26 1-8-in., 2 1-4-in. | 5 (2 sub.) | 18-0 | 905 1825 | 798 |
| <i>l.</i> | A 10 (Patrie?) | S. | 1721 | 181 0 40 | 4 11 10 2 | 1700 | | | Cherbourg | Pro. | 100,000 | 8 | 8 | 2½ | 1 10-8-in., 3 3-9-in. Q.F., 2 1-8-in., 4 M. | .. | 13-0 | 100 | 101 |
| <i>a.g.b.</i> | Achéron | I. & S. | 10,014 | 453 0 63 | 3 24 7 3 | 20,500 | B | | St. Nazaire | Bdg. | 973,440 | 6 H.S. | 5-7½ | 2 | 2 7-6-in., 8 6-4-in. Q.F., 4 3-9-in., 26 small Q.F. and M. | 4 (2 sub.) | 21-0 | 970 1590 | .. |
| <i>a.c.</i> | Amiral Aube | S. | 11,911 | 321 6 39 | 10 26 2 2 | 8320 | B | | Brest | 1883 1899 | 600,000 | 21½ | 16½ | 4 | 2 14-6-in., 4 6-4-in. Q.F., 8 5-5-in., 26 small Q.F. and M. | 4 | 15-0 | 800 | 630 |
| <i>b.</i> | Amiral Baudin | I. & S. | 4792 | 348 0 46 | 0 19 2 2 | 8300 | B | | Rocheport | 1893 | 353,200 | 3½ | 2 | 2 | 2 7-6-in., 6 5-5-in. Q.F., 14 small Q.F. and M. | 5 | 18-2 | 413 | 375 |
| <i>a.c.</i> | Amiral Charner | S. | 11,209 | 311 0 66 | 11 26 9 2 | 8120 | B | | La Seyne | 1879 1901 | 570,000 | 21½ | 15½ | 2½ | 3 13-3-in., 4 6-4-in. Q.F., 1 5-5-in., 14 4-in., 42 small Q.F. and M.* | 4 | 14-22 | 850 | 664 |
| <i>b.</i> | Amiral Duperré | I. & S. | 9317 | 459 0 63 | 8 24 7 3 | 20,200 | Nic. | | Lorient | 1899 | 817,994 | 6-3¾ H.S. | 8, 3¾ | 2 | 2 7-6-in., 8 6-4-in. Q.F., 4 3-9-in., 16 1-8-in., 6 1-4-in. | 2 (sub.) | 21-0 | 1020 1600 | 612 |
| <i>a.c.</i> | Amiral de Gueydon | S. | 5360 | 370 6 50 | 2 21 0 2 | 10,398 | B | | Havre | 1895 | 384,000 | 3½-2 | 9½ | 3¾ | 2 7-6-in., 10 5-5-in. Q.F., 16 1-8-in., 8 1-4-in. | .. | 19-2 | 538 | 461 |
| <i>a.c.</i> | Amiral Pothuan | S. | 6629 | 293 2 58 | 4 23 2 2 | 8500 | B | | Lorient | 1893 | 593,100 | 17¾ | 14½ | 4 | 2 12-in., 8 3-9-in. Q.F., 4 1-8-in. Q.F., 4 1-4-in., 8 M. | 2 | 15-76 | 300 | 337 |
| <i>l.</i> | Amiral Tréhouart | S. | 12,200 | 401 2 70 | 3 27 6 3 | 14,000 | B | | Lorient | 1896 | 1,100,770 | 15¾-8 H.S. | 14½ | 3½ | 2 12-in., 2 10-8-in., 8 5-5-in. Q.F., 8 3-9-in., 19 small Q.F. (2 sub.) and M. | 4 | 18-2 | 621 | 621 |
| <i>l.</i> | Bouvet | S. | 6610 | 293 9 58 | 3 23 3 2 | 8400 | A'D | | La Seyne | 1892 | 594,640 | 17¾ | 14½ | 4 | 2 12-in., 8 3-9-in. Q.F., 4 1-8-in., 10 1-4-in. M. | 2 | 16-05 | 300 | 323 |

* New armament.

| | | | | | | | | | | | | | | | | | | | |
|----------------------|-----------------|---------|--------|-----------|-----------|--------|------|--|-------------|-----------|-----------|-----------|-------|----|---|------------|-------|----------|-----|
| <i>l.</i> | Brennus | S. | 11,395 | 361 0 67 | 0 26 3 2 | 14,000 | B | | Lorient | 1891 | 991,767 | 15¾ comp. | 15¾ | 4½ | 3 13-4-in., 10 6-4-in. Q.F., 23 small Q.F. and M. | 4 | 17-1 | 800 | 696 |
| <i>a.c.</i> | Bruix | S. | 4754 | 365 3 46 | 0 19 10 2 | 9049 | B | | Rocheport | 1894 | 409,622 | 3¾ | 3¾ | 2 | 2 7-6-in., 6 5-5-in. Q.F., 4 2-5-in., 4 1-8-in., 6 1-4-in., M. | 4 | 18-3 | 406 | 391 |
| <i>l.</i> | Caiman† | I. & S. | 7239 | 278 3 59 | 0 24 7 2 | 6000 | | | Toulon | 1885 | .. | 19½ | 9½ | 3 | 2 10-8-in., 6 3-9-in. Q.F., 6 1-8-in., 2 M., 6 1-4-in. | 4 | 14-5 | 400 | 332 |
| <i>l.</i> | Carnot | S. | 12,008 | 352 2 70 | 6 27 3 2 | 16,300 | | | Toulon | 1894 | 1,070,088 | 17¾ 10¾ | 14½ | 2¾ | 2 12-in., 2 10-8-in., 8 5-5-in. Q.F., 4 2-5-in., 16 1-8-in., 10 1-4-in. | 4 (2 sub.) | 17-86 | 705 | 625 |
| <i>a.c.</i> | Chanzy | S. | 4933 | 348 0 46 | 0 19 2 2 | 8300 | B | | Bordeaux | 1894 | 360,000 | 3¾ | 2 | 2 | 2 7-6-in., 6 5-5-in. Q.F., 4 2-5-in., 6 1-8-in., 6 1-4-in., M. | 4 | 19-0 | 413 | 375 |
| <i>l.</i> | Charlemagne | S. | 11,275 | 385 6 66 | 6 27 6 3 | 14,500 | B | | Brest | 1895 | 1,096,432 | 15¾ | 15¾ | 3½ | 4 12-in., 10 5-5-in. Q.F., 8 3-9-in., 16 1-8-in., 10 1-4-in. (2 sub.) in., 8 M. | 4 | 18-1 | 680 | 631 |
| <i>l.</i> | Charles Martel | S. | 11,880 | 392 6 71 | 0 27 6 2 | 14,996 | | | Brest | 1893 | 1,092,830 | 17¾ | 15¾ | 3½ | 2 12-in., 2 10-8-in., 8 5-5-in. Q.F., 4 2-5-in., 14 1-8-in., 5 1-4-in. | 6 | 18-1 | 677 | 632 |
| <i>a.g.b.</i> | Coccyte | I. & S. | 1714 | 181 10 40 | 4 11 10 2 | 1700 | | | Cherbourg | 1887 | 100,000 | 8 | 8 | 2½ | 1 10-8-in., 2 3-9-in. Q.F., 2 1-8-in., 4 M. | .. | 13-0 | 100 | 101 |
| <i>a.c.</i> | Condé | S. | 10,000 | 453 0 63 | 9 24 7 3 | 20,500 | Nic. | | Cherbourg | Bdg. | 863,790 | 6-5 H.S. | 8, 5 | 2 | 2 7-6-in., 8 6-4-in. Q.F., 6 3-9-in., 16 1-8-in., 6 1-4-in. | 5 (2 sub.) | 21-0 | .. | .. |
| <i>e.b. & b.</i> | Courbet | I. & S. | 10,808 | 312 0 67 | 0 25 0 2 | 8100† | B | | Toulon | 1881 1899 | 800,000 | 15 | 9½ | 2½ | 4 10-8-in., 4 9-4-in., 6 5-5-in., 2 Q.F., 18 M.* | 5 | 15-4 | 1000 | 669 |
| <i>a.c.</i> | Desaix | S. | 7700 | 426 6 58 | 4 24 4 3 | 17,100 | B | | St. Nazaire | 1901 | 762,739 | 4 | 3½ | 2½ | 8 6-4-in. Q.F., 4 3-9-in., 10 1-8-in., 4 1-4-in.† | 2 | 21-0 | 880 1200 | 531 |
| <i>e.b. & b.</i> | Dévastation | I. & S. | 10,704 | 312 0 67 | 0 25 0 2 | 8320 | B | | Lorient | 1879 1901 | .. | 15 | 9½ | 2½ | 4 10-8-in., 2 9-4-in., 6 5-5-in., 4 3-9-in., 9 smaller Q.F., 18 M.* | 4 | 15-17 | 950 | 685 |
| <i>a.c. & b.</i> | Duguesclin | I. shd. | 6210 | 266 0 57 | 0 25 3 2 | 3300 | | | Rocheport | 1883 | 220,000 | 9 comp. | 8 | 2 | 4 9-4-in., 1 7-6-in., 6 5-5-in., 1 3-5-in. Q.F., 10 M. | 2 | 14-0 | 400 | 430 |
| <i>a.c.</i> | Dupetit-Thouars | S. | 9517 | 452 9 63 | 8 24 7 3 | 19,600 | B | | Toulon | Bdg. | 831,839 | 6-3¾ H.S. | 8, 3¾ | 2 | 2 7-6-in., 8 6-4-in. Q.F., 4 3-9-in., 16 1-8-in., 6 1-4-in. | 2 (2 sub.) | 21-0 | 1020 | 612 |

* New armament.

† Has received new boilers.

‡ Intended Armament. Reconstruction of Amiral Duperré to be completed 1901.

§ Including liquid fuel.

FRANCE.—Armoured Ships—continued.

310

| Class. | NAME | Material of Hull | Displacement. | Length. | Beam. | Draught. | Propellers. | Indicated Horse-power. | Where Built. | Date of Launch. | Cost. | Armour. | | | Armament. | | Speed. | Normal Coal Supply. | Complement. |
|------------|---------------|------------------|---------------|---------|---------|----------|-------------|------------------------|--------------|-----------------|-----------|---------|---------------|---------------|---|----------------|--------|---------------------|-------------|
| | | | metric tons. | ft. in. | ft. in. | ft. in. | no. | | | | £ | Belt. | Gun Position. | Deck Plating. | Guns. | Torpedo Tubes. | knots. | tons. | |
| a.c. | Dupleix | S. shd. | 7700 | 426 | 658 | 424 | 4 | 17,100 | Rocheport | 1900 | 652,354 | 4 | 3½ | 2½ | 10 6-4-in. Q.F., 10 1-8-in. 1-4-in. | 2 | 21-0 | 880 | 531 |
| " | Dupuy de Lôme | S. | 6406 | 374 | 651 | 623 | 6 | 14,000 | Brest | 1890 | 416,000 | 4 | 4 | 2 | 2 7-6-in., 6 6-4-in. Q.F., 12 2-5-in., 1-8-in., 8 M. | 4 | 20-0 | 900 | 515 |
| a.g.b. | Flamme | S. | 1128 | 165 | 632 | 710 | 4 | 1500 | Cherbourg | 1885 | 68,000 | 10 | 4 | 2 | 1 9-4-in., 1 3-5-in., 4 M. | 1 | 13-0 | 120 | 84 |
| b. | Formidable | S. | 12,165 | 321 | 639 | 626 | 2 | 9700* | Lorient | 1885 | 467,520 | 21½ | 17½ | 3 | 2 14-6-in., 8 6-4-in. Q.F., 8 5-5-in., 9 1-8-in., 14 M.** | 6 | 16-0 | 900 | 640 |
| a.b. & b. | Friedland | I. | 8994 | 317 | 658 | 629 | 11 | 4428 | Lorient | 1873 | .. | 8 | 7 | .. | 8 10-8-in., 8 5-5-in., 20 M. | 4 | 13-8 | 800 | 676 |
| c.d.s., t. | Fulminant | I. & S. | 5965 | 248 | 657 | 921 | 4 | 4500 | Cherbourg | 1877 | .. | 13 | 12 | 2 | 2 10-8-in., 4 1-8-in. Q.F., 6 M. | 2 | 13-8 | 400 | 248 |
| c.d.s., b. | Furieux | I. & S. | 6019 | 247 | 1059 | 921 | 9 | 5033 | Cherbourg | 1883 | 234,640 | 20 | 17½ | 3½ | 2 9-4-in., 5 Q.F., 10 M.** | 2 | 14-0 | 290 | 248 |
| a.g.b. | Fusée | S. shd. | 1142 | 165 | 632 | 710 | 4 | 1500 | Lorient | 1884 | 68,000 | 10 | 4 | 2 | 1 9-4-in., 1 3-5-in., 4 M. | 1 | 13-0 | 120 | 84 |
| t. | Gaulois | S. | 11,275 | 385 | 666 | 627 | 6 | 14,500 | Brest | 1896 | 1,063,925 | 15½ | 15½ | 3½ | 4 12-in., 10 5-5-in. Q.F., 8 3-9-in., 16 1-8-in., 10 1-4-in., 8 M. | 6 | 18-0 | 680 | 632 |
| a.c. | Gloire | S. | 10,000 | 453 | 663 | 924 | 7 | 20,500 | Lorient | 1900 | 883,269 | 6-5 | 8, 5 | 2 | 2 7-6-in., 8 6-4-in. Q.F., 6 3-9-in., 16 1-8-in., 6 1-4-in. | 5 | 21-0 | .. | .. |
| a.g.b. | Grenade | S. shd. | 1089 | 165 | 632 | 710 | 4 | 1500 | Lorient | 1888 | 68,000 | 10 | 4 | 2 | 1 9-4-in., 1 3-5-in., 4 M. | 1 | 13-0 | 120 | 84 |
| t. | Henri IV. | S. | 8948 | 354 | 472 | 322 | 11 | 11,500 | Cherbourg | 1899 | 801,248 | 11-4½ | 11½ | 3 | 2 10-8-in., 7 5-5-in. Q.F., 12 1-8-in., 2 M. | 2 | 17 | 725 | 464 |
| t. & b. | Hoche | I. & S. | 10,997 | 333 | 665 | 727 | 3 | 11,300 | Lorient | 1886 | 700,000 | 18 | 16 | 3 | 2 13-4-in., 2 10-8-in., 12 5-5-in. Q.F., 4 2-5-in., 9 1-8-in., 12 1-4-in., 8 M. | 5 | 16-0 | 800 | 660 |
| t. | Iéna | S. | 12,052 | 400 | 968 | 227 | 6 | 15,500 | Brest | 1898 | 1,111,340 | 13½-4½ | .. | 2½ | 4 12-in., 8 6-4-in. Q.F., 8 3-9-in., 16 1-8-in., 5 1-4-in., 13 1-4-in. M. | 4 | 18-0 | 820 | 631 |

| | | | | | | | | | | | | | | | | | | | | |
|----------------------|-------------------|---------|--------|-----|------|-------|----|---|-----------------|-------------|--------------|-----------|-----------------|---------------|-------------|--|---------------|-------|------|-----|
| <i>t.</i> | Indomptable† | I. & S. | 7234 | 279 | 1059 | 0 23 | 6 | 2 | 6605 Nic. | Lorient | 1883 1900 | .. | 20 | 9½ | 3 | 2 10-8-in., 6 3-9-in. Q.F., 6 1-8-in., 6 1-4-in., 2 M. | 4 | 14-8 | 400 | 332 |
| <i>t.</i> | Jauréguiberry | S. | 11,824 | 364 | 672 | 10 27 | 9 | 2 | 15,800 D'A. | La Seyne | 1893 | 1,069,536 | 17½ | 14½ | 2½ | 2 12-in., 2 10-8-in., 8 5-5-in. Q.F., 4 2-5-in., 12 1-8-in., 8 1-4-in., 8 M. | 6 | 18-07 | 700 | 625 |
| <i>a.c.</i> | Jeanne d'Arc | S. | 11,329 | 477 | 263 | 8 26 | 7 | 3 | 28,000 Guyot | Toulon | 1899 | 875,847 | 6-3 H.S. | 6 | 2 2 H.S. | 2 7-6-in., 8 5-5-in. Q.F., 10 3-9-in., 16 1-8-in., 8 1-4-in., 2 M. | 2 (sub.) | 23 | 1400 | 626 |
| <i>c.d.s., t.</i> | Jemmapes | S. | 6592 | 284 | 657 | 8 22 | 0 | 2 | 9250 D'A. | St. Nazaire | 1892 | 525,000 | 17½-10 | 17½ | 4-2½ | 2 13-4-in., 4 3-9-in. Q.F., 4 1-8-in. Q.F., 10 1-4-in. M. | 2 | 16-7 | 300 | 334 |
| <i>a.c.</i> | Jules Ferry | S. | 12,416 | 474 | 671 | 2 26 | 3 | 3 | 24,000 W.T. | Cherbourg | 1891 | 1,169,940 | 6 H.S. | 5-7½ | 2 | 4 7-6-in., 16 6-4-in. Q.F., 20 1-8-in., 4 1-4-in. | 5 (2 sub.) | 21-0 | 1350 | .. |
| <i>a.c.</i> | Kléber | S. | 7700 | 426 | 658 | 4 24 | 4 | 3 | 18,000 Nic. | Bordeaux | 1890 | 770,320 | 4 | 3½ | 2½ | 10 6-4-in. Q.F., 10 1-8-in., 1-4-in. | 2 | 21-0 | 880 | 531 |
| <i>a.c.</i> | Latouche-Tréville | S. | 4756 | 348 | 646 | 0 19 | 2 | 2 | 8300 B | Havre | 1892 | 360,000 | 3½ | 3½ | 2-1½ | 2 7-6-in., 6 5-5-in. Q.F., 4 2-5-in., 4 1-8-in., 6 1-4-in. M. | 4 | 18-2 | 406 | 375 |
| <i>a.c.</i> | Léon Gambetta | S. | 12,416 | 474 | 671 | 2 26 | 3 | 3 | 24,000 W.T. | Brest | 1891 | 1,169,940 | 6 H.S. | 5-7½ | 2 | 4 7-6-in., 16 6-4-in. Q.F., 20 1-8-in., 4 1-4-in. | 5 (2 sub.) | 21-0 | 1350 | .. |
| <i>b.</i> | Magenta | I. & S. | 10,851 | 330 | 665 | 7 27 | 3 | 2 | 12,000 | Toulon | 1890 | 760,960 | 18 | 16 | 3 | 4 13-4-in., 17 5-5-in. Q.F., 4 2-5-in., 12 1-8-in., 8 M. | 3 | 16-25 | 800 | 660 |
| <i>b.</i> | Marceau | I. & S. | 10,850 | 330 | 665 | 7 27 | 3 | 2 | 14,000 Nic. | La Seyne | 1887 | 769,080 | 18 | 16 | 3 | 4 13-4-in., 17 5-5-in. Q.F., 4 2-5-in., 12 1-8-in., 8 M. | 6 | 16-4 | 800 | 660 |
| <i>a.c.</i> | Marseillaise | S. | 10,014 | 453 | 663 | 9 24 | 7 | 3 | 20,500 B. | Brest | 1901 | 881,270 | 6 H.S. | 5-7½ | 2 | 2 7-6-in., 8 6-4-in. Q.F., 6 3-9-in., 2 2-5-in., 18 1-8-in., 6 1-4-in. | 4 (2 sub.) | 21-0 | 970 | .. |
| <i>t.</i> | Masséna | S. | 11,924 | 384 | 1066 | 0 27 | 0 | 3 | 13,500 D'A. | St. Nazaire | 1895 | 1,100,400 | 17½-15½ H.S. | 15½ | 3½ | 2 12-in., 2 10-8-in., 8 5-5-in. Q.F., 8 3-9-in., 12 1-8-in., and 12 1-4-in. | 6 (2 sub.) | 17-1 | 630 | 642 |
| <i>a.g.b.</i> | Mitraille | S. | 1128 | 165 | 632 | 7 10 | 4 | 2 | 1500 | Rocheport | 1886 | 70,000 | 10 | 4 | 2 | 1 9-4-in., 1 3-5-in., 4 M. | .. | 13-0 | 120 | 84 |
| <i>a.c.</i> | Montcalm | S. | 9517 | 452 | 963 | 8 24 | 7 | 3 | 19,600 N. S. | La Seyne | 1900 | 902,809 | 6-3½ H.S. | 8, 3½ H.S. | 2 | 2 7-6-in., 8 6-4-in. Q.F., 4 3-9-in., 16 1-8-in., 6 1-4-in. | 2 (sub.) | 21-0 | 1020 | 612 |
| <i>b.</i> | Neptune | I. & S. | 10,983 | 330 | 665 | 7 27 | 3 | 2 | 12,000 B | Brest | 1887 | 780,000 | 18 | 16 | 3 | 4 13-4-in., 17 5-5-in. Q.F., 4 2-5-in., 12 1-8-in., 8 M. | 5 | 16-02 | 800 | 660 |
| <i>c.d.s.</i> | Onondaga | I. | 2593 | 226 | 649 | 3 16 | 0 | 2 | 642 | New York | 1863 | .. | 5½ | 11½ | 1 | 4 9-4-in., 4 M. | .. | 6-5 | 200 | 100 |
| <i>a.g.b.</i> | Phlégron | I. & S. | 1796 | 187 | 640 | 4 11 | 10 | 2 | 1700 | Cherbourg | 1890 | 142,000 | 9 | 8 | 2 | 1 10-8-in., 1 5-5-in. Q.F., 4 1-8-in., 4 M. | .. | 12-4 | 72 | 101 |
| <i>c.b. & b.</i> | Redoutable | I. & S. | 9437 | 318 | 264 | 8 25 | 6 | 2 | 6071 | Lorient | 1876 | .. | 14 | 9½ | 2½ | 8 9-4-in., 6 3-9-in. Q.F., 2 Q.F., 12 M.** | 4 | 14-66 | 1000 | 700 |

* Has received new boilers.

† New armament, armour, and approximately reduced displacement given. Reconstruction of Furieux, Magenta, Mareau and Neptune to be completed 1901.

** New armament.

‡ Including liquid fuel.

311

FRANCE.—Armoured Ships—continued.

| Class. | NAME. | Material. | Displacement. | Length. | Beam. | Draught. | Propellers. | Indicated Horse-power. | Where Built. | Date of Launch. | Cost. | Armour. | | | Armament. | | Speed. | Normal Coal Supply. | Complement. |
|------------|-------------|-----------|--------------------------|---------------------------------------|-------|----------|----------------|------------------------|--------------|-----------------|-----------|----------------|---------------|---|---|----------------|----------------|---------------------|-------------|
| | | | | | | | | | | | | Belt. | Gun Position. | Deck Plating. | Guns. | Torpedo Tubes. | | | |
| b. | Requin | I. & S. | metric tons. 7822 279 | ft. in. ft. in. no. 10 59 0 24 7 2 | | | | 7000 Nic. | Bordeaux | 1885 1900 | £ .. | inches. 19½ | inches. 9½ | inches. 3 | 2 10·8-in., 6 3·9-in. Q.F., 2 1·8-in., 6 1·4 in., 12 M.* | 4 | knots. 15·0 | tons. 400 | 332 |
| t. | Saint Louis | S. | 11,275 385 | 6 65 6 27 6 3 | | | 14,500 B | Lorient | | 1896 | 1,080,997 | 15½ H.S. | 3-15½ H.S. | 3½ | 4 12-in., 10 5·5-in. Q.F., 8 3·9-in., 16 1·8-in., 10 1·4-in., 8 M. (2 sub.) | 4 | 18·0 | 820 1150 | 631 |
| a.g.b. | Styx | I. & S. | 1796 187 | 0 40 4 11 10 2 | | | 1700 | Cherbourg | | 1892 | 142,000 | 9 | 8 | 2 1 10·8-in., 1 5·5-in. Q.F., 4 1·8-in., 4 M. | .. | 13·0 | 72 | 101 | |
| t. | Suffren | S. | 12,728 411 | 970 4 27 6 3 | | | 16,500 Nic. | Brest | | 1899 | 1,195,564 | 11½-5 H.S. | .. | 2½ | 4 12-in., 10 6·4-in. Q.F., 8 3·9-in., 20 1·8-in. (2 sub.) | 4 | 18·0 | 1820 1100 | .. |
| a.c. | Sully | S | 10,000 453 | 0 63 9 24 7 3 | | | 20,000 B. | La Seyne | | Bldg. | 954,536 | 6-5 H.S. | 8·5 H.S. | 2 | 2 7·6-in., 8 6·4-in. Q.F., 6 3·9-in., 16 1·8-in., 6 1·4-in. (2 sub.) | 5 | 21·0 | .. | .. |
| c.d.s., t. | Tempête | I. & S. | 4869 248 | 0 57 9 16 9 1 | | | 2193 | Brest | | 1876 | .. | 13 | 12 | 2 2 10·8-in., 4 1·8-in. Q.F., 6 M. | 2 | 11·7 | 200 | 197 | |
| b. | Terrible | I. & S. | 7575 279 | 10 59 0 24 7 2 | | | 6230 | Brest | | 1881 1899 | .. | 19½ | 17½ | 3 2 13·4-in., 6 3·9-in. Q.F., 2 1·8-in., 12 M.* | 4 | 14·5 | 400 | 332 | |
| c.d.s., b. | Tonnant | I. & S. | 5091 248 | 7 58 5 17 3 1 | | | 1935 | Roche fort | | 1880 | .. | 18 | 14½ | 3 2 13·4-in., 4 M. | .. | 11 5 | 200 | 197 | |
| c.d.s., t. | Tonnerre | I. & S. | 5858 248 | 0 57 9 21 4 1 | | | 4165 | Toulon | | 1875 | .. | 13 | 12 | 2 2 10·8-in., 4 1·8-in. Q.F., 6 M. | 2 | 14·01 | 400 | 249 | |
| c.d.s., t. | Valmy | S. | 6592 293 | 9 57 4 23 3 2 | | | 8954 | St. Nazaire | | 1892 | 578,957 | 17½ | 17½ | 4 2 13·4-in., 4 3·9-in. Q.F., 4 1·8-in., 10 M. | 2 | 16·7 | 300 | 297 | |
| a.c. | Vauban | I. | 6208 267 | 9 57 3 24 0 2 | | | 4560 | Cherbourg | | 1882 | .. | 10 | 8 | 2 4 9·4-in., 1 7·6-in., 6 5·5-in., 12 M. | 2 | 14·32 | 550 | 440 | |
| c.d.s., t. | Vengeur | I. & S. | 4709 248 | 0 57 9 16 9 2 | | | 2030 | Cherbourg | | 1878 | .. | 13 | 12 | 2 2 12·5-in., 4 1·8-in. Q.F., 6 M. | 2 | 10·83 | 200 | 107 | |
| a.c. | Victor Hugo | S. | 12,500 480 | 7 70 2 26 11 3 | | | 27,500 W.T. | Toulon | | Bldg. | 1,169,940 | 6 H.S. | 5-7½ H.S. | 2 | 4 7·6-in., 16 6·4-in. Q.F., 2 1·8-in., 2 1·4 in. (2 sub.) | 5 | 22·0 | 1920 2100 | 728 |

* New armament.

FRANCE.—Cruising Ships, &c.

| Class. | NAME. | Material. | Displacement. | Length. | Beam. | Draught. | Propellers. | Where Built. | Date of Launch. | Cost. | Armour. | | Armament. | | Speed. | Normal Coal Supply. | Complement. |
|-------------|------------------------------|-----------|----------------------|------------------|-------------------|----------------|-------------|--------------|-----------------|--------------|---------------|-------|--|----------------|-----------------|---------------------|-------------|
| | | | | | | | | | | | Gun Position. | Deck. | Guns. | Torpedo Tubes. | | | |
| 2nd cl. cr. | Alger | S. | metric tons. 4382 | ft. in. 346 0 | ft. in. 45 319 | ft. in. 6 2 | no. | Cherbourg | 1889 | £ 280,000 | in. | in. | 4 6·4-in. Q.F., 6 5·5-in., 10 other Q.F., 10 M. 4 5·5-in., 4 M. | 4 | knots. 19·61 | tons. 860 | 325 |
| g. v. | Amiral Parseval | W. & I. | 869 | 197 6 | 28 012 | 2 1 | 1 | Rocheport | 1879 | 33,772 | .. | .. | .. | .. | 12·33 | 150 | 116 |
| cr. | Amiral Rigault de Genouilly. | W. | 1756 | 236 3 | 35 517 | 0 1 | 1 | Brest | 1876 | 62,796 | .. | .. | 8 5·5-in., 8 M. | .. | 14·49 | 200 | 198 |
| cr. | Aréthuse | W. | 3665 | 277 6 | 43 621 | 9 1 | 1 | Toulon | 1882 | .. | .. | .. | 4 6·4-in., 22 5·5-in., 8 M. | .. | 14·0 | 500 | 474 |
| g. v. | Aspic | C. | 476 | 145 4 | 23 1010 | 6 1 | 1 | Rocheport | 1880 | .. | .. | .. | 2 5·5-in., 2 3·9-in. | .. | 10·3 | 50 | 80 |
| to. g. b. | Bombe | S. | 420 | 196 10 | 21 7 511 | 2 | 2 | Havre | 1885 | .. | .. | .. | 4 1·8-in. Q.F., 3 M. | 2 | 18·0 | 100 | 63 |
| 2nd cl. cr. | Bugeaud | S. | 3740 | 308 6 | 43 620 | 6 2 | 2 | Cherbourg | 1893 | 308,650 | 2 shield | 3 | 6 6·4-in. Q.F., 4 3·9-in., 1·8-in., 11 1·4-in. 2 5·5-in., 2 3·9-in. | 6 | 18·9 | 587 | 358 |
| g. v. | Capricorne | W. | 483 | 148 4 | 23 1010 | 5 1 | 1 | Havre | 1882 | .. | .. | .. | .. | .. | 11·18 | 70 | 80 |
| to. g. b. | Casabianca | S. | 960 | 262 6 | 26 1011 | 6 2 | 2 | Bordeaux | 1895 | 98,985 | .. | ½ | 1 3·9-in. Q.F., 3 2·5-in., 5 1·8-in., 4 1·4-in. | .. | 22·0 | 116 | 143 |
| 2nd cl. cr. | Cassard | S. | 3952 | 325 6 | 44 1120 | 6 2 | 10, 143 | Cherbourg | 1896 | 318,712 | 2 shield | 3 | 6 6·4-in. Q.F., 4 3·9-in., 1·8-in., 3 1·4-in., 2 M. | 2 | 19·8 | 630 | 385 |
| to. g. b. | Cassini | S. | 958 | 262 6 | 27 411 | 6 2 | 2 | Bordeaux | 1894 | 98,500 | .. | ½ | 1 3·9-in. Q.F., 3 2·5-in., 4 1·4-in. | 2 | 21·2 | 110 | 118 |
| 2nd cl. cr. | Catinat | S. Shd. | 4065 | 331 10 | 44 821 | 1 2 | 2 | Havre | 1896 | 324,992 | 2 shield | 3 | 4 6·4-in. Q.F., 10 3·9-in., 1·8-in., 4 1·4-in. M. | 2 | 19·0 | 563 | 384 |
| 2nd cl. cr. | Cécille | I. & S. | 5933 | 378 9 | 49 319 | 9 2 | 10, 200 | La Seyne | 1888 | 299,666 | .. | 4 | 8 6·4-in. Q.F., 10 5·5-in., 6 1·8-in., 14 M. | 4 | 19·0 | 940 | 486 |
| 2nd cl. cr. | Chasseloup-Laubat | S. | 3758 | 308 6 | 43 620 | 10 2 | 2 | Cherbourg | 1893 | 256,320 | .. | 3 | 6 6·4-in. Q.F., 4 3·9-in., 1·8-in., 12 1·4-in. M. | 6 | 19·25 | 587 | 358 |
| 1st cl. cr. | Châteaurenault | S. Shd. | 8018 | 442 10 | 55 924 | 6 3 | 23, 900 | La Seyne | 1898 | 606,656 | 2 shield | 2½ | 2 6·4-in. Q.F., 6 5·5-in., 10 1·8-in. | .. | 23 | 1400 | 625 |
| | | | | | | | N.S. | | | | | | | | | 2100 | |

| Class. | NAME. | Material. | Displacement. | Length. | | Beam. | | Draft. | | Propellers. | Indicated Horse-power. | Where Built. | Date of Launch. | Cost. | Armour. | | Armament. | | Speed. | Complement. |
|-------------|-----------------|-----------|---------------|---------|-----|-------|-------|--------|-----|-------------|------------------------|--------------|-----------------|-------|---------------|-------|--|----------------|--------|-------------|
| | | | | ft. | in. | ft. | in. | ft. | in. | | | | | | Gun Position. | Deck. | Guns. | Torpedo Tubes. | | |
| 3rd cl. cr. | Cœlogon | S. | 1932 | 312 | 0 | 30 | 5 14 | 0 | 2 | 5800 | St. Nazaire | 1889 | 134,000 | £ | in. | in. | 4 5.5-in. Q.F., 3 other Q.F., 4 M. | 5 | 19.3 | 200 |
| g. v. | Comète | C. | 495 | 151 | 6 | 24 | 9 10 | 6 | 1 | 631 | Cherbourg | 1884 | .. | .. | .. | .. | 2 5.5-in., 2 3.9-in., 2 M. | .. | 12.2 | 60 |
| to. cr. | Condor | S. | 1243 | 216 | 6 | 29 | 3 15 | 5 | 2 | 3800 | Rocheport | 1885 | 80,000 | .. | .. | .. | 5 3.9-in. Q.F., 1 2.5-in., 6 M. | 5 | 17.7 | 160 |
| 3rd cl. cr. | Cosmao | S. | 1954 | 312 | 0 | 30 | 5 14 | 0 | 2 | 6000 | Bordeaux | 1888 | 133,000 | .. | .. | .. | 4 5.5-in. Q.F., 8 other Q.F., 4 M. | 5 | 20.5 | 200 |
| to. g. b. | Couleuvrine | S. | 435 | 196 | 10 | 21 | 7 5 | 11 | 2 | 2047 | Havre | 1885 | 33,778 | .. | .. | .. | 4 1.8-in. Q.F., 3 M. | 2 | 18.0 | 100 |
| to. g. b. | Dague | S. | 408 | 196 | 10 | 21 | 7 5 | 11 | 2 | 2000 | Havre | 1885 | 36,119 | .. | .. | .. | 4 1.8-in. Q.F., 3 M. | 2 | 18.0 | 100 |
| 2nd cl. cr. | D'Assas | S. | 4000 | 325 | 6 | 44 | 11 20 | 6 | 2 | 9500 | St. Nazaire | 1896 | 292,682 | .. | 2 shield | 3 | 6 6.4-in. Q.F., 4 3.9-in., 10 1.8-in., 11 1.4-in. | 2 | 19.25 | 630 |
| 2nd cl. cr. | Davout | S. | 2291 | 295 | 4 | 40 | 0 17 | 6 | 2 | 9000 | Toulon | 1890 | 221,827 | .. | .. | .. | 6 6.4-in. Q.F., 4 3.9-in., 4 2.5-in., 4 1.8-in., 6 M. | 4 | 20.07 | 600 |
| g. v. | Décidée | S. | 645 | 184 | 8 | 26 | 3 12 | 2 | 1 | Nic. | Lorient | 1899 | 54,100 | .. | .. | .. | 2 3.9-in. Q.F., 4 2.5-in., 4 1.4-in. | .. | 13.0 | 99 |
| 1st cl. cr. | D'Entrecasteaux | S. | 8114 | 383 | 7 | 58 | 6 25 | 9 | 2 | 13,500 | La Seyne | 1896 | 667,740 | .. | 10-2 1/2 H.S. | 4 | 2 9.4-in., 12 5.5-in. Q.F., 12 1.8-in. | 6 | 19.24 | 650 |
| 2nd cl. cr. | Descartes | shd. | 3990 | 326 | 0 | 42 | 4 21 | 4 | 2 | 9000 | St. Nazaire | 1894 | 334,725 | .. | .. | .. | 4 6.4-in. Q.F., 10 3.7-in., 8 1.8-in., 4 1.4-in. | 2 | 21.04 | 552 |
| cr. | D'Estaing | W. & L. | 2435 | 262 | 5 | 37 | 5 18 | 8 | 1 | 3700 | Brest | 1879 | 84,718 | .. | .. | .. | 15 5.5-in., 8 M. | .. | 15.31 | 300 |
| 3rd cl. cr. | D'Estrées | S. | 2452 | 311 | 8 | 39 | 4 17 | 8 | 2 | 8500 | Rocheport | 1897 | 208,200 | .. | .. | .. | 2 5.5-in. Q.F., 4 3.9-in., 8 1.8-in., 2 1.4-in. | .. | 20.5 | 345 |
| to. g. b. | D'Iberville | shd. | 967 | 262 | 6 | 27 | 0 11 | 2 | 2 | 5060 | St. Nazaire | 1893 | 99,120 | .. | .. | .. | 1 3.9-in. Q.F., 1 2.5-in., 4 1.4-in. | 6 | 21.4 | 117 |
| to. g. b. | Dragonne | S. | 410 | 196 | 10 | 21 | 7 5 | 11 | 2 | 2000 | Havre | 1885 | 36,074 | .. | .. | .. | 4 5.5-in. Q.F., 3 M. | 2 | 18.0 | 100 |
| cr. | Dubourdieu | W. | 3577 | 253 | 7 | 46 | 6 22 | 10 | 1 | 3300 | Cherbourg | 1884 | 154,553 | .. | .. | .. | 4 6.4-in., 12 5.5-in., 10 M. | 2 | 14.0 | 600 |
| 2nd cl. cr. | Du Chayla | S. | 3952 | 325 | 6 | 44 | 11 20 | 6 | 2 | 10,000 | Cherbourg | 1895 | 315,835 | .. | 2 shield | 3 | 6 6.4-in. Q.F., 4 3.9-in., 10 1.8-in., 3 1.4-in., 2 M. | 2 | 20.2 | 624 |

| | | | | | | | | | | | | | | | | | | | | | |
|-------------|----------------------------|---------|------|-----|----|----|-------|----|---|--------|-------------|-----------|---------|---------|-----------|----|---|----|-------|------|-----|
| to. g. b. | Dunois (ex M 3). | S. | 896 | 256 | 0 | 27 | 10 12 | 8 | 2 | 7000 | N.S. | Cherbourg | 1897 | 123,383 | .. | .. | 6 2.5-in. Q.F., 6 1.8-in. | .. | 23.0 | 137 | 128 |
| cr. | Duquesne | I. & W. | 5986 | 333 | 5 | 50 | 3 25 | 6 | 1 | 6589 | Rocheport | 1876 | 221,570 | .. | .. | .. | 7 6.4-in. Q.F., 14 5.5-in., 8 M. | .. | 16.8 | 900 | 550 |
| cr. | Éclairer | I. & W. | 1769 | 236 | 3 | 35 | 5 17 | 0 | 1 | 2050 | Toulon | 1877 | 16,232 | .. | .. | .. | 8 5.5-in., 6 M. | .. | 15.0 | 200 | 195 |
| to. cr. | Epervier | S. | 1288 | 216 | 6 | 29 | 3 15 | 5 | 2 | 3200 | Rocheport | 1885 | 80,000 | .. | .. | 1½ | 5 3.9-in. Q.F., 1 2.5-in., 6 M. | 5 | 17.6 | 160 | 134 |
| g. v. | Etoile | C. | 502 | 149 | 3 | 24 | 7 8 | 4 | 2 | 450 | France | 1885 | 29,782 | .. | .. | .. | 6 3.9-in., 1 2.5-in., 2 M. | .. | 10.0 | 60 | 77 |
| cr. | Fabert | W. | 2100 | 294 | 4 | 36 | 0 18 | 4 | 1 | 1107 | Rocheport | 1874 | 61,967 | .. | .. | .. | 8 5.5-in., 4 M. | .. | 12.42 | 300 | 218 |
| to. cr. | Faucon | S. | 1239 | 216 | 6 | 29 | 3 15 | 5 | 2 | 3200 | Toulon | 1887 | 80,000 | .. | .. | 1½ | 5 3.9-in. Q.F., 1 2.5-in., 6 M. | 5 | 18.0 | 150 | 134 |
| to. g. b. | Flèche | S. | 425 | 196 | 10 | 21 | 7 5 | 11 | 2 | 2000 | Havre | 1885 | 37,517 | .. | .. | .. | 4 1.8-in. Q.F., 3 M. | 2 | 18.0 | 100 | 63 |
| 3rd cl. cr. | Fleurus | S. | 1310 | 229 | 8 | 29 | 2 15 | 4 | 2 | 4000 | Cherbourg | 1893 | 128,830 | .. | .. | .. | 5 3.9-in. Q.F., 6 1.8-in., 4 M. | .. | 17.6 | 118 | 179 |
| " | Forbin | S. | 1820 | 312 | 0 | 30 | 5 16 | 0 | 2 | 5700 | Rocheport | 1888 | 123,739 | .. | .. | 1½ | 4 5.5-in. Q.F., 8 other Q.F., 4 M. | 5 | 20.6 | 200 | 190 |
| cr. | Forfait | W. & L. | 2464 | 249 | 4 | 38 | 0 18 | 0 | 1 | 2764 | Toulon | 1879 | 77,019 | .. | .. | .. | 15 5.5-in., 8 M. | .. | 13.44 | 400 | 264 |
| cr. | Foudre (torpedo transport) | S. | 6090 | 370 | 6 | 52 | 6 23 | 6 | 2 | 11,900 | Bordeaux | 1895 | 407,712 | .. | .. | 3½ | 10 3.9-in. Q.F., 4 2.5-in., 4 1.4-in. | 4 | 19.9 | 840 | 410 |
| 2nd cl. cr. | Friant | S. | 3739 | 308 | 6 | 43 | 6 20 | 10 | 2 | 9000 | Brest | 1893 | 308,750 | .. | .. | 3 | 6 6.4-in. Q.F., 4 3.9-in., 8 1.8-in., 6 1.4-in. | 2 | 18.19 | 587 | 358 |
| g. v. | Fulton | W. | 913 | 199 | 5 | 28 | 5 12 | 8 | 1 | 850 | Lorient | 1887 | 37,000 | .. | .. | .. | 2 5.5-in., 1 3.9-in., 5 M. | .. | 13.0 | 160 | 116 |
| " | Gabès | C. | 493 | 151 | 6 | 24 | 9 10 | 6 | 1 | 450 | Rocheport | 1884 | 28,624 | .. | .. | .. | 2 5.5-in., 2 3.9-in. | .. | 11.0 | 60 | 84 |
| 3rd cl. cr. | Galilée | S. | 2317 | 330 | 2 | 34 | 6 17 | 10 | 2 | 6600 | Rocheport | 1896 | 208,152 | .. | 2 shields | 1½ | 4 5.5-in. Q.F., 2 3.9-in., 8 1.8-in., 8 1.4-in. | 8 | 20.0 | 226 | 248 |
| 1st cl. cr. | Guichen | S. | 8277 | 436 | 4 | 54 | 10 24 | 7 | 3 | 24,000 | St. Nazaire | 1897 | 611,945 | .. | 2 shield | 2½ | 2 6.4-in. Q.F., 6 5.5-in., 10 1.8-in. | .. | 23.0 | 1460 | 625 |
| cr. | Iphigénie (Training ship) | W. | 3431 | 244 | 6 | 46 | 6 22 | 4 | 1 | 2800 | .. | 1881 | 115,323 | .. | .. | .. | 6 6.4-in., 2 3.5-in., 10 M. | 1 | 14.6 | 400 | 391 |

FRANCE.—Cruising Ships, &c.—*continued.*

| Class. | NAME. | Material of Hull. | Displacement. | Length. | Beam. | Draught. | Propellers. | Indicated Horse-power. | Where Built. | Date of Launch. | Cost. | Armour. | | Armament. | | Speed. | Complement. |
|------------------|-----------------------|-------------------|-------------------|---------------|--------------|--------------|-------------|------------------------|--------------|-----------------|-----------|-----------------|-------|--|----------------|-------------|---------------|
| | | | | | | | | | | | | Gunn. Position. | Deck. | Guns. | Torpedo Tubes. | | |
| 3rd cl. cr. | Infernet . | S. shd. | metric tons. 2452 | ft. in. 311 8 | ft. in. 39 4 | ft. in. 15 6 | 2 | 8500 | Bordeaux | 1899 | £ 193,000 | inches. . | .. | 2 5.5-in. Q.F., 4 3.9-in. 8 1.8-in. | .. | knots. 20.5 | 345 tons. 234 |
| 2nd cl. cr. | Isly . | S. | 4477 | 346 0 | 43 6 | 19 6 | 2 | 8100 | Brest . | 1891 | 252,760 | .. | 3 | 4 6.4-in. Q.F., 6 5.5-in., 14 2.5-in. and 1.8-in., 8 M. | 5 | 18.3 | 880 332 |
| 2nd cl. cr. | Jurien de la Gravière | S. shd. | 5605 | 440 0 | 48 8 | 22 0 | 3 | 17,000 | Lorient | 1899 | 475,979 | .. | 3 | 8 6.4-in. Q.F., 12 1.8-in. | 2 | 23.0 | 600 511 |
| 2nd cl. cr. | Jean Bart | S. | 4109 | 346 0 | 43 6 | 19 6 | 2 | 8000 | Rochefort | 1889 | 283,240 | .. | 4 | 4 6.4-in. Q.F., 6 5.5-in., 14 2.5-in., and 1.8-in., 8 M. | 5 | 19.0 | 940 332 |
| <i>g. v.</i> | Kersaint . | S. shd. | 1243 | 226 0 | 34 5 | 15 0 | 1 | 2200 | Rochefort | 1897 | 107,933 | .. | .. | 1 5.5-in. Q.F., 5 3.9-in., 7 1.4-in. | .. | 15.0 | 199 110 |
| <i>to. g. b.</i> | La Hire . | S. | 896 | 256 0 | 27 10 | 12 9 | 2 | 7000 | Cherbourg | 1898 | 123,383 | .. | .. | 6 2.5-in. Q.F., 6 1.8-in. | .. | 23.0 | 137 128 |
| 3rd cl. cr. | Lalande . | S. | 1926 | 311 6 | 31 2 | 14 0 | 2 | 6000 | Bordeaux | 1888 | 133,800 | .. | 1½ | 6 5.5-in. Q.F., 8 other Q.F., 4 M. | 5 | 22.0 | 200 190 |
| <i>to. g. b.</i> | Lance . | S. | 402 | 196 10 | 21 7 | 5 11 | 2 | 2000 | Havre . | 1886 | 39,964 | .. | .. | 4 1.8-in. Q.F., 3 M. | 2 | 18.0 | 100 63 |
| cr. | Lavoisier | S. | 2317 | 330 2 | 34 6 | 17 10 | 2 | 6400 | Rochefort | 1897 | 202,024 | 2 shield | 1½ | 4 5.5-in. Q.F., 2 3.9-in., 8 1.8-in., 2 1.4-in., 4 M. | 2 | 20.0 | 226 248 |
| <i>to. g. b.</i> | Léger . | S. | 517 | 197 0 | 23 0 | 10 6 | 2 | 2360 | Lorient | 1891 | 52,000 | .. | .. | 1 3.9-in. Q.F., 3 2.5-in., 4 1.4-in. | 3 | 18.8 | 130 69 |
| <i>to. g. b.</i> | Lévrier . | S. | 505 | 197 0 | 23 0 | 10 6 | 2 | 2240 | Lorient | 1891 | 52,000 | .. | .. | 1 3.9-in. Q.F., 3 2.5-in., 4 1.4-in. | 3 | 18.5 | 130 69 |

| | | | | | | | | | | | | | | | | | | | | | |
|-------------|--------------|---------|------|-----|----|----|-----|----|----|------|-----------|-------------|---------|----------|----|---|----------------------|-------|-------|-----|-----|
| 3rd cl. cr. | Linols | S. | 2345 | 321 | 6 | 34 | 617 | 5 | 2 | 6800 | La Seyne | 1894 | 163,014 | 8-9 | 1½ | 4 5-5-in. Q.F., 2 3-9-in., 8 1-8-in., 4 1-4-in., 4 M. | 4 | 20-5 | 200 | 248 | |
| g. v. | Lion. | C. | 503 | 151 | 6 | 24 | 910 | 6 | 1 | 576 | Hayre. | 1884 | 23,146 | .. | .. | 2 5-5-in., 4 M. | .. | 11-8 | 70 | 84 | |
| " | Lutin | C. | 493 | 141 | 9 | 23 | 11 | 9 | 4 | 1 | 373 | Cherbourg | 1877 | 20,295 | .. | .. | 2 5-5-in., 2 3-9-in. | .. | 10-0 | 60 | 77 |
| " | Lynx | C. | 485 | 141 | 9 | 23 | 11 | 9 | 4 | 1 | 427 | Cherbourg | 1878 | 21,478 | .. | .. | 2 5-5-in., 2 3-9-in. | .. | 10-38 | 60 | 77 |
| " | Météore | C. | 504 | 151 | 6 | 24 | 910 | 6 | 1 | 434 | Cherbourg | 1886 | 26,262 | .. | .. | 2 5-5-in., 3 M. | .. | 10-0 | 70 | 77 | |
| 3rd cl. cr. | Milan | S. | 1733 | 303 | 2 | 32 | 10 | 14 | 7 | 2 | 3986 | St. Nazaire | 1886 | 89,058 | .. | .. | 5 3-9-in. Q.F., 8 M. | 2 | 13-1 | 400 | 186 |
| cr. | Naiade | L. shd. | 3686 | 246 | 0 | 47 | 222 | 10 | 1 | 2700 | Toulon | 1881 | 128,275 | .. | .. | 2 6-4-in., 18 5-5-in., 10 M. | .. | 13-68 | 500 | 490 | |
| cr. | Nielly | W. & I. | 2400 | 262 | 5 | 37 | 518 | 8 | 1 | 2921 | Brest | 1880 | 84,037 | .. | .. | 15 5-5-in., 8 M. | .. | 15-23 | 300 | 264 | |
| 2nd cl. cr. | Pascal | S. | 4015 | 326 | 0 | 42 | 421 | 4 | 2 | 9000 | Toulon | 1895 | 322,321 | .. | 1½ | 4 6-4-in. Q.F., 10 3-9-in., 8 1-8-in., 4 1-4-in. M. | 2 | 20-0 | 650 | 378 | |
| cr. | Primauguet | W. & I. | 2447 | 262 | 5 | 37 | 518 | 8 | 1 | 2263 | Rochefort | 1882 | 108,592 | .. | .. | 15 5-5-in., 8 M. | .. | 14-50 | 300 | 264 | |
| 2nd cl. cr. | Protet | S. shd. | 4055 | 331 | 10 | 44 | 821 | 1 | 2 | 9300 | Bordeaux | 1898 | 324,992 | 2 shield | 2½ | 4 6-4-in. Q.F., 10 3-9-in., 10 1-8-in., 2 1-4-in. | 2 | 20-2 | 563 | 384 | |
| cr. | Roland | W. | 2476 | 249 | 4 | 38 | 017 | 7 | 1 | 2294 | Cherbourg | 1882 | 84,184 | .. | .. | 15 5-5-in., 8 M. | .. | 14-50 | 350 | 264 | |
| to g. b. | Sainte Barbe | S. | 437 | 196 | 10 | 21 | 7 | 5 | 11 | 2 | 2000 | Rouen | 1885 | 43,233 | .. | 1½ | 4 1-8-in. Q.F., 3 M. | 2 | 18-0 | 100 | 63 |
| " | Salve | S. | 413 | 196 | 10 | 21 | 7 | 5 | 11 | 2 | 2000 | Rouen | 1886 | 42,538 | .. | 1½ | 4 1-8-in. Q.F., 3 M. | 2 | 18-0 | 100 | 63 |
| g. v. | Scorpion | C. | 505 | 151 | 6 | 24 | 910 | 6 | 1 | 511 | Hayre. | 1883 | 23,459 | .. | .. | 2 5-5-in., 3 M. | .. | 11-0 | 70 | 84 | |

FRANCE.—Cruising Ships, &c.—continued.

816

| Class. | NAME. | Material of Hull. | Displacement. | | Length. | | Beam. | | Draught. | | Propellers. | Indicated Horse-Power. | Where Built. | Date of Launch. | Cost. | Armour. | | Armament. | | Speed. | Normal Coal Supply. | Complement. |
|-------------|------------|-------------------|---------------|---------|---------|---------|---------|---------|----------|---------|-------------|------------------------|--------------|-----------------|-------|---------------|-------|---|----------------|--------|---------------------|-------------|
| | | | metric tons. | ft. in. | ft. in. | ft. in. | ft. in. | ft. in. | ft. in. | ft. in. | | | | | | Gun Position. | Deck. | Guns. | Torpedo Tubes. | | | |
| 2nd cl. cr. | Sfax | S. & W. | 4728 | 288 | 9 | 49 | 3 | 24 | 9 | 2 | 6522 | Brest | 1884 1898 | 200,000 | £ | inches. | 1½ | 6 6·4-in. Q.F., 10 5·5-in., 6 1·8-in., 6 1·4-in., 4 M.† | 2 | 16·84 | 715 | 473 |
| 2nd cl. cr. | Suchet | S. | 3440 | 318 | 3 | 43 | 6 | 17 | 6 | 2 | 9000 | Toulon | 1893 | 226,360 | £ | .. | 3 | 4 6·4-in. Q.F., 4 3·9-in., 4 1·8-in., 8 1·4-in., 6 M. | 7 | 20·4 | 480 | 246 |
| 3rd cl. cr. | Surcouf | S. | 2044 | 312 | 0 | 30 | 5 | 14 | 0 | 2 | 6000 | Cherbourg | 1888 | 131,200 | £ | .. | 1½ | 4 5 5-in. Q.F., 8 other Q.F., 4 M. | 5 | 20 5 | 200 | 190 |
| g. v. | Surprise | S. | 627 | 184 | 8 | 24 | 7 | 12 | 3 | 1 | 853 | Havre | 1895 | 50,954 | £ | .. | .. | 2 3·9-in. Q.F., 4 2·5-in., 4 1·4-in. | .. | 13·4 | 73 | 99 |
| 1st cl. cr. | Tage | S. shd. | 7589 | 390 | 0 | 53 | 8 | 22 | 10 | 2 | 12,410 | St. Nazaire | 1886 | 93,857 | £ | .. | .. | 8 6·4-in., 10 5·5-in., 2 2·5-in., 6 Q.F., 14 M. | 7 | 19·0 | 1000 | 400 |
| 2nd cl. cr. | Tourville* | I. & W. | 5576 | 333 | 5 | 50 | 3 | 25 | 4 | 1 | 7466 | La Seyne | 1876 | 271,499 | £ | .. | .. | 7 6·4-in. Q.F., 14 5·5-in., 8 M. | .. | 16·89 | 800 | 550 |
| 3rd cl. cr. | Troude | S. | 2026 | 311 | 6 | 31 | 2 | 14 | 0 | 2 | 6000 | Bordeaux | 1888 | 33,383 | £ | .. | 1½ | 4 5·5-in. Q.F., 8 other do., 4 M. | 5 | 20·9 | 200 | 190 |
| t. g. b. | Vantour | S. | 1235 | 216 | 6 | 29 | 3 | 15 | 5 | 2 | 3391 | Toulon | 1886 | 87,733 | £ | .. | 1½ | 5 3 9-in. Q.F., 1 2 5-in. do., 6 M. | 5 | 17·3 | 150 | 134 |
| g. v. | Vipère | C. | 486 | 145 | 4 | 23 | 10 | 10 | 6 | 1 | 441 | Rochefort | 1881 | 26,835 | £ | .. | .. | 2 5·5-in., 2 3·9-in. | .. | 10·3 | 60 | 80 |
| " | Voltigeur | W. & L. | 943 | 199 | 5 | 28 | 5 | 12 | 7 | 1 | 999 | Brest | 1878 | 23,077 | £ | .. | .. | 4 5·5-in., 4 M. | .. | 12·48 | 150 | 116 |
| t. g. b. | Wattignies | S. | 1292 | 230 | 0 | 29 | 3 | 15 | 0 | 2 | 4189 | Rochefort | 1891 | 111,000 | £ | .. | .. | 5 3·9-in. Q.F., 6 1·8-in., 7 1·4-in., M. | 4 | 18·61 | 160 | 180 |
| g. v. | Zélée | S. | 646 | 185 | 6 | 26 | 0 | 10 | 6 | 1 | 1000 | Rochefort | 1899 | .. | £ | .. | .. | 2 3·9-in. Q.F., 4 2·5-in., 4 1·4-in. | .. | 13·0 | .. | 75 |

* New engines, 1893.

† New armament.

Shallow-draught gunboats Argus and Vigilante launched at Chiswick (Thornycroft) 1900:—displacement, 122 tons; length, 145 ft.; beam, 24 ft.; draught, 2 ft.; 2 screws; 550 I.H.P.; 13 knots; 2 3·5-in., 4 1·4-in. Q.F. guns; complement, 30; coal capacity, 80.

Merchant Cruisers (Auxiliary to French Navy).

| To what Company belonging. | Name. | Register Tonnage. | Length. | Beam. | Depth. | H.P. (nominal.) | Speed. | When built. |
|-------------------------------------|--------------------|-------------------|---------|-------|--------|-----------------|--------|-------------|
| | | Tons. | Feet. | Feet. | Feet. | | Knots. | |
| Compagnie Générale Transatlantique* | La Touraine | 8893 | 520.2 | 56.0 | 34.6 | 1616 | 19 | 1890 |
| | Duc de Bragance | 2096 | 334.6 | 34.2 | 16.8 | 426 | 17½ | 1889 |
| | Eugène Pereire | 2078 | 331.6 | 35.1 | 23.9 | 437 | 17½ | 1888 |
| | Général Chanzy | 2299 | 341.2 | 35.7 | 15.5 | 478 | 17½ | 1891 |
| | La Bretagne | 7112 | 495.4 | 51.8 | 34.5 | 1149 | 17½ | 1886 |
| | La Champagne | 7087 | 493.4 | 51.8 | 34.5 | 1149 | 17½ | 1885 |
| | La Gascogne | 7395 | 495.4 | 52.2 | 34.8 | 1308 | 17½ | 1886 |
| | Maréchal Bugeaud | 2206 | 342.5 | 34.1 | 23.0 | 482 | 17½ | 1890 |
| | Ville d'Alger | 2211 | 342.7 | 36.1 | 23.0 | 208 | 17½ | 1890 |
| | La Navarre | 6648 | 471.0 | 50.5 | 36.4 | 983 | 17 | 1892 |
| | La Normandie | 6283 | 459.3 | 49.2 | 34.1 | 1147 | 16 | 1882 |
| | Ville de Tunis | 1966 | 317.3 | 34.6 | 16.8 | 444 | 15½ | 1884 |
| | Moïse | 1873 | 310.0 | 33.5 | 16.7 | 443 | 15 | 1880 |
| | St. Augustin | 1854 | 314.0 | 33.8 | 16.5 | 443 | 15 | 1880 |
| Messageries Maritimes† | Versailles | 4336 | 373.7 | 45.3 | 27.0 | 780 | .. | 1882 |
| | Ville de Madrid | 1874 | 308.7 | 33.5 | 16.7 | 370 | 15 | 1880 |
| | Ville de Naples | 1879 | 311.6 | 34.1 | 16.7 | 506 | 15 | 1881 |
| | Armand Béhic | 6467 | 486.6 | 50.1 | 36.8 | 821 | 17½ | 1892 |
| | Australien | 6428 | 482.3 | 49.2 | 34.1 | 818 | 17½ | 1889 |
| | Polynésien | 6506 | 482.3 | 49.2 | 34.1 | 818 | 17½ | 1890 |
| | Ville de la Ciotat | 6461 | 485.8 | 49.9 | 36.8 | 819 | 17½ | 1892 |
| | Ernest Simons | 4562 | 442.9 | 47.1 | 36.7 | 727 | .. | 1893 |
| | Indus | 6357 | 446.2 | 50.8 | 35.1 | 417 | .. | 1897 |
| | Brésil | 5876 | 463.9 | 46.4 | 32.5 | 743 | 16½ | 1889 |
| | Chili | 6375 | 462.6 | 47.6 | 36.7 | 719 | .. | 1894 |
| | Cordillère | 6379 | 462.6 | 47.6 | 36.1 | 721 | .. | 1895 |
| | La Plata | 5807 | 462.6 | 45.9 | 32.5 | 520 | 16½ | 1889 |

NOTE.—The armament for the larger ships is 7 5.5-in and smaller quick-firers.

* Also the Lorraine and Savoie, 11,200 tons, and the Aquitaine, 8810 tons.

† Also the Tonkin, 7364 tons, and the Annam, 6343 tons.

| Class. | NAME. | Material. | Displacement. metric tons. | Length. ft. in. ft. in. | Beam. ft. in. ft. in. | Draught. ft. in. ft. in. | Propellers. no. | Where Built. | Date of Launch. | Cost. £ | Armour. Gun Position Belt. | Deck Plating. | Armament. Guns. Torpedo Tubes. | Speed. knots. | Normal Coal Supply. tons. | Complement. |
|----------|-------------|-----------|----------------------------------|----------------------------|--------------------------|-----------------------------|--------------------|------------------|-----------------|--------------|-------------------------------------|------------------|---|------------------|---------------------------------|-------------|
| c. d. s. | Aegir | S. | 3800 236 6 50 | 6 17 9 2 | 4800 | T. | 4800 | Kiel | 1895 233,500 | 9½ H.S. | ins. 8½ H.S. | 2 | 39 4-in., 10 3 4-in. Q.F., 6 M. (1 sub.) | 14·8 | 225 | 276 |
| a. c. | B. | S. | 8868 836 0 64 | 3 25 3 3 | 15,000 | Dürr. | 15,000 | Kiel | Bldg. 1897 | 4 K.S. | 6 K.S. | 2½ | 4 8-2-in., 10 5-9-in. Q.F., 12 3-4-in., 10 1-4-in., 4 M. (3 sub.) | 20·5 | 950 | 528 |
| b. | Baden | L. | 7441 821 6 60 | 0 15 8 2 | 6200 | Dürr. | 6200 | Kiel | 1880 444,886 | 16 | 10 | 3 | 6 10-2-in., 8 3-4-in. Q.F., 8 1-4-in., 1 l., 6 M. (2 sub.) | 14·0 | 700 | 376 |
| a. g. b. | Basilisk | L. | 1109 154 3 36 | 0 10 2 2 | 759 | | 759 | Bremen | 1878 58,042 | 8 | 8 | 2 | 1 12-in., 2 3-3-in., 2 M. | 9·0 | 40 | 76 |
| b. | Bayern | L. | 7441 821 6 60 | 0 19 8 2 | 6326 | W.T. | 6326 | Kiel | 1878 406,660 | 16 | 10 | 3 | 6 10-2-in., 8 3-4-in. Q.F., 8 1-4-in., 1 l., 6 M. (2 sub.) | 14·0 | 700 | 376 |
| c. d. s. | Beowulf | S. | 3500 259 2 49 | 3 17 9 2 | 4800 | T.S. | 4800 | Bremen | 1890 175,000 | 9½ | 8 | 1½ | 39 4-in., 8 3-4-in. Q.F., 6 M. | 14·8 | 225 | 276 |
| b. | Brandenburg | S. | 10,100 354 4 65 | 0 24 7 2 | 9640 | | 9640 | Stettin (Vulcan) | 1891 606,500 | 15½ comp. | 11½ comp. | 2½ | 6 11-in., 6 4-1-in. Q.F., 8 3-4-in., 12 1-4-in., 8 M., 2 l. | 16·5 | 750 | 552 |
| a. g. b. | Biene | L. | 1109 154 3 36 | 0 10 2 2 | 759 | | 759 | Bremen | 1876 62,853 | 8 | 8 | 2 | 1 12-in., 2 3-3-in., 2 M. | 10·0 | 40 | 76 |
| a. g. b. | Camaleon | L. | 1109 154 3 36 | 0 10 2 2 | 759 | | 759 | Bremen | 1878 57,564 | 8 | 8 | 2 | 1 12-in., 2 3-3-in., 2 M. | 10·0 | 40 | 76 |
| " | Crocodil | L. | 1109 154 3 36 | 0 10 2 2 | 759 | | 759 | Bremen | 1879 57,237 | 8 | 8 | 2 | 1 12-in., 2 3-3-in., 2 M. | 10·0 | 40 | 76 |
| b. | Deutschland | L. | 7319 280 0 62 | 4 24 7 1 | 5380 | | 5380 | Poplar | 1874 412,022 | 10 | 8 | 2 | 8 10-2-in., 7 5-9-in., 9 3-4-in. Q.F., 12 M., 2 l. | 14·5 | 710 | 668 |

| | | | | | | | | | | | | | | | | | |
|----------|-----------------------------|----|-----------------|-----------|--------|---------|--------|----------------------------|--------------|------------|------------------|------|--|---|------|-------|-----|
| t. | Friedrich der Grosse | L. | 6770 307 0 53 | 6 24 7 1 | 5400 | | 5400 | Kiel | 1874 365,170 | 9½ | 8 br. 10 tur. | 8 | 4 10-2-in., 2 6-6-in., 10 3-4-in. Q.F., 8 M., 2 l. | 4 | 14·0 | 550 | 537 |
| a. c. | Fürst Bismarck | S. | 10,650 398 8 66 | 9 26 0 3 | 14,000 | Dürr. | 14,000 | Kiel | 1897 | 7½ H.S. | 7½ H.S. | 3 | 4 9-4-in., 12 5-9-in. Q.F., 10 3-4-in., 10 1-4-in., 8 M. (5 sub.) | 6 | 19·0 | 1000† | 565 |
| c. d. s. | Friehjof | S. | 3500 240 0 49 | 3 17 9 2 | 4800 | T.S. | 4800 | Bremen | 1891 175,000 | 9½ | 7½ H.S. | 1½ | 39 4-in., 8 3-4-in. Q.F., 6 M. | 4 | 14·8 | 225 | 276 |
| a. d. s. | Hagen* | S. | 3500 267 0 49 | 3 17 9 2 | 5250 | T. | 5250 | Kiel | 1893 1900 | 9½ H.S. | 7½ H.S. | 1½ | 3 9-4-in., 10 3-4-in. Q.F., 6 1-4-in., 8 M. (3 sub.) | 4 | 15·0 | 580 | 297 |
| a. d. s. | Heimdall | S. | 3500 240 0 49 | 3 17 9 2 | 4393 | T.S. | 4393 | Wilhelmshaven | 1892 233,500 | 9½ | 7½ H.S. | 1½ | 39 4-in., 8 3-4-in. Q.F., 6 M. | 4 | 14·8 | 225 | 276 |
| a. d. s. | Hildebrand | S. | 3500 240 0 49 | 3 17 9 2 | 4413 | T.S. | 4413 | Kiel | 1892 218,000 | 9½ | 7½ H.S. | 1½ | 39 4-in., 8 3-4-in. Q.F., 6 M. | 4 | 14·8 | 225 | 276 |
| a. g. b. | Hummel. | L. | 1109 143 0 35 | 0 10 2 2 | 759 | | 759 | Bremen | 1881 56,741 | 8 | 8 | 2 | 1 12-in., 2 3-3-in., 2 M. | 2 | 10·0 | 40 | 76 |
| b. | Kaiser | L. | 7531 292 0 62 | 4 24 7 1 | 5700 | | 5700 | Poplar | 1874 411,301 | 10 | 10 | 2 | 8 10-2-in., 15-9-in., 6 4-in., 9 3-4-in. Q.F., 2 M., 2 l. | 5 | 14·6 | 710 | 668 |
| t. | Kaiser Barbarossa | | 13,000 | | 13,000 | | 13,000 | Danzig (Schlesien) | 1896 | | | | | | | | |
| t. | Kaiser Friedrich III. | | 13,000 | | 13,000 | | 13,000 | Wilhelmshaven | 1900 | | | | | | | | |
| t. | Kaiser Wilhelm II. | S. | 11,130 377 4 66 | 10 25 6 3 | 13,000 | C.&T.S. | 13,000 | Wilhelmshaven | 1897 | 706,000 | 11½ H.N.S. | 9½-6 | 4 9-4-in. Q.F., 18 5-9-in. Q.F., 12 3-3-in., 12 1-4-in., 8 M. (5 sub.) | 6 | 18·0 | 650 | 700 |
| t. | Kaiser Wilhelm der Grosse. | | 13,000 | | 13,000 | | 13,000 | Kiel | 1899 | | | | | | | | |
| t. | Kaiser Karl der Grosse | | 13,000 | | 13,000 | | 13,000 | Hamburg (Blohm & Voss) | 1899 | | | | | | | | |
| t. | D. E. F. G. | S. | 11,800 398 9 68 | 2 24 10 3 | 14,000 | C.&T.S. | 14,000 | Danzig (Kiel) | 1897 | 832,500 | 9-4 K.S. | 10-6 | 4 9-4-in. Q.F., 18 5-9-in. Q.F., 12 3-3-in., 12 1-4-in., 8 M. (5 sub.) | 6 | 1·0 | 650 | 715 |
| t. | H. J.† | S. | 13,000 | | 13,000 | | 13,000 | Stettin (Wilhelmshaven) | 1896 | | | | | | | | |
| b. | König Wilhelm | L. | 9757 355 0 60 | 0 25 7 1 | 8350 | | 8350 | Blackwall | 1896 | 505,141 | 12 | 6 | 20 5-9-in. Q.F., 18 3-4-in., 8 M., 4 l. | 5 | 14·7 | 700 | 759 |
| a. c. | König Wilhelm | S. | 8868 396 0 64 | 3 25 3 3 | 15000 | Dürr. | 15000 | Hamburg | 1901 | | | | 3 4-in., 10 1-4-in. Q.F., 12 3-4-in., 10 1-4-in., 4 M. (3 sub.) | 4 | 20·5 | 950 | 528 |
| b. | Kurfürst Friedrich Wilhelm. | S. | 10,100 354 4 65 | 0 24 7 2 | 9959 | | 9959 | Wilhelmshaven | 1891 | 653,000 | 15½ comp. | 11½ | 6 11-in., 6 4-1-in. Q.F., 8 3-4-in., 12 1-4-in., 8 M., 2 l. | 6 | 16·0 | 750 | 552 |
| a. g. b. | Mücke | L. | 1109 154 3 36 | 0 10 2 2 | 759 | | 759 | Bremen | 1877 60,960 | 8 | 8 | 2 | 1 12-in., 2 3-3-in., 2 M. | 2 | 10·0 | 40 | 76 |

* The Hagen has been reconstructed, and lengthened 27 ft. by the addition of a new middle section.

† Also liquid fuel.

‡ Estimates, 1901; particulars not known.

GERMANY.—Armoured Ships—continued.

322

| Class. | NAME. | Material of Hull. | Displacement. | Length. | Beam. | Draught. | Propellers. | Indicated Horse-Power. | Where Built. | Date of Launch. | Cost. | Armour. | | | Armament. | | Speed. | Normal Supply. | Complement. |
|-------------|--------------------|-------------------|----------------|---------|---------|----------|-------------|------------------------|---------------|-----------------|---------|-------------|---------------|---------------|---|----------------|--------|----------------|-------------|
| | | | metric tons. | ft. in. | ft. in. | ft. in. | no. | | | | £ | Belt. | Gun Position. | Deck Plating. | Guns. | Torpedo Tubes. | knots. | Coal Supply. | |
| a. g. b. | Natter | I. | 1109 154 336 | 0 10 2 | 2 | 759 | | | Bremen | 1880 | 52,822 | in. | in. | in. | 1 12-in., 2 3-3-in., 2 m. | 2 | 10-0 | 40 | 76 |
| a. d. s. b. | Odin | S. | 3600 236 650 | 6 17 9 | 2 | 4800 | | | Danzig | 1894 | .. | 9½ H.S. | 8½ H.S. | 2 | 3 9-4 in., 10 3-4-in. Q.F., 6 m. | 3 | 15-0 | 225† | 266 |
| b. | Oldenburg | S. | 5200 246 059 | 0 19 6 | 2 | 3900 | | | Stettin | 1884 | 235,342 | 13 comp. | 8 comp. | 1 | 8 9-4-in. (Krupp), 2 3-4-in. Q.F., 6 m. | 4 | 13-5 | 475 | 356 |
| t. | Preussen | I. | 6770 308 653 | 6 24 7 | 1 | 4383 | | | Stettin | 1873 | 351,904 | 9 | 8 10 | .. | 4 10-2-in. (Krupp), 2 6-6-in., 10 3-4-in. Q.F., 6 m., 2 l. | 4 | 14-0 | 550 | 537 |
| a. e. | Prinz Heinrich (A) | S. | 8868 396 064 | 3 25 3 | 3 | 15000 | | | Kiel | 1900 | .. | 4 | 6 | 2½ | 2 9-4-in., 10 5-9-in. Q.F., 10 3-4-in., 10 1-4-in., 4 m. | 4 | 20-5 | 950 | 528 |
| b. | Sachsen | I. | 7441 321 659 | 0 21 0 | 2 | 6000 | | | Stettin | 1877 | 422,178 | 15½ K.S. | 15½ | 3 | 6 10-2-in. (Krupp), 8 3-4-in. Q.F., 8 1-4-in., 1 l., 6 m., 2 l. | 5 | 14-0 | 700 | 376 |
| c. d. s. | Siegfried | S. | 3500 240 049 | 3 17 9 | 2 | 4800 | | | Kiel | 1889 | 175,000 | 9½ | 7½ | 1½ | 3 9-4-in., 6 3-4-in. Q.F., 6 m. | 4 | 14-8 | 225† | 276 |
| a. g. b. | Salamander | I. | 1109 154 336 | 0 10 2 | 2 | 759 | | | Bremen | 1880 | 56,914 | | | | 1 12-in., 2 3-3-in., 2 m. | 2 | 10-0 | 40 | 76 |
| " | Skorpion | I. | 1109 154 336 | 0 10 2 | 2 | 759 | | | Bremen | 1877 | 60,796 | 8 | 8 | 2 | | | | | |
| " | Viper | I. | 1109 154 336 | 0 10 2 | 2 | 759 | | | Bremen | 1876 | 61,463 | | | | | | | | |
| " | Wespe | I. | 1109 154 336 | 0 10 2 | 2 | 759 | | | Bremen | 1876 | 53,771 | | | | | | | | |
| b. | Weissenburg | S. | 10,100 354 465 | 0 24 7 | 2 | 9000 | | | Stettin | 1891 | 659,475 | 15½ | 11½ | 2½ | 6 11-in., 6 4-1-in. Q.F., 8 3-4-in., 12 1-4-in., 8 m., 2 l. | 6 | 16-0 | 750† | 552 |
| t. | Wittelsbach | S. | 11,800 414 868 | 2 24 10 | 3 | 15,000 | | | Wilhelmshaven | 1900 | 832,500 | 9-4 K.S. | 10-6 K.S. | 3 | 4 9-4-in. Q.F., 18 5-9-in. Q.F., 12 3-3-in., 12 1-4-in., 8 m., (5 sub.) | 6 | 19-0 | 650 | 715 |
| b. | Wörth | S. | 10,100 354 465 | 0 24 7 | 2 | 10,224 | | | Kiel | 1892 | 595,250 | 15½ | 11½ | 2½ | 6 11-in., 6 4-1-in. Q.F., 8 3-4-in., 12 1-4-in., 8 m., 2 l. | 6 | 16-0† | 750† | 552 |
| b. | Württemberg | I. | 7441 321 660 | 0 19 8 | 2 | 6000 | | | Stettin | 1878 | 402,512 | 15½ | 10 | 3 | 6 10-2-in. (Krupp), 8 3-4-in. Q.F., 8 1-4-in., 1 l., (2 sub.) 6 m.* | 5 | 14-0 | 700 | 376 |

* New armament.

† Also liquid fuel.

The Arminius, Friedrich Carl, and Kronprinz are now used for harbour service.

† Wörth: trial, 17-2 knots.

GERMANY—Cruising Ships.

| Class. | NAME. | Material of Hull. | Displacement. | Length. | Beam. | Draught. | Propellers. | Indicated Horse-power. | Where Built. | Date of Launch. | Cost. | Armour. | Armament. | Speed. | Normal Coal Supply. | Complement. |
|-------------|-------------|-------------------|---------------|---------|---------|----------|-------------|------------------------|----------------------|-----------------|-------|---------------|--|----------------|---------------------|-------------|
| | | | metric tons. | ft. in. | ft. in. | ft. in. | no. | | | | £ | Gun Position. | Deck. | Torpedo Tubes. | knots. | tons. |
| 3rd cl. cr. | Alexandrine | I. S. & W. | 2373 236 | 3 42 | 7 18 | 4 1 | 2400 | Kiel | 1885 | 102,877 | .. | .. | 10 5·9-in., 4 1·1-in., 10 M., 1 L. | 1 | 14 0 | 267 |
| " | Amazona (F) | S. | 2650 344 | 6 38 | 7 16 | 0 2 | 5000 T.S. | Kiel (Germania) | 1900 | 167,500 | .. | 2 | 10 4·1-in. Q.F., 14 1·4-in., 4 M., 2 L. | 2 (sub.) | 21·5 | 550 |
| " | Arcona | I. S. & W. | 2373 236 | 3 42 | 7 18 | 4 1 | 2400 | Danzig | 1885 | 109,875 | .. | .. | 10 5·9-in., 4 1·1-in., 10 M., 1 L. | 1 | 14·0 | 267 |
| " | Ariadne | S. | 2600 328 | 0 38 | 4 16 | 0 2 | 8000 T.S. | Bremen (Weser) | 1900 | 167,500 | .. | 2 | 10 4·1-in. Q.F., 14 1·4-in., 4 M., 2 L. | 2 (sub.) | 21·5 | 550 |
| " | Blitz | S. | 1382 246 | 0 32 | 10 13 | 5 2 | 2839 | Kiel | 1882 | 66,935 | .. | .. | 6 3·4-in., 4 M. | 1 | 16·0 | 127 |
| g. b. | Bremse | S. | 866 203 | 5 27 | 10 10 | 6 1 | 1500 | Bremen | 1884 | 49,308 | .. | 2½ | 1 8·2-in. | .. | 15·0 | 65 |
| g. b. | Brummer | S. | 866 203 | 5 27 | 10 10 | 6 1 | 1500 | Bremen | 1884 | 52,422 | .. | 2½ | 1 8·2-in. | .. | 15·0 | 65 |
| 3rd cl. cr. | Bussard | S. | 1857 256 | 0 30 | 2 18 | 4 2 | 2900 | Danzig | 1890 | .. | .. | .. | 8 4·1-in. Q.F., 7 M. | 2 | 16·5 | 400 |
| " | Falke | S. & W. | 1731 246 | 0 33 | 6 15 | 0 2 | 2900 | Kiel | 1891 | .. | .. | .. | 8 4·1-in. Q.F., 7 M. | 2 | 15·5 | 400 |
| 2nd cl. cr. | Freya | S. | 5650 344 | 5 57 | 0 20 | 8 3 | 10,000 Nic. | Danzig | 1897 | .. | .. | 4 N.S. | 2 8·2-in. Q.F., 8 6-in. Q.F., 10 3·4-in., 10 1·4-in., 4 M. | 3 (sub.) | 20 | 500† |
| 3rd cl. cr. | Gt. H. J. | S. | 2650 344 | 6 38 | 7 16 | 0 2 | {8000 T.S.} | Kiel (Germania) | Bldg. Pro. } 167,500 | .. | .. | .. | 10 4·1-in. Q.F., 14 1·4-in., 4 M., 2 L. | 2 (sub.) | 21·5 | 550 |
| 3rd cl. cr. | Gazelle | S. & bronze shd. | 2650 328 | 0 38 | 7 16 | 9 2 | 7000 Ni. | Kiel (Germania) | 1898 | 130,000 | .. | .. | 10 4·1-in. Q.F., 14 1·4-in., 4 M., 2 L. | 3 (sub.) | 19·0 | 210 |
| 2nd " | Gefion | S. | 4207 344 | 6 42 | 8 20 | 8 2 | 9000 | Danzig (Schichau) | 1893 | .. | .. | .. | 10 4·1-in. Q.F., 6 2·1-in., 1 L., 8 M. | 2 | 19·0 | 950 |
| 3rd " | Geier | S. & W. shd. | 1776 249 | 4 34 | 10 15 | 6 2 | 2960 | Wilhelmshaven | 1894 | .. | .. | .. | 8 4·1-in. Q.F., 7 M. | 2 | 16·2 | 400 |
| " | Greif | S. | 2000 218 | 32 | 14 | 9 2 | 5400 | Kiel | 1886 | .. | .. | .. | 2 3·4-in. Q.F., 4 M. | .. | 19·0 | 130 |
| g. v. | Habicht | I. & W. | 848 174 | 0 29 | 6 11 | 5 1 | 600 | Elbing | 1879 | 33,054 | .. | .. | 5 4·9-in., 5 M. | .. | 12·0 | 128 |
| 2nd cl. cr. | Hansa | S. shd. | 5900 345 | 7 57 | 10 21 | 8 3 | 10,000 B | Stettin (Vulcan) | 1898 | .. | .. | 4 N.S. | 2 8·2-in. Q.F., 8 6-in., 10 3·4-in., 10 1·4-in., 4 M. | 3 (sub.) | 19·0 | 500 |

GERMANY.—Cruising Ships—continued.

| Class. | NAME. | Material of Hull. | Displacement. | Length. | Beam. | Draught. | Propellers. | Indicated Horse-power. | Where Built. | Date of Launch. | Cost. | Armour. | Armament. | Torpedo Tubes. | Speed. | Normal Coal supply. | Complement. |
|--------------------|--------------------|-------------------|------------------------------|--------------------|--------------------|--------------------|-------------|------------------------|--------------|-----------------|-------|---------|---|----------------|-------------|---------------------|-------------|
| <i>d.v.</i> | Hela . | S. | metric tons. 2000 328 0 36 0 | ft. in. ft. 0 36 0 | ft. in. ft. 0 36 0 | ft. in. ft. 0 36 0 | 2 | 5850 | Bremen . | 1895 | £ | in. | 4 3·4-in. Q.F., 6 1·9-in., 2 M. | 3 | knots. 20·0 | 347 | 169 |
| 2nd cl. <i>cr.</i> | Hertha . | S. | 5650 344 6 57 0 | 21 8 3 | 10 10 8 | 2 2 | 10,000 | Stettin (Vulcan) | 1897 | .. | .. | 4 | 2 8·2-in. Q.F., 8 6-in., 10 3·4-in., 10 1·4-in., 4 M. | 3 (sub.) | 20·0 | 500† | 440 |
| <i>g. b.</i> | Ilitis . | S. (shd.) | 895 203 6 29 10 10 | 8 2 | 1300 | 8 2 | 1300 | Danzig (Schichau) | 1898 | 100,000 | .. | .. | 8 3·4-in. Q.F., 6 1·4-in., 2 M. | .. | 18·5 | 160 | 121 |
| 2nd cl. <i>cr.</i> | Irene . | S. | 4400 308 0 46 0 | 21 0 2 | 8000 | 2 2 | 8000 | Stettin | 1887 | 220,000 | .. | 3 | 4 5·9-in., 8 4·1-in. Q.F., 6 1·9-in., 1 1, 8 M. | 4 | 19·8 | 900 | 358 |
| <i>to. g. b.</i> | Jagd . | S. | 1250 275 6 31 6 13 | 9 2 | 4000 | 2 2 | 4000 | Bremen . | 1888 | .. | .. | 2 | 4 3·4-in. Q.F., 2 M. | 3 | 20·0 | .. | 126 |
| <i>g. b.</i> | Jaguar . | S. (shd.) | 895 203 6 29 10 10 | 8 2 | 1300 | 8 2 | 1300 | Danzig (Schichau) | 1898 | 100,000 | .. | .. | 8 3·4-in. Q.F., 6 1·4-in., 2 M. | .. | 18·5 | 160 | .. |
| 1st cl. <i>cr.</i> | Kaiserin Augusta . | S. (shd.) | 6331 387 0 52 6 23 | 0 3 | 14,000 | 3 3 | 14,000 | Kiel (Germania) | 1892 | .. | .. | 3½ | 12 5·9-in., 8 3·4-in. Q.F., 2 1, 8 M. | 5 | 21·0 | 800 | 427 |
| <i>to. g. b.</i> | Komet . | S. | 946 262 6 31 2 13 | 9 2 | 5000 | 2 2 | 5000 | Stettin . | 1892 | .. | .. | 2 | 4 3·4-in. Q.F., 2 M. | 1 | 21·0 | .. | 90 |
| 3rd cl. <i>cr.</i> | Kondor . | S. & W. | 1640 246 0 33 6 15 | 0 2 | 2930 | 2 2 | 2930 | Hamburg | 1892 | .. | .. | 3 | 8 4·1-in. Q.F., 7 M. | 2 | 16·5 | 400 | .. |
| 3rd cl. <i>cr.</i> | Kormoran . | S. & W. | 1640 246 0 33 6 15 | 0 2 | 2930 | 2 2 | 2930 | Danzig . | 1892 | .. | .. | 3 | 8 4·1-in. Q.F., 7 M. | 2 | 16·0 | 400 | .. |
| <i>g. b.</i> | Luchs . | S. | 894 203 6 29 10 10 | 8 2 | 1300 | 8 2 | 1300 | Danzig . | 1890 | .. | .. | .. | 8 3·4-in. Q.F., 6 1·4-in., 2 M. | .. | 13·5 | 160 | .. |
| 3rd cl. <i>cr.</i> | Medusa . | S. | 2600 328 0 38 4 16 | 0 2 | 8000 | 2 2 | 8000 | Bremen (Weser) | 1900 | 167,500 | .. | 2 | 10 4·1-in. Q.F., 14 1·4-in., 4 M., 2 1. | 2 (sub.) | 21·5 | 550 | 249 |
| <i>d. v.</i> | Meteor . | S. | 946 262 6 29 6 11 | 6 2 | 4500 | 2 2 | 4500 | Gaarden . | 1890 | .. | .. | 2 | 2 3·4-in. Q.F., 2 M. | 3 | 21·0 | .. | 90 |
| 3rd cl. <i>cr.</i> | Niobe . | S. (shd.) | 2600 328 0 38 7 15 | 1 2 | 8000 | 2 2 | 8000 | Bremen (Weser) | 1899 | 167,500 | .. | 2 | 10 4·1-in. Q.F., 14 1·4-in., 4 M., 2 1. | 2 (sub.) | 21·5 | .. | 250 |
| <i>cr.</i> | Nixe §. | L. & W. | 1760 177 2 42 8 18 | 0 1 | 700 | 2 2 | 700 | Danzig . | 1885 | .. | .. | .. | 8 5·9-in. | .. | 10·5 | .. | 116 |
| 3rd cl. <i>cr.</i> | Nymphe . | S. | 2600 328 0 38 7 15 | 1 2 | 8000 | 2 2 | 8000 | Kiel (Germania) | 1899 | 167,500 | .. | 2 | 10 4·1-in. Q.F., 14 1·4-in., 4 M., 2 1. | 2 (sub.) | 21·5 | 550 | 210 |
| <i>cr.</i> | Olga . | L. & W. | 2100 225 4 42 7 18 | 4 1 | 2100 | 4 1 | 2100 | Stettin . | 1880 | 113,812 | .. | .. | 8 5·9-in., 23·4-in. Q.F., 1 1, 6 M. | .. | 14·0 | 320 | 267 |

| | | | | | | | | | | | | | | | | | |
|--------------------|-----------------------|---------|---------------------|-----|--------|-----|--------|---------------|------|---------|----|----|--|----------|------|-----|-----|
| <i>cr.</i> | Pelikan (mining ship) | S. | 2360 259 0 38 0 14 | 5 2 | 3000 | 5 2 | 3000 | Kiel . | 1890 | .. | .. | .. | 4 3·4-in. Q.F., 4 M. | .. | 15·4 | 370 | 183 |
| 3rd cl. <i>cr.</i> | Pfeil . | S. | 1382 246 0 32 10 13 | 5 2 | 2700 | 5 2 | 2700 | Wilhelmshaven | 1882 | 73,605 | .. | .. | 4 3·4-in. Q.F., 4 M. | 1 | 16·0 | 250 | 127 |
| 2nd cl. <i>cr.</i> | Prinzess Wilhelm . | S. | 4400 339 6 46 0 21 | 0 2 | 8000 | 0 2 | 8000 | Gaarden . | 1887 | 220,000 | .. | 3 | 4 5·9-in., 8 4·1-in. Q.F., 6 1·9-in., 1 1, 8 M. | 4 | 18·7 | 900 | 358 |
| 3rd cl. <i>cr.</i> | Schwalbe . | S. & W. | 1120 203 0 30 6 12 | 4 2 | 1500 | 4 2 | 1500 | Wilhelmshaven | 1887 | .. | .. | 3 | 8 4·1-in. Krupp, 7 M. | .. | 13·5 | 300 | 150 |
| " | Seeadler . | S. & W. | 1640 246 0 33 6 15 | 0 2 | 2800 | 0 2 | 2800 | Hamburg | 1892 | .. | .. | 3 | 8 4·1-in., 7 M. | 2 | 16·0 | 400 | 156 |
| " | Sophie . | L. & W. | 2100 226 4 42 7 18 | 4 1 | 2100 | 4 1 | 2100 | Danzig . | 1892 | 117,155 | .. | .. | 8 5·9-in., 23·4-in. Q.F., 1 1, 6 M. | .. | 14·0 | 320 | 267 |
| " | Sperber . | S. & W. | 1120 236 0 29 8 12 | 6 2 | 1500 | 6 2 | 1500 | Wilhelmshaven | 1888 | .. | .. | 3 | 8 4·1-in., 6 M. | .. | 13·5 | 300 | 150 |
| " | Thetis . | S. | 2650 344 6 38 7 16 | 0 2 | 5000 | 0 2 | 5000 | Danzig . | 1900 | 167,500 | .. | 2 | 10 4·1-in. Q.F., 14 1·4-in., 4 M., 2 1. | 2 (sub.) | 21·5 | 550 | 249 |
| <i>g. b.</i> | Tiger . | S. | 894 203 6 29 10 10 | 8 2 | 1300 | 8 2 | 1300 | Danzig . | 1899 | .. | .. | .. | 8 3·4-in. Q.F., 6 1·4-in., 2 M. | .. | 13·5 | 160 | .. |
| <i>g. b.</i> | "A." . | S. | 894 203 6 29 10 10 | 8 2 | 1300 | 8 2 | 1300 | Danzig . | 1899 | .. | .. | .. | 8 3·4-in. Q.F., 6 1·4-in., 2 M. | .. | 13·5 | 160 | .. |
| 2nd cl. <i>cr.</i> | Victoria Luise . | S. | 5650 344 5 57 0 21 | 8 3 | 10,000 | 8 3 | 10,000 | Bremen . | 1897 | .. | .. | 4 | 2 8·2-in. Q.F., 8 6-in. Q.F., 10 3·4-in., 10 1·4-in., 4 M., 2 1. | 3 (sub.) | 19·1 | 500 | 440 |
| " | Vineta . | S. shd. | 5900 345 7 57 10 21 | 8 3 | 10,000 | 8 3 | 10,000 | Danzig . | 1897 | .. | .. | 4 | 2 8·2-in. Q.F., 8 6-in. Q.F., 10 3·4-in., 10 1·4-in., 4 M., 2 1. | 3 (sub.) | 18·0 | 500 | 440 |
| 3rd cl. <i>cr.</i> | Wacht . | S. | 1250 262 0 31 6 13 | 9 2 | 4000 | 9 2 | 4000 | Bremen . | 1887 | .. | .. | 2 | 4 3·4-in. Q.F., 2 M. | 3 | 19·6 | 230 | 126 |
| <i>d. v.</i> | Zieten . | L. | 975 196 10 29 6 11 | 6 1 | 2323 | 6 1 | 2323 | Blackwall | 1876 | 81,755 | .. | .. | 4 1·9-in. Q.F., 6 M. | .. | 16·0 | 140 | 111 |

The Charlotte, Marie, Mars, Grille, Hay, Ulan, Moltke, Stein and Stosch, in addition to others given in the list, are used as schoolships. The Gneisenau, training ship, was lost at Malaga, December 16, 1900. The Butcher (2850 tons), built at Kiel in 1877, is the torpedo training ship, and the Carola (2169 tons), built at Stettin in 1880, the gunnery ship.

The Imperial Yacht Hohenzollern, 4187 tons, 9460 I.H.P., 22 knots, carries 8 1·9-in. Q.F., but provision is made for mounting 3 4·1-in., 12 1·9-in. Q.F. and 4 M. The station vessel for Constantinople is named the Loreley.

Storeships—Mowe, Wolf, Hyäne.

† Displacement with 260 tons of coal, 6100 tons. Provision made for liquid fuel.

§ Training Ship.

Merchant Cruisers (Auxiliaries to the German Navy).

| To what Company belonging. | Name of Ship. | Displacement. | Length. | Beam. | Draught of Water. | Indicated H.P. | Ocean Speed. | When Built. | Armament of each Ship. |
|----------------------------|---------------------------|---------------|---------|-------|-------------------|----------------|--------------|-------------|--|
| Hamburg-American S.S. Co. | Fürst Bismarck | 10,500 | 502 0 | 57 6 | 22 3 | 16,400 | 19½ | 1891 | 8 5.9-in., 4 4.7-in., 2 3.4-in. Q.F., 2 2.2-in., 14 M. |
| | Augusta Victoria | 9,500 | 459 3 | 56 0 | 23 0 | 12,280 | 18 | 1889 | |
| | Deutschland | 23,000 | 682 6 | 67 0 | .. | 33,000 | | 1900 | |
| | Spree | 8,900 | 462 6 | 51 10 | 22 0 | 12,770 | 19 | 1890 | |
| North German Lloyd | Lahn | 7,700 | 449 6 | 49 0 | 22 0 | 9,500 | 18½ | 1887 | Not known. |
| | Kaiser Wilhelm der Grosse | 20,000 | 625 0 | 66 0 | 27 0 | 27,000 | 22 | 1897 | |
| | Kaiser Friedrich III. | 17,000 | 580 9 | 63 11 | .. | 25,000 | 22 | 1897 | |
| | Aller | 4,965 | 436 6 | 48 0 | .. | 1,300(a) | 16 | 1885 | |
| | Saale | 4,965 | 436 6 | 48 0 | .. | 1,300(a) | 16 | 1886 | |
| | Trave | 4,965 | 436 6 | 48 0 | .. | 1,300(a) | 16 | 1886 | |

For the transport of troops to China the following vessels of the North German Lloyd were employed: the Aachen, Crefeld, Darmstadt, Dresden, Frankfurt, Gera, Halle, Hannover, Meier, Köln, Rhein, Roland, Strassburg, and Wittekind; and of the Hamburg-American line, the Adria, Andalusia, Arcadia, Batavia, Palatia, Phönixia, Sardinia, and Valdivia.

(a) Nominal horse-power.

GREECE.—Armoured Ships.

| Class. | NAME. | Material of Hull. | Displacement. metric tons. | Length. ft. in. | Beam. ft. in. | Draught. ft. in. | Propellers. no. | Indicated Horse- power. | Where Built. | Date of Launch. | Cost. | Armour. | | | Armament. | | Speed. knots. | Normal Coal Supply. tons. | Complement. |
|---------------|-------------------|-------------------|----------------------------------|--------------------|------------------|---------------------|--------------------|----------------------------|-------------------------|-----------------|-------|---------|----------------------|------------------|--|-------------------|------------------|---------------------------------|-------------|
| | | | | | | | | | | | | Belt. | Battery. Plating. | Deck Plating. | Guns. | Torpedo Tubes. | | | |
| <i>c.d.s.</i> | Basileos Georgios | I. | 1774 | 200 2 36 | 0 15 6 | 2 2100 | 2 | 2100 | Blackwall | 1867 | .. | 7 | 6 | 9 | 2 6-6-in. (Krupp), 1 5-9-in. 9 m. | 1 | 12 0 | 210 | 120 |
| <i>br.</i> | Basilissa Olga* | W. | 2030 | 230 0 59 | 0 18 0 | 1 1950 | 1 | 1950 | San Rocco | 1869 | .. | 6 | 4½ | .. | 4 6-6-in. 5½-ton (Krupp), 2 6-6-in. 3½-ton, 4 m., 4 l. | 3 | 10-0 | 240 | 400 |
| <i>b.</i> | Hydra | S. | 4885 | 334 6 51 | 10 23 3 | 2 7000 | 2 | 7000 | St. Nazaire La Seyne | 1889 1900 | .. | 11½ | 13½ | 2½ | 3 10-6-in. Canet, 5 5-9-in., 1 3-9-in., 8 2-5-in., 4 1-8-in., 12 1-4-in. | 3 | 17-0 | 600 | 400 |
| <i>b.</i> | Psara | S. | 4885 | 334 6 51 | 10 23 3 | 2 7000 | 2 | 7000 | Havre La Seyne | 1890 1897 | .. | 11½ | 13½ | 2½ | 3 10-6-in. Canet, 5 5-9-in., 1 3-9-in., 8 2-5-in., 4 1-8-in., 12 1-4-in. | 3 | 17-0 | 600 | 400 |
| <i>b.</i> | Spetsai | S. | 4885 | 334 6 51 | 10 23 3 | 2 7000 | 2 | 7000 | Havre La Seyne | 1889 1900 | .. | 11½ | 13½ | 2½ | 3 10-6-in. Canet, 5 5-9-in., 1 3-9-in., 8 2-5-in., 4 1-8-in., 12 1-4-in. | 3 | 17 0 | 600 | 400 |

* Has received two fighting masts and new machinery; similar changes in the Georgios.

ITALY.—Armoured Ships.

| Class. | NAME. | Material of Hull. | Displacement. | Length. | Beam. | Draft. | Propellers. | Indicated Horse-power. | Where Built. | Date of Launch. | Armour. | | | Armament. | | Speed. | Normal Coal Supply. | Complement. |
|--------|-----------------------|-------------------|---------------|---------|---------|---------|-------------|------------------------|----------------|-----------------|------------|---------------|---------------|--|----------------|--------|---------------------|-------------|
| | | | | | | | | | | | Belt. | Gun Position. | Deck Plating. | Guns. | Torpedo Tubes. | | | |
| | | | Metric tons. | ft. in. | ft. in. | ft. in. | ft. in. | ft. in. | | | inches. | inches. | ins. | | | knots. | tons. | |
| t. | Affondatore . | I. | 4052 | 290 | 0 40 | 0 20 | 0 1 | 3240 | Millwall . | 1865 | 5 | 5 | 2 | 2 28-ton (Armstrong), 6 4-7-in. Q.F., 2 2-9-in., 4 2-2-in., 4 1-4-in., 2 M. | 2 | 12-0 | 460 | 303 |
| " | Ammiraglio di St. Bon | S. | 9800 | 344 | 6 69 | 4 24 | 9 2 | 13,500 | Venice . | 1897 | 9 1/2 H.S. | 9 1/2 H.S. | 3-1 1/2 | 4 10-in., 8 6-in. Q.F., 8 4-7-in., 2 2-9-in., 8 2-2-in., 12 1-4-in., 2 M. | 4 | 18-0 | 600 | 548 |
| a.c. | Ancona . | I. | 4460 | 256 | 0 50 | 0 25 | 0 1 | 2548 | Bordeaux | 1864 | 4 1/2 | 4 1/2 | .. | 6 6-in. Q.F., 6 4-7-in., 2 2-9-in., 8 2-2-in., 12 1-4-in., 2 M. | 3 | 12-0 | 485 | 423 |
| b. | Andrea Doria . | S. | 11,090 | 328 | 2 65 | 4 27 | 2 2 | 10,500 | Spezia . | 1885 | 18 comp. | 18 comp. | 3 | 4 105-ton (Armstrong), 2 6-in. Q.F., 2 2-9-in., 10 2-2-in., 17 1-4-in., 2 M. | 5 (2 sub.) | 16-1 | 850 | 526 |
| b. | Benedetto Brin | S. | 13,427 | 426 | 6 78 | 2 27 | 4 2 | 19,000 | Castellamare | Bldg. | 6 H.S. | 8 H.S. | 3 | 4 12-in., 12 6-in. Q.F., 4 8-in., 18 3-in., 8 1-8-in., 4 M. | 4 (sub.) | 20-0 | 1000 | 700 |
| a.c. | Carlo Alberto . | S. | 6500 | 325 | 0 59 | 0 22 | 11 2 | 13,220 | Spezia . | 1896 | 6 H.S. | 6 H.S. | 1 1/2 | 12 6-in. Q.F., 6 4-7-in., 2 2-9-in., 10 2-2-in., 10 1-4-in., 2 M. | 4 | 19-2 | 1000 | 500 |
| a.c. | Castelfidardo . | I. | 4250 | 256 | 0 50 | 0 21 | 11 1 | 3070 | St. Nazaire | 1863 | 4 1/2 | 4 1/2 | 13 1/2 | 6 6-in. Q.F., 6 4-7-in., 2 2-9-in., 8 2-2-in., 12 1-4-in., 2 M. | 3 | 12-0 | 485 | 423 |
| t. | Dandolo * . | I & S | 11,202 | 340 | 11 64 | 9 26 | 7 2 | 8045 | Spezia . | 1878 1898 | 21 1/2 | 18 | 2 | 4 10-in. (Armstrong), 7 6-in. Q.F., 5 4-7-in., 2 2-9-in., 10 2-2-in., 14 1-4-in., 2 M. | 4 | 15-6 | 732 | 506 |
| t. | Duilio . | I & S | 11,138 | 340 | 11 64 | 9 26 | 7 2 | 7710 | Castellamare | 1876 | 21 1/2 | 18 | 2 | 4 100-ton M.L.R. (Armstrong), 3 4-7-in. Q.F., 2 2-9-in., 8 2-2-in., 22 1-4-in., 2 M. | 3 | 15-0 | 1000 | 487 |
| t. | Emanuele Filiberto. | S. | 9800 | 344 | 6 69 | 4 24 | 9 2 | 13,500 | Castellamare | 1897 | 9 1/2 H.S. | 9 1/2 H.S. | 3-1 | 4 10-in., 8 6-in. Q.F., 8 4-7-in., 2 2-9-in., 8 2-2-in., 12 1-4-in., 2 M. | 4 | 18-0 | 600 | 536 |
| b. | Francesco Morosini | S. | 11,000 | 328 | 2 65 | 4 27 | 2 2 | 9560 | Venice . | 1885 | 18 comp. | 18 comp. | 3 | 4 105-ton (Armstrong), 2 6-in. Q.F., 2 2-9-in., 10 2-2-in., 17 1-4-in., 2 M. | 5 (3 sub.) | 17-0 | 850 | 509 |
| a.c. | Francesco Ferruccio. | S. | 7350 | 344 | 0 59 | 9 23 | 4 2 | 13,500 | Venice . | Bldg. | 6 H.S. | 6 H.S. | 1 1/2 | 2 2-in., 17 1-4-in., 2 M. | 4 | 20-0 | 655 | 540 |
| a.c. | Giuseppe Garibaldi | S. | 7410 | 344 | 0 59 | 9 23 | 4 2 | 14,713 | Sestri-Ponente | 1899 | 6 H.S. | 6 H.S. | 1 1/2 | 1 10-in., 2 8-in. Q.F., 14 6-in., 10 2-9-in., 6 1-8-in., 2 M. | 4 (sub.) | 20-0 | 1200 | 540 |

* New armament given. The reconstruction of the Duilio is not likely to be proceeded with.

ITALY.—Armoured Ships—continued.

330

| Class. | NAME. | Material of Hull. | Displacement. metric tons. | Length. ft. in. ft. in. ft. in. no. | Beam. ft. in. ft. in. ft. in. no. | Draught. ft. in. ft. in. ft. in. no. | Propellers. | Indicated Horse-power. | Where Built. | Date of Launch. | Cost. | Armour. | | | Armament. | | Speed. knots. | Normal Coal Supply. tons. | Complement. |
|--------|--------------------------------|-------------------|-------------------------------|--|--------------------------------------|---|-------------|------------------------|--------------|-----------------|-------|--------------------------|-----------------------------|------------------|---|-------------------|------------------|---------------------------------|-------------|
| | | | | | | | | | | | | Belt. | Gun Position Plating. | Deck Plating. | Guns. | Torpedo Tubes. | | | |
| b. | Italia* | S. | 14,387 | 400 6 74 0 31 2 2 | 11,986 | Castellamare | 1880 | 1,167,680 | | | | 16 funnel openings | 19 comp. | 3 | 4 100-ton (Armstrong), 8 6-in., 4 4 7-in. Q.F., 12 2 2-in., 24 1 4-in., 2 M. | 4 | 18.0 | 1200 | 748 |
| b. | Lepanto | S. | 14,400 | 400 6 74 0 31 2 2 | 15,800 | Leghorn (Orlando) | 1883 | 1,150,880 | | | | 16 funnel pinnings | 19 comp. | 3 | 4 100-ton (Armstrong), 8 6-in., 4 4 7-in. Q.F., 12 2 2-in., 34 1 4-in., 2 M. | 4 | 18.38 | 1650 | 748 |
| a.c. | Marco Polo | S. | 4583 | 327 0 48 3 19 6 2 | 10,543 | Castellamare | 1890 | 344,400 | | | | 4 | 4 | 1 | 6 5 9-in. Q.F., 10 4 7-in., 2 2 9-in., 9 2 2-in., 4 1 4-in., 2 M. (1 sub.) | 5 | 19.0 | 600 | 391 |
| a.c. | Maria Pia | I. | 4268 | 256 0 49 4 22 7 1 | 2243 | La Seyne | 1863 | 215,000 | | | | 4½ | 4½ | .. | 8 5 9-in., 6 4 7-in. Q.F., 2 2 9-in., 10 2 2-in., 10 1 4-in., 2 M. | 3 | 12.0 | 485 | 423 |
| b. | Regina Elena | S. | 12,624 | 435 0 73 6 25 7 2 | 20,000 | Spezia | 1901 | 1,000,000 | | | | 9½ H.S. | 9½ H.S. | 2 | 2 12-in., 12 8-in., 12 3-in. Q.F., 12 1 8-in. | 4 | 22.0 | 1000 | .. |
| b. | Regina Margherita | S. | 13,427 | 426 6 78 2 27 4 2 | 19,000 | Spezia | 1901 | .. | | | | 6 H.S. | 8 H.S. | 3 | 4 12-in., 4 8-in., 12 6-in. Q.F., 18 3-in., 8 1 8-in., 4 M. | 4 | 20.0 | 1000 | 700 |
| b. | Re Umberto | S. | 13,825 | 400 0 76 9 28 6 2 | 19,500 | Castellamare | 1888 | 1,058,500 | | | | 4 | 18 | 3 | 4 67-ton (Armstrong), 8 6-in. Q.F., 16 4 7-in., 2 9-in., 15 2 2-in., 14 1 4-in., 2 M. | 8 | 19.0 | 1200 | 785 |
| b. | Ruggiero di Lauria. | S. | 11,000 | 328 2 65 4 27 2 2 | 10,600 | Castellamare | 1884 | 777,560 | | | | 18 comp. | 18 comp. | 3 | 4 105-ton (Armstrong), 2 6-in. 4 4 7-in. Q.F., 2 2 9-in., 10 2 2-in., 17 1 4-in., 2 M. | 5 | 17.0 | 910 | 509 |
| a.c. | San Martino (training service) | I. | 4268 | 256 0 49 4 22 7 1 | 2620 | La Seyne | 1863 | 213,880 | | | | 4½ | 4½ | .. | 8 5 9-in., 6 4 7-in. Q.F., 2 2 9-in., 10 2 2-in., 10 1 4-in., 2 M. | 3 | 12.0 | 490 | 423 |
| b. | Sardegna | S. | 13,860 | 411 0 76 9 28 6 2 | 19,650 | Spezia | 1890 | 1,057,440 | | | | 4 | 14½ comp. | 3 | 4 67-ton (Armstrong), 8 5 9-in. Q.F., 16 4 7-in., 2 2 9-in., 20 2 2-in., 10 1 4-in., 2 M. | 5 | 20.1 | 1200 | 735 |
| " | Sicilia | S. | 13,375 | 400 0 76 9 28 6 2 | 19,500 | Venice | 1891 | 1,050,000 | | | | 4 | 18 comp. | 3 | 4 67-ton (Armstrong), 8 5 9-in. Q.F., 16 4 7-in., 2 2 9-in., 20 2 2-in., 10 1 4-in., 2 M. | 5 | 19.2 | 1200 | 735 |
| a.c. | Varese | S. | 7400 | 344 6 59 9 23 9 2 | 13,500 | Leghorn (Orlando) | 1899 | .. | | | | 6 H.S. | 6 H.S. | 1½ | 1 10-in., 2 8-in. Q.F., 14 6-in., 10 2 9-in., 6 1 8-in., 2 M. | 4 | 20.0 | 650 | 500 |
| b. | Vittorio Emanuele III | S. | 12,624 | 435 0 73 6 25 7 2 | 20,000 | Castellamare | 1901 | 1,000,000 | | | | 9½ H.S. | 9½ H.S. | 4 | 2 12-in., 12 8-in., 12 3-in. Q.F., 12 1 8-in. | 4 | 22.0 | 1000 | .. |
| a.c. | Vettor Pisani | S. | 6500 | 325 0 59 0 22 11 2 | 13,000 | Castellamare | 1895 | .. | | | | 6 H.S. | 6 H.S. | 1½ | 12 6-in. Q.F., 6 4 7-in., 2 2 9-in., 10 2 2-in., 10 1 4-in., 2 M. | 5 | 20.0 | 600 | 504 |

Note.—The Palestro, Principe Amedeo, and Roma are non-effective, or only available for coast defence.

* The Italia is at present dismantled, and is to be reconstructed.

ITALY.—Cruising Ships.

| Class. | NAME. | Material of Hull. | Displacement. | Length. | Beam. | Draught. | Propellers. | Indicated Horse-power. | Where Built. | Date of Launch. | Cost. | Armour. | | Armaments. | | Speed. | Normal Coal Supply. | Comments. | | |
|--------------------|-----------------------------|-------------------|---------------|---------|-------|----------|-------------|------------------------|--------------|---------------------|-------|----------------|-------|------------|----------------|--|---------------------|-----------|-----------|-----|
| | | | | | | | | | | | | Gunn Position. | Deck. | Guns. | Torpedo Tubes. | | | | | |
| <i>to.cr.</i> | Agordat . . . | S. | 1313 | 287 | 630 | 611 | 1 | 2 | 8000 | Castellamare . | 1899 | £ | in. | 1 | 4 | 4.7-in. Q.F., 8 2.2-in., 2 1.4-in. | 2 | 23.0 | 160 tons. | 158 |
| 3rd cl. <i>cr.</i> | Amerigo Vespucci (training) | S. | 2795 | 255 | 1142 | 717 | 0 | 1 | 3340 | Venice . | 1882 | 176,300 | .. | .. | 4 | 4 4.7-in., 1 3-in., 4 2.2-in., 4 1.4-in., 4 M. | 2 | 14.0 | 500 | 265 |
| <i>g.v.</i> | Andrea Provana . | S. | 733 | 167 | 426 | 310 | 2 | 1 | 1080 | Leghorn . (Orlando) | 1884 | 39,760 | .. | .. | 4 | 4.7 in., 3 1.4-in., Q.F. | .. | 13.0 | 120 | 103 |
| <i>d.v.</i> | Archimede . . . | S. | 784 | 230 | 026 | 310 | 0 | 1 | 1401 | Venice . | 1887 | 60,120 | .. | .. | 4 | 4.7-in., 2 2.2-in. Q.F., 2 1.4-in. | 2 | 16.0 | 210 | 109 |
| <i>to.g.b.</i> | Aretusa . . . | S. | 846 | 230 | 026 | 1011 | 9 | 2 | 4420 | Leghorn . (Orlando) | 1891 | 72,920 | .. | 1 | 1 | 4.7-in., 6 2.2-in., and 3 1.4-in. | 6 | 20.7 | 120 | 111 |
| 3rd cl. <i>cr.</i> | Calabria . . . | S. | 2442 | 249 | 442 | 016 | 7 | 2 | 4094 | Spezia . | 1894 | 183,120 | .. | 2 | 4 | 5.9-in. Q.F., 6 4.7-in., 1 2.9-in., 8 2.2-in., 8 1.4-in., 2 M. | 2 | 16.4 | 500 | 257 |
| <i>to.g.b.</i> | Calatafimi . . . | S. | 840 | 229 | 627 | 010 | 2 | 2 | 4136 | Castellamare . | 1893 | 72,920 | .. | 1 | 1 | 4.7-in. Q.F., 6 2.2-in., 3 1.4-in. | 6 | 20.0 | 120 | 111 |
| " | Caprera . . . | S. | 853 | 230 | 027 | 410 | 2 | 2 | 4189 | Leghorn . (Orlando) | 1894 | 72,920 | .. | 1 | 2 | 4.7-in. Q.F., 4 2.2-in., 2 1.4-in. Q.F. | 5 | 21.0 | 120 | 111 |
| <i>g.v.</i> | Cariáci . . . | W. | 1050 | 177 | 228 | 612 | 5 | 1 | 844 | Castellamare . | 1875 | 65,480 | .. | .. | 2 | 4.7-in., 4 2.2-in. Q.F. | .. | 10.0 | 140 | 112 |
| <i>to.cr.</i> | Coatit . . . | S. | 1313 | 287 | 630 | 611 | 1 | 2 | 8000 | Castellamare . | 1899 | .. | .. | 1 | 4 | 4.7-in. Q.F., 8 2.2-in., 2 1.4-in. | 2 | 23.0 | 160 | 158 |
| <i>to.g.b.</i> | Confienza . . . | S. | 768 | 230 | 025 | 6 | 9 | 0 | 1887 | Spezia . | 1887 | 61,480 | .. | 1 | 1 | 4.7-in. Q.F., 6 2.2-in., 2 1.4-in. | 4 | 17.0 | 180 | 111 |

ITALY.—Cruising Ships—continued.

332

| Class. | NAME. | Material of Hull. | Displacement. | Length. | Beam. | Draft. | Propellers. | Indicated Horse-power. | Where Built. | Date of Launch. | Cost. | Armour. | | Armament. | Speed. | Coal Supply. | Complement. |
|----------------|-------------------------|-------------------|---------------|---------|-------|--------|-------------|------------------------|-------------------|-----------------|---------|---------|-------|--|--------|--------------|-------------|
| | | | | | | | | | | | | Gunn. | Deck. | | | | |
| 3rd cl. cr. | Cristoforo Colombo | S. | 2757 | 249 | 36 | 0 17 | 6 | 2321 | Venice | 1892 | 157,240 | in. | in. | 6 4-7-in., 2 2-2-in., Q.F., 4 1-4-in. | 16-0 | 445 | 238 |
| <i>g.v.</i> | Curtatone | S. | 1292 | 177 | 332 | 8 13 | 6 | 1100 | Venice | 1887 | 58,440 | .. | .. | 4 2-2-in., 2 1-4-in., 2 M. | 12-0 | 197 | 131 |
| 3rd cl. cr. | Dogali | S. | 2088 | 250 | 0 37 | 0 14 | 6 | 7600 | Elswick | 1887 | 156,040 | 4½ | 2 | 6-6-in. (Armstrong), 1 2-9-in., 9 2-2-in. Q.F., 2 1-4-in., 2 M. | 19-66 | 480 | 257 |
| " | Elba | S. | 2730 | 272 | 6 40 | 8 16 | 7 | 7471 (t) | Castellamare | 1893 | 200,000 | 4½ | 2 | 4 5-9-in. Q.F., 6 4-7-in., 1 2-9-in., 8 2-2-in., 8 1-4-in., 2 M. | 17-94 | 500 | 272 |
| 2nd cl. cr. | Etna | S. | 3530 | 282 | 2 42 | 7 19 | 0 | 6169 | Castellamare | 1885 | 226,720 | 5 | 1½ | 2 9-8-in. (Armstrong), 6 5-9-in., 1 2-9-in., 5 2-2-in. Q.F., 8 1-4-in., 2 M. | 17-8 | 630 | 315 |
| <i>to g.b.</i> | Euridice | S. | 840 | 229 | 6 27 | 0 10 | 2 | 4162 | Castellamare | 1891 | 72,920 | .. | 1 | 1 4-7-in. Q.F., 6 2-2-in., 3 1-4-in. | 19-84 | 120 | 111 |
| 3rd cl. cr. | Etruria | S. | 2280 | 262 | 6 39 | 6 16 | 7 | 7585 (t) | Leghorn (Orlando) | 1891 | 183,120 | 4½ | 2 | 4 5-9-in. Q.F., 6 4-7-in., 1 2-9-in., 8 2-2-in., 10 1-4-in., 2 M. | 19-84 | 400 | 257 |
| 2nd cl. cr. | Fieramosca | S. | 3600 | 290 | 0 43 | 6 19 | 4 | 7700 | Leghorn (Orlando) | 1888 | 240,120 | 5 | 1½ | 2 9-8-in., 6 6-in. Q.F., 1 2-9-in., 5 2-2-in., 8 1-4-in., 2 M. | 17-5 | 450 | 315 |
| cr. | Flavio Gioja (training) | S. | 3064 | 255 | 11 42 | 7 17 | 0 | 4150 | Castellamare | 1881 | 193,920 | .. | 1½ | 4 4-7-in., 1 3-in., 4 2-2-in. Q.F., 4 1-4-in., 4 M. | 15-0 | 500 | 265 |
| <i>d.v.</i> | Gailei | S. | 900 | 230 | 0 26 | 3 8 | 2 | 1384 | Venice | 1887 | 56,720 | .. | .. | 4 4-7-in., 2 2-2-in. Q.F., 2 1-4-in. | 15-0 | 210 | 109 |

| | | | | | | | | | | | | | | | | | |
|----------------|---------------------|----|------|-----|------|-------|----|-----------|-------------------|------|---------|----|----|---|-------|-----|-----|
| 3rd cl. cr. | Giovanni Bausan | S. | 3068 | 275 | 7 42 | 7 18 | 4 | 6500 | Elswick | 1883 | 179,120 | 5 | 1½ | 2 9-8-in. (Armstrong), 6 5-9-in., 1 2-9-in., 4 2-2-in. Q.F., 8 1-4-in., 2 M. | 17-5 | 600 | 295 |
| <i>to g.b.</i> | Goito | S. | 812 | 230 | 0 25 | 6 11 | 9 | 2620 | Castellamare | 1887 | 70,680 | .. | 1 | 4 2-2-in. Q.F., 5 1-4-in. | 19-0 | 130 | 111 |
| <i>g.v.</i> | Governolo | S. | 1255 | 185 | 0 33 | 9 13 | 9 | 1100 | Venice | 1894 | 58,440 | .. | .. | 4 4-7-in. Q.F., 4 2-2-in., 2 1-4-in., 2 M. | 13-0 | 200 | 131 |
| <i>to g.b.</i> | Iride | S. | 840 | 229 | 6 27 | 0 10 | 2 | 4242 | Castellamare | 1891 | 72,920 | .. | 1 | 1 4-7-in. Q.F., 6 2-2-in., 3 1-4-in. | 19-6 | 120 | 111 |
| 3rd cl. cr. | Liguria | S. | 2280 | 262 | 6 39 | 4 16 | 9 | 7677 (t) | Sestri (Ansaldo) | 1893 | 183,120 | 4½ | 2 | 4 5-9-in. Q.F., 6 4-7-in., 1 2-9-in., 8 2-2-in., 10 1-4-in., 2 M. (2 Maxims). | 19-64 | 430 | 257 |
| " | Lombardia | S. | 2380 | 262 | 6 39 | 6 16 | 7 | 6843 (t) | Castellamare | 1890 | 183,120 | 4½ | 2 | 4 5-9-in. Q.F., 6 4-7-in., 1 2-9-in., 8 2-2-in., 8 1-4-in., 2 M. | 17-04 | 430 | 257 |
| <i>d.v.</i> | Marcantonio Colonna | S. | 656 | 216 | 6 23 | 11 10 | 10 | 1700 | .. | 1879 | 51,480 | .. | .. | 5 2-2-in. Q.F., 2 M. | 15-4 | 197 | 82 |
| <i>to g.b.</i> | Minerva | S. | 846 | 246 | 0 27 | 6 11 | 9 | 4800 W.T. | Sestri (Ansaldo) | 1892 | 72,720 | .. | 1 | 1 4-7-in. Q.F., 6 2-2-in., 3 1-4-in. | 21-0 | 120 | 111 |
| " | Montebello | S. | 814 | 230 | 0 25 | 6 11 | 9 | 2776 | Spezia | 1888 | 74,120 | .. | 1 | 6 2-2-in. Q.F., 2 1-4-in. | 19-0 | 100 | 111 |
| " | Monzambano | S. | 840 | 230 | 0 25 | 6 11 | 9 | 1953 | Spezia | 1888 | 70,680 | .. | 1 | 6 2-2-in. Q.F., 2 1-4-in. | 17-0 | 100 | 111 |
| " | Partenope | S. | 840 | 246 | 0 27 | 6 11 | 9 | 4200 | Castellamare | 1890 | 71,000 | .. | 1 | 1 4-7-in. Q.F., 6 2-2-in., 3 1-4-in. | 19-0 | 100 | 111 |
| 3rd cl. cr. | Piemonte | S. | 2500 | 300 | 0 38 | 0 15 | 0 | 12,000 | Elswick | 1888 | 220,000 | 3 | 3 | 6 6-6-in. Q.F., 6 4-7-in., 10 2-2-in., 6 1-4-in., 4 M. | 21-0 | 560 | 325 |
| 3rd cl. cr. | Puglia | S. | 2550 | 269 | 0 41 | 0 16 | 9 | 7000 | Taranto | 1898 | 200,000 | 4½ | 1 | 4 5-9-in. Q.F., 6 4-7-in., 1 2-9-in., 8 2-2-in., 8 1-4-in., 2 M. | 20-0 | 650 | 257 |
| <i>d.v.</i> | Rapido | I. | 1568 | 262 | 5 30 | 6 12 | 6 | 1450 | Leghorn (Orlando) | 1876 | 77,400 | .. | .. | 5 2-2-in. Q.F., 2 M. | 13-4 | 300 | 135 |
| <i>to g.b.</i> | Saetta | S. | 400 | 187 | 0 19 | 8 6 | 7 | 2400 | Castellamare | 1887 | 38,880 | .. | .. | 2 2-2-in. Q.F., 4 1-4-in. | 20-0 | 90 | 70 |

333

ITALY.—Cruising Ships—continued.

334

| Class. | NAME. | Material of Hull. | Displacement. | Length. | Beam. | Draught. | Propellers. | Indicated Horse-power. | Where Built. | Date of Launch. | Cost. | Armour. | | Armament. | | Speed. | Normal Coal Supply. | Complement. |
|-------------|--------------------|-------------------|---------------|---------|-------|----------|-------------|------------------------|-------------------------|-----------------|-----------|---------------|---------|--|----------------|-----------|---------------------|-------------|
| | | | | | | | | | | | | Gun Position. | Deck. | Gun. | Torpedo Tubes. | | | |
| cr. | Savoia | S. | 2850 | 275 | 642 | 717 | 0 1 | 3340 | Castellamare | 1883 | £ 176,160 | inches. | inches. | 4 2·2-in. Q.F. | 2 | knots. | 600 | 216 |
| g.v. | Scilla | W. | 1076 | 177 | 228 | 612 | 5 1 | 826 | Castellamare | 1874 | 65,520 | .. | .. | 4 2·2-in. Q.F., 2 M. | .. | 10·0 | 140 | 111 |
| g.b. | Sebastiano Veniero | S. | 713 | 170 | 026 | 310 | 6 1 | 1160 | Leghorn (Orlando) | 1884 | 36,160 | .. | .. | 4 4·7-in., 3 1·4-in. Q.F. | .. | 13·0 | 150 | 103 |
| d.v. | Staffetta | I. | 1806 | 252 | 730 | 1013 | 2 1 | 1800 | S. Piandarena (Ansaldo) | 1876 | 82,600 | .. | .. | 4 4·7-in., 2 1·4-in. Q.F. | 1 | 13·5 | 300 | 135 |
| 2nd cl. cr. | Stromboli | S. | 3475 | 282 | 242 | 719 | 0 2 | 6298 | Venice | 1886 | 220,080 | 5 | 1·5 | 2 9·8-in. (Armstrong), 6 5 9-in., 1 2·9-in., 5 2·2-in. Q.F., 8 1·4-in., 2 M. | 4 | 17·0 | 600 | 315 |
| to. g.b. | Tripoli | S. | 848 | 230 | 025 | 1011 | 9 3 | 2543 | Castellamare | 1886 | 72,080 | .. | 1 | 7 2·2-in. | 4 | 18·0 | 130 | 107 |
| 3rd cl. cr. | Umbria | S. | 2280 | 262 | 639 | 616 | 7 2 | 7104 (t) | Leghorn (Orlando) | 1891 | 183,120 | 4½ | 2 | 4 5·9-in. Q.F., 6 4·7-in., 8 2·2-in., 10 1·4-in., 1 1·2 M. | 2 | 18·83 (t) | 430 | 257 |
| to. g.b. | Urania | S. | 846 | 230 | 027 | 011 | 2 2 | 4397 | Sestri (Odero) | 1891 | 72,920 | .. | 1 | 1 4·7-in. Q.F., 6 2·2-in., 3 1·4-in. | 6 | 20·0 | 120 | 111 |
| d.v. | Vedetta | I. | 827 | 183 | 926 | 1111 | 5 1 | 466 | Genoa | 1866 | 32,400 | .. | .. | 4 4·7-in., 2 1·4-in. Q.F. | .. | 11·0 | 137 | 85 |
| 2nd cl. cr. | Vesuvio | S. | 3427 | 282 | 242 | 719 | 0 2 | 6820 | Leghorn (Orlando) | 1886 | 218,320 | 5 | 1·5 | 2 9·8-in., 6 5·9-in., 1 2·9-in., 5 2·2-in. Q.F., 8 1·4-in., 2 M. | 4 | 17·0 | 600 | 315 |
| g.v. | Volturno | S. | 1174 | 177 | 332 | 814 | 4 1 | 1100 | Venice | 1887 | 58,960 | .. | .. | 4 4·7-in., 4 2·2-in. Q.F., 2 1·4-in., 2 M. | .. | 13·0 | 206 | 131 |

Subsidised auxiliary cruisers and despatch vessels.—Nord America, Vittoria, Duca de Galliera, and Duchessa di Genova (La Veloce S.S. Co.), Regina Margherita, Elettrico, Candia, Malta, Persico and Oriomo (Navigazione Generale). The armament of these vessels is 2 2·2-in. Q.F., and 4 1·4-in. M. The gun vessels Castore and Polluce (530 tons) have been converted into tank-ships, and their guns landed and placed in the forts at Taranto.

JAPAN.—Armoured Ships.

| Class. | NAME. | Material of Hull. | Displacement. | Length. | Beam. | Draught. | Propellers. | Indicated Horse-power. | Where Built. | Date of Launch. | Cost. | Armour. | | | Armament. | | Speed. | Normal Coal Supply. | Complement. |
|--------|----------------------------|-------------------|---------------|---------|---------|----------|-------------|------------------------|---------------|-----------------|-------|-------------------|------------------|-----------------|---|----------------|--------|---------------------|-------------|
| | | | tons. | ft. in. | ft. in. | ft. in. | no. | | | | | Belt. | Gun Position. | Deck Plating. | Guns.† | Torpedo Tubes. | knots. | | |
| t. | Asahi . . . | S. | 15,200 | 400 | 075 | 227 | 3 2 | 15,000 | Clydebank . | 1899 | .. | inches. 9-4 | inches. 14-10 | inches. 4-2½ | 4 12-in., 14 6-in. Q.F., 20 12-pr., 8 3-pr., 4 2½-pr. | 4 (sub.) | 18 | 1400 | .. |
| a.c. | Asama . . . | S. | 9750 | 408 | 067 | 024 | 3 3 | 19,000 | Elswick . | 1898 | .. | H. S. 7-3½ | H. S. 6 | 2 | 4 8-in. Q.F., 14 6-in. (Armstrong), 12 12-pr., 7 2½-pr. | 5 (4 sub.) | 22-1 | 600 | .. |
| a.c. | Azuma . . . | S. | 9436 | 445 | 1059 | 628 | 0 2 | 17,000 | St. Nazaire . | 1899 | .. | H. S. 6 | .. | 3 | 4 8-in., 12 6-in. Q.F., 12 3-in., 12 1-8-in. | 5 (4 sub.) | .. | .. | 482 |
| b. | Chin-Yen (Ex. Chen Yuen) | S. | 7400 | 308 | 559 | 020 | 0 2 | 6200 | Stettin . | 1882 | .. | 14 | 12 | 3 | 4 12-in. (Krupp), 4 6-in. Q.F., 8 1, 8 M. | 3 | 14 | 1000 | 250 |
| a.c. | Chiyoda . . | S. | 2450 | 308 | 042 | 614 | 0 2 | 5700 | Clydebank . | 1889 | .. | 4½ | .. | 1-2 | 10 4-7-in. Q.F., 14 3-pr., 3 M. | 3 | 17-5 | 420 | 300 |
| b. | Fuji . . . | S. | 12,320 | 374 | 073 | 026 | 6 2 | 14,000 | Thames . | 1896 | .. | 18-6 | 14 | 2½ | 4 12-in., 10 6-in. Q.F., 20 3-pr., 4 4½-pr. | 5 (4 sub.) | 19-2 | 1100 | 600 |
| b. | Hatsuse . . | S. | 15,000 | 400 | 076 | 627 | 0 2 | 16,300 | Elswick . | 1899 | .. | H. S. 9-4 | H. S. 14-6 | 4 | 4 12-in., 14 6-in. Q.F., 20 12-pr., 8 3-pr., 4 2½-pr. | 4 (sub.) | 19-11 | 1100 | 741 |
| c.d.s. | Hei-Yen (Ex. Ping-Yuen-Go) | S. | 2000 | 200 | 040 | 016 | 0 2 | 2400 | Foo Chow . | 1890 | .. | 8 | 5 | 2 | 1 10-2-in. (Krupp), 2 5-9-in., 6 M. | 4 | 11-0 | 350 | 250 |
| a.c. | Hi-yei* . . | C. | 2200 | 231 | 040 | 917 | 4 1 | 2490 | Milford . | 1878 | .. | 4½ | .. | .. | 3 6-in. (Krupp), 6 5-9-in., 4 M., 1 L. | .. | 13-0 | 280 | 308 |
| a.c. | Idzumo . . | S. | 9750 | 400 | 068 | 624 | 3 2 | 17,300 | Elswick . | 1899 | .. | 7-3½ | 6 | 2½ | 4 8-in. Q.F., 14 6-in., 12 12-pr., 8 2½-pr. | 4 (sub.) | 20-0 | 700 | 672 |
| a.c. | Iwate . . | S. | 9750 | 400 | 068 | 624 | 3 2 | 17,300 | Elswick . | 1900 | .. | H. N. S. H. N. S. | H. N. S. | .. | .. | .. | 1600 | .. | .. |
| " | Kon-go* . . | C. | 2200 | 231 | 040 | 917 | 4 1 | 2450 | Hull . | 1877 | .. | 4½ | .. | .. | 3 6-in. (Krupp), 6 5-9-in., 4 M., 1 L. | .. | 13-7 | 280 | 308 |
| b. | Mikasa . . | S. | 15,200 | 400 | 076 | 027 | 3 2 | 15,000 | Barrow . | 1900 | .. | 9-6 | 14-6 | 3 | 4 12-in., 14 6-in. Q.F., 20 12-pr., 8 3-pr., 4 2½-pr. | 5 (4 sub.) | 18-0 | 700 | 935 |
| b. | Shikishima . | S. | 14,850 | 400 | 075 | 627 | 3 2 | 14,500 | Thames . | 1898 | .. | H. N. S. H. N. S. | H. N. S. | 3-5 | 4 12-in., 14 6-in. Q.F., 20 12-pr., 8 M. | 5 (4 sub.) | 18-5 | 700 | 741 |
| a.c. | Tokiwa . . | S. | 9750 | 408 | 067 | 024 | 3 2 | 20,000 | Elswick . | 1898 | .. | 7-8½ | 6 | 2 | 4 8-in. Q.F., 14 6-in. (Armstrong), 12 12-pr., 7 2½-pr. | 5 (4 sub.) | 23-0 | 600 | 500 |
| a.c. | Yakumo . . | S. | 9850 | 407 | 964 | 423 | 9 2 | 16,000 | Stettin . | 1899 | .. | 7-8½ | H. S. | 2½ | 4 8-in. (Armstrong) Q.F., 12 7 2½-pr. | 5 (4 sub.) | 20-0 | 1200 | 500 |
| b. | Yashima . . | S. | 12,320 | 374 | 073 | 026 | 6 2 | 14,000 | Elswick . | 1896 | .. | 18-6 | 14 | 2½ | 4 12-in., 10 6-in. Q.F., 20 3-pr., 4 4½-pr. | 5 (4 sub.) | 19-2 | 1100 | 600 |

* These are now used as training ships; they have no armour as against end-on fire, and no armoured deck; also the older Rito (2459 tons)—gunnery—now without engines.

† All Q.F. guns and 12-in. for new ships are Armstrong.

The old central battery ironclad *Fu-So* (3718 tons) built on the Thames, 1877, and sunk off Shikoku Island, 1897, has been refloated, and is being repaired at Kure dockyard.

JAPAN.—Cruising Ships, &c.

| Class. | NAME. | Material of Hull. | Displacement. | Length. | Beam. | Draught. | Propellers. | Indicated Horse power. | Where Built. | Date of Launch. | Cost. | Armour. | Armament. | Speed. | Normal Coal Supply. | Complement. |
|---------------|------------------------|-------------------|---------------|----------|---------|----------|-------------|------------------------|------------------|-----------------|---------|---------------|-----------|----------------|---------------------|-------------|
| | | | tons. | ft. in. | ft. in. | ft. in. | no. | | | | £ | Gun position. | Deck. | Torpedo Tubes. | knots. | |
| <i>g.v.</i> | Akagi. | S. | 615 | 164 0 27 | 0 10 | 0 1 | 1 | 700 | Japan | 1889 | .. | in. | in. | .. | 13.0 | 113 |
| <i>cr.</i> | Akashi | S. | 2700 | 306 9 40 | 0 16 | 4 2 | 2 | 8500 | Japan (Yokosuka) | 1895 | 327,000 | .. | 2-1 | 2 | 20.0 | .. |
| " | Akatsushima | S. | 3150 | 302 0 42 | 7 18 | 5 2 | 2 | 8400 | Japan | 1892 | .. | 4½ | 3 | 4 | 19.0 | 330 |
| <i>g.v.</i> | Atago. | S. | 615 | 154 0 27 | 0 10 | 6 2 | 2 | 700 | Japan | 1887 | .. | .. | .. | .. | 12.0 | 113 |
| <i>t.g.b.</i> | Chihaya | S. | 875 | 240 0 27 | 6 13 | 0 2 | 2 | 5500 | Yokosuka | 1900 | .. | .. | .. | 5 | 21.0 | .. |
| <i>cr.</i> | Chitose* | S. | 4760 | 396 0 49 | 0 17 | 7 2 | 2 | 15,500 | San Francisco | 1898 | 205,200 | 4½ | 4½-1½ | 5 | 22.5 | 405 |
| " | Hashidate | S. | 4277 | 295 0 50 | 10 21 | 2 2 | 2 | 5400 | Japan | 1891 | .. | 12 | 2 | 4 | 17.0 | 350 |
| " | Itsukushima | S. | 4277 | 295 0 50 | 10 21 | 2 2 | 2 | 5400 | La Seyne | 1891 | .. | .. | .. | .. | .. | .. |
| <i>g.v.</i> | Iwaki. | W. | 700 | 147 0 25 | 0 11 | 0 1 | 1 | 700 | Japan | 1883 | .. | .. | .. | .. | 10.0 | 115 |
| " | Idzumi (ex Esmeralda). | S. | 2950 | 270 0 40 | 0 18 | 3 2 | 2 | 6500 | Elswick | 1878 | .. | 22 | 5-1 | 3 | 18.6 | 300 |
| <i>cr.</i> | Kasagi | S. | 5416 | 393 6 48 | 9 19 | 0 2 | 2 | 15,797 | Philadelphia | 1897 | 205,200 | 4½ | 4½-1½ | 5 | 22.5 | 405 |
| <i>t.c.</i> | Katsuraki. | S. | 1476 | 206 9 36 | 0 15 | 0 2 | 2 | 1600 | Japan | 1885 | .. | .. | .. | 2 | 13.0 | 242 |
| " | Musashi | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. |
| <i>g.v.</i> | Maya. | S. | 615 | 154 0 27 | 0 10 | 0 2 | 2 | 700 | Japan | 1886 | .. | .. | .. | .. | 13.0 | 113 |
| <i>cr.</i> | Matsushima | S. | 4277 | 295 0 50 | 10 21 | 2 2 | 2 | 5400 | La Seyne | 1890 | .. | 12 | 2 | 4 | 17.5 | 350 |
| " | Miyako | S. | 1800 | 314 9 36 | 0 13 | 2 2 | 2 | 6130 | Kure | Bldg. | .. | .. | .. | 2 | 20.0 | .. |

| | | | | | | | | | | | | | | | | |
|----------------|---------------------------|-------|------|----------|------|-----|---|--------|------------------|--------------|---------|----|-------|----|-------|-----|
| <i>cr.</i> | Naniwa | S. | 3650 | 300 0 46 | 0 18 | 6 2 | 2 | 7235 | Elswick | 1885 | .. | 1½ | 3-2 | 4 | 18.72 | 350 |
| <i>g.v.</i> | Oshima | S. | 630 | 164 0 27 | 0 10 | 0 1 | 1 | 700 | Japan | 1890 | .. | .. | .. | .. | 13.0 | .. |
| <i>cr.</i> | Sai yen (ex Tai Yuen). | S. | 2300 | 263 3 33 | 0 15 | 9 2 | 2 | 2300 | Stettin | 1883 | .. | 9 | 3 | 4 | 14.5 | 200 |
| <i>cr.</i> | Suma | S. | 2700 | 306 9 40 | 0 16 | 4 2 | 2 | 8500 | Japan (Yokosuka) | 1896 | 237,000 | .. | 2-1 | 2 | 20.0 | .. |
| " | Takao | S.&W. | 1774 | 230 0 33 | 0 13 | 0 2 | 2 | 2330 | Japan | 1888 | .. | .. | .. | .. | 15.0 | 255 |
| " | Takachiho | S. | 3700 | 300 0 46 | 0 18 | 6 2 | 2 | 7500 | Elswick | 1885 | .. | 1½ | 3-2 | 4 | 13.7 | 365 |
| " | Takasago | S. | 4160 | 360 0 46 | 6 17 | 0 2 | 2 | 15,500 | Elswick | (1897) Bldg. | .. | 4½ | 4½ | 5 | 23.0 | .. |
| <i>to g.b.</i> | Unnamed | S. | 875 | 240 0 27 | 6 13 | 0 2 | 2 | 5500 | Elswick | 1894 | .. | .. | .. | 5 | 21.0 | .. |
| " | Tatsuta | S. | 1500 | 200 0 32 | 0 16 | 5 1 | 1 | 1250 | Japan | 1882 | .. | .. | .. | .. | 12.0 | 222 |
| " | Ten-riu | W. | 1350 | 210 0 32 | 0 15 | 0 2 | 2 | 2387 | Elswick | 1882 | .. | 4½ | .. | 2 | 16.5 | 190 |
| <i>cr.</i> | Tsukushi (ex Arturo Prat) | S. | 1600 | 315 0 34 | 6 15 | 0 2 | 2 | 5400 | Japan | 1889 | .. | .. | .. | 2 | 20.0 | 200 |
| " | Yayeyama | S. | 1476 | 206 9 36 | 0 15 | 0 1 | 1 | 1600 | Japan | 1885 | .. | .. | .. | 2 | 13.0 | 242 |
| " | Yamato | .. | 4180 | 350 0 46 | 6 17 | 0 2 | 2 | 15,000 | Elswick | 1892 | .. | 4½ | 4½-1½ | 5 | 23.0 | 300 |

The gunboats Chen-Pei, Chen Pien, Chen Nan, Chen Hsi, Chen Chung and Chen Tung (440 tons) were captured from the Chinese.

* Dimensions doubtful.

NETHERLANDS.—Armoured Ships.

338

| Class. | NAME. | Material of Hull. | Displacement. metric tons. | Length. ft. in. | Beam. ft. in. | Draft. ft. in. | Tropellers. no. | Indicated Horse-power. | Where Built. | Date of Launch. | Cost. | Armour. | | Guns. | Torpedoes. | Speed. knots. | Normal Coal Supply. | Complement. |
|--------------------|---|-------------------|-------------------------------|--------------------|------------------|-------------------|--------------------|------------------------|----------------|-----------------|---------|--------------|---------|---------------|--|------------------|---------------------|-------------|
| | | | | | | | | | | | | Belt. | Turret. | Deck Plating. | | | | |
| <i>c.d.s.t.</i> | Bloedhond | L. | 1683 | 182 | 8-46 | 3-10 | 6 | 2 | 680 Amsterdam | 1869 | .. | 5½ | 9½ | 1 | 1 11-in. 28-ton (Krupp), 1 2-9-in., 2 3-pr. Q.F., 2 M. | .. | 7-7 | 104 118 |
| " | Cerberus | L. | 1584 | 185 | 8-44 | 0-9 | 9 | 2 | 534 Amsterdam | 1869 | .. | 5½ | 9½ | 1 | 1 11-in. 28-ton (Krupp), 1 2-9-in., 2 3-pr. Q.F., 2 M. | .. | 7-0 | 80 118 |
| " | De Ruyter | S. | 4950 | 316 | 10-51 | 6-21 | 8 | 2 | 6000 Amsterdam | 1900 | 347,500 | 6 | 10 | 2 | 2 9-4-in., 4 5-9 Q.F., 4 2-9-in., 8 1-4-in. | 2 sub. | 16-0 | 680 .. |
| " | Draak | L. | 2234 | 213 | 6-49 | 2-12 | 0 | 2 | 807 Amsterdam | 1877 | .. | 8 | 11 | 1 | 2 11-in. (Krupp), 1 2-9-in., 2 3-pr. Q.F., 2 M. | .. | 8-0 | 100 133 |
| " | Evertsen | S. | 3400 | 282 | 9-47 | 0-16 | 9 | 2 | 4735 Flushing | 1894 | .. | 6 | 9½ | 2 | 3 8-2-in., 2 5-9-in., 6 2-9-in. Q.F., 3 8 1-4-in. | 3 | 16-0 | 280 260 |
| <i>c.d.s.t.</i> | Haal | L. | 1530 | 195 | 2-44 | 0-9 | 6 | 2 | 672 Rotterdam | 1871 | .. | H.S. | 9½ | 1 | 1 11-in. 28-ton (Krupp), 1 2-9-in., 2 3-pr. Q.F., 2 M. | .. | 8-0 | 76 118 |
| " | Heiligerlee | L. | 1543 | 187 | 0-44 | 0-9 | 6 | 2 | 630 Birkenhead | 1868 | .. | 5½ | 9½ | 1 | 1 11-in. 28-ton (Krupp), 1 2-9-in., 2 3-pr. Q.F., 2 M. | .. | 9-0 | 120 118 |
| " | Hyena | L. | 1580 | 192 | 2-44 | 0-9 | 6 | 2 | 654 Amsterdam | 1870 | .. | 5½ | 9½ | 1 | 1 11-in. 28-ton (Krupp), 1 2-9-in., 2 3-pr. Q.F., 2 M. | .. | 7-0 | 76 118 |
| <i>a.g.b.</i> | Isala | L. | 383 | 159 | 4-25 | 0-4 | 5 | 2 | 306 Amsterdam | 1876 | .. | 5 | 5 | 1 | 2 4-7-in. (Krupp) | .. | 7-7 | 28 44 |
| <i>t.</i> | Koning der Nederlanden (I) | L. | 5400 | 279 | 9-49 | 9-19 | 8 | 2 | 4500 Amsterdam | 1874 | .. | 7½ | 9½ | 3 | 4 11-in., 4 4-7-in., 2 2-9-in., 1 4-in., 4 1-4-in. Q.F. | 6 | 12-0 | 520 308 |
| <i>c.d.s.t.</i> | Koningin Regentes | S. | 4950 | 316 | 10-51 | 6-21 | 8 | 2 | 6000 Amsterdam | 1900 | 347,500 | 6 | 10 | 2 | 2 9-4-in., 4 5-9 Q.F., 4 2-9-in., 8 1-4-in. | 2 sub. | 16-0 | 680 .. |
| <i>c.d.s.t.</i> | New Ship* | S. | 4600 | 327 | 5-48 | 10-20 | 0 | 2 | 5900 Amsterdam | 1892 | .. | H.N.S.H.N.S. | 11 | 3 | 1 11-in., 1 8 2-in., 2 6-6-in., 2 6-9-in., 4 2-9-in. Q.F., 4 1-4-in., 6 1-4-in. Q.F., 2 M. | 4 | 16-5 | 448 274 |
| <i>t. & b.</i> | Koningin Wilhelmina der Nederlanden † (I) | shd. | 3400 | 282 | 9-46 | 11-16 | 9 | 2 | 4658 Amsterdam | 1894 | .. | 6 | 9½ | 2 | 3 8-2-in., 2 5-9-in., 6 2-9-in. Q.F., 3 8 1-4-in. | 3 | 16-0 | 280 260 |
| <i>c.d.s.t.</i> | Kortenaar. | S. | 1547 | 187 | 0-44 | 0-9 | 8 | 2 | 630 Birkenhead | 1868 | .. | H.S. | 9½ | 1 | 1 11-in. 28-ton (Krupp), 1 2-9-in., 2 3-pr. Q.F., 2 M. | .. | 9-0 | 120 118 |
| " | Krokodil | L. | 1610 | 194 | 9-44 | 0-9 | 7 | 2 | 680 Rotterdam | 1876 | .. | 5½ | 9½ | 1 | 1 11-in. 28-ton (Krupp), 1 2-9-in., 2 3-pr. Q.F., 2 M. | .. | 9-0 | 120 118 |
| " | Luipaard | L. | 1610 | 194 | 9-44 | 0-9 | 7 | 2 | 680 Rotterdam | 1876 | .. | 5½ | 9½ | 1 | 1 11-in. 28-ton (Krupp), 1 2-9-in., 2 3-pr. Q.F., 2 M. | .. | 9-0 | 120 118 |

| | | | | | | | | | | | | | | | | | | |
|--------------------|-------------------------------|----|------|-----|------|-------|----|---|-----------------|------|----|------------|----|----|---|----|------|---------|
| <i>c.d.s.t.</i> | Matador | L. | 2000 | 209 | 6-47 | 3-10 | 6 | 2 | 691 Rotterdam | 1878 | .. | 5½ | 11 | .. | 2 11-in. 28-ton (Krupp), 1 2-9-in., 2 3-pr. Q.F., 2 M. | .. | 7-5 | 100 130 |
| <i>a.g.b.</i> | Merva | L. | 383 | 159 | 4-24 | 1-4 | 5 | 2 | 395 Amsterdam | 1879 | .. | 5 | 5 | 1 | 2 4-7-in. (Krupp) | .. | 8-0 | 28 44 |
| " | Mosa | L. | 373 | 159 | 6-24 | 1-4 | 5 | 2 | 400 Amsterdam | 1878 | .. | 5 | 5 | 1 | 2 4-7-in. (Krupp) | .. | 8-0 | 28 44 |
| <i>c.d.s.t.</i> | Panther | L. | 1580 | 159 | 3-44 | 0-9 | 6 | 2 | 560 Amsterdam | 1870 | .. | 5½ | 9½ | .. | 1 11-in. 28-ton (Krupp), 1 2-9-in., 2 3-pr. Q.F., 2 M. | .. | 7-0 | 76 118 |
| <i>c.d.s.t.</i> | Piet-Hein | S. | 3400 | 282 | 9-46 | 11-16 | 9 | 2 | 4736 Rotterdam | 1894 | .. | 6 | 9½ | 2 | 3 8-2-in., 2 5-9-in., 6 2-9-in. Q.F., 8 1-4-in. | 3 | 16-2 | 280 260 |
| <i>t.</i> | Prins Hendrik der Nederlanden | L. | 3375 | 240 | 0-44 | 0-17 | 10 | 2 | 2000 Birkenhead | 1866 | .. | H.S. | 10 | 8 | 4 9-in. 13-ton M.L.R. (Armstrong), 4 4-7-in. (Krupp), 2 2-9-in., 4 1-4-in. Q.F., 6 M. | .. | 11-0 | 380 228 |
| <i>t. & b.</i> | Reinier Claeszen | S. | 2479 | 229 | 5-44 | 4-15 | 0 | 2 | 350 Ansteran | 1891 | .. | 4½-2 comp. | 11 | 3 | 1 8-2-in. (Krupp), 1 6-6-in., 1 2-9-in., 4 1-9-in. Q.F., 3 1-4-in., 2 4-7-in. (Krupp) | 2 | 12-5 | 88 160 |
| <i>a.g.b.</i> | Rhenus | L. | 388 | 160 | 5-25 | 0-4 | 6 | 2 | 310 Amsterdam | 1877 | .. | 5 | 5 | 1 | 2 4-7-in. (Krupp) | .. | 7-5 | 28 44 |
| <i>c.d.s.t.</i> | Schorpioen | L. | 2235 | 205 | 0-38 | 0-16 | 6 | 2 | 2225 La Seyne | 1868 | .. | 6 | 11 | 1 | 1 11-in. 28-ton (Krupp), 2 2-9-in., 5 3-pr. Q.F., 2 M. | .. | 13-0 | 200 160 |
| " | Stier | L. | 2112 | 205 | 0-38 | 0-16 | 4 | 2 | 2250 Birkenhead | 1868 | .. | 11 | 8 | 1 | 1 11-in. 28-ton (Krupp), 2 2-9-in., 5 3-pr. Q.F., 2 M. | .. | 12-4 | 160 154 |
| <i>a.g.b.</i> | Vahalis | L. | 365 | 126 | 0-27 | 9-5 | 3 | 2 | 240 Rotterdam | 1870 | .. | 4 | 1 | ½ | 2 3-pr. Q.F. | .. | 7-5 | 24 34 |
| <i>c.d.s.t.</i> | Wesp | L. | 1580 | 195 | 2-44 | 0-9 | 6 | 2 | 740 Amsterdam | 1871 | .. | 5½ | 9½ | 1 | 1 11-in. 28-ton (Krupp), 1 2-9-in., 2 3-pr. Q.F., 2 M. | .. | 8-0 | 76 118 |

* Estimates, 1901.

† Has received new engines and boilers.

339

NETHERLANDS.—Cruising Ships.

((I) denotes vessels of the Dutch Indian Navy.)

| Class. | NAME. | Material of Hull. | Displacement. | Length. | Beam. | Draft. | Propellers. | Indicated Horse-power. | Where Built. | Date of Launch. | Cost. | Armour. | | Armament. | | Speed. | Normal Coal Supply. | Complement. |
|--------|---------------|-------------------|-------------------|------------------|-----------------|--------------------|-------------|------------------------|--------------|-----------------|---------|---------------|-------|---|----------------|-------------|---------------------|-------------|
| | | | | | | | | | | | | Gun Position. | Deck. | Guns. | Torpedo Tubes. | | | |
| cr. | Alkmaar | Op. shd. | metric tons. 1083 | ft. in. 178 9 30 | ft. in. 215 7 1 | ft. in. no. 6 36 1 | 1 | 686 | Amsterdam | 1874 | £ .. | inches. .. | .. | 15 9-in. (Krupp), 6 4 7-in., 1 2 9-in., 4 1 4-in. Q.F., 2 M. | .. | knots. 10-0 | 130 | 112 |
| cr. | Atjeh | I. & W. | 3440 | 301 0 41 | 0 21 4 1 | 2700 | 1 | 2700 | Amsterdam | 1876 | .. | .. | .. | 6 6 6-in. 6-ton, 8 4 7-in. (Krupp), 2 2 9-in., 8 3-pr. Q.F., 8 smaller. | .. | 13-5 | 440 | 301 |
| g. v. | Bali (I) | I. & W. shd. | 853 | 175 9 29 | 6 21 1 1 | 400 | 1 | 400 | Rotterdam | 1878 | .. | .. | .. | 15 9-in., 3 4 7-in. (Krupp), 1 2 9-in., 2 1 4-in. Q.F. | .. | 9-0 | 80 | 104 |
| " | Batavia (I) | I. & W. shd. | 850 | 175 6 29 | 6 11 10 1 | 400 | 1 | 400 | Amsterdam | 1876 | .. | .. | .. | 17-in. 7-ton M.L.R. (Armstrong), 2 4 7-in. (Krupp), 1 2 9-in., 2 1 4-in. Q.F. | .. | 9-0 | 95 | 104 |
| " | Bellona | I. | 920 | 178 5 32 | 9 12 6 1 | 310 | 1 | 310 | Amsterdam | 1892 | .. | .. | .. | 15 9-in., 7 4 7-in., 3 2 9-in., 13 smaller. | .. | 8-5 | 50 | 87 |
| " | Benkoelen (I) | I. & W. shd. | 853 | 147 7 29 | 6 11 10 1 | 446 | 1 | 446 | Rotterdam | 1879 | .. | .. | .. | 1 5 9-in., 3 4 7-in. (Krupp), 1 2 9-in., 2 1 4-in. Q.F. | .. | 9-5 | 100 | 99 |
| " | Bonaire | I. & W. shd. | 853 | 175 6 29 | 6 12 7 1 | 412 | 1 | 412 | Rotterdam | 1877 | .. | .. | .. | 1 5 9-in., 2 4 7-in. (Krupp), 1 2 9-in., 2 1 4-in. Q.F., 2 M. | .. | 9-0 | 104 | 84 |
| " | Borneo (I) | Op. shd. | 800 | 176 6 31 | 0 13 4 1 | 1040 | 1 | 1040 | Glasgow | 1892 | .. | .. | .. | 6 4 1-in., 1 2 9-in., 2 1 4-in. Q.F., 2 M. | .. | 13-0 | 124 | 106 |
| " | Ceram (I) | S. & W. shd. | 550 | 173 2 25 | 7 10 3 1 | 800 | 1 | 800 | Flushing | 1887 | .. | .. | .. | 3 4 7-in. (Krupp), 1 2 9-in., 2 1 4-in. Q.F. | .. | 12-5 | 70 | 82 |
| " | Condor (I) | Op. shd. | 350 | 126 0 20 | 0 10 0 1 | 300 | 1 | 300 | Amsterdam | 1885 | .. | .. | .. | 1 2 3-in., 2 2-in. | .. | 10-0 | 26 | 40 |
| cr. | De Ruyter | I. & W. shd. | 3517 | 302 1 41 | 0 22 1 1 | 3300 | 1 | 3300 | Amsterdam | 1880 | .. | .. | .. | 6 6 6-in. 6-ton, 8 4 7-in. (Krupp), 2 2 9-in., 8 3-pr. Q.F., 8 smaller. | .. | 14-5 | 360 | 30 |
| g. v. | Edi (I) | S. | 810 | 166 0 30 | 9 11 9 2 | 1100 | 2 | 1100 | Flushing | 1897 | .. | .. | .. | 3 4 7-in. Q.F., 2 2 9-in., 4 1 4-in. | .. | 13-0 | 113 | 95 |
| " | Flores (I) | S. & W. shd. | 550 | 173 2 25 | 7 11 4 1 | 650 | 1 | 650 | Amsterdam | 1887 | .. | .. | .. | 3 4 7-in., 1 2 9-in., 2 1 4-in. Q.F. | .. | 11-7 | 75 | 82 |
| cr. | Friesland | S. | 3900 | 294 0 48 | 0 17 8 2 | 1000 | 2 | 1000 | Rotterdam | 1896 | 285,700 | .. | 2 | 2 5 9-in. Q.F., 6 4 7-in., 4 2 9-in., 8 1 4-in., 4 smaller. | 4 | 19-8 | 400 | 306 |

| | | | | | | | | | | | | | | | | | | | |
|-------|-------------------------------|--------------|------|-----------|------------|------|---|------|---------------------|------|---------|----|-------|-------|--|----|-------|-----|-----|
| cr. | Gelderland | S. | 4033 | 310 8 48 | 6 17 8 2 | 1000 | 2 | 1000 | Poijenoord | 1898 | .. | .. | 2 1/2 | 2 1/2 | 2 5 9-in. Q.F., 6 4 7-in., 4 2 9-in., 4 1 4-in., 4 M. | 4 | 20-0 | 850 | .. |
| cr. | Holland | S. | 3800 | 294 0 48 | 6 17 8 2 | 1000 | 2 | 1000 | Amsterdam | 1896 | 285,700 | .. | 2 | 2 | 2 5 9-in. Q.F., 6 4 7-in., 4 2 9-in., 8 1 4-in., 4 M. | 4 | 19-6 | 400 | 306 |
| g. v. | Java (I) | I. & W. shd. | 1300 | 205 4 31 | 2 14 1 1 | 1050 | 1 | 1050 | Rotterdam | 1885 | .. | .. | .. | .. | 1 5 9-in., 3 4 7-in., 1 2 9-in., 2 1 4-in. Q.F. | .. | 12-5 | 160 | 114 |
| cr. | Koningin Emma der Nederlanden | I. & W. shd. | 3528 | 301 0 41 | 0 21 4 1 | 2730 | 1 | 2730 | Amsterdam | 1879 | .. | .. | .. | .. | 6 6 6-in. 6-ton, 8 4 7-in. (Krupp), 2 2 9-in., 8 3-pr. Q.F., 8 M. | .. | 14-0 | 470 | 301 |
| g. v. | Lombok (I) | S. & W. shd. | 600 | 172 0 27 | 3 11 0 1 | 990 | 1 | 990 | Amsterdam | 1891 | .. | .. | .. | .. | 3 4 7-in., 1 2 9-in., 2 3-pr. Q.F. | .. | 12-0 | 55 | 87 |
| " | Makassar (I) | I. & W. shd. | 850 | 177 0 29 | 6 11 10 1 | 320 | 1 | 320 | Amsterdam | 1877 | .. | .. | .. | .. | 1 6 3-in. 7-ton M.L.R. (Armstrong), 2 4 7-in. (Krupp), 1 2 9-in., 2 1 4-in. Q.F. | .. | 8-5 | 96 | 104 |
| " | Madura (I) | I. & W. shd. | 853 | 177 0 29 | 6 11 10 1 | 400 | 1 | 400 | Amsterdam | 1880 | .. | .. | .. | .. | 1 5 9-in., 3 4 7-in. (Krupp), 1 2 9-in., 2 1 4-in. Q.F. | .. | 9-0 | 85 | 104 |
| " | Mataram (I) | S. | 810 | 166 0 30 | 9 11 9 2 | 1100 | 2 | 1100 | Amsterdam | 1896 | .. | .. | .. | .. | 3 4 7-in. Q.F., 2 3-in., 2 1 4-in. | .. | 13-0 | 113 | 95 |
| " | Nias (I) | S. | 810 | 166 0 30 | 9 11 9 2 | 1227 | 2 | 1227 | Amsterdam (Huygens) | 1895 | .. | .. | .. | .. | 3 4 7-in. Q.F., 2 2 9-in., 4 1 4-in. | .. | 13-0 | 120 | 95 |
| cr. | Noord-Brabant | S. | 4033 | 299 0 48 | 6 17 9 2 | 1000 | 2 | 1000 | Flushing | 1899 | .. | .. | 2 1/2 | 2 1/2 | 2 5 9-in. Q.F., 6 4 7-in., 4 2 9-in., 4 1 4-in., 4 M. | 4 | 20-0 | 850 | .. |
| " | Padang (I) | I. & W. shd. | 853 | 176 6 29 | 6 11 10 1 | 400 | 1 | 400 | Rotterdam | 1878 | .. | .. | .. | .. | 1 5 9-in., 3 4 7-in. (Krupp), 1 2 9-in., 2 1 4-in. Q.F. | .. | 9-0 | 80 | 104 |
| " | Pelikaan (I) | S. & W. shd. | 400 | 131 2 24 | 1 8 8 .. | 485 | 1 | 485 | Rotterdam | 1891 | .. | .. | .. | .. | 3 4 7-in. Q.F., 1 3-in., 2 3-pr. do. | .. | 11-35 | 43 | 40 |
| " | Pontianak (I) | S. & W. shd. | 730 | 163 8 30 | 3 11 9 1 | 360 | 1 | 360 | Amsterdam | 1873 | .. | .. | .. | .. | 1 6 3-in. 7-ton M.L.R. (Armstrong), 2 4 7-in. (Krupp), 1 2 9-in., 2 1 4-in. Q.F. | .. | 9-5 | 90 | 104 |
| " | Sambas (I) | C. | 654 | 137 10 28 | 10 11 10 1 | 374 | 1 | 374 | Rotterdam | 1874 | .. | .. | .. | .. | 1 7-in. 7-ton M.L.R. (Armstrong), 2 4 7-in. (Krupp), 1 2 9-in., 1 1 4-in. Q.F. | .. | 8-5 | 85 | 100 |
| " | Serdang (I) | S. | 810 | 166 0 30 | 9 11 9 2 | 1100 | 2 | 1100 | Flushing | 1897 | .. | .. | .. | .. | 3 4 7-in. Q.F., 2 2 9-in., 4 1 4-in. | .. | 13-0 | 113 | 95 |
| sl. | Sommelsdijk | I. & W. shd. | 1013 | 178 5 31 | 0 14 0 1 | 700 | 1 | 700 | Amsterdam | 1881 | .. | .. | .. | .. | 1 5 9-in., 3 4 7-in. (Krupp), 1 2 9-in. | .. | 10-0 | 150 | 88 |
| cr. | Sumatra (I) | S. | 1720 | 229 6 37 | 0 14 0 | 3750 | 1 | 3750 | Amsterdam | 1890 | .. | .. | 1 1/2 | 1 1/2 | 1 8 2-in., 1 5 9-in., 2 4 7-in., 2 9-in., 4 3-pr. Q.F., 2 M. | 1 | 17-0 | 225 | 183 |

NETHERLANDS.—Cruising Ships—continued.

342

(I) denotes vessels of the Dutch Indian Navy.)

| Class. | NAME. | Material of Hull. | Displacement. | Length. | Beam. | Draught. | Propellers. | Indicated Horse-power. | Where Built. | Date of Launch. | Cost. | Armour. | | Armament. | | Speed. | Normal Coal Supply. | Complement. |
|-------------|-------------|-------------------|---------------|----------|---------|----------|-------------|------------------------|--------------|-----------------|---------|---------------|-------|---|----------------|--------|---------------------|-------------|
| | | | metric tons. | ft. in. | ft. in. | ft. in. | no. | | | | £ | Gun Position. | Deck. | Guns. | Torpedo Tubes. | knots. | tons. | |
| <i>g.v.</i> | Sumbawa (I) | S. | 600 | 174 6 26 | 6 11 | 4 1 | 1 | 980 | Flushing | 1891 | .. | .. | .. | 3 4·7-in., 1 2·9-in., 2 3-pr. Q.F. | .. | 12·5 | 60 | 87 |
| " | Suriname | I. & W. shd. | 884 | 177 0 29 | 6 11 | 5 1 | 1 | 440 | Amsterdam | 1877 | .. | .. | .. | 1 5·9-in. (Krupp), 2 4·7-in., 1 2·9-in., 2 1·4-in. Q.F., 3 M. | .. | 9·0 | 105 | 84 |
| <i>cr.</i> | Tromp. | I. & W. shd. | 3512 | 301 0 41 | 0 21 | 4 1 | 1 | 2772 | Amsterdam | 1877 | .. | .. | .. | 6 6·6-in. 6-ton, 8 4·7-in. (Krupp), 2 2·9-in., 6 3-pr. Q.F., 2 M. | .. | 14·0 | 470 | 301 |
| <i>cr.</i> | Utrecht | S. | 4033 | 310 8 48 | 6 17 | 8 2 | 2 | 10000 Y | Amsterdam | 1898 | .. | .. | 2½ | 2 5·9-in. Q.F., 6 4·7-in., 4 2·9-in., 4 1·4-in., 4 M. | 4 | 20·0 | 850 | .. |
| <i>cr.</i> | Van Speyk | I. & W. shd. | 3728 | 302 1 41 | 0 23 | 0 1 | 1 | 2891 | Amsterdam | 1880 | .. | .. | .. | 6 6·6-in. 6-ton, 8 4·7-in. (Krupp), 2 2·9-in., 6 3-pr. Q.F., 2 M. | .. | 14·0 | 360 | 301 |
| <i>cr.</i> | Zeeland | S. | 3900 | 294 0 48 | 6 17 | 8 2 | 2 | 10539 Y L | Flushing | 1897 | 285,700 | .. | 2 | 2 5·9-in. Q.F., 6 4·7-in., 4 2·9-in., 8 1·4-in., 4 M. | 4 | 19·4 ½ | 400 | 306 |
| <i>g.v.</i> | Zwaluw (I). | I. & W. shd. | 340 | 126 0 20 | 0 10 | 0 1 | 1 | 240 | Flushing | 1882 | .. | .. | .. | 2 3-in., 2 2-in. | .. | 10·0 | 26 | 40 |

Gun-vessels of the Indian Navy, Arend, Flamingo, Raaf, Reiger, Valk, Zeeduij, and Zwaan (400 tons), launched between 1880 and 1891; Glatik (417 tons), 1894; Argus and Cycloop (438 tons), 1893; Sindoro and Soembing (642 tons), built at Soerabaja, 1877-78.

Sixteen Gunboats (Staunch class) of 268 tons, and of 100 to 171 h.p.; also five *small gunboats*, of 210 tons, and 124 to 174 h.p., and one *steel gunboat* of 108 tons and 172 h.p. The new programme contemplates the building of 3 unarmoured monitors, 14 gunboats and 3 schooners (see Chap. II.).

| Class. | NAME | Material of Hull. | Displacement. metric tons. | Length. ft. in. | Beam. ft. in. | Draught. ft. in. | Propellers. no. | Indicated Horse- power. | Where Built. | Date of Launch. | Cost. £ | Armour. | | | Armament. | | Speed. knots. | Normal Coal Supply. tons. | Complement. |
|----------|------------------------|-------------------|----------------------------------|--------------------|------------------|---------------------|--------------------|----------------------------|--------------|-----------------|------------|-------------|--------------------------|------------------|--|-------------------|------------------|---------------------------------|-------------|
| | | | | | | | | | | | | Belt. | Gun Position Plating. | Deck Plating. | Guns. | Torpedo Tubes. | | | |
| c.d.s.t. | Eidsvold. New Ship. | S. | 3847 | 290 | 0 50 | 6 16 | 6 | 2 | Elswick | { 1900 Blag. | .. | in. 6 | in. 6 | 2 | 2 8-in. Q.F., 6 3-pr. | 2 | 16·5 | 400 | 261 |
| " | Mjølner. | L. | 1515 | 203 | 5 45 | 11 11 | 10 | 1 | Norroping. | 1868 | 66,800 | H.N.S. 5 | H.N.S. 12 | 1 | 2 4·7-in., 2 2·5-in. Q.F., 3 M., 1 l. | (sub.) | 8·0 | 138 | 80 |
| " | Norge | S. | 3847 | 290 | 0 50 | 6 16 | 6 | 2 | Elswick | 1900 | .. | 6 | 6 | 2 | 2 8·2-in., 6 5·9-in. Q.F., 8 12-pr., 6 3-pr. | .. | 2 16·5 | 250 | 248 |
| " | Harald Haar- fagre. | S. | 3556 | 280 | 0 48 | 6 16 | 6 | 2 | Low Walker | 1896 | { 190,000 | H.S. 7 | H.S. 8 | 2 | 2 8-in. Q.F., 6 4·7-in., 6 12-pr., 6 1½-pr.. | (sub.) | 400 | 200 | 248 |
| " | Torkenskjold | L. | 1447 | 200 | 2 45 | 11 11 | 6 | 1 | Horten | { 1897 | .. | 5 | 12 | 1 | 2 4·7-in., 2 2·5-in. Q.F., 3 M., 1 l. | (sub.) | 2 17·2½ | 500 | 138 |
| " | Skorpionen | L. | 2003 | 203 | 5 49 | 3 13 | 2 | 1 | Horten | 1866 | .. | 7 | 14½ | 1 | 2 4·7-in., 2 2·5-in. Q.F., 3 M., 1 l. | .. | 6·0 | 138 | 80 |
| " | Thor | L. | 1515 | 200 | 2 45 | 11 11 | 10 | 1 | Horten | 1872 | .. | 5 | 12 | 1 | 2 4·7-in., 2 2·5-in. Q.F., 3 M., 1 l. | .. | 8·0 | 200 | 90 |
| " | Thrudvang | L. | 1515 | 200 | 2 45 | 11 11 | 10 | 1 | Horten | 1867 | .. | 5 | 12 | 1 | 2 4·7-in., 2 2·5-in. Q.F., 3 M., 1 l. | .. | 8·0 | 138 | 80 |

† Natural draught.

Cruising Ships.

| Class. | NAME | Material of Hull. | Displacement. | Length. | Beam. | Draught. | Propellers. | Indicated Horse-power. | Where Built. | Date of Launch. | Cost. | Armour. | Armament. | Speed. | Normal Coal Supply. | Complement. |
|---------|---------------|-------------------|---------------|---------|---------|----------|-------------|------------------------|--------------|-----------------|-------|---------------|-----------|--|---------------------|-------------|
| | | | metric tons. | ft. in. | ft. in. | ft. in. | no. | | | | £ | Gun Position. | Deck. | Torpedo Tubes. | | |
| g.b. | Æger. | S. | 338 | 108 | 6 29 | 6 | 8 | 0 | 2 | 450 Horten | 1892 | .. | in. 1 1/2 | in. 1 8-2-in., 1 2-7-in. Q.F., 2 1-9-in. | .. | 128 |
| g.v. | Eihda | W. | 1000 | 187 | 0 32 | 8 | 14 | 4 | 2 | 900 Horten | 1880 | .. | .. | 5 5-9-in. 4-ton (Krupp), 1 4-7-in., 1 L., 2 M. | 1 | 97 |
| " | Frithjof | S. | 1371 | 216 | 6 32 | 10 | 13 | 3 | 2 | 300 Horten | 1896 | .. | .. | 2 4-7-in. 4 2-9-in. Q.F., 4 1-4-in., 2 L. | 3 | .. |
| " | Heimdal | S. | 630 | 167 | 3 26 | 9 | 11 | 8 | 1 | 700 Christiania | 1892 | .. | .. | 4 2 5-in. Q.F. | (1 sub.) | .. |
| corr. | Nord Stjernen | W. | 1603 | 216 | 6 39 | 4 | 17 | 9 | 1 | 800 Horten | 1862 | .. | .. | 6 6-2-in. 3-ton M.L.R., 10 8-in. smooth-bore, 3 L. | .. | 22 |
| g.v. | Sleipner | L. | 580 | 173 | 10 25 | 11 | 9 | 6 | 2 | 800 Horten | 1877 | .. | .. | 1 10-2-in. 22-ton (Krupp), 1 5 9-in. 4-ton do., 1 M. | 1 | 195 |
| to.g.b. | Valkyrien. | S. | 380 | 190 | 0 24 | 2 | 9 | 2 | 2 | 3300 Elbing. | 1896 | .. | .. | 2 2-7-in. Q.F., 1 M. | 2 | 80 |
| g.v. | Viking | S. | 1113 | 203 | 6 30 | 6 | 13 | 0 | 2 | 2000 Horten | 1891 | .. | 1 1/2 | 2 5-9-in. (Arms), 4 2-5-in. Q.F., 4 1-4-in., 2 M. | 3 | 87 |

Eleven Gunboats, of 189 to 280 tons, and of 180 to 450 H.P., armed with one large gun and machine guns in each.

Sixteen smaller Gunboats, of 60 tons, 70 H.P., and 7 1/2 knots speed; each armed with one 5 1/2-inch gun. Also several smaller gunboats.

A first-class gunboat, No. 4, of 395 tons, in hand.

| Class. | NAME. | Material of Hull. | Displacement. metric tons. | Length. ft. in. ft. in. ft. in. | Beam. ft. in. ft. in. ft. in. | Draught. ft. in. ft. in. ft. in. | Propellers. | Indicated Horse- power. | Where Built. | Date of Launch. | Cost. £ | Armour. | | | Armament. | | Speed. knots. | Normal Coal Supply. tons. | Complement. |
|--------|---------------|-------------------|----------------------------------|------------------------------------|----------------------------------|-------------------------------------|-------------|----------------------------|--------------|-----------------|------------|---------|----------|---|-----------|-------------------|------------------|---------------------------------|-------------|
| | | | | | | | | | | | | Belt. | Battery. | Deck Plating. | Guns. | Torpedo Tubes. | | | |
| c.b. | Vasco da Gama | I. | 2422 | 200 040 | 018 0 | 2 | 3600 | Blackwall | 1876 | 132,000 | 9 | 10 | 3 | 2 10 2-in. 18-ton (Krupp), 1 5-9-in., 2 2-5-in., Q.F., 2 M. | .. | .. | 13-2 | 280 218 | .. |
| c.d.s. | 2 Unnamed | S. | 2500 | 229 842 | 813 6 | 2 | 3000 | .. | Pro. | .. | 7½ | 7½ | 2 | 2 9 4-in., 4 4-7-in. Q.F., 4 1-8-in., 4 M. | 2 | 15-0 | .. | .. | .. |

Cruising Ships.

| Class. | NAME. | Material of Hull. | Displacement. | Length. | Beam. | Draught. | Propellers. | Indicated Horse-power. | Where Built. | Date of Launch. | Cost. | Armour. | | Armament. | | Speed. | Normal Coal Supply. | Complement. |
|--------------|-----------------------|-------------------|---------------|-------------------------|-------------------------|-------------------------|-------------|------------------------|--------------|-----------------|-------|---------------|-------|--|----------------|--------|---------------------|-------------|
| | | | metric tons. | ft. in. ft. in. ft. in. | ft. in. ft. in. ft. in. | ft. in. ft. in. ft. in. | | | | | £ | Gun Position. | Deck. | Guns. | Torpedo Tubes. | knots. | tons. | |
| <i>cr.</i> | Adamastor | S. | 1993 | 250 035 | 014 0 | 2 | 4000 | Leghorn | 1893 | .. | .. | 5 | 3 | 2 5-9-in. Q.F., 4 4-7-in., 2 2-in., 4 M. | 3 | 18-0 | .. | .. |
| <i>corr.</i> | Afonso de Albuquerque | L & W. | 1111 | 203 033 | 013 6 | 1 | 1360 | Blackwall | 1884 | 56,500 | .. | .. | .. | 2 6-in. (Armstrong), 5 4-7-in., 2 2-5-in. Q.F., 2 M. | .. | 13-3 | 140 | 183 |
| " | Bartholomeu Dias | W. | 2377 | 207 037 | 520 6 | 1 | 400 (nom.) | Blackwall | 1858 | .. | .. | .. | .. | 8 5-in. | .. | 10-0 | 360 | 271 |
| <i>g.v.</i> | Bengo | L & W. | 462 | 125 624 | 6 9 0 | 1 | 400 | Birkenhead | 1879 | 22,500 | .. | .. | .. | 1 6-in., 2 3-4-in. | .. | 10-0 | 80 | 88 |
| <i>g.v.</i> | Diu | W. | 729 | 147 027 | 613 0 | 1 | 700 | Lisbon. | 1889 | .. | .. | .. | .. | 1 5-9-in. (Krupp), 2 4-7-in., 1 3-pr. Q.F., 2 M. | .. | 12-0 | 80 | 114 |

| | | | | | | | | | | | | | | | | | | |
|--------------|------------------------------|---------|------|---------|--------|----|--------|------------|-------|--------|----|----|---|----|------|------|-----|----|
| <i>cr.</i> | Dom Carlos I. | S. shd. | 4100 | 360 046 | 617 6 | 2 | 12,500 | Elswick Y. | 1898 | .. | .. | 4 | 4 5 9-in. Q.F. (Armstrong), 8 4-7-in., 12 3-pr., 6 1-pr., 4 M. (3 sub.) | 5 | 22-0 | 1000 | 260 | .. |
| <i>g.v.</i> | Dom Luiz I. | S. | 721 | 151 027 | 313 8 | 2 | 512 | Lisbon. | 1895 | .. | .. | .. | 4 4 1-in., 3 2-5-in. Q.F., 3 M. | .. | 9-9 | 100 | 107 | .. |
| " | Douro | W. | 587 | 142 926 | 011 0 | 1 | 400 | Lisbon. | 1873 | .. | .. | .. | 1 5-9-in. 4-ton, 2 4 7-in., 1 M. | .. | 10-0 | 85 | 107 | .. |
| <i>corr.</i> | Duque da Terceira (training) | W. | 1430 | 179 634 | 015 6 | 1 | 660 | Lisbon | 1864 | .. | .. | .. | 2 4 7-in., 2 2-5-in. Q.F., 1 M. | .. | 9-0 | 130 | 178 | .. |
| <i>g.v.</i> | Liberal | I. shd. | 580 | 140 025 | 610 6 | 1 | 580 | Birkenhead | 1884 | 32,500 | .. | .. | 1 6-in. 4-ton (Armstrong), 3 4-in., 2 M. | .. | 11-0 | 90 | 109 | .. |
| <i>corr.</i> | Mindello | C. | 1124 | 170 035 | 914 0 | 1 | 900 | Blackwall | 1876 | 74,500 | .. | .. | 2 7-in. 4-ton M.L.R. (Armstrong), 4 4-7-in. 2 M. | .. | 11-5 | 130 | 169 | .. |
| <i>g.v.</i> | Mandovi | I. shd. | 462 | 125 624 | 6 9 0 | 1 | 400 | Birkenhead | 1879 | 22,500 | .. | .. | 1 5-9-in., 2 3-4-in., 2 M. | .. | 10-0 | 80 | 86 | .. |
| " | Quanza | W. | 587 | 142 926 | 011 0 | 1 | 500 | Lisbon. | 1877 | .. | .. | .. | 1 5 9-in. 4-ton, 2 4-7-in., 1 M. | .. | 10-0 | 85 | 107 | .. |
| <i>corr.</i> | Rainha de Portugal | C. | 1124 | 170 035 | 914 0 | 1 | 900 | Blackwall | 1876 | 74,500 | .. | .. | 2 7-in. M.L.R. (Armstrong), 4 4-7-in., 2 M. | .. | 11-5 | 130 | 169 | .. |
| <i>cr.</i> | Rainha Amelia | S. | 1660 | 246 036 | 014 8 | 2 | 5000 | Lisbon | 1899 | .. | .. | 1 | 4 5-9-in. Q.F., 2 3-9-in., 2 3-pr., 4 M. | 2 | 17-5 | .. | 250 | .. |
| <i>g.v.</i> | Rio Ave | W. | 378 | 120 022 | 010 6 | 1 | 180 | Lisbon. | 1880 | .. | .. | .. | 1 4-7-in. (Armstrong), 2 3-in. | .. | 8-0 | 60 | 90 | .. |
| " | Rio Lima | I. shd. | 638 | 148 627 | 610 6 | 1 | 500 | Birkenhead | 1875 | 33,000 | .. | .. | 1 7-in. 4-ton (Armstrong), 4 4-in., 2 M. | .. | 11-0 | 100 | 109 | .. |
| " | Sado | C. | 645 | 148 628 | 010 6 | 1 | 500 | Birkenhead | 1875 | 35,500 | .. | .. | 1 7-in. 4-ton (Armstrong), 4 4-7-in., 1 M. | .. | 11-0 | 100 | 109 | .. |
| <i>cr.</i> | São Gabriel | S. shd. | 1800 | 246 035 | 614* 3 | 2 | 4000 | Havre. | 1808 | .. | .. | 1½ | 2 5-9-in. Q.F. (Canet), 4 4-7-in., 8 1-8-in., 2 M. | 1 | 17-5 | 500 | .. | .. |
| <i>g.v.</i> | São Rafael | S. | 721 | 151 027 | 313 8 | 2 | .. | Lisbon. | Bldg. | .. | .. | .. | 4 4 1-in., 3 5-2-in. Q.F., 3 M. | .. | 11-0 | 100 | .. | .. |
| " | São Salvador | C. | 645 | 148 628 | 010 6 | 1 | 500 | Birkenhead | 1875 | 35,500 | .. | .. | 1 7-in. 4-ton (Armstrong), 4 4-7-in., 1 M. | .. | 11-0 | 100 | 109 | .. |
| " | Tamaga | W. | 587 | 142 926 | 011 0 | 1 | 400 | Lisbon. | 1869 | .. | .. | .. | 1 5-9-in. 4-ton, 2 4-7-in. | .. | 10-0 | 85 | 107 | .. |
| " | Tejo | W. | 730 | 160 927 | 612 0 | 1 | 600 | Lisbon | 1882 | .. | .. | .. | 4 4-in., 2 1-8-in. Q.F., 2 M. | .. | 10-0 | 100 | 109 | .. |
| " | Vouga | I. shd. | 580 | 140 025 | 610 6 | 1 | 580 | Birkenhead | 1884 | 32,500 | .. | .. | 1 6-in. (Armstrong), 3 4-in., 2 M. | .. | 11-0 | 90 | 109 | .. |
| " | Zaire | W. | 641 | 143 025 | 912 0 | 1 | 500 | Lisbon. | 1886 | .. | .. | .. | 1 6-in. (Armstrong), 2 4-in., 2 M. | .. | 10-0 | 85 | 107 | .. |
| <i>g.v.</i> | Zambeze | S. | 300 | .. | .. | .. | .. | Lisbon | Bldg. | .. | .. | .. | .. | .. | .. | .. | .. | .. |

* Mean draught.

† Banker capacity.

Fifteen small Gunboats and about 29 light draught steel river-gunboats.

Two gunboats of 220 tons, the Al. Baptista de Andrade and Thomaz Andrea, are building for Mozambique and Timor.

RUSSIA.—Armoured Ships.

346

(B.S., Black Sea Fleet.)

| Class. | NAME. | Material of Hull. | Displacement. | Length. | Beam. | Draft. | Propellers. | Where Built. | Date of Launch. | Cost. | Armour. | | | Armament. | Speed. | Normal Coal Supply. | Complement. |
|------------|----------------------|-------------------|---------------|---------|-------|--------|-------------|--|-----------------|---------|----------|---------------|---------------|---|----------------|---------------------|-------------|
| | | | | | | | | | | | Belt. | Gun Position. | Deck Plating. | Guns. | Torpedo Tubes. | | |
| c.d.s., t. | Adm. Chichagoff | I. | 3505 | 254 | 0 42 | 7 18 | 0 1 | 2060 St. Petersburg. | 1868 | £ .. | n. | 6 | in. | 2 11-in. 28-ton, 4 4-pr., 6 Q.F., 4 l. | 10 5 | 300 264 | |
| " | Adm. Greig | I. | 3462 | 254 | 0 42 | 7 17 | 6 1 | 2031 St. Petersburg. | 1868 | .. | 4½ | 6 | .. | 3 11-in. 28-ton, 6 Q.F., 2 l. | 10 0 | 300 280 | |
| " | Adm. Lazareff | I. | 3462 | 254 | 0 43 | 0 17 | 6 1 | 2004 St. Petersburg. | 1867 | .. | 4½ | 6 | .. | 3 11-in. 28-ton, 6 Q.F., 4 l. | 10 25 | 300 280 | |
| a.c. | Adm. Nahimoff | S. shd. | 8524 | 333 | 0 61 | 0 25 | 0 2 | 9000 St. Petersburg. | 1885 | 572,000 | 10 | 8 | 3 | 8 8-in., 10 6-in., 10 Q.F., 4 3-pr., 6 M. | 16 7 | 1200 567 | |
| " | Adm. Boutakoff * | S. | 5985 | 341 | 6 59 | 3 17 | 3 2 | 7000 St. Petersburg. (New Admiralty) | 1900 | .. | comp. 7 | 7-8 | 3 | 1 12-in., 2 8-in., 4 6-in. Q.F., 6 1 8-in., 8 M. | 16 0 | 400 318 | |
| " | Adm. Oushakoff | S. | 4126 | 265 | 0 52 | 6 17 | 0 2 | 5000 St. Petersburg. | 1893 | 410,000 | 10 | 7-8 | 3 | 4 9-in., 4 6-in. Q.F., 6 1 8-in. Q.F., 8 M. | 16 0 | 400 318 | |
| " | Adm. Seniavin | I. | 3505 | 254 | 3 42 | 7 19 | 1 1 | 2007 St. Petersburg. | 1868 | .. | 6 | 6 | .. | 2 11-in. 28-ton, 4 4-pr., 6 Q.F., 4 l. | 10 5 | 300 260 | |
| c.d.s., t. | Adm. Spiridoff | I. | 3505 | 254 | 3 42 | 7 19 | 1 1 | 2007 St. Petersburg. | 1868 | .. | 6 | 6 | .. | 2 11-in. 28-ton, 4 4-pr., 6 Q.F., 4 l. | 10 5 | 300 260 | |
| b. | Alexander II. | S. shd. | 9927 | 326 | 0 67 | 0 23 | 0 2 | 8000 St. Petersburg. | 1887 | .. | comp. 14 | 10 | 2½ | 2 12-in. 50-ton, 4 9-in. 19-ton, 8 6-in., 4 6-pr. Q.F., 4 3-pr., 6 M. | 16 5 | 1200 504 | |
| b. | Alexander III. | S. | 13,600 | 397 | 0 76 | 0 26 | 0 2 | 16,000 St. Petersburg. (Baltic) | Bldg. | .. | 9 | 6 | 4 | 4 12-in., 12 6-in. Q.F., 20 3-in., 20 3-pr., 6 l-pr. | 18 | 2000 | |
| a.c. | Bayan | S. | 7890 | 445 | 0 57 | 0 22 | 0 2 | 16,500 La Seyne | 1900 | .. | 8-3 | 6 | 2 | 2 8-in., 8 6-in. Q.F., 20 2-9-2 sub in., 7 l-8-in. | 21 | 750 | |
| b. | Borodino | S. | 13,600 | 397 | 0 76 | 0 26 | 0 2 | 16,000 St. Petersburg. (New Admiralty) | Bldg. | .. | 9 | 5 | 4 | 4 12-in., 12 6-in. Q.F., 20 3-in., 20 3-pr., 6 l-pr. | 18 | 2000 | |
| b. | Catherine II. (B.S.) | I. & S. | 10,180 | 331 | 0 69 | 0 26 | 6 2 | 10,600 Nicolaieff | 1886 | 900,000 | comp. 16 | 14 | 3 | 6 12-in. (56-ton), 7 6-in., 8 6-pr. Q.F., 6 M. | 15 5 | 886 325 | |
| b. | Cesarevitch | S. | 13,110 | 388 | 8 76 | 2 26 | * 0 2 | 16,300 La Seyne | 1901 | .. | 9½-8½ | 10-11 | 2½ | 4 12-in., 12 6-in. Q.F., 20 3-in., 20 1 8-in., 6 1 4-in., 4 M., 2 l. | 18 0 | 900 | |

* Particulars doubtful.

| | | | | | | | | | | | | | | | | | |
|-------------|---|---------|--------|-----|-------|-------|-----|-------------------------------------|-------|---------|----|--------|----|---|------|----------|----|
| c.d.s., t. | Charodeika | I. | 1881 | 206 | 9 42 | 7 10 | 6 2 | 786 St. Petersburg. | 1867 | .. | 4½ | 6 | 1 | 4 9-in., 2 Q.F. and 2 M. | 8 0 | 250 171 | |
| a.c. | Dmitri Donskoi | S. shd. | 5882 | 296 | 5 52 | 0 24 | 4 2 | 7000 St. Petersburg. | 1883 | .. | 6 | unard. | 2½ | 6 6-in. Q.F., 10 4 7-in. Q.F., 16 Q.F. and M., 4 l. | 16 5 | 400 510 | |
| t. | Dvenadzat Apostoloff (Twelve Apostles) B.S. | S. | 8076 | 330 | 0 60 | 0 25 | 6 2 | 11,500 Nicolaieff | 1890 | .. | 14 | 12 | 2½ | 4 12-in. 52-ton, 4 6-in., 8 3-pr. Q.F., 10 M. | 16 6 | 800 500 | |
| a.c. | General Admiral | I. shd. | 4722 | 285 | 5 49 | 3 21 | 0 1 | 4472 St. Petersburg | 1873 | .. | 6 | comp. | .. | 6 8-in., 2 6-in., 10 Q.F. and M., 5 l. | 14 2 | 100 312 | |
| c.d.s. | General Admiral Apraxine | S. | 4200 | 277 | 6 52 | 6 17 | 6 2 | 5757 St. Petersburg (New Admiralty) | 1896 | .. | 10 | 7-8 | 3 | 3 10-in., 4 6-in. Q.F., 6 1 8-in., 8 1 4-in. | 15 0 | 215 318 | |
| a.c. | Gertzog Edinburgski | I. & W. | 5050 | 285 | 5 49 | 3 21 | 0 1 | 5222 St. Petersburg | 1875 | .. | 6 | 6 | .. | 4 8-in., 5 6-in., 12 Q.F., 6 l. | 15 2 | 1000 500 | |
| b. | Georgi Pobledonosetz (George the Victorious) B.S. | S. | 10,280 | 320 | 0 69 | 0 26 | 7 2 | 10,600 Sebastopol | 1892 | 431,000 | 16 | 12 | .. | 6 12-in. 56-ton, 7 6-in., 8 3-9-in. Q.F., 6 M. | 16 5 | 700 500 | |
| a.g.b. | Gremiastchy | S. | 1500 | 225 | 0 41 | 0 11 | 0 2 | 2500 St. Petersburg | 1892 | .. | 5 | .. | 1½ | 1 9-in., 1 6-in., 10 Q.F. | 15 0 | 100 142 | |
| a.c. | Gromoboi | S. | 12,336 | 473 | 0 68 | 6 26 | 0 3 | 14,500 St. Petersburg (Baltic) | 1899 | .. | 6 | 6 | 3 | 4 8-in. Q.F., 16 6-in., 6 4 7-in., 20 3-in., 36 small Q.F., 4 sub. and M. | 20 | 2500 | |
| a.g.b. | Grozjastchy | S. | 1492 | 229 | 0 41 | 8 11 | 0 2 | 2000 St. Petersburg | 1890 | .. | 5 | .. | 1½ | 1 9-in., 1 6-in., 8 Q.F. | 15 0 | 100 120 | |
| " | Khrabry | S. | 1492 | 229 | 0 41 | 8 11 | 0 2 | 3000 St. Petersburg | 1895 | .. | 5 | .. | 1½ | 1 9-in., 1 6-in., 8 Q.F. | 15 0 | 100 120 | |
| c.b. | Kniaz Pojarski | I. | 5138 | 272 | 4 49 | 3 23 | 1 1 | 2835 St. Petersburg (New Admiralty) | 1867 | .. | 4½ | 4½ | .. | 2 8-in., 2 6-in., 10 Q.F. and M., 4 l. | 11 0 | 600 452 | |
| t. | Kniaz Potemkine Tavritchesky, B.S. | S. | 12,480 | 372 | 4 72 | 10 27 | 0 2 | 10,600 Nicolaieff | 1900 | .. | 10 | 11½-9½ | 2½ | 4 12-in., 12 6-in. Q.F., 20 3-in., 1 4-in., 2 l. | 17 0 | 900* 636 | |
| b. | Kniaz Souvaroff | S. | 13,600 | 397 | 0 76 | 0 26 | 0 2 | 16,000 St. Petersburg (Baltic) | Bldg. | .. | 9 | 5 | 4 | 4 12-in., 12 6-in. Q.F., 20 3-in., 20 3-pr., 6 l-pr. | 18 | 2000 | |
| c.d.s., br. | Kreml. | I. | 3480 | 219 | 10 52 | 5 15 | 0 1 | 2822 St. Petersburg | 1864 | .. | 4½ | 4½ | .. | 8 8-in., 6 6-in., 5 Q.F., 6 l. | 9 0 | .. | 63 |
| a.c. | Minin | I. | 6136 | 298 | 6 49 | 3 25 | 3 1 | 6000 St. Petersburg | 1878 | .. | 7 | 8 | .. | 4 8-in., 12 6-in., 16 Q.F., 4 l. | 14 0 | 1200 450 | |
| c.d.s., br. | Netron-Menya | I. | 3494 | 219 | 10 53 | 0 15 | 6 1 | 1600 St. Petersburg | 1864 | .. | 4½ | 4½ | .. | 14 8-in., 4 Q.F., 2 M., 4 l. | 9 0 | 500 | 63 |
| t. | Navarin | S. | 10,206 | 338 | 0 67 | 0 25 | 0 2 | 9000 St. Petersburg | 1891 | 772,995 | 16 | 12 | .. | 4 12-in., 8 6-in., 14 Q.F., 4 l. | 16 0 | 1200 | .. |

* And liquid fuel.

347

RUSSIA.—Armoured Ships—continued.

(B.S., Black Sea Fleet.)

| Class. | NAME. | Material of Hull. | Displacement. | Length. | Beam. | Draught. | Propellers. | Indicated Horse-power. | Where Built. | Date of Launch. | Cost. | Armour. | | | Armament. | | Speed. | Normal Coal Supply. | Complement. |
|--------------------|-------------------|-------------------|---------------|------------|---------|----------|-------------|------------------------|--------------------------------|-----------------|-----------|---------|---------------|---------------|--|----------------|--------|---------------------|-------------|
| | | | tons. | ft. in. | ft. in. | ft. in. | | | | | £ | Belt. | Gun Position. | Deck Plating. | Guns. | Torpedo Tubes. | knots. | tons. | |
| <i>t.</i> | Nicolai I. | S. shd. | 9672 326 | 0 67 0 23 | 0 2 | 8000 | 2 | 8000 | St. Petersburg | 1888 | 453,000 | 14 in. | 10 in. | 2½ | 2 12-in. 52-ton, 4 9-in. 19-ton, 8 6-in. 12 Q.F., 8 M., 4 1. | 6 | 14.8 | .. | 604 |
| <i>pr. c.d.s.</i> | Novgorod, B.S. | L. shd. | 2706 101 | 0 101 0 13 | 0 6 | 2000 | 6 | 2000 | Nicolaieff | 1873 | .. | 9-7 | comp. | .. | 2 11-in., 8 Q.F., 2 M., 2 1. | .. | 6.0 | 200 | 150 |
| <i>b.</i> | Orel | S. | 13,600 397 | 0 76 0 26 | 0 2 | 16,000 | 2 | 16,000 | St. Petersburg (Galerney) | Bldg. | .. | 9 K.S. | 6 K.S. | 4 | 4 12-in., 12 6-in. Q.F., 20 3-in., 20 3-pr., 6 1-pr. | 6 | 18 | 2000 | .. |
| <i>t.</i> | Oslabya | S. | 12,674 401 | 3 71 6 25* | 3 3 | 14,500 | 3 | 14,500 | St. Petersburg (New Admiralty) | 1898 | .. | 9½ H.S. | 9 H.S. | 2½ | 4 10-in., 11 6-in. Q.F., 16 3-in., 10 18-in., 17 1-4-in., 2 1. | 6 | 18.0 | 1063 | 732 |
| <i>a.g.b.</i> | Otvazny | S. | 1500 225 | 0 41 0 11 | 0 2 | 2000 | 2 | 2000 | St. Petersburg | 1892 | .. | 5 | .. | 1½ | 1 9-in., 1 6-in., 10 Q.F. | 2 | 15.0 | 100 | 142 |
| <i>a.c.</i> | Pamyat Azova | S. shd. | 6675 377 | 0 51 0 23 | 0 2 | 8000 | 2 | 8000 | St. Petersburg | 1898 | 350,000 | 9 comp. | 8 comp. | 2½ | 2 8-in., 13 6-in., 14 Q.F., and 3 M. | 7 | 18.8 | 1000 | 525 |
| <i>t.</i> | Peresviet | S. | 12,674 401 | 3 71 9 26 | 0 3 | 14,500 | 3 | 14,500 | St. Petersburg (Baltic) | 1898 | .. | 9½ H.S. | 9 H.S. | 2½ | 4 10-in., 11 6-in. Q.F., 16 3-in., 10 18-in., 17 1-4-in., 2 1. | 6 | 18.0 | 1063 | 732 |
| <i>c.d.s., br.</i> | Pervenetz | L. | 3279 219 | 10 52 5 14 | 9 1 | 1067 | 1 | 1067 | Blackwall | 1863 | .. | 4½ | 4½ | .. | 6 8-in., 9 6-in., 7 Q.F., 8 1. | .. | 9.0 | .. | 63 |
| <i>t.</i> | Peter Veliky | L. | 9891 328 | 2 62 4 23 | 9 2 | 8253 | 2 | 8253 | St. Petersburg | 1872 | .. | 11 8 | 8-9 | 3 | 4 12-in. 40-ton, 13 Q.F., 4 1. | 1 | 14.5 | 1200 | 436 |
| <i>t.</i> | Petropavlovsk | S. | 10,960 367 | 6 69 0 26 | 0 2 | 14,213 | 2 | 14,213 | St. Petersburg | 1894 | 1,098,000 | 15½ | 10 H.S. | 3½ | 4 12-in., 12 5.9-in. Q.F., 34 smaller. | 6 | 16.3½ | 900 | .. |
| <i>t.</i> | Poltava | S. | 10,960 367 | 6 69 0 26 | 0 2 | 11,255 | 2 | 11,255 | St. Petersburg | 1894 | 1,098,000 | 15½ | 10 H.S. | 3½ | 4 12-in., 12 5.9-in. Q.F., 34 smaller. | 6 | 16.2 | 900 | .. |
| <i>b.</i> | Pobieda (Victory) | S. | 12,674 401 | 3 71 6 25* | 3 3 | 14,500 | 3 | 14,500 | St. Petersburg (Baltic) | 1900 | .. | 9½ H.S. | 9 H.S. | 2½ | 4 10-in., 11 6-in. Q.F., 16 3-in., 10 18-in., 17 1-4-in., 2 1. | 6 | 18.0 | 1063 | 732 |

| | | | | | | | | | | | | | | | | | | | |
|------------------------|---------------------------------------|---------|------------|------------|-----|--------|---|--------|----------------|------|-----------|------------|-----------|-----|---|-----|-------|------|-----|
| <i>b.</i> | Retvizan | S. | 12,700 374 | 0 72 2 25 | 0 2 | 16,000 | 2 | 16,000 | Philadelphia | 1900 | .. | 9 K.S. | 10 K.S. | 4 | 4 12-in., 12 6-in. Q.F., 20 3-in., 20 3-pr., 6 1-pr. | .. | 18.0 | 1016 | .. |
| <i>a.c.</i> | Rossia | S. shd. | 12,130 480 | 0 68 6 26 | 0 3 | 14,500 | 3 | 14,500 | St. Petersburg | 1896 | .. | 10 H.S. | 2 H.S. | 2½ | 4 8-in., 16 6-in. Q.F., 12 3-in., 36 small Q.F. & M. | 5 | 20.0 | 2500 | 725 |
| <i>t.</i> | Rostislav, B.S. | S. | 8880 341 | 0 66 6 24 | 0 2 | 8500 | 2 | 8500 | Nicolaieff | 1896 | .. | 15½ comp. | 15½ comp. | 2-3 | 4 10-in., 8 5.9-in. (Canet), 12 1.8-in. Q.F., 4 1.5-in., 2 M. | 2-3 | 16.0 | 550 | 1.. |
| <i>a.c.</i> | Rurik | S. | 10,923 336 | 6 67 0 26 | 0 2 | 13,250 | 2 | 13,250 | St. Petersburg | 1894 | .. | 10 comp. | .. | 2½ | 4 8-in., 16 6-in., 6 4.7-in., Q.F., 18 small Q.F. & M. | 5 | 18.0 | 2000 | 768 |
| <i>t.</i> | Sevastopol. | S. | 10,960 367 | 6 69 0 26 | 0 2 | 13,600 | 2 | 13,600 | St. Petersburg | 1895 | 1,098,000 | 15½ | 10 H.S. | 3½ | 4 12-in., 12 5.9-in. Q.F., 34 smaller. | 6 | 17.5 | 900 | .. |
| <i>b.</i> | Sinope, B.S. | L. & S. | 10,180 331 | 0 69 0 26 | 6 2 | 13,000 | 6 | 13,000 | Sebastopol | 1887 | 900,000 | 16 comp. | 14 comp. | 3 | 6 12-in. 50-ton, 7 6-in., 8 Q.F., 6 M. | 7 | 16.75 | 886 | 325 |
| <i>t.</i> | Sissoi Veliky (Sissoi the Great) | S. | 8880 341 | 0 66 6 24 | 0 2 | 8500 | 2 | 8500 | St. Petersburg | 1894 | 796,333 | 15½ comp. | 15½ comp. | 3 | 4 12-in., 6 6-in. Q.F., 12 1.8-in., 4 1.4-in., 2 M. | 6 | 16.0 | 550 | .. |
| <i>b.</i> | Tchesmé, B.S. | L. & S. | 10,180 331 | 0 69 0 26 | 6 2 | 11,000 | 6 | 11,000 | Sebastopol | 1886 | 900,000 | 16 comp. | 14 comp. | 3 | 6 12-in. 50 ton, 7 6-in., 8 Q.F., 6 M. | 7 | 15.0 | 886 | 325 |
| " | Tria Sviatitelia, B.S. (Three Saints) | S. | 12,480 357 | 6 72 2 27 | 0 2 | 10,600 | 2 | 10,600 | Nicolaieff | 1893 | .. | 18-16 H.S. | 16 H.S. | 3 | 4 12-in., 12 6-in. Q.F., 4 4-in., 4 7-in., 56 smaller Q.F. & M. | 6 | 16.0 | 1000 | 582 |
| <i>circular c.d.s.</i> | Vice-Admiral Popoff, B.S. | L. shd. | 3590 120 | 0 120 0 13 | 5 6 | 3066 | 6 | 3066 | Nicolaieff | 1875 | .. | 16 | 16 | .. | 2 12-in. 40-ton, 2 Q.F., 6 1. | .. | 8.0 | 250 | 458 |
| <i>a.c.</i> | Vladimir Monomach | S. shd. | 6061 296 | 6 52 0 24 | 0 2 | 7000 | 2 | 7000 | St. Petersburg | 1882 | .. | 6 comp. | .. | 2 | 5 8-in., 12 6-in., 18 Q.F. & M., 4 1. | 2 | 15.2 | 400 | 550 |

* Mean draught.

† And liquid fuel.

Ten old Monitors of 1566 tons have been removed from this list:—Uragan, Tifon, Streletz, Edinorog, Koldum, Lava, Bronnoseltz, Latnik, Perun, and Vieschun; and one of 1461 tons—Smerch.

RUSSIA.—Cruising Ships, &c. (B.S., Black Sea Fleet.)

350

| Class. | NAME. | Material of Hull. | Displacement. | Length. | Beam. | Draft. | Propellers. | Where Built. | Date of Launch. | Cost. | Armour. | | Torpedo Tubes. | Speed. | Complement. |
|----------------|----------------------|-------------------|---------------|-----------|-------|--------|--------------------------------|--------------|-----------------|-------|---------------|-------|----------------|-----------|-------------|
| | | | | | | | | | | | Gun Position. | Deck. | | | |
| <i>to g.b.</i> | Abrek. | S. | 535 212 | 224 10 | 9 0 | 2 | 4506 Abo | 1896 | 53,600 | £ | .. | ins. | 2 | 21.2 (k.) | .. |
| 2nd cl. cr. | Admiral Korniloff | S. & W. | 5000 351 | 048 620 | 0 2 | 2 | 9000 St. Nazaire | 1887 | 296,000 | .. | .. | 2½ | 6 | 17.5 | 425 |
| cr. | Afrika | L. | 2590 285 | 539 417 | 1 1 | 1 | 1350 Chester, U.S. | 1877 | .. | .. | .. | .. | .. | 13.0 | 257 |
| cr. | Asia | L. | 2500 269 | 036 016 | 5 1 | 1 | 1100 Philadelphia | 1878 | .. | .. | .. | .. | .. | 13.0 | 260 |
| cr. | Askold | S. | 6000 426 | 649 320 | 4 3 | 3 | 1900 Kiel (Germania) | 1900 | .. | .. | .. | 3 | 6 | 23.0 | 500 |
| cr. | Aurora | S. | 6630 413 | 455 921 | 0 3 | 3 | 11610 St. Petersburg (Galerny) | 1900 | .. | .. | .. | 2½ | 4 | 20.0 | 1100 |
| <i>to g.b.</i> | Bakan (Mining) | S. | 840 180 | 615 711 | 6 2 | 2 | 3300 St. Petersburg (Baltic) | 1895 | .. | .. | .. | .. | .. | 12.0 | .. |
| <i>g.v.</i> | Bobr | S. | 950 187 | 035 2 9 | 6 2 | 2 | 1150 Kretona | 1894 | 43,000 | .. | .. | .. | .. | 12.0 | .. |
| cr. | Bogatyr | S. | 6750 416 | 854 620 | 10 2 | 2 | 1900 Stettin (Vulcan) | 1900 | .. | .. | 5 | 2½ | 6 | 23.0 | 580 |
| cr. | Boyarin | S. | 3000 347 | 1040 0 | .. | 3 | 11500 Copenhagen | 1900 | .. | .. | N.S. | .. | .. | 1100 | .. |
| cr. | Unnamed | S. | 3000 347 | 1040 0 | .. | 3 | 17000 St. Petersburg (Baltic) | 1900 | .. | .. | .. | 2 | 2 | 25.0 | .. |
| <i>to g.b.</i> | Captain Sacken, B.S. | S. | 742 210 | 024 0 8 | 10 2 | 2 | 3400 Nicolaieff | 1888 | 40,700 | .. | .. | .. | 6 | 18.5 | 97 120 |
| <i>g.v.</i> | Chernomoretz, B.S. | S. | 1224 210 | 035 0 11 | 1 1 | 1 | 2000 Nicolaieff | 1889 | 40,000 | .. | .. | .. | 2 | 13.5 | 250 161 |
| " | Coreetz | S. | 1213 206 | 035 0 10 | 6 2 | 2 | 1500 Stockholm | 1886 | .. | .. | .. | 1½ | 2 | 13.5 | .. |
| cr. | Diana | S. | 6630 413 | 455 921 | 0 3 | 3 | 11610 St. Petersburg (Galerny) | 1899 | .. | .. | .. | 2½ | 4 | 20.0 | .. |
| corr. | Djigit | L. & W. | 1456 206 | 932 10 16 | 1 1 | 1 | 1700 St. Petersburg | 1876 | .. | .. | .. | .. | .. | 13.0 | 250 172 |
| " | Donetz, B.S. | S. | 1224 210 | 035 0 11 | 0 1 | 1 | 2000 Nicolaieff | 1887 | 40,000 | .. | .. | .. | 2 | 13.5 | 250 161 |

| | | | | | | | | | | | | | | | |
|----------------|------------------------|---------|----------|-----------|------|---|-------------------------------------|------|---------|----|----|----|----|------|----------|
| <i>to g.b.</i> | Gaidamak | S. | 500 192 | 624 2 7 | 6 2 | 2 | 3000 Abo | 1893 | .. | .. | .. | .. | 3 | 22.0 | 90 87 |
| <i>g.v.</i> | Gilyak | S. | 963 200 | 037 0 9 | 3 2 | 2 | 1000 St. Petersburg (New Admiralty) | 1897 | .. | .. | 2 | .. | 1 | 12.0 | .. |
| <i>to g.b.</i> | Griden, B.S. | S. | 400 192 | 624 2 7 | 6 2 | 2 | 3500 Nicolaieff | 1893 | 65,600 | .. | .. | .. | 3 | 22.0 | 90 60 |
| <i>g.v.</i> | Jermak | L. | 706 154 | 326 3 11 | 2 1 | 1 | 125 St. Petersburg | 1870 | .. | .. | .. | .. | .. | .. | .. |
| <i>to g.b.</i> | Kazarsky, B.S. | S. | 400 190 | 024 0 8 | 6 2 | 2 | 3500 Elbing | 1890 | 32,500 | .. | .. | .. | 2 | 23.0 | 90 60 |
| corr. | Kreisser | L. & W. | 1653 206 | 932 10 16 | 1 1 | 1 | 1800 St. Petersburg | 1875 | .. | .. | .. | .. | .. | 13.0 | .. |
| <i>g.v.</i> | Kubanetz, B.S. | S. | 1224 210 | 035 0 11 | 0 1 | 1 | 1500 Sebastopol (B.) | 1888 | 40,000 | .. | .. | .. | 2 | 13.8 | 250 151 |
| <i>to g.b.</i> | Lieutenant Ilyin | S. | 714 230 | 024 0 8 | 10 2 | 2 | 3500 St. Petersburg | 1887 | 40,150 | .. | .. | .. | 7 | 20.1 | 97 120 |
| <i>g.v.</i> | Mandjur | S. | 1416 210 | 035 0 11 | 0 2 | 2 | 1400 Copenhagen | 1886 | .. | .. | .. | 1½ | 2 | 14.0 | .. |
| corr. | Nayezdnik | L. & W. | 1334 206 | 932 10 14 | 0 1 | 1 | 1719 St. Petersburg | 1878 | .. | .. | .. | .. | .. | 13.0 | 250 172 |
| cr. | Novik | S. | 3000 347 | 1040 0 | .. | 3 | 17000 Danzig (Schichan) | 1900 | .. | .. | .. | 2 | 2 | 25.0 | .. |
| corr. | Oprichnik | S. & W. | 1426 206 | 932 10 14 | 0 1 | 1 | 1268 St. Petersburg | 1880 | .. | .. | .. | .. | .. | 13.0 | 230 172 |
| cr. | Pallada | S. | 6530 413 | 455 821 | 0 3 | 3 | 11610 St. Petersburg (Galerny) | 1899 | .. | .. | .. | 2½ | 4 | 20.0 | .. |
| 3rd cl. cr. | Pamyat Merkuriya, B.S. | L. & S. | 3050 295 | 041 0 17 | 0 1 | 1 | 3000 Toulon | 1880 | .. | .. | .. | .. | 2 | 16.0 | 1100 200 |
| sl. | Plastun | L. & W. | 1255 206 | 932 10 14 | 0 1 | 1 | 1268 St. Petersburg | 1879 | .. | .. | .. | .. | .. | 13.0 | 250 172 |
| <i>to g.b.</i> | Posadnik | S. | 452 192 | 624 2 7 | 6 2 | 2 | 3900 Elbing | 1892 | 111,000 | .. | .. | .. | 3 | 22.0 | 90 87 |
| corr. | Razboynik | L. & W. | 1329 206 | 932 10 14 | 0 1 | 1 | 1786 St. Petersburg | 1878 | 125,000 | .. | .. | .. | .. | 13.0 | 250 172 |

351

RUSSIA.—Cruising Ships, &c.—continued.

352

| Class. | NAME. | Material of Hull. | Displacement. | Length. | Beam. | Draught. | Propellers. | Where Built. | Date of Launch. | Cost. | Armour. | | Armament. | | Speed. | Normal Coal Supply. | Complement. | |
|-------------|---------------|-------------------|---------------|---------|-------|----------|-------------|--------------|-----------------|-------|---------------|-------|-----------|---|--------|---------------------|-------------|-----|
| | | | | | | | | | | | Gun Position. | Deck. | Guns. | Torpedo Tubes. | | | | |
| 3rd cl. cr. | Rynda | S. shd. | 3508 | 265 | 9 45 | 11 16 | 1 2 | 3000 | St. Petersburg. | 1885 | £ | in. | in. | 10 6-in., 9 q.f., M., & 4 l. | 4 | knots. 14.8 | 710 | 322 |
| g.v. | Sivooch | S. | 950 | 187 | 0 35 | 0 9 | 6 2 | 1125 | Stockholm | 1884 | 43,000 | .. | .. | 1 9-in., 1 6-in., 5 q.f., M., & 6 l. | .. | 12.5 | .. | .. |
| corr. | Strjelok | I. & W. | 1343 | 206 | 9 32 | 10 14 | 0 1 | 1528 | St. Petersburg. | 1880 | .. | .. | .. | 3 6-in., 7 q.f., M., & 4 l. | .. | 13.0 | 250 | 172 |
| cr. | Svietlana | S. | 3828 | 331 | 3 42 | 8 18 | 9 2 | 3828 | Havre | 1896 | .. | 4 | 2 | 6 5.9 q.f. (Canet), 10 1.8-in. | 4 | 20.2 (t.) | 1000 | .. |
| g.v. | Teretz, B.S. | S. | 1224 | 210 | 0 35 | 0 11 | 0 .. | 1500 | Sebastopol | 1888 | 40,000 | .. | .. | 2 8-in., 1 6-in., 7 q.f. & M. | 2 | 13.8 | 250 | 161 |
| " | Uraletz, B.S. | S. | 1224 | 210 | 0 35 | 0 11 | 0 .. | 1500 | Sebastopol | 1888 | 40,000 | .. | .. | 2 8-in., 1 6-in., 7 q.f. & M. | 2 | 13.8 | 250 | 161 |
| cr. | Varyag | S. | 6500 | 420 | 0 52 | 0 20 | 8 2 | 2000 | Philadelphia | 1890 | .. | .. | 3 | 12 6-in. q.f., 12 3-in., 6 1.4 Hotchkiss. | 6 | 23.0 | 770 | 571 |
| to.g.b. | Voevoda | S. | 400 | 192 | 6 24 | 2 7 | 6 2 | Nic. 3600 | Elbing | 1892 | 111,000 | .. | .. | 2 1.8-in. q.f., 7 1 4-in., 3 M. | 3 | 22.0 | 1250 90 | 87 |
| sl. | Vjestnik | I. & W. | 1255 | 206 | 9 32 | 10 14 | 2 1 | 1268 | St. Petersburg. | 1879 | .. | .. | .. | 3 6-in., 7 q.f. & M., & 4 l. | .. | 13.0 | 250 | 172 |
| to.g.b. | Vzadnik | S. | 400 | 192 | 6 24 | 2 7 | 6 2 | 3000 | Abo | 1893 | .. | .. | .. | 4 1 8-in. q.f., 7 1 4-in. 10 M. & l. | 3 | 22.0 | 250 | 172 |
| sl. | Zabiyaka | I. | 1234 | 219 | 10 29 | 6 14 | 9 1 | 1194 | Philadelphia | 1878 | .. | .. | .. | 6 q.f., 4 M., 5 l. | .. | 14.5 | 90 | 87 |
| g.v. | Zaporozjetz | S. | 1224 | 210 | 0 35 | 0 10 | 0 2 | 1500 | Nicolaieff | 1887 | 40,000 | .. | .. | 2 8-in., 1 6-in., 7 q.f. & M. | 2 | 13.5 | 250 | 161 |
| cr. | Unnamed, A. | S. | 6375 | 413 | 4 52 | 5 20 | 8 2 | 2000 | Windau. | 1890 | .. | .. | 2 | 12 6-in. q.f., 12 3-in., 8 1.8-in. | 5 | 23.0 | .. | .. |
| cr. | " B. | S. | 6500 | .. | .. | .. | .. | B. | St. Petersburg. | Pro. | .. | .. | .. | .. | .. | .. | .. | .. |
| cr. | " C. | S. | 6500 | .. | .. | .. | .. | .. | Nicolaieff | Pro. | .. | .. | .. | .. | .. | .. | .. | .. |
| cr. | " D. | S. | 6500 | .. | .. | .. | .. | .. | Nicolaieff | Pro. | .. | .. | .. | .. | .. | .. | .. | .. |

Baltic:—Ten Gunboats, *Staunch*. Class of 270 to 402 tons, 195 to 445 I.H.P., with 1 11-inch breech-loader, and 9 knots speed, and two Gunboats of about 180 tons and 7 knots speed. *Training Ships*, *Bajan*, *Voin*, *Vierny*, and *Moriak*. *Ernach*, very powerful ice-breaker. Black Sea:—*Three Steamers* (Gun-vessels, *Despatch-vessels*, &c.) 90 to 298 tons. *Imperial Yachts*, *Standart*, *Poharna Svezda*, *Tsarevna*, &c.

Auxiliary Steamers.

| Class. | NAME. | Material of Hull. | Displacement. | Length. | Beam. | Draught. | Propellers. | Indicator Horse-power. | Where Built. | Date of Launch. | Sp. ed. |
|-------------------|----------------------------------|-------------------|---------------|---------|-------|----------|-------------|-----------------------------|----------------------|-----------------|---------|
| Auxiliary Cruiser | BLACK SEA CO. | | | | | | | | | | |
| " | Czar | S. | 2340 | 319 0 | 37 0 | 23 6 | 1 | 350 nom. | Newcastle | 1883 | 14 |
| " | Czarevna | " | 2340 | 319 0 | 37 0 | 23 6 | 1 | 350 nom. | " | 1883 | 14 |
| " | Czaritza | " | 2340 | 319 0 | 37 0 | 23 6 | 1 | 350 nom. | " | 1883 | 14 |
| " | Grand Duke Alexis | " | 2350 | 284 0 | 37 0 | 14 9 | 1 | 3500 | Heburn | 1890 | 16 |
| " | Grand Duke Constantine | " | 2400 | 284 0 | 37 0 | 15 0 | 1 | 3500 | " | 1891 | 16 |
| " | Grand Duke No. 1. | " | 2400 | 283 0 | 37 0 | 15 0 | 1 | 2500 | " | Bldg. | 14½ |
| " | Grand Duke No. 2. | " | 2400 | 288 0 | 37 0 | 15 0 | 1 | 2500 | " | " | 14½ |
| " | Emperor Nicolas II. | " | " | " | " | " | " | " | " | 1895 | " |
| " | Roumantzeff | " | 760 | 212 0 | 28 0 | 7 6 | 2 | 1000 | " | 1894 | 13 |
| VOLUNTEER FLEET. | | | | | | | | | | | |
| " | Ekaterrinoslav | " | 10,500 | 440 0 | 49 6 | 24 0 | 2 | 3200 | " | 1896 | 12 |
| " | Khabarovsk | I. | 2700 | 265 0 | 36 0 | 14 6 | 2 | 1800 | " | 1894 | 13 |
| " | Kherson* | S. | 10,225 B | 493 0 | 54 3 | 24 0 | 2 | { 12,500 B 13,150 (L.) } | " | 1895 | 19½ |
| " | Kiev | " | 10,500 | 440 0 | 49 6 | 24 0 | 2 | 3200 | Glydebank | 1895 | 13 |
| " | Kostroma | I. | 7975 | 360 0 | 42 0 | 23 6 | 1 | 2700 | Hebburn | 1888 | 14 |
| " | Moskva* | S. | 11,700 B | 508 0 | 58 0 | 25 0 | 2 | 12,500 B. | Glydebank | 1898 | 20 |
| " | Nijni Novgorod | I. | 7876 | 325 0 | 40 0 | 23 6 | 1 | 2000 | Elswick | 1891 | 11½ |
| " | Orel | " | 7990 | 445 0 | 48 0 | 23 6 | 2 | 10,000 | Hebburn | 1889 | 19 |
| " | Petersburg | " | 9252 | 460 0 | 52 0 | 24 0 | 2 | 11,000 | " | 1894 | 19 |
| " | Poltava | S. | 10,225 B | 493 0 | 54 3 | 24 0 | 2 | 12,500 | Dumbarton | Bldg. | 14½ |
| " | Saratoff | " | 8556 | 462 0 | 50 0 | 24 0 | 2 | 10,000 | Glasgow | 1892 | 19 |
| " | Smolensk | " | 11,850 | 506 6 | 58 0 | 24 0 | 2 | 16,500 B. | Newcastle (Hawthorn) | 1901 | 20 |
| " | Tamboff | " | 8640 | 585 0 | 45 0 | 24 6 | 1 | 2,500 | Dumbarton | 1893 | 12½ |
| " | Vladimir | " | 10,500 | 440 0 | 49 6 | 24 0 | 2 | 3,200 | " | 1895 | 12 |
| " | Voronej | " | 10,500 | 440 0 | 49 6 | 24 0 | 2 | 3,200 | " | 1895 | 12 |
| " | Yaroslav | " | 8640 | 385 0 | 45 0 | 24 6 | 1 | 2,500 | " | 1893 | 12½ |

* Armament, 3 4-7-in. Q.F., 20 smaller.

SPAIN.—Armoured Ships.

354

| Class. | NAME. | Material of Hull. | Displacement. | Length. | Beam. | Draft. | Propellers. | Indicated Horse-power. | Where Built. | Date of Launch. | Cost. | Armour. | | | Armament. | | | Speed. | Normal Coal Supply. | Complement. |
|----------|---|-------------------|----------------------|-------------------|-------|--------|---------------------|------------------------|--------------|-----------------|----------|---------|---|---------------|-------------|----------------|-----|--------|---------------------|-------------|
| | | | | | | | | | | | | Belt. | Gun Position. | Deck Plating. | Guns. | Torpedo Tubes. | | | | |
| a.c.b. | Cardenal Cisneros . | S. | metric tons. 7000 | 347 10 61 0 21 10 | 2 | 15,000 | Ferrol . | 1896 | £ 600,000 | ins. 12 | ins. 10½ | ins. 2 | 2 11-in., 10 5·5-in. Q.F., 2 2·7-in., 4 2·2-in., 4 1·4-in., 2 M. | 5 | knots. 20·0 | 1200 | 500 | | | |
| " | Cataluña . . . | S. | 7000 | 347 10 61 0 21 10 | 2 | 15,000 | Cartagena . | 1900 | 600,000 | 12 | 10½ | 2 | 2 11-in., 10 5·5-in. Q.F., 2 2·7-in., 4 2·2-in., 4 1·4-in., 2 M. | 5 (sub.) | 20·0 | 1200 | 484 | | | |
| a.c.f. | Emperador Carlos V. | S. | 9235 | 380 0 67 0 25 0 | 2 | 18,500 | Cadiz (Vea Murguia) | 1895 | 734,000 | 2 | 10 | 6½ | 2 11-in. (Hontoria), 8 5·5-in. Q.F., 4 3·9-in., 2 2·7-in., 4 2·2-in., 6 M. | 6 | 20·0 | 1200 | 535 | | | |
| br. | Numancia . . . | I. | 7305 | 314 10 55 9 25 3 | 1 | 3708 | La Seyne | 1863 1897 | 315,600 | 5½ | 5 | .. | 8 10-in. M.L.R. (Armstrong), 6 6·2-in. Q.F., 6 4·7 in. (Hontoria), 8 M., 3 L. | 2 | 8·0 | 1100 | 600 | | | |
| b. | Pelayo . . . | S. | 9900 | 330 0 66 0 24 11 | 2 | 9000 | La Seyne Nic. | 1887 1897 | .. | 17¾ | 19½ | 4 | 2 12·5-in. 48-ton, 2 11-in. 38-ton, 9 5·5-in. Q.F., 6 smaller, 12 M. | 7 | 16·0 | 800 | 600 | | | |
| a.c.b. | Princesa de Asturias | S. | 7000 | 347 10 61 0 21 10 | 2 | 15,000 | Carraca | 1896 | 600,000 | 12 | 10½ | 2 | 2 11-in., 10 5·5-in. Q.F., 2 2·7-in., 4 2·2-in., 4 1·4-in., 2 M. | 5 | 20·0 | 1200 | 500 | | | |
| a.s., t. | Puig-cerda. (Monitor) (torpedo training) | I. | 553 | 127 11 29 6 6 7 | 2 | 328 | La Seyne | 1874 | .. | 4 | 4 | 9 | 1 6·2-in. (Palliser), 2 4·7-in. bronze smooth bores. | .. | 8·0 | 23 | .. | | | |
| br. | Vitoria (training) * | I. | 7250 | 318 3 55 10 25 3 | 1 | 4500 | Blackwall | 1865 | .. | 5½ | 5 | .. | 8 9-in. M.L.R. (Armstrong), 3 8-in., 1 7·8-in. (Hontoria), 8 M., 2 L. | 2 | 11·0 | 875 | 561 | | | |

* Furnished with fighting-masts and 5·5-in. Q.F. guns at La Seyne.

SPAIN.—Cruising Ships.

| Class. | NAME. | Displacement. | Length. | Beam. | Draught. | Propellers. | Indicated Horse-power. | Where Built. | Date of Launch. | Cost. | Armour. | | Armament. | | Speed. | Coal Supply. | Complement. |
|---------|---|---------------|-----------|----------|----------|-------------|------------------------|--------------|-----------------|-------|---------------|-------|--|----------------|--------|--------------|-------------|
| | | metric tons. | ft. in. | ft. in. | ft. in. | in. no. | | | | £ | Gun Position. | Deck. | Guns. | Torpedo Tubes. | knots. | tons. | |
| cr. | Alfonso XII. | S. 3090 | 278 10 42 | 7 16 5 | 1 | 4800 | Ferrol. | 1887 | .. | .. | .. | ins. | 6 6·2-in. (Hontoria), 2 2·7-in. 6·6-pr. Q.F., 4 3-pr, 5 M. | 5 | 17·5 | 600 | 300 |
| cr. | Alfonso XIII. | S. 5000 | 318 6 50 | 6 20 0 | 2 | 11,000 | Ferrol. | 1891 | .. | .. | .. | 4½ | 4 7·8-in. (Hontoria), 6 4·7-in., 6 2·2-in. Q.F., 6 1·4-in., 3 M. | 5 | 20·0 | 1200 | 276 |
| cr. | Aragon | W. 3342 | 246 0 45 | 11 20 11 | 1 | 4400 | Cartagena | 1879 | .. | .. | .. | .. | 6 6·2-in. (Hontoria), 2 3·3-in. (Krupp), 4 2·9-in., 2 M. | 2 | 14·0 | 470 | 300 |
| g.b. | General Concha | L. 524 | 157 5 25 | 7 8 7 | 2 | 600 | Ferrol. | 1883 | .. | .. | .. | .. | 3 4·7-in. (Hontoria), 2 Q.F., 1 M. | 1 | 11·5 | 80 | 93 |
| cr. | Conde de Venadito. | L. 1130 | 210 0 32 | 0 12 6 | 1 | 1600 | Cartagena | 1888 | .. | .. | .. | .. | 4 4·7-in. (Hontoria), 2 2·7-in., 2 Q.F., 5 M. | 2 | 14·0 | 220 | 130 |
| to.g.b. | Don Alvaro de Bazan | S. 823 | 233 0 26 | 9 22 0 | 2 | 4600 | Ferrol. | 1897 | .. | .. | .. | .. | 2 4·7-in. (Hontoria) Q.F., 4 1·6-in., 2 M. | 4 | 20 0 | .. | 110 |
| to.g.b. | Doña Maria de Molina | S. 823 | 233 0 26 | 9 22 0 | 2 | 4600 | Ferrol | 1896 | .. | .. | .. | .. | 2 4·7-in. (Hontoria), Q.F., 4 1·6-in., 2 M. | 4 | 20·0 | .. | 110 |
| to.g.b. | Destructor | S. 458 | 192 6 25 | 0 7 0 | 2 | 3300 | Clydebank | 1887 | .. | .. | .. | .. | 1 3·5-in., 4 6-pr. Q.F., 4 M. | 3 | 22·56 | 104 | 55 |
| cr. | Estremadura | S. 2030 | 290 0 36 | 0 14 0 | 2 | 7000 | Cadiz | 1900 | .. | .. | .. | 2 | 4 5·9-in. Q.F., 4 4·2-in., 4 2·2-in., 2 M. | .. | 20·0 | .. | .. |
| d.v. | Fernando el Catolico (Torpedo training) | L. 500 | 157 5 25 | 7 8 5 | 2 | 550 | La Seyne | 1875 | .. | .. | .. | .. | 1 6·2-in. M.L.R. (Paliser), 2 4·7-in., smooth-bores, 1 M. | .. | 10·0 | 20 | 98 |
| to.g.b. | Filipinas | S. 750 | 213 0 27 | 0 8 6 | 2 | 4600 | Cadiz | 1892 | .. | .. | .. | .. | 2 4·7-in. Q.F., 4 1·5-in., 4 M. | 4 | 20·0 | 120 | 110 |
| to.g.b. | Galicia | S. 571 | 190 0 23 | 0 10 4 | 2 | 2600 | Le Graña | 1891 | .. | .. | .. | .. | 2 4·7-in. (Hontoria), 4 2·2-in. Q.F., 1 M. | 2 | 19·0 | 106 | 80 |

SPAIN.—Cruising Ships—continued.

356

| Class. | NAME. | Material of Hull. | Displacement. | Length. | | Beam. | Draught. | Propellers. | Indicated Horse-power. | Where Built. | Date of Launch. | Cost. | Armour. | | Armament. | | Speed. | Normal Coal Supply. | Complement. |
|----------------|------------------------|-------------------|---------------|---------|-----|-------|----------|-------------|------------------------|--------------|-----------------|-------|---------------|-------|---|----------------|--------|---------------------|-------------|
| | | | | ft. | in. | | | | | | | | Gun Position. | Deck. | Guns. | Torpedo Tubes. | | | |
| <i>g. v.</i> | General Lezo . . . | I. | 524 157 | 525 | 7 8 | 6 2 | | 600 | Carthagena . | 1885 | £ | ins. | ins. | .. | 2 4.7-in. (Hontoria), 1 3.5-in. Q.F., 1 M. | 2 | 11.0 | 80 | 97 |
| <i>cr.</i> | Infanta Isabel . . . | I. | 1130 210 | 1132 | 212 | 5 1 | | 1500 | Cadiz . | 1885 | .. | .. | .. | .. | 4 4.7-in. (Hontoria), 2 2.7-in., 3 Q.F., 4 M. | 2 | 14.0 | 220 | 130 |
| <i>cr.</i> | Isabel II. | I. | 1130 210 | 1132 | 212 | 5 1 | | 1500 | Ferrol . | 1886 | .. | .. | .. | .. | 4 4.7-in. (Hontoria), 2 7.7-in., 4 Q.F., 3 M. | 2 | 14.0 | 220 | 130 |
| <i>cr.</i> | Isabel la Catolica . . | S. | 3500 | .. | .. | .. | .. | .. | Carraca . | Bldg. | .. | .. | .. | .. | .. | .. | .. | .. | .. |
| <i>cr.</i> | Lepanto | S. | 4826 318 | 650 | 620 | 0 2 | | 12,000 | Carthagena . | 1892 | .. | .. | 4 3/4 | .. | 4 7.8-in. (Hontoria), 6 4.7-in. Q.F., 6 6-pr., 4 3-pr. 5 M. | 5 | 20.0 | 1100 | 276 |
| <i>g. v.</i> | Magallanes | I. | 524 157 | 525 | 7 8 | 6 2 | | 600 | Cadiz . | 1885 | .. | .. | .. | .. | 3 4.7-in. (Hontoria), 3 M. | 1 | 11.0 | 80 | 97 |
| <i>to.g.b.</i> | Marques de la Victoria | S. | 823 233 | 026 | 922 | 0 2 | | 4600 | Ferrol . | 1897 | .. | .. | .. | .. | 2 4.7-in. (Hontoria) Q.F., 4 1.6-in., 2 M. | 4 | 20.0 | .. | 110 |
| <i>cr.</i> | Marques de la Enseñada | S. | 1030 135 | 030 | 011 | 6 2 | | 1600 | Carraca . | 1890 | .. | .. | 2 1/2 | .. | 4 4.7-in (Hontoria), 5 Q.F., 4 M. | 4 | 15.0 | 160 | 154 |
| <i>d.v.</i> | Marques del Duero . . | I. | 500 157 | 525 | 7 8 | 5 2 | | 550 | La Seyne . | 1875 | .. | .. | .. | .. | 1 6.2-in. M.L.R. (Palliser), 2 4.7-in. smooth-bore, 1 M. | .. | 10.0 | 90 | 98 |
| <i>to.g.b.</i> | Marques de Molins . . | S. | 571 190 | 053 | 010 | 4 2 | | 2600 | La Graña . | 1891 | .. | .. | .. | .. | 2 4.7-in. (Hontoria), 4 2.2-in. Q.F., 1 M. | 2 | 19.0 | 105 | 80 |
| " | Martin Alonzo Pinzon . | S. | 571 190 | 023 | 010 | 4 2 | | 2600 | La Graña . | 1892 | .. | .. | .. | .. | 4 5.9-in., 2 4.7-in., 2 3.4-in., 4 2.9-in., 4 M. | 2 | 14.0 | 470 | 300 |
| <i>cr.</i> | Navarra | W. | 3342 232 | 1142 | 720 | 4 1 | | 4400 | Ferrol . | 1881 | .. | .. | .. | .. | .. | .. | .. | .. | .. |

| | | | | | | | | | | | | | | | | | | |
|----------------|-----------------------|----|----------|---------|-----|------|-----------------|--|--|--|----|----|----|--|----|------|-----|----|
| <i>cr.</i> | Nueva España . . . | S. | 630 190 | 023 011 | 9 2 | 2600 | Carraca . 1889 | | | | .. | .. | .. | 2 4.7-in. (Hontoria), 4 2.2-in. Q.F., 1 M. | 2 | 18.0 | 106 | 91 |
| <i>to.g.b.</i> | Rapido | S. | 570 190 | 023 010 | 4 2 | 2600 | Carraca . 1891 | | | | .. | .. | .. | 2 4.7-in. (Hontoria), 4 2.2-in. Q.F., 1 M. | 2 | 18.0 | 106 | 80 |
| <i>cr.</i> | Reina Regente . . . | S. | 5000 | .. | .. | .. | Ferrol . Bldg. | | | | .. | .. | .. | .. | .. | 20.0 | .. | .. |
| " | Rio de la Plata . . . | S. | 1800 246 | 035 415 | 0 2 | 7100 | Havre . 1898 | | | | .. | 1 | .. | 2 5.5-in. Q.F., 4 3.9-in., 4 2.2-in., 6 M. | 2 | 20.0 | 270 | .. |
| <i>to.g.b.</i> | Temerario | S. | 570 190 | 023 010 | 4 2 | 2600 | .. 1889 | | | | .. | .. | .. | 2 4.7-in. (Hontoria), 4 2.2-in. Q.F., 1 M. | 2 | 20.5 | 106 | 82 |
| " | Veloz | S. | 750 213 | 027 0 8 | 6 2 | 4500 | .. Bldg. | | | | .. | .. | .. | 2 5.9-in. (Hontoria), 4 2.2-in. Q.F., 4 M. | 2 | 20.0 | 106 | .. |
| " | Vincente Yanez Pinzon | S. | 571 190 | 023 010 | 4 2 | 2600 | La Graña . 1891 | | | | .. | .. | .. | 2 4.7-in. (Hontoria), 4 2.2-in. Q.F., 1 M. | 2 | 19.0 | 106 | 80 |

In the war with the United States a number of Spanish gunboats, including nearly all of the first class, were captured (see the United States Tables), while many were destroyed, and after the war many gunboats were sold to the United States Government. The cruisers lost at Manila and Santiago have been removed from the list.

SWEDEN.—Armoured Ships.

| Class. | NAME. | Material of Hull. | Displacement. | Length. | Beam. | Draught. | Propellers. | Indicated Horse-power. | Where Built. | Date of Launch. | Cost. | Armour. | | | Armament. | | Speed. | Normal Coal Supply. | Complement. |
|-------------------|---------------|-------------------|---------------|-------------|-----------------|-----------------|-------------|------------------------|---|-----------------|-------|---------|---------------|-------------------------|--|----------------|--------|---------------------|-------------|
| | | | metric tons. | ft. in. ft. | in. ft. in. ft. | in. ft. in. ft. | | | | | £ | Belt. | Gun Position. | Back-Ing. Deck Plating. | Guns. | Torpedo Tubes. | knots. | tons. | |
| <i>c.d.s., t.</i> | A. B. C. | S. | 3570 287 | 0 49 3 16 | 5 2 | | | 6000 | Stockholm } Gothen- } borg } Malmö } | 1874 | .. | 7½ | 5½-7½ | 1½ | 2 8-2-in., 6 5-9-in. Q.F., 10 2-2-in., 2 1-4-in., 2 M. | 2 sub. | 16·5 | 300 | .. |
| <i>a.g.b.</i> | Berserk | L. | 460 130 | 3 26 3 8 | 3 2 | | | 155 | Norrköping. | 1874 | .. | 3 | 16½ | ¾ | 1 4-7-in. Q.F., 2 2-2-in. | .. | 8·0 | 19 | 45 |
| " | Björn | L. | 460 130 | 3 26 3 8 | 3 2 | | | 155 | Norrköping. | 1874 | .. | 3½ | 16½ | ¾ | 1 9-4-in., 2 M. | .. | 8·0 | 19 | 45 |
| <i>c.d.s., t.</i> | Dristigheten | S. | 3500 285 | 1 48 7 16 | 1 2 | | | 6000 | Gothenborg. | 1900 | .. | 7½ | 5½-7½ | 1½ | 2 8-2-in., 6 5-9-in. Q.F., 10 2-2-in., 2 M. | 2 sub. | 16·5 | 300 | .. |
| " | Folke | L. | 460 130 | 3 26 3 8 | 3 2 | | | 155 | Norrköping. | 1875 | .. | N.S. | N.S. | ¾ | 1 9-4-in., 2 M. | .. | 8·0 | 19 | 45 |
| " | Gerda | L. | 460 130 | 3 26 3 8 | 3 2 | | | 133 | Stockholm. | 1873 | .. | 3 | 16½ | ¾ | 1 9-4-in., 2 M. | .. | 7·6 | 19 | 45 |
| <i>c.d.s., t.</i> | Göta* | S. | 3290 258 | 6 47 11 16 | 9 2 | | | 4750 | Gothenborg. | 1890 | .. | 11½-7½ | 11½-9½ | 2 | 2 10-in., 4 6-in., 5 2-2 Q.F., 8 M. | 3 | 16·0 | 240 | 150 |
| <i>a.g.b.</i> | Hildur | L. | 460 130 | 3 26 3 8 | 3 2 | | | 133 | Stockholm. | 1872 | .. | 3 | 16½ | ¾ | 1 9-4-in., 2 M. | .. | 7·6 | 19 | 45 |
| <i>c.d.s., t.</i> | John Ericsson | L. | 1500 199 | 10 45 3 12 | 2 1 | | | 380 | Norrköping. | 1865 | .. | 4½ | 10½ | 1½ | 2 6-in., 2 2-2-in. Q.F., 2 M. | .. | 7·5 | 112 | 80 |
| " | Loke | L. | 1600 204 | 9 44 11 11 | 10 1 | | | 430 | Norrköping. | 1871 | .. | 4½ | 17½ | 1 | 2 9-4-in., 2 M. | .. | 8·5 | 112 | 75 |
| " | Njord | S. | 3500 278 | 3 48 7 17 | 5 2 | | | 5350 | Gothenborg. | 1898 | .. | 9·5 | 7½ | 1½ | 2 9-8-in., 6 4-7-in. Q.F., 10 2-2-in., 4 M. | 1 | 16·5 | 275 | 200 |
| " | Oden | S. | 3500 278 | 3 48 7 17 | 6 2 | | | 5330 | Stockholm. | 1896 | .. | 9·5 | 9½-7½ | 1½ | 2 9-8-in., 6 4-7-in. Q.F., 10 2-2-in., 4 M. | 1 | 16·5 | 275 | 200 |
| <i>a.g.b.</i> | Sölve | L. | 460 130 | 3 26 3 8 | 3 2 | | | 155 | Norrköping. | 1875 | .. | 3 | 16½ | ¾ | 1 9-4-in., 2 M. | .. | 8·0 | 19 | 45 |
| <i>c.d.s., t.</i> | Svea* | S. | 3100 248 | 4 49 3 17 | 1 2 | | | 3640 | Gothenborg. | 1886 | .. | 11½-7½ | 11½-9½ | 1½ | 2 10-in. (Armstrong), 4 4-7-in., 6 2-2-in., 8 M. | 1 | 14·7 | 220 | 268 |
| " | Thor. | S. | 3500 278 | 3 48 7 17 | 6 2 | | | 5350 | Stockholm. | 1898 | .. | 9·5 | 7½ | 1½ | 2 9-8-in., 6 4-7-in. Q.F., 10 2-2-in., 4 M. | 1 | 16·5 | 275 | 200 |
| <i>t.</i> | Thordön* | L. | 1500 199 | 10 45 3 11 | 10 1 | | | 380 | Norrköping. | 1866 | .. | 4½ | 10½ | 1 | 2 9-4-in., 2 M. | .. | 6·7 | 112 | 80 |
| <i>c.d.s., t.</i> | Thule* | S. | 3300 260 | 10 47 11 16 | 9 2 | | | 4740 | Stockholm. | 1892 | .. | 11½-7½ | 11½-9½ | 1½ | 2 10-in. (Armstrong), 4 6-in., 5 2-2 Q.F., 8 M. | 2 | 16·2 | 250 | 165 |
| " | Tirfing* | L. | 1500 199 | 10 45 3 11 | 10 1 | | | 380 | Norrköping. | 1867 | .. | 4½ | 10½ | 1 | 2 9-4-in., 2 M. | .. | 6·8 | 112 | 80 |
| <i>a.g.b.</i> | Ulf | L. | 460 130 | 3 26 3 8 | 3 2 | | | 155 | Norrköping. | 1873 | .. | 3½ | 16½ | ¾ | 1 4-7-in. Q.F., 2 2-2-in. Q.F. | .. | 8·0 | 20 | 45 |

* In course of reconstruction.

SWEDEN.—Cruising Ships, &c.

| Class. | NAME. | Material of Hull. | Displacement. | Length. | Beam. | Draught. | Propellers. | Indicated Horse-power. | Where Built. | Date of Launch. | Cost. | Armour. | Armament. | Torpedo Tubes. | Speed. | Normal Coal Supply. | Complement. |
|--------------------|--------------------------|-------------------|---------------|-----------|---------|----------|-------------|------------------------|--------------|-----------------|-------|---------------|--|----------------|--------|---------------------|-------------|
| | | | metric tons. | ft. in. | ft. in. | ft. in. | no. | | | | | Gun Position. | Deck. | | knots. | tons. | |
| corr. | Balder | W. | 1886 | 202 9 36 | 5 18 | 4 18 | 1 | 1380 | Carlskrona | 1870 | .. | .. | 1 6-in. (Armstrong), 8 4.7-in., 2 1.5-in., 1 2.5-in., 5 m. | .. | 12.1 | 200 | 218 |
| g.v. | Blenda | I. | 500 | 167 8 25 | 11 9 | 10 9 | 2 | 590 | Gothenburg | 1874 | .. | .. | 1 10.6-in., 1 4.7-in., 2 m. | .. | 11.5 | 98 | 71 |
| to.g.b. to.g.b. | Psilander Claes Uggla | S. | 800 | 232 0 27 | 3 8 | 10 2 | 2 | 4500 | Stockholm | Blag. | .. | .. | 2 4.7-in. Q.F., 4 2.2-in. | 1 (sub.) | 20.5 | .. | .. |
| g.v. | Disa | I. | 500 | 167 8 25 | 11 9 | 2 9 | 2 | 590 | Carlskrona | 1877 | .. | .. | 1 6-in., 1 4.7-in., 2 2.2, 2 m. | .. | 11.6 | 98 | 72 |
| tor. ship. | Drott (ex Ran) | I. | 630 | 175 2 25 | 11 9 | 10 2 | 2 | 960 | Stockholm | 1877 | .. | .. | 4 Engström, Q.F. | 1 | 13.0 | 100 | .. |
| g.v. | Edda | I. | 640 | 183 9 26 | 11 10 | 2 2 | 2 | 960 | Carlskrona | 1885 | .. | .. | 1 10.6-in., 1 6-in., 2 1.5, 2 m. | .. | 13.6 | 80 | 76 |
| corr. | Freja | S.&W. | 2000 | 215 11 40 | 0 19 | 8 19 | 1 | 1750 | Malmö | 1885 | .. | .. | 4 6-in., 8 4.7-in., 4 1.5-in., 2 2.5-in., 5 m. | .. | 14.1 | 180 | 250 |
| to.g.b. | Jacob Bagge | S. | 800 | 222 1 26 | 11 10 | 2 2 | 2 | 3970 | Malmö | 1898 | .. | .. | 2 4.7-in. Q.F., 4 2.2-in. | 1 (sub.) | 19.5 | .. | .. |
| " | Ornen | S. | 800 | 222 1 26 | 11 10 | 2 2 | 2 | 4100 | Gothenburg | 1896 | .. | .. | .. | .. | 19.5 | .. | .. |
| " | Claes Horn | S. | 800 | 222 1 26 | 11 10 | 2 2 | 2 | 3600 | Stockholm | 1899 | .. | .. | .. | .. | 20.0 | .. | .. |
| g.v. | Rota | I. | 536 | 171 3 25 | 3 10 | 10 2 | 2 | 780 | Stockholm | 1878 | .. | .. | 1 10.6-in., 1 4.7-in., 2 m. | .. | 13.0 | 80 | 72 |
| corr. | Saga | W. | 1530 | 200 6 34 | 5 17 | 1 17 | 1 | 900 | Carlskrona | 1878 | .. | .. | 1 6-in. (Armstrong), 6 4.7-in., 1 m., 3 l. | .. | 11.2 | 170 | 189 |
| g.v. | Skaggald | I. | 536 | 171 3 25 | 11 9 | 10 2 | 2 | 780 | Stockholm | 1879 | .. | .. | 1 10.6-in., 1 4.7-in., 2 m. | .. | 13.2 | 80 | 72 |
| " | Skagul | I. | 536 | 171 7 25 | 7 10 | 2 2 | 2 | 780 | Stockholm | 1878 | .. | .. | 1 6-in., 1 4.7-in., 2 2.2-in., 2 m. | .. | 13.1 | 80 | 72 |
| " | Skuld | I. | 536 | 171 3 25 | 3 10 | 10 2 | 2 | 780 | Carlskrona | 1879 | .. | .. | 1 10.6-in., 1 4.7-in., 2 m. | .. | 13.0 | 80 | 72 |
| " | Urd | I. | 536 | 172 3 25 | 7 10 | 6 2 | 2 | 780 | Malmö | 1877 | .. | .. | 1 6-in., 1 4.7-in., 2 2.2 Q.F., 2 m. | .. | 13.5 | 80 | 71 |
| " | Verdande | I. | 536 | 171 7 25 | 7 10 | 2 2 | 2 | 780 | Carlskrona | 1879 | .. | .. | 1 10.6-in., 1 4.7-in., 2 m. | .. | 13.2 | 80 | 72 |
| cr. | New Ship | S. | .. | .. | .. | .. | .. | 12000 | .. | Pro. | .. | .. | .. | .. | .. | .. | .. |

Four gunboats of 190 to 200 tons, and about 130 I.H.P. each, and carrying 1 5-in B.L.R. and 2 m.; also one vessel of 280 tons and 440 H.P., armed with 4 quick-firing guns—the Svenskund, used as a mining and torpedo-ship and ice-breaker.

TURKEY.—Armoured Ships.

A number of ships have been struck out of these lists owing to information obtained from Constantinople. Of the remainder few have any fighting value.

| Class. | NAME. | Material. | Displacement. | Length. | Beam. | Draught. | Propellers. | Indicated Horse-power. | Where Built. | Date of Launch. | Cost. | Armour. | | | Armament. | | | Speed. | Normal Coal Supply | Complement. |
|--------|-------------------|-----------|---------------|---------|-------|----------|-------------|------------------------|------------------------------------|-----------------|--------------|---------|--------------|--------------|---------------|--|----|----------------|--------------------|-------------|
| | | | | | | | | | | | | Belt. | Gun Position | Deck. | Guns. | Torpedo Tubes. | | | | |
| c. | Assar-i-Shefket | I. | 2080 | 203 | 5.42 | 7.16 | 5 | 2 | 1750 | La Seyne | 1868 | 6 | 5 | inches. 5 | inches. .. | 1 9-in. (Armstrong), 4 7-in., 4 M., 4 L. | .. | knots. 11.0 | 375 | 220 |
| c.b. | Assar-i-Tewfik | I. | 4687 | 272 | 4.52 | 6.24 | 11 | 1 | 3560 | La Seyne | 1868 | 8 | 6 | 6 | .. | 2 9.2-in., 6 6-in. Q.F., 10 12-pr., 12 6-pr.* | .. | 13.0 | 400 | .. |
| c. | Avni-illah | I. | 2400 | 226 | 4.36 | 0.16 | 5 | 1 | 2200 | Thames | 1869 | 6 | 6 | 6 | 1½ | 4 9-in. M.L.R. (Armstrong), 4 M., 4 L. | 1 | 12.0 | 220 | 225 |
| b. | Azizieh | I | 6400 | 292 | 0.55 | 9.25 | 7 | 1 | 3735 | Clyde | 1864 | 5½ | 4½ | .. | .. | 2 9.2-in. (Krupp), 8 8.2-in., 6 3.9-in., 7 M., 2 L. | 2 | 13.0 | 750 | 600 |
| c.b. | Feth-i-Bulend | I. | 2806 | 236 | 3.39 | 4.18 | 1 | 1 | 3250 | Thames | 1869 | 9 | 9 | 5 | 5 | 4 9-in. M.L.R. (Armstrong), 4 M., 4 L. | 1 | 13.0 | 300 | 250 |
| a.g.b. | Feth-el-Islam | I. | 335 | 101 | 9.24 | 7 | 5 | 11 | 290 | Gironde | 1864 | 3 | 3 | 3 | .. | 2 7-in. (Armstrong), 2 L. | .. | 8.0 | 20 | .. |
| c.b. | Hamidieh | I. | 6700 | 292 | 0.55 | 9.24 | 10 | 1 | 4500 | Turkey | 1885 | 9 | 5 | 5 | 3 | 10 10.2-in. (Krupp), 2 6.6-in., 6 L., 2 M. | 2 | 13.0 | 600 | .. |
| b. | Mahmoudieh | I. | 6400 | 292 | 0.55 | 9.25 | 7 | 1 | 3735 | Thames | 1864 | 5½ | 4½ | .. | .. | 2 9.2-in. (Krupp), 8 8.2-in., 6 3.9-in., 7 M., 2 L. | 2 | 12.0 | 750 | 600 |
| c.b. | Messoudieh | I. | 9120 | 331 | 5.59 | 0.25 | 11 | 2 | 11,000 Nc. Sestri Ponente | Thames | 1874 1901 | 12 | 6.9 | 1 | 1 | 2 9.2-in., 12 6-in. Q.F., 14 3-in., 10 6-pr., 2 3-pr.* | .. | 15.0 | 600 | .. |
| " | Muin-i-Zaffer | I. | 2400 | 230 | 0.36 | 0.16 | 5 | 2 | 2200 | Thames | 1869 | 6 | 6 | 6 | 1½ | 4 10-in. M.L.R. (Armstrong), 1 4.7-in. (Krupp), 4 M., 4 L. | 1 | 12.0 | 220 | .. |
| " | Mukadim-i-Hair | I. | 2806 | 236 | 3.39 | 4.18 | 1 | 1 | 3000 | Turkey | 1872 | 9 | 9 | 9 | 5 | 4 10-in. M.L.R. (Armstrong), 1 4.7-in. (Krupp), 4 M., 4 L. | 1 | 12.0 | 300 | 250 |
| " | Nedjim-i-Schefket | I. | 2050 | 203 | 5.42 | 7.16 | 5 | 2 | 1900 | La Seyne | 1868 | 6 | 5 | 5 | .. | 1 9-in., 4 7-in. (Armstrong), 4 M., 4 L. | 1 | 11.0 | 300 | 220 |
| b. | Orkanieh | I. | 6400 | 292 | 0.55 | 9.25 | 7 | 1 | 3735 | Clyde | 1865 | 5½ | 4½ | .. | .. | 2 9.2-in. (Krupp), 8 8.2-in., 6 3.9-in., 7 M., 2 L. | 2 | 12.0 | 750 | 600 |
| " | Osmanieh | I. | 6400 | 292 | 0.55 | 9.25 | 7 | 1 | 3735 | Clyde | 1864 | 5½ | 4½ | .. | .. | 2 9.2-in. (Krupp), 8 8.2-in., 6 3.9-in., 7 M., 2 L. | 2 | 12.0 | 750 | 600 |

* The Assar-i-Tewfik and Messoudieh are now at Genoa, and the latter is in hand at Messrs. Ansaldo's yard, receiving the new armament and machinery indicated. The hull has been partially rebuilt to suit the new armament, and Messrs. Ansaldo have built the engines. Nothing has as yet been decided in regard to the Assar-i-Tewfik.

TURKEY.—Cruising Ships, &c.

| Class. | NAME. | Material of Hull. | Displacement. | Length. | Beam. | Draft. | Propellers. | Horse-power. | Where Built. | Cost. | Date of Launch. | Armour. | | Armament. | | Speed. | Normal Coal Supply. | Complement. |
|---------|--------------------------|-------------------|---------------|---------|--------|--------|-------------|--------------|--------------|-------|-----------------|---------------|-------|---|----------------|-------------|---------------------|-------------|
| | | | | | | | | | | | | Gun Position. | Deck. | Guns. | Torpedo Tubes. | | | |
| cr. | Fezibahri | S. | 1815 tons. | 226 ft. | 35 ft. | 14 ft. | 2 | 2500 | Turkey | £ . . | Bldg. | in. | in. | 6 6-in. (Krupp) | 7 | 17-0 knots. | .. | .. |
| " | Heibetnuma | S. & W. | 1960 | 226 | 37 | 14 | 1 | 2500 ind. | Turkey | .. | 1890 | .. | .. | 3 6-6-in. (Krupp), 6 4-7-in., 6 Q.F. | 2 | 14-0 | .. | .. |
| " | Hundavendikar | S. | 4050 | 279 | 49 | 32 | 2 | .. | Turkey | .. | Bldg. | .. | 2 | 2 8-9-in. (Krupp), 6 5-9-in., 4 3-9-in. | 5 | .. | .. | 300 |
| g.v. | Lutfi-hamayoun | C. | 1313 | 210 | 35 | 14 | 1 | 2800 | Turkey | .. | 1892 | .. | .. | 4 6-in. (Krupp), 6 4-7-in., 6 Q.F. | 2 | 13-0 | .. | .. |
| to.g.b. | Namet | S. | 900 | 230 | 31 | 16 | 2 | 4500 | Gaarden | .. | 1890 | ½ | .. | 2 4-in. (Krupp), 16 M. | 2 | 19-0 | .. | 111 |
| " | Pelenk-i-deria | S. | 840 | 236 | 31 | 16 | 2 | 5000 | Gaarden | .. | 1890 | ½ | .. | 2 4-in. (Krupp), 16 M. | 2 | 20-0 | .. | 111 |
| g.v. | Sedul Bahr | W. | 800 | 173 | 26 | 11 | 1 | 160 | Turkey | .. | 1894 | .. | 2 | 4 4-7-in. (Krupp), 6 M. | 2 | 12-7 | 120 | .. |
| cr. | Selimieh | S. | 4050 | 279 | 49 | 32 | 2 | .. | Turkey | .. | Bldg. | .. | ½ | 2 8-2-in. (Krupp), 6 5-9-in., 4-in., 6 M. | .. | .. | .. | 300 |
| " | Shadie | S. | 1315 | 226 | 35 | 14 | 2 | 2500 | Turkey | .. | Bldg. | .. | .. | 6 5-9-in. (Krupp) | 7 | 17-0 | .. | .. |
| to.g.b. | Shahani-deria | S. | 450 | 200 | 23 | 9 | 2 | 3000 | Turkey | .. | 1892 | .. | .. | 2 4-7-in. Q.F. (Krupp), M. | 4 | 22-0 | .. | .. |
| g.v. | Zuhaf | W. | 800 | 173 | 26 | 11 | 1 | 160 | Turkey | .. | 1894 | .. | .. | 4 4-7-in. (Krupp), 6 M. | 2 | 12-7 | 120 | .. |

UNITED STATES.—Armoured Ships.

| Class. | NAME. | Material of Hull. | Displacement. | | Length. | Beam. | | Draught. | Propellers. | Indicated Horse-power. | Where Built. | Date of Launch. | Cost. | Armour. | | | Armament. | Speed. | *Coal Supply. | Complement. | |
|-------------------------|--------------|-------------------|---------------|---------|---------|---------|---------|----------|-------------|------------------------|--------------|-----------------|--------|---------|---------------|---|---|--------|---------------|-------------|-----|
| | | | tons. | ft. in. | | ft. in. | ft. in. | | | | | | | Belt. | Gun Position. | Deck Plating. | | | | | |
| t. | Alabama . | S. | 11,565 | 368 | 072 | 324 | 9 | 2 | 11,366 | Philadelphia | 1898 | 544,539 | 9½-16½ | 10-15 | 2½-4 | 4 | 4 13-in., 14 6-in. Q.F., 16 6-pr., 6 1-pr., 4 M., 2 L. | 4 | 17-1 | 800 | 593 |
| c.d.s., t. (2 t.) | Amphitrite . | L. | 3990 | 259 | 655 | 614 | 8 | 2 | 1600 | Wilmington. | 1883 | rebld. | 5-9 | 7½-11½ | 1½ | 4 | 10-in., 2 4-in. Q.F., 2 6-pr., 2 3-pr., 7 1-pr., 3 M., 1 L. | .. | 10-5 | 250 | 182 |
| c.d.s., t. (1 t.) | Arkansas . | S. | 3235 | 252 | 050 | 012 | 6 | 2 | 2400 | Newport | 1900 | 197,267 | 11 | 10-11 | 1½ | 2 | 12-in., 4 4-in. Q.F., 3 6-pr., 6 1-pr., 2 M. | .. | 11-5 | 400 | 131 |
| a. c. | Brooklyn . | S. | 9215 | 400 | 664 | 826 | 2 | 2 | 18,769 | Philadelphia | 1895 | 613,583 | 3 | 5½-8 | 6-3 | 4 | 8 8-in., 12 5-in. Q.F., 12 6-pr., 4 1-pr., 4 M., 2 L. | 4 | 21-9 | 900 | 517 |
| a. c. | California . | S. | 13,680 | 502 | 069 | 624 | 6 | 2 | 23,000 | S. Francisco | 1896 | 756,000 | 5-6 | 6 | 4 | 4 8-in., 14 6-in. Q.F., 18 3-in., 12 3-pr., 8 1-pr., 6 M., 2 L. | sub. | 22-0 | 900 | 822 | |
| c.d.s., t. (1 t.) | Canonicus . | L. | 2100 | 225 | 043 | 813 | 9 | 1 | 340 | Boston | 1864 | 123,011 | 5 | 10 | .. | 2 | 15-in. smooth-bored, 2 12-pr. H. | .. | 6-0 | 160 | 106 |
| c.d.s., t. (1 t.) | Catskill . | L. | 1875 | 200 | 046 | 011 | 9 | 1 | 340 | Brooklyn | 1863 | 87,900 | 5 | 11 | .. | 2 | 15-in. smooth-bored | .. | 6-0 | 150 | 105 |
| a. c. | Charleston . | S. | 9,700 | 424 | 066 | 025 | 6 | 2 | 21,000 | Newport | 1896 | .. | 4 | 4 | 3 | 14 6-in. Q.F., 18 14-pr., 12 3-pr., 8 1-pr., 4 M. | 8 | 22-0 | 650 | .. | |
| a. c. | Colorado . | S. | 13,680 | 502 | 069 | 6 | .. | 2 | 23,000 | Philadelphia | 1896 | 756,000 | 5-6 | 6 | 4 | 4 8-in., 14 6-in. Q.F., 18 3-in., 12 3-pr., 8 1-pr., 6 M., 2 L. | sub. | 22-0 | 900 | 822 | |
| c.d.s., t. (1 t.) | Florida . | S. | 3235 | 252 | 050 | 012 | 6 | 2 | 2400 | Elizabeth- port | 1896 | 190,075 | 11 | 10-11 | 1½ | 2 | 12-in., 4 4-in. Q.F., 3 6-pr., 6 1-pr., 2 M. | .. | 11-5 | 400 | 131 |
| Super-posed turrets. | Georgia . | S. | 14,948 | 435 | 076 | 3 | .. | 2 | 19,000 | Bath, Me. | 1896 | .. | 8-11 | 6-11 | 3 | 4 | 12-in., 8 8-in., 12 6-in. Q.F., 12 3-in., 12 3-pr., 8 1-pr., 8 M., 2 L. | 2 | 19-0 | 900 | 695 |
| t. | Illinois . | S. | 11,565 | 368 | 072 | 324 | 9 | 2 | 10,000 | Newport | 1898 | 533,237 | 9½-16½ | 10-15 | 2½-4 | 4 | 13-in., 14 6-in. Q.F., 16 6-pr., 6 1-pr., 4 M., 2 L. | 4 | 16-0 | 800 | 536 |
| b. | Indiana . | S. | 10,288 | 348 | 069 | 327 | 2 | 2 | 9,738 | Philadelphia | 1893 | 620,569 | 18 | 6-17 | 2½ | 4 | 13-in., 8 8-in., 4 6-in. Q.F., 20 6-pr., 6 1-pr., 2 L. | 2 | 15-5 | 400 | 497 |

| | | | | | | | | | | | | | | | | | |
|----------------------|-----------------|--------|---------|---------|---|--------|---------------|------|---------|--------|--------|------|---|------|------|------|-----|
| b. | Iowa . | 11,340 | 360 072 | 3 26 10 | 2 | 12,105 | Philadelphia | 1896 | 618,514 | 5-14 | 7-15 | 2½ | 4 12-in., 8 8-in., 6 4-in. Q.F., 20 6-pr., 4 1-pr., 4 M., 2 L. | 4 | 17-1 | 625 | 510 |
| c.d.s., t. (1 t.) | Jason . | 1875 | 200 046 | 0 11 6 | 1 | 340 | Chester | 1864 | 86,872 | 5 | 11 | .. | 2 15-in. smooth-bored, 2 12-pr. H. | .. | 6-0 | 150 | 105 |
| c.d.s., t. (1 t.) | Katahdin . | 2155 | 250 943 | 5 16 0 | 2 | 5,068 | Bath, Me. | 1893 | 191,102 | 3-6 | 18 | 2-6 | 4 6-pr. Q.F. | .. | 16-1 | 175 | 97 |
| super-posed turrets | Kearsarge . | 11,525 | 368 072 | 2 25 10 | 2 | 11,954 | Newport | 1898 | 462,345 | 9½-16½ | 9-17 | 2½-5 | 4 13-in., 4 8-in., 14 5-in. Q.F., 20 6-pr., 8 1-pr., 4 M., 2 L. | 4 | 16-8 | 1586 | 589 |
| c.d.s., t. (1 t.) | Kentucky . | 1875 | 200 046 | 0 11 9 | 1 | 340 | Chester | 1864 | 86,864 | 5 | 11 | .. | 2 15-in. smooth-bored, 2 12-pr. H. | .. | 6-0 | 150 | 105 |
| c.d.s., t. (1 t.) | Lehigh . | 2100 | 225 043 | 8 13 9 | 1 | 340 | Jersey City | 1865 | 130,560 | 5 | 10 | .. | 2 15-in. smooth-bored, 2 12-pr. H. | .. | 6-0 | 160 | 105 |
| c.d.s., t. (1 t.) | Mahopac . | 12,300 | 388 072 | 2 25 6 | 2 | 16,000 | Philadelphia | 1896 | 592,828 | 7½-11 | 9-12 | 2½-4 | 4 12-in., 16 6-in. Q.F., 6 3-in., 8 6-pr., 6 1-pr., 2 M., 1 L. | sub. | 18-0 | 1000 | 551 |
| t. | Maine . | 2100 | 225 043 | 8 13 9 | 1 | 340 | Jersey City | 1865 | 129,247 | 5 | 10 | .. | 2 15-in. smooth-bored, 2 12-pr. H. | .. | 6-0 | 160 | 105 |
| c.d.s., t. (1 t.) | Manhattan . | 13,680 | 502 069 | 6 .. | 2 | 23,000 | Newport | 1896 | 756,400 | 5-6 | 6 | 4 | 4 8-in., 14 6-in. Q.F., 18 3-in., 12 3-pr., 8 1-pr., 6 M., 2 L. | 2 | 22-0 | 900 | 822 |
| a. c. | Maryland . | 10,288 | 348 069 | 3 27 2 | 2 | 10,415 | Philadelphia | 1893 | 620,569 | 18 | 6-17 | 2½ | 4 13-in., 8 8-in., 4 6-in. Q.F., 20 6-pr., 8 1-pr., 2 M. | sub. | 16-2 | 400 | 495 |
| b. | Massachusetts . | 4005 | 259 655 | 6 15 0 | 2 | 1,426 | Chester | 1876 | .. | 7 | 11½ | 1½ | 4 10-in., 2 6-pr. Q.F., 2 3-pr., 6 1-pr., 1 M., 1 L. | .. | 10-5 | 250 | 149 |
| c.d.s., t. (2 t.) | Miantonomoh . | 9,700 | 424 063 | 0 25 6 | 2 | 21,000 | .. | Pro. | .. | 4 | 4 | 3 | 14 6-in. Q.F., 18 14-pr., 12 3-pr., 8 1-pr., 4 M. | .. | 22-0 | 650 | .. |
| a. c. | Milwaukee . | 12,230 | 388 072 | 3 25 6 | 2 | 16,000 | Newport | 1896 | 592,828 | 8½-12 | 9-12 | 2½-4 | 4 12-in., 16 6-in. Q.F., 6 3-in., 8 6-pr., 6 1-pr., 2 M., 2 L. | 2 | 18-0 | 1000 | 551 |
| t. | Missouri . | 3990 | 259 655 | 6 14 7 | 2 | 3,000 | Vallejo, Cal. | 1883 | .. | 5-9 | 7½-11½ | 1½ | 4 10-in., 2 4-in. Q.F., 2 6-pr., 2 3-pr., 2 14-in., 2 1-pr., 2 M., 1 L. | sub. | 12-0 | 250 | 213 |
| c.d.s., t. (2 t.) | Monadnock . | 1875 | 200 046 | 0 11 9 | 1 | 340 | Brooklyn | 1864 | 86,903 | 5 | 11 | .. | 2 15-in. smooth-bored, 2 12-pr. H. | .. | 5-5 | 160 | 105 |
| c.d.s., t. (1 t.) | Montauk . | 4084 | 256 059 | 0 15 4 | 2 | 5244 | S. Francisco | 1891 | 345,731 | 6-13 | 7½-13 | 3 | 2 12-in., 2 10-in., 6 6-pr., 4 1-pr., 2 M., 1 L. | .. | 13-6 | 200 | 218 |
| c.d.s., t. (1 t.) | Monterey . | 1875 | 200 046 | 0 11 6 | 1 | 340 | Boston | 1863 | 84,910 | 5 | 11 | .. | 2 15-in. smooth-bored, 2 12-pr. H. | .. | 6-0 | 160 | 105 |
| c.d.s., t. (1 t.) | Nahant . | 14,948 | 435 076 | 3 .. | 2 | 19,000 | Seattle | 1896 | .. | 8-11 | 6-11 | 3 | 4 12-in., 8 8-in., 12 6-in. Q.F., 12 3-in., 12 3-pr., 8 1-pr., 8 M., 2 L. | sub. | 19-0 | 900 | 695 |
| Super-posed turrets. | Nebraska . | 3235 | 252 050 | 0 12 6 | 2 | 2,400 | Bath, Me. | 1900 | 197,267 | 11 | 10-11 | 1½ | 2 12-in., 4 4-in. Q.F., 3 6-pr., 6 1-pr., 2 M. | .. | 11-5 | 400 | 131 |
| c.d.s., t. (1 t.) | Nevada . | 11,340 | 360 072 | 3 26 10 | 2 | 12,105 | Philadelphia | 1896 | 618,514 | 5-14 | 7-15 | 2½ | 4 12-in., 8 8-in., 6 4-in. Q.F., 20 6-pr., 4 1-pr., 4 M., 2 L. | 4 | 17-1 | 625 | 510 |

* The figures below the line in this column are bunker capacity; the draught given is the maximum with bunkers full; the displacement is with all stores on board and normal coal supply; L.H.P. and speed are on trial for completed vessels.

| Class. | NAME. | Material of Hull. | Displacement. | Length. | Beam. | Draught. | Propellers. | Indicated Horse-power. | Where Built. | Dates of Launch. | Cost. | Armour. | | | Armament. | | | Speed. | Normal Coal Supply. | Complement. |
|--|---------------|-------------------|---------------|---------|-------|----------|-------------|------------------------|--------------------------|------------------|---------|----------------------|----------------------|---------------|---|----------------|------|--------------|---------------------|-------------|
| | | | | | | | | | | | | Belt. | Gun Position. | Deck Plating. | Guns. | Torpedo Tubes. | | | | |
| Super-posed turrets. a.c. | New Jersey. | S. | 14,948 | 435 | 076 | 3 | 2 | 19,000 W.T. | Fore River | Blg. | .. | in. 8-11 K. S. | in. 6-11 K. S. | in. 3 | 4 12-in., 8 8-in., 12 6-in. Q.F., 12 3-in., 12 3-pr., 8 1-pr., 8 M., 2 L. | 2 sub. | 19.0 | 900 1900 | 695 | |
| t. | New York. | S. | 8200 | 380 | 664 | 10 26 | 8 | 17,401 | Philadelphia | 1891 | 613,377 | 4 | 5½-10 | 6-3 | 6 8-in., 12 4-in. Q.F., 8 6-pr., 2 1-pr., 2 M. | 2 | 21.0 | 750 | 562 | |
| | Ohio | S. | 12,440 | 388 | 072 | 3 25 | 6 | 16,000 T. | S. Francisco. | Blg. | 595,705 | 7-11 K. S. | 8-12 K. S. | 3-4 | 4 12-in., 16 6-in. Q.F., 6 3-in., 8 6-pr., 6 1-pr., 2 M., 2 L. | 2 sub. | 18.0 | 1000 2000 | 521 | |
| b. | Oregon | S. | 10,288 | 348 | 069 | 3 27 | 2 | 11,111 | S. Francisco. | 1893 | 653,447 | 18 H. S. | 6-17 H. S. | 2½ | 4 13-in., 8 8-in., 4 6-in. Q.F., 20 6-pr., 6 1-pr., 2 M., 2 L. | 2 | 16.7 | 400 1594 | 494 | |
| a.c. | Pennsylvania | S. | 13,680 | 502 | 069 | 6 24 | 6 | 23,000 W.T. | Philadelphia | Blg. | 756,000 | 5-6 K. S. | 6 K. S. | 4 | 4 8-in., 14 6-in. Q.F., 18 3-in., 12 3-pr., 8 1-pr., 6 M., 2 L. | 2 sub. | 22.0 | 900 2000 | 822 | |
| c.d.s., t. (2 t.) Super-posed turrets. a.c. | Puritan | I. | 6060 | 290 | 3 60 | 1½ 18 | 6 | 3,700 | Chester | 1882 rebt. | .. | 6-14 | 8-14 | 2 | 4 12-in., 6 4-in. Q.F., 6 6-pr., 2 1½-in., 2 1-pr., 1 L. | .. | 12.4 | 307 | 230 | |
| | Rhode Island | S. | 14,948 | 435 | 076 | 3 | 2 | 19,000 W.T. | Fore River | Blg. | .. | 8-11 K. S. | 6-11 K. S. | 3 | 4 12-in., 8 8-in., 12 6-in. Q.F., 12 3-in., 12 3-pr., 8 1-pr., 8 M., 2 L. | 2 sub. | 19.0 | 900 1900 | 695 | |
| | St. Louis | S. | 9,700 | 424 | 066 | 0 25 | 6 | 21,000 W.T. | Philadelphia (Neafie) | Blg. | .. | 4 K. S. | 4 K. S. | 3 | 14 6-in. Q.F., 18 14-pr., 12 3-pr., 8 1-pr., 4 M. | .. | 22.0 | 650 1500 | | |
| a.c. | South Dakota | S. | 13,680 | 502 | 069 | 6 | 2 | 23,000 W.T. | S. Francisco. | Blg. | 756,000 | 5-6 K. S. | 6 K. S. | 4 | 4 8-in., 14 6-in. Q.F., 18 3-in., 12 3-pr., 8 1-pr., 6 M., 2 L. | 2 sub. | 22.0 | 900 2000 | 822 | |
| c.d.s., t. (2 t.) t. | Terror | I. | 3990 | 259 | 6 55 | 6 15 | 4 | 1,600 | Philadelphia | 1883 rebt. | .. | 4-7 | 11½ | 1½ | 4 10-in., 2 6-pr., 23-pr., 2 1½-in., 1 L. | .. | 10.5 | 250 285 | 443 | |
| | Texas | S. | 6315 | 301 | 4 64 | 1 25 | 3 | 8,610 | Norfolk | 1892 | 513,716 | 12 | 12 | 2 | 2 12-in., 6 6-in., 12 6-pr. Q.F., 10 1-pr., 2 M., 1 L. | 2½ | 17.8 | 500 850 | 177 | |
| | Virginia | S. | 14,948 | 435 | 076 | 3 | 2 | 19,000 W.T. | Newport | Blg. | .. | 8-11 K. S. | 6-11 K. S. | 3 | 4 12-in., 8 8-in., 12 6-in. Q.F., 12 3-in., 12 3-pr., 8 1-pr., 8 M., 2 L. | 2 sub. | 19.0 | 900 1900 | 695 | |
| Super-posed turrets. a.c. | West Virginia | S. | 13,680 | 502 | 069 | 6 24 | 6 | 23,000 W.T. | Newport | Blg. | 756,000 | 5-6 K. S. | 6 K. S. | 4 | 4 8-in., 14 6-in. Q.F., 18 3-in., 12 3-pr., 8 1-pr., 6 M., 2 L. | 2 sub. | 22.0 | 900 2000 | 822 | |
| t. | Wisconsin | S. | 11,565 | 368 | 072 | 3 25 | 5 | 10,000 | S. Francisco. | 1898 | 549,666 | 9½-16½ K. S. | 10-15 | 3-4 | 4 13-in., 14 6-in. Q.F., 16 6-pr., 4 1-pr., 4 M., 2 L. | 4 | 16.0 | 800 1200 | 531 | |
| c.d.s., t. (1 t.) | Wyoming | S. | 3,235 | 252 | 0 50 | 0 12 | 6 | 2,400 B.&W. | S. Francisco. | 1900 | 200,350 | 11 | 10-11 | 1½ | 2 12-in., 4 4-in. Q.F., 3 6-pr., 6 1-pr., 2 M. | .. | 11.5 | 400 | 131 | |

UNITED STATES.—Cruising Ships, &c.

| Class. | NAME. | Material of Hull. | Displacement. | Length. | Beam. | Draft. | Propellers. | Indicated Horse-power. | Where Built. | Date of Launch. | Armour. | | Armament. | | Speed. | Normal Coal Supply. | Complement. |
|--------|-------------------|-------------------|---------------|---------|-------|--------|-------------|------------------------|----------------------------|-----------------|---------------|-------|---|----------------|-------------|---------------------|-------------|
| | | | | | | | | | | | Gun Position. | Deck. | Guns. | Torpedo Tubes. | | | |
| cr. | Albany (ex Abreu) | S. sh. | 3769 345 | 0 43 | 9 20 | 0 | 2 | 7400 | Elswick | 1899 247,611 | in. | in. | 6 6-in. Q.F., 4 4-7-in., 10 6-pr., 4 1-pr., 4 M., 2 l. | 3 | knots. 20·0 | 512 tons. 754 | 260 |
| g.l. | Annapolis | S. | 1000 168 | 0 36 | 0 12 | 7 | 1 | 1227 B.&W. | Elizabeth Pt. | 1896 46,789 | .. | .. | 6 4-in. Q.F., 4 6-pr., 2 1-pr., 1 M. | .. | 13·1 (t) | 100 225 | 135 |
| cr. | Atlanta | S. | 3000 271 | 3 42 | 2 21 | 1 | 1 | 4030 B.&W. | Chester | 1884 126,785 | .. | 1½ | 2 8-in., 6 6-in. Q.F., 6 6-pr., 4 1-pr., 2 M., 1 l. | .. | 15·6 | 490 | 278 |
| cr. | Baltimore | S. | 4413 327 | 6 48 | 7 23 | 11 | 2 | 10,064 B.&W. | Philadelphia | 1888 272,270 | 4½ | 4-2½ | 4 8-in., 6 6-in., 4 6-pr., 2 3-pr., 2 1-pr., 6 M., 1 l. | 5 | 20·1 | 400 1143 | 386 |
| g.v. | Bancroft | S. | 839 187 | 6 32 | 0 12 | 11 | 2 | 1213 | Elizabeth Pt. | 1892 51,371 | .. | ½ | 4 4-in. Q.F., 8 3-pr., 1 1-pr., 1 M. | 1 | 14·37 | 100 | 195 |
| g.v. | Bennington | S. | 1710 230 | 0 36 | 0 16 | 7 | 2 | 3436 | Chester | 1890 100,894 | .. | ½ | 6 6-in., 2 6-pr., 2 3-pr., 2 1-pr., 2 M. | .. | 17·5 | 200 403 | 195 |
| cr. | Boston | S. | 3000 271 | 3 42 | 2 21 | 1 | 1 | 4300 | Chester | 1884 127,196 | .. | 1½ | 2 8-in., 6 6-in., 2 6-pr., 2 3-pr., 2 1-pr., 2 1·8-in., 2 1·4-in., 2 M., 1 l. | .. | 15·6 | 495 | 278 |
| g.v. | Castine | S. | 1177 204 | 0 32 | 1 14 | 4 | 2 | 2199 | Bath, Me. | 1892 65,450 | .. | ½ | 8 4-in. Q.F., 4 6-pr., 2 1-pr., 1 M., 1 l. | .. | 16·0 | 125 292 | 151 |
| cr. | Chattanooga | S. sh. | 3200 292 | 0 44 | 0 16 | 8 | 2 | 4700 W. T. | (Elizabeth Pt., Bath, Me.) | 212,325 | .. | 2 | 10 5-in. Q.F., 8 6-pr., 2 1-pr., 4 M., 1 l. | .. | 16·5 | 470 700 | 298 |
| cr. | Cleveland | S. | 4500 325 | 0 48 | 2 22 | 6 | 2 | 9000 C. & B.&W. | Chester | 1885 182,677 | 4 | 1½ | 4 8-in. Q.F., 14 5-in. Q.F., 7 6-pr., 2 1-pr., 2 M., 1 l. | .. | 18·0 | 831 | 409 |
| cr. | Cincinnati | S. | 3213 300 | 0 42 | 0 20 | 2 | 2 | 10,000 | Brooklyn | 1892 226,055 | .. | 2½ | 1 6-in., 10 5-in. Q.F., 8 6-pr., 2 1-pr., 2 M., 1 l. | 2 | 19·0 | 350 468 | 314 |
| cr. | Columbia | S. | 7375 412 | 0 58 | 2 25 | 7 | 3 | 18,509 | Philadelphia | 1892 559,950 | 4 | 4-2½ | 1 8-in., 2 6-in., 8 4-in. Q.F., 12 6-pr., 2 1-pr., 2 M., 1 l. | 4 | 22·8 (t) | 750 1670 | 477 |
| g.v. | Concord | S. | 1710 230 | 0 36 | 0 16 | 7 | 2 | 3405 | Chester | 1890 100,894 | .. | ½ | 6 6-in., 2 6-pr. Q.F., 2 3-pr., 2 1·4-in., 2 M., 1 l. | .. | 16·8 | 200 401 | 194 |
| cr. | Detroit | S. | 2089 257 | 0 37 | 0 16 | 8 | 2 | 5227 | Baltimore | 1891 125,860 | .. | ½ | 10 5-in. Q.F., 6 6-pr., 2 1-pr., 2 M., 1 l. | 2 | 18·71 | 200 340 | 256 |

UNITED STATES.—Cruising Ships, &c.—continued.

366

| Class. | NAME. | Material of Hull. | Displacement. | Length. | Beam. | Draught. | Propellers. | Indicated Horse-power. | Where Built. | Date of Launch. | Cost. | Armour. | Armament. | Speed. | Normal Coal Supply. | Complement. |
|--------|----------------------|-------------------|---------------|-----------------|---------|----------|-------------|------------------------|-------------------------------|-----------------|---------|---------------|-----------|---|---------------------|-------------|
| | | | tons. | ft. in. ft. in. | ft. in. | ft. in. | no. | | | | \$ | Gun Position. | D. ck. | Torpedo Tubes. | tons. | |
| cr. | Denver | S. | 3200 | 292 0 44 | 0 16 | 8 2 | 2 | 4700 | Philadelphia, Weymouth, Mass. | 1884 | 212,325 | .. | 2 | 10 5-in. Q.F., 8 6-pr., 2 1-pr., 4 M., 1 L. | 470 | 293 |
| cr. | Des Moines | shd. | | | | | | | | | | | | | 700 | |
| g.v. | Dolphin | S. | 1485 | 240 0 32 | 0 17 | 1 1 | 1 | 2253 | Chester | 1884 | 64,728 | .. | .. | 3 4-in. Q.F., 2 14-pr., 2 6-pr., 2 3-pr., 2 M. | 173 | 117 |
| cr. | Don Juan de Austria* | L. | 1130 | 210 0 32 | 0 13 | 0 1 | 1 | 1600 | Carliagena | 1889 | .. | .. | .. | 4 5-in. Q.F., 4 6-pr., 4 M., 1 L. | 210 | 130 |
| cr. | Galveston | S. | 3200 | 292 0 44 | 0 16 | 8 2 | 2 | 4700 | Richmond, Va. | 1884 | 212,325 | .. | 2 | 10 5-in. Q.F., 8 6-pr., 2 1-pr., 4 M., 1 L. | 470 | 293 |
| g.v. | General Alava | shd. | | | | | | 770 | .. | .. | .. | .. | .. | 4 M. | 700 | .. |
| g.v. | Helena | S. | 1397 | 250 9 40 | 1 10 | 0 2 | 2 | 1988 | Newport News | 1896 | 57,536 | 1 | 1 | 8 4-in. Q.F., 4 6-pr., 4 1-pr., 2 M., 1 L. | 106 | 256 |
| c.v. | Isla de Cuba* | S. | 1125 | 192 0 30 | 0 12 | 4 2 | 2 | 1000 | Elswick | 1887 | .. | .. | .. | 15 5 (2) | 300 | .. |
| c.v. | Isla de Luzon* | S. | 1177 | 204 0 32 | 1 14 | 4 2 | 2 | 2046 | Bath, Me. | 1891 | 65,450 | .. | 1 | 8 4-in. Q.F., 4 6-pr., 2 1-pr., 1 M., 1 L. | 125 | 151 |
| g.v. | Machias | S. | 2089 | 257 0 37 | 0 16 | 8 2 | 2 | 5451 | Boston | 1892 | 138,498 | .. | 1 | 10 5-in. Q.F., 6 6-pr., 2 1-pr., 2 M., 1 L. | 200 | 248 |
| cr. | Marblehead | S. | 2089 | 257 0 37 | 0 16 | 8 2 | 2 | 5451 | Boston | 1892 | 138,498 | .. | 1 | 10 5-in. Q.F., 6 6-pr., 2 1-pr., 2 M., 1 L. | 200 | 248 |
| g.v. | Marietta | S. | 1000 | 174 0 34 | 0 13 | 5 2 | 2 | 1054 | S. Francisco | 1896 | 45,823 | .. | .. | 6 4-in. Q.F., 4 6-pr., 2 1-pr., 1 M., 1 L. | 120 | 140 |
| cr. | Minneapolis | S. | 7375 | 412 0 58 | 2 25 | 7 3 | 3 | 20,862 | Philadelphia | 1893 | 552,754 | 4 | 4-2 1/2 | 1 8-in., 2 6-in., 8 4-in. Q.F., 12 6-pr., 2 1-pr., 2 M., 1 L. | 750 | 477 |
| cr. | Montgomery | S. | 2089 | 257 0 37 | 0 16 | 11 2 | 2 | 5580 | Baltimore | 1891 | 125,860 | .. | 1 | 10 5-in. Q.F., 6 6-pr., 2 1-pr., 2 M., 1 L. | 200 | 257 |
| g.v. | Nashville | S. | 1371 | 220 0 38 | 1 12 | 0 2 | 2 | 2536 | Newport News | 1895 | 57,536 | .. | 1 | 8 4-in. Q.F., 4 6-pr., 2 1-pr., 2 M., 1 L. | 340 | 176 |
| cr. | Newark | S. | 4098 | 311 7 49 | 2 22 | 7 2 | 2 | 8869 | Philadelphia | 1880 | 256,437 | 3 | 3-2 | 12 6-in. Q.F., 8 6-pr., 4 1-pr., 2 M., 1 L. | 400 | 384 |
| g.v. | Newport | S. | 1100 | 168 0 36 | 0 13 | 0 1 | 1 | 1008 | Bath, Me. | 1896 | .. | .. | .. | 6 4-in. Q.F., 4 6-pr., 2 1-pr., 1 M. | 809 | 147 |

| | | | | | | | | | | | | | | | | |
|------|-----------------------------|---------|------|-----------|------|------|---|--------|--------------|------|---------|-------------|---------|--|------|-----|
| cr. | New Orleans (ex Amazonas). | S. shd. | 3769 | 846 0 43 | 9 19 | 9 2 | 2 | 7500 | Elswick | 1896 | 238,684 | .. | 3-1 1/2 | 6 6-in. Q.F., 4 4-7-in., 10 6-pr., 4 3-pr., 4 M., 2 L. | 700 | 407 |
| g.v. | Newport | S. | 1000 | 168 0 36 | 0 12 | 7 1 | 1 | 1008 | Bath, Me. | 1896 | 47,406 | .. | .. | 6 4-in. Q.F., 4 6-pr., 2 1-pr., 1 M. | 100 | 135 |
| cr. | Olympia | S. | 5570 | 840 0 53 | 1 24 | 10 2 | 2 | 17,313 | S. Francisco | 1892 | 369,054 | 4 1/2-3 1/2 | 4-2 1/2 | 4 8-in., 10 5-in. Q.F., 14 6-pr., 7 1-pr., 2 M., 1 L. | 400 | 450 |
| g.v. | Petrel | S. | 892 | 176 3 31 | 0 13 | 5 1 | 1 | 1095 | Baltimore | 1888 | 50,755 | .. | 1 | 4 6-in., 2 3-pr., 2 1-pr., 2 1-4-in., 2 M. | 1169 | 122 |
| cr. | Philadelphia | S. | 4324 | 327 6 48 | 7 23 | 5 2 | 2 | 8815 | Philadelphia | 1889 | 277,405 | .. | 4-2 1/2 | 12 6-in., 4 6-pr., 4 1-pr., 2 M., 1 L. | 200 | 384 |
| g.v. | Princeton | S. | 1000 | 168 0 36 | 0 12 | 7 1 | 1 | 800 | Camden | 1897 | 47,262 | .. | .. | 6 4-in. Q.F., 4 6-pr., 2 1-pr., 1 M. | 100 | 135 |
| cr. | Raleigh | S. | 3213 | 300 0 42 | 0 20 | 2 2 | 2 | 10,000 | Norfolk | 1892 | 226,055 | .. | 2 1/2 | 1 6-in., 10 5-in. Q.F., 8 6-pr., 4 1-pr., 2 M., 1 L. | 238 | 313 |
| cr. | Reina Mercedes† | S. | 3090 | 279 10 43 | 3 19 | 6 1 | 1 | 3700 | Ferrol | 1887 | .. | .. | .. | 6 6-2-in., 2 2-7-in., 3 2-2-in. Q.F. | 460 | 370 |
| cr. | San Francisco | S. | 4098 | 310 0 49 | 2 22 | 3 2 | 2 | 9913 | S. Francisco | 1889 | 293,435 | .. | 3-2 | 12 6-in. Q.F., 4 6-pr., 4 3-pr., 2 1-pr., 6 M., 1 L. | 350 | 383 |
| cr. | Tacoma | S. | 3200 | 292 0 44 | 0 16 | 8 2 | 2 | 4700 | S. Francisco | 1884 | 212,325 | .. | 2 | 10 5-in. Q.F., 8 6-pr., 2 1-pr., 4 M., 1 L. | 470 | 293 |
| g.v. | Topeka | I | 1814 | 250 0 35 | 0 .. | 1 | 1 | 1095 | Kiel | 1881 | .. | .. | .. | 6 4-in. Q.F., 6 3-pr., 2 1-pr., 1 M. | 700 | 167 |
| cr. | Vesuvius (Dynamite Gunboat) | S. | 929 | 252 4 26 | 6 11 | 2 2 | 2 | 3795 | Philadelphia | 1888 | 71,963 | .. | 1 | 3 15-in. dynamite guns, 3 3-pr., 2 M. | 152 | 69 |
| g.v. | Vicksburg | S. | 1000 | 168 0 36 | 0 12 | 7 1 | 1 | 1118 | Bath, Me. | 1896 | 47,406 | .. | .. | 6 4-in. Q.F., 4 6-pr., 2 1-pr., 1 M. | 100 | 135 |
| g.v. | Wheeling | S. | 1000 | 174 0 34 | 0 12 | 7 2 | 2 | 1081 | S. Francisco | 1897 | 65,540 | .. | .. | 6 4-in. Q.F., 4 6-pr., 2 1-pr., 1 M., 1 L. | 249 | 140 |
| g.v. | Wilmington | S. | 1397 | 250 9 40 | 1 10 | 0 2 | 2 | 1894 | Newport News | 1895 | 57,536 | 1 | 1 | 8 4-in. Q.F., 4 6-pr., 4 1-pr., 4 M., 1 L. | 226 | 175 |
| g.v. | Yorktown | S. | 1710 | 230 0 36 | 0 15 | 7 2 | 2 | 3392 | Philadelphia | 1888 | 93,496 | .. | 1 | 6 5-in. Q.F., 2 6-pr. Q.F., 2 3-pr., 4 1-pr., 2 M., 1 L. | 300 | 195 |

Also the sailing training ship Chesapeake (1175 tons), built at Bath, Me., and launched 1899.

* Captured at Manila after the battle of May 1, 1898, and under repair at Hong Kong. The following gunboats were captured during the war with Spain, or subsequently purchased: Albay, Alvarado, Anayal, Bare lo, Iasco, Belusan, Caramianes, Caliao, El Cano, Guardoqui, Layre, Manileño, Mariveles, Mindoro, Pampana, Panay, Pargua, Quirós, Samar, Sandoval, Urdaneta, Villaloba.

† New armament of the captured cruisers.

367

Enrolled Auxiliary Cruisers of the United States Navy.

| Class. | NAME. | Material of Hull. | Gross Tonnage. | Length. | Beam. | Depth. | Propellers. | Indicated Horse-Power. | Where Built. | When Built. | Owners. | Armament, all Q.F. | Speed. |
|--------|--------------------------|-------------------|----------------|---------|-------|--------|-------------|------------------------|---------------------|-------------|-----------------------------------|---------------------------------|--------|
| 1st | St. Louis . . . | S. | 11,629 535 | 5 63 | 0 26 | 8 | 2 | 18,000 | Philadelphia . | 1895 | International Navigation Company. | 8 5.5-in., 4 6-pr., 4 M. | 22.2 |
| 1st | St. Paul . . . | S. | 11,629 535 | 5 63 | 0 26 | 8 | 2 | 18,000 | " | 1895 | " | 8 5.5-in., 4 6-pr., 4 M. | 22.5 |
| 1st | Paris . . . | S. | 10,794 517 | 0 63 | 3 22 | 0 | 2 | 20,000 | Clydebank, Scotland | 1889 | " | 12 5.5-in., 6 6-pr., 6 M. | 20.7 |
| 1st | New York . . . | S. | 10,802 517 | 0 63 | 3 22 | 0 | 2 | 20,000 | " | 1888 | " | 12 5.5-in., 6 6-pr., 6 M. | 20.6 |
| 3rd | Newport . . . | I. | 2735 326 | 0 38 | 2 23 | 9 | 1 | .. | Chester, Pa. | 1880 | Pacific Mail. | 8 4-in., 8 M. | 16.0 |
| 3rd | City of Para . . . | I. | 3532 345 | 0 38 | 6 19 | 9 | 1 | 2250 | " | 1878 | " | 8 4-in., 8 M. | 12.0 |
| 3rd | Caracas . . . | I. | 2584 283 | 6 40 | 2 20 | 5 | 1 | .. | Philadelphia . | 1889 | Red D Line. | 8 4-in., 6 M. | 13.0 |
| 3rd | Philadelphia . . . | I. | 2520 300 | 0 35 | 0 20 | 6 | 1 | .. | " | 1885 | " | 8 4-in., 6 M. | 12.0 |
| 3rd | Venezuela . . . | I. | 2843 303 | 6 40 | 2 20 | 5 | 1 | .. | " | 1889 | " | 8 4-in., 8 M. | .. |
| 3rd | Orizaba . . . | S. | 3497 336 | 2 43 | 2 22 | 0 | 1 | .. | Chester, Pa. | 1889 | Cuba Mail. | 8 4-in., 6 M. | 14.0 |
| 3rd | Yumuri . . . | S. | 3497 336 | 2 43 | 2 22 | 3 | 1 | .. | " | 1889 | " | 8 4-in., 6 M. | 14.0 |
| 3rd | City of Washington . . . | I. | 2684 300 | 5 38 | 4 19 | 2 | 1 | 2500 | " | 1877 | " | 8 4-in., 8 M. | 15.0 |
| 3rd | Saratoga . . . | I. | 2820 298 | 0 38 | 6 23 | 5 | 1 | .. | " | 1878 | " | 8 4-in., 8 M. | 14.0 |
| 3rd | Seneca . . . | I. | 2729 271 | 5 40 | 0 16 | 4 | 1 | .. | " | 1884 | " | 8 4-in., 6 M. | .. |
| 3rd | Yucatan . . . | I. & S. | 3525 336 | 2 43 | 2 22 | 3 | 1 | .. | " | 1890 | " | 8 4-in., 6 M. | 14.0 |
| 3rd | Segurança . . . | S. | 4033 321 | 3 45 | 3 17 | 4 | 1 | .. | " | 1890 | " | 6 5-in., 4 4-in., 4 1-pr., 3 M. | 14.0 |
| 3rd | Vigilância . . . | S. | 4115 321 | 8 45 | 2 16 | 5 | 1 | .. | " | 1890 | " | 6 5-in., 4 4-in., 4 1-pr., 3 M. | 14.0 |
| 4th | Advance . . . | I. | 2605 295 | 0 38 | 0 23 | 4 | 1 | 1350 | " | 1883 | Panama R. R. Co. | Small Q.F. | 15.0 |
| 4th | Alliança . . . | I. | 2985 303 | 0 42 | 0 15 | 0 | 1 | 2250 | " | 1886 | " | " | 14.0 |

Atlantic Coast.

| | | | | | | | | | | | | | |
|-----|------------------------------|----|----------|------|------|---|---|------|----------------|------|---------------|-------------------------|------|
| 3rd | City of Sydney . . . | I. | 3017 339 | 0 40 | 2 20 | 5 | 1 | 1950 | " | 1875 | Pacific Mail. | 6 6-in., 10 6-pr., 2 M. | 15.0 |
| 3rd | City of Peking . . . | I. | 5079 408 | 0 47 | 0 19 | 5 | 1 | 4500 | " | 1874 | " | 6 5-in., 12 6-pr. | 13.0 |
| 3rd | City of Rio de Janeiro . . . | I. | 3548 345 | 0 38 | 6 19 | 9 | 1 | 2000 | " | 1878 | " | 8 4-in., 8 M. | 14.0 |
| 3rd | Peru . . . | S. | 3528 336 | 0 45 | 9 27 | 6 | 1 | 2800 | San Francisco. | 1892 | " | 9 5-in., 12 6-pr. | 14.0 |
| 4th | City of Panama . . . | I. | 1490 248 | 0 36 | 0 20 | 2 | 1 | 650 | Chester, Pa. | 1873 | " | Small Q.F. | .. |
| 4th | Colon . . . | I. | 2686 280 | 0 40 | 0 23 | 6 | 1 | 1350 | " | 1872 | " | " | .. |
| 4th | San Jose . . . | I. | 2081 283 | 0 37 | 0 21 | 0 | 1 | 1400 | " | 1882 | " | " | .. |
| 4th | San Blas . . . | I. | 2075 283 | 0 37 | 0 21 | 0 | 1 | 1400 | " | 1882 | " | " | .. |
| 4th | San Juan . . . | I. | 2076 283 | 0 37 | 0 21 | 0 | 1 | 1400 | " | 1882 | " | " | .. |
| 4th | Acapulco . . . | I. | 2572 290 | 0 40 | 0 20 | 0 | 1 | 1350 | Wilmington . | 1873 | " | " | .. |

Pacific Coast.

Converted Merchant Vessels Retained.

| Class. | NAME. | Material of Hull. | Displacement. | Length. | Beam. | Draught. | Propellers. | Indicated Horse-Power. | Where Built. | Date of Launch. | Cost. | Armour. | Armament. | Speed. | Coal Supply. | Complement. |
|--------|------------------------|-------------------|---------------|---------|-------|----------|-------------|------------------------|--------------|-----------------|---------|---------|--|-------------|--------------|-------------|
| cr. | Buffalo . . . | S. | 6888 880 | 6 48 | 0 22 | 0 | 1 | 3600 | Newport News | 1893 | 117,949 | in. . . | 2 5-in. Q.F., 4 4-in., 6 6-pr., 2 M. | knots, 14.5 | 100 | 237 |
| cr. | Dixie . . . | S. | 6114 339 | 2 48 | 0 19 | 11 | 1 | 1371 | Newport News | 1893 | 117,949 | in. . . | 10 6-in. Q.F., 6 6-pr., 2 M. | 16.0 | 1371 | 181 |
| cr. | Panther . . . | I. | 4260 310 | 0 40 | 0 18 | 3 | 1 | .. | Philadelphia | 1889 | 77,055 | in. . . | 6 5-in. Q.F., 2 4-in., 6 3-pr., 1 M., 1 l. | 13.0 | 475 | 198 |
| cr. | Prairie . . . | I. | 6872 890 | 6 46 | 10 22 | 0 | 1 | 3800 | Philadelphia | 1890 | 117,949 | in. . . | 10 6-in. Q.F., 6 6-pr., 2 M. | 14.5 | 1000 | 235 |
| cr. | Yankee . . . | I. | 6888 880 | 6 48 | 0 22 | 0 | 1 | 3800 | Newport News | 1892 | 117,949 | in. . . | 10 5-in. Q.F., 6 6-pr., 2 M. | 14.5 | 1000 | 232 |
| cr. | Yosemite . . . | I. | 6179 389 | 2 48 | 0 20 | 1 | 1 | 3800 | Newport News | 1892 | 117,949 | in. . . | 10 6-in. Q.F., 6 6-pr., 2 M. | 16.0 | 1371 | 285 |
| cr. | Mayflower(yacht) . . . | S. | 2590 275 | 0 36 | 0 17 | 3 | 2 | 4700 | Clydebank . | 1896 | 88,359 | in. . . | 2 5-in. Q.F., 12 6-pr., 2 M. | 16.8 | 584 | 160 |

There are also 22 other converted yachts, varying in displacement from 82 tons to 975 tons.

SHIPS BELONGING TO POWERS WHOSE NAVIES ARE OF LITTLE OR NO IMPORTANCE.

Belgium.—Twelve steam vessels, between 419 and 684 tons net, launched between 1870 and 1888, principally employed as packets, which are under the orders of the Government.

Bulgaria.—Eleven steamers of small size, of which one is used as the Prince's Yacht. Two armoured gunboats, for the defence of the Danube, building at Leghorn. Other ships are to be laid down. The *Nadiezda*, a despatch vessel (715 tons) of the French *Casabianca* type; length, 219 ft. 6 in.; beam, 27 ft. 6 in.; draught, 12 ft. 6 in.; launched at Bordeaux in 1898, steamed at 18·85 knots at her trials; engines, 2600 I.H.P.; Lagrafel and d'Allest boilers; armament, 2 3·9-in., 3 1·8-in. Q.F., and 2 torpedo-tubes.

Ecuador.—The two old (1886) French despatch vessels, *Papin* and *Inconstant* (891 tons) built of wood and iron have been bought. The Republic also possesses a torpedo-boat and two steam transport vessels.

Egypt.—This Power has now no efficient warships.

Hayti.—Steel gun vessel—*Crête à Pierrot*—940 tons, length 210 ft., beam 30 ft.; 1 6·2-in., 1 4·7-in., and 4 3·9-in. Q.F., 6 M. Steel gunboat—*Capois la Mort*—260 tons, 1 3·9-in., and 4 1-pr. Q.F. Iron corvette—*Dessalines*—1200 tons, armed with 1 3·9-in. Q.F., 2 3·9-in. B.L., 2 l., 2 M. Three iron or steel sloops:—*St. Michael*, 1804, and *Toussaint L'Ouverture*, of from 500 to 900 tons, all of 12 to 14 knots speed, and armed with one large and four to eight small guns. Gun vessel, 22nd of December, of 900 tons, 9 knots speed, armed with four 40-pr. Armstrongs.

Mexico.—The *Zaragoza*, built of steel, 1200 tons, 1300 horse-power, 15 knots speed, and armed with four 4·7-in. guns and 4 rapid-firing guns. Two gun vessels, *Democrata* and *Mexico*, of 450 tons and 11 knots speed, armed with two 6½-inch muzzle loaders and two small guns. Two small gunboats of 10 knots speed. A gunboat is in hand at New Orleans. Five torpedo-boats. An account of the shipbuilding programme will be found in the chapter on the "Progress of Foreign Navies."

Morocco.—A torpedo cruiser, of 1200 tons displacement 2500 HP., 18 knots speed, and carrying two guns, 4·7-in. B.L., and 4 Q.F. guns, built in 1892. A gunboat of 450 tons, 1200 I.H.P.

14·5 knots, is completing at Sampierdarena (Maclaren & Wilson), and another has been laid down.

Persia.—Despatch vessel—the *Persepolis*—of 1200 tons and 10 knots speed. She is armed with 5 small breech-loading guns.

Peru.—Lima, built in 1881, of 1700 tons displacement, 1800 horse-power, and 16 knots speed; armed with two 6-in. B.L.R. guns. Screw steamer *Santa Rosa*, of about 400 tons.

Roumania.—*Elizabetha*, protected cruiser (deck 3 in. thick), built in 1887 at Elswick; 230 ft. long, 32 ft. 10 in. beam, 1320 tons, 4500 I.H.P.; 4 5·9-in. B.L.R., 4 Q.F., 2 M., 4 torpedo tubes. Composite gunboat *Mircea*, 350 tons; *Grivitza*, 180 tons. Six gunboats of 45 to 110 tons, 7 to 9 knots speed. Six coast-guard vessels—*Oltul*, *Siretul*, *Bistritza*, *Olteano*, *Smeo*, and *Monteano*—95 tons, 100 ft. long, 13·6 in. beam, 6 ft. draught; speed, natural draught 11 knots, forced draught 13½ knots; 1 Q.F., 2 M. Screw steamer—*Romania*—240 tons, repaired 1890. Six first-class torpedo-boats (120 ft. 6 in., 21 knots); 2 second class (63 ft., 16·5 knots), built 1882–1888. The shipbuilding programme contemplates the building of 8 monitors of 500 tons, 12 torpedo-boats and 8 vedettes for the Danube, and 6 coast-defence vessels of 3500 tons, 4 destroyers of 300 tons, and 12 torpedo-boats for the Black Sea.

Saint Domingo.—The *Independencia*, built in England 1894, 170 ft. long, 25 ft. broad, displacement 322 tons, and armed with seven Hotchkiss quick-firing guns. *Restauracion*, steel gun-vessel, 1000 tons, launched at Glasgow in 1896. The 14-knot cruiser *Presidente* has been reconstructed, and carries seven guns.

Sarawak.—Two gunboats, of 175 and 118 tons respectively of low speed, each armed with two guns.

Siam.—Two corvettes (800 tons, 8 guns); six gunboats. One deck-protected cruiser, the *Maha Chakrkri*, 290 ft. long, 39 ft. 4 in. broad, of 2500 tons displacement and 17 to 18 knots speed; armament, four 4·7-in. quick-firing guns, and ten 6-pr. quick-firing guns. Cruiser *Makut-Rajakamar*, 650 tons.

Uruguay.—Gunboats: *General Artigas*, 274 tons, 12½ knots speed, 2 4·7-in. (Krupp), 2 M.; *General Rivera*, 300 tons, 12 knots speed, armed with 1 5·9-in. and 1 2·3-in. gun; and the *General Jaurez*.

Venezuela.—Gun-vessel, *Libertador*, 832 tons. Four river gunboats building.

BRITISH AND FOREIGN TORPEDO-BOAT FLOTILLAS.

Great Britain and Dependencies.

| Name or Number. | Where Built. | Launched. | Dimensions. | | | Number of Screws. | Displacement. | Indicated Horse-Power. | Mean Speed on Trial, or expected. | Armament. | Torpedo Tubes. | Complement. | Coal Capacity. |
|--------------------------------|---------------|-----------|-------------|-------|----------|---------------------|---------------|------------------------|-----------------------------------|-------------------|----------------|-------------|----------------|
| | | | Length. | Beam. | Draught. | | | | | | | | |
| | | | Feet. | Feet. | Feet. | | Tons. | | Knots. | | | | Tons. |
| <i>Great Britain.</i> | | | | | | | | | | | | | |
| TORPEDO-BOAT DESTROYERS | | | | | | | | | | | | | |
| †Ardent | Chiswick .. | 1894 | 201·6 | 19 | 7·3 | 2 | 247 | 4,500 | 27·97 | 1-12 pr. 5-6 prs. | 2 | 45 | 60 |
| Banshee | Birkenhead .. | 1894 | 210 | 19·5 | .. | 2 | 290 | 4,400 | 27·97 | 1-12 pr. 5-6 prs. | 2 | 50 | 60 |
| †Boxer | Chiswick .. | 1894 | 201·6 | 19 | 7·3 | 2 | 247 | 4,500 | 27·17 | 1-12 pr. 5-6 prs. | 2 | 45 | 60 |
| †Bruiser | Chiswick .. | 1895 | 201·6 | 19 | 7·3 | 2 | 247 | 4,500 | 27·97 | 1-12 pr. 5-6 prs. | 2 | 45 | 60 |
| *Charger | Poplar .. | 1894 | 180 | 18·5 | 5·25 | 2 | 250 | 3,100 | 27·98 | 1-12 pr. 5-6 prs. | 2 | 45 | 60 |
| Conflict | East Cowes .. | 1894 | 205·6 | 20 | .. | 2 | 270 | 4,370 | 27·21 | 1-12 pr. 5-6 prs. | 2 | 50 | 60 |
| Contest | Birkenhead .. | 1894 | 210 | 19·5 | .. | 2 | 290 | 4,400 | 27·4 | 1-12 pr. 5-6 prs. | 2 | 50 | 60 |
| †Daring | Chiswick .. | 1893 | 185 | 19 | 7 | 2 | 237 | 4,300 | 27·70 | 1-12 pr. 3-6 prs. | 3 | 45 | 50 |
| *Dasher | Poplar .. | 1895 | 190 | 18·5 | 5·25 | 2 | 250 | 3,182 | 26·21 | 1-12 pr. 5-6 prs. | 2 | 45 | 60 |
| †Decoy | Chiswick .. | 1894 | 185 | 19 | 7 | 2 | 237 | 4,300 | 27·76 | 1-12 pr. 3-6 prs. | 3 | 45 | 50 |
| Dragon | Birkenhead .. | 1894 | 210 | 19·5 | .. | 2 | 290 | 4,500 | 27·14 | 1-12 pr. 5-6 prs. | 2 | 50 | 60 |
| Ferret | Birkenhead .. | 1893 | 194 | 19·25 | 5 | 2 | 280 | 4,810 | 27·62 | 1-12 pr. 3-6 prs. | 3 | 50 | 70 |
| Fervent | Paisley .. | 1895 | 200 | 19 | 7·8 | 2 | 270 | 3,800 | [27] | 1-12 pr. 5-6 prs. | 2 | 50 | 70 |
| †Handy | Fairfield .. | 1895 | 200 | 19 | 7·8 | 2 | 261 | 3,800 | 27·04 | 1-12 pr. 5-6 prs. | 2 | 50 | 70 |
| Hardy | Sunderland .. | 1895 | 196 | 19 | 5 | 2 | 245 | 4,200 | 26·8 | 1-12 pr. 5-6 prs. | 2 | 50 | 70 |
| †Hart | Fairfield .. | 1895 | 185 | 19 | 7 | 2 | 260 | 4,010 | 27·07 | 1-12 pr. 5-6 prs. | 2 | 50 | 70 |
| *Hasty | Poplar .. | 1894 | 190 | 18·5 | 5·25 | 2 | 250 | 3,250 | 26·08 | 1-12 pr. 5-6 prs. | 2 | 45 | 60 |
| Haughty | Sunderland .. | 1895 | 196 | 19 | 5 | 2 | 265 | 4,000 | 27·1 | 1-12 pr. 5-6 prs. | 2 | 50 | 60 |
| Havock | Poplar .. | 1893 | 180 | 18·5 | 5·25 | 2 | 240 | 3,500 | 26·77 | 1-12 pr. 3-6 prs. | 3 | 43 | 57 |
| Hornet | Poplar .. | 1893 | 180 | 18·5 | 5·25 | 2 | 240 | 4,000 | 27·31 | 1-12 pr. 3-6 prs. | 3 | 43 | 57 |
| †Hunter | Fairfield .. | 1895 | .. | .. | .. | 2 | 260 | 4,000 | 27·2 | 1-12 pr. 5-6 prs. | 2 | 50 | 60 |
| Janus | Jarrow .. | 1895 | 200 | 19·7 | 6·5 | 2 | 252 | 3,789 | 27·8 | 1-12 pr. 5-6 prs. | 2 | 50 | 60 |
| Lightning | Jarrow .. | 1895 | 200 | 19·7 | 6·5 | 2 | 252 | 4,007 | 27·94 | 1-12 pr. 5-6 prs. | 2 | 50 | 60 |
| Lynx | Birkenhead .. | 1894 | 194 | 19·25 | 5 | 2 | 280 | 4,000 | 27·00 | 1-12 pr. 3-6 prs. | 3 | 50 | 70 |
| Opossum | Hebburn .. | 1895 | 200 | 19 | 5·2 | 2 | 290 | 4,052 | 28·24 | 1-12 pr. 5-6 prs. | 2 | 50 | 60 |
| Porcupine | Jarrow .. | 1895 | 200 | 19·7 | 6·5 | 2 | 288 | 3,866 | 27·91 | 1-12 pr. 5-6 prs. | 2 | 50 | 60 |
| Ranger | Hebburn .. | 1895 | 200 | 19 | 5·2 | 2 | 264 | 3,900 | 27·13 | 1-12 pr. 5-6 prs. | 2 | 50 | 60 |
| Rocket | Clydebank .. | 1894 | 205·6 | 19·5 | 5·25 | 2 | 280 | 4,200 | 27·37 | 1-12 pr. 5-6 prs. | 2 | 50 | 60 |
| Salmon | Hull .. | 1895 | 200 | 19·5 | 5·4 | 2 | 264 | 3,580 | 27·63 | 1-12 pr. 5-6 prs. | 2 | 50 | 60 |
| Shark | Clydebank .. | 1894 | 205·6 | 19·5 | 5·25 | 2 | 280 | 4,250 | 27·59 | 1-12 pr. 5-6 prs. | 2 | 50 | 60 |
| Skate | Barrow .. | 1895 | 195 | 20·5 | .. | 2 | 265 | 4,100 | 27·10 | 1-12 pr. 5-6 prs. | 2 | 50 | 60 |
| Snapper | Hull .. | 1895 | 200 | 19·5 | 5·5 | 2 | 270 | 4,500 | 27·9 | 1-12 pr. 5-6 prs. | 2 | 50 | 60 |
| Spitfire | Elswick .. | 1895 | 200 | 19 | 5·3 | 2 | 300 | 3,780 | 27·5 | 1-12 pr. 5-6 prs. | 2 | 45 | 60 |
| Starfish | Barrow .. | 1894 | 195 | 20·5 | .. | 2 | 265 | 4,000 | 27·97 | 1-12 pr. 5-6 prs. | 2 | 45 | 60 |
| Sturgeon | Barrow .. | 1894 | 195 | 20·5 | .. | 2 | 265 | 4,010 | 27·16 | 1-12 pr. 5-6 prs. | 2 | 45 | 60 |
| Sunfish | Hebburn .. | 1895 | 200 | 19 | 5·2 | 2 | 290 | 4,292 | 27·62 | 1-12 pr. 5-6 prs. | 2 | 50 | 60 |
| Surly | Clydebank .. | 1894 | 205·6 | 19·5 | 5·25 | 2 | 280 | 4,400 | 28·05 | 1-12 pr. 5-6 prs. | 2 | 50 | 60 |
| Swordfish | Elswick .. | 1895 | 200 | 19 | 5·3 | 2 | 300 | 4,100 | [27] | 1-12 pr. 5-6 prs. | 2 | 45 | 60 |
| Teazer | East Cowes .. | 1895 | 200 | 19·5 | 5·6 | 2 | 270 | 4,500 | [27] | 1-12 pr. 5-6 prs. | 2 | 50 | 60 |
| Wizard | East Cowes .. | 1895 | 200 | 19·5 | 5·2 | 2 | 270 | 4,400 | [27] | 1-12 pr. 5-6 prs. | 2 | 45 | 60 |
| Zebra | Blackwall .. | 1895 | 200 | 20 | 6 | 2 | 300 | 3,850 | 27·00 | 1-12 pr. 5-6 prs. | 2 | 50 | 60 |
| Zephyr | Paisley .. | 1895 | 200 | 19 | 5·3 | 2 | 270 | 3,850 | [27] | 1-12 pr. 5-6 prs. | 2 | 50 | 60 |
| †Albatross | Chiswick .. | 1898 | 227·6 | 21·25 | 8·5 | 2 | 360 | 7,900 | 32 | 1-12 pr. 5-6 prs. | 2 | 68 | 100 |
| †Angler | Chiswick .. | 1896 | 210 | 19·6 | 7·1 | 2 | 278 | 5,800 | 30·37 | 1-12 pr. 5-6 prs. | 2 | 60 | 80 |
| Arab | Clydebank .. | bldg. | .. | .. | .. | Design not complete | | | .. | 1-12 pr. 5-6 prs. | 2 | 60 | 80 |
| †Ariel | Chiswick .. | 1897 | 210 | 19·6 | 7·1 | 2 | 278 | 5,800 | 30·59 | 1-12 pr. 5-6 prs. | 2 | 60 | 80 |
| †Avon | Barrow .. | 1896 | 210·6 | 21·6 | 5·6 | 2 | 300 | 6,000 | 30 | 1-12 pr. 5-6 prs. | 2 | 60 | 80 |
| Bat | Jarrow .. | 1896 | 215 | 20·75 | 6·8 | 2 | 326 | 6,185 | 30·1 | 1-12 pr. 5-6 prs. | 2 | 60 | 91 |
| †Bittern | Barrow .. | 1897 | 210·6 | 21·6 | 5·6 | 2 | 300 | 6,000 | 30 | 1-12 pr. 5-6 prs. | 2 | 60 | 80 |
| Brazen | Clydebank .. | 1896 | 218 | 20·0 | 5·6 | 2 | 300 | 6,000 | 30 | 1-12 pr. 5-6 prs. | 2 | 60 | 80 |
| †Bullfinch | Hull .. | bldg. | .. | .. | .. | 2 | 300 | 5,800 | 30 | 1-12 pr. 5-6 prs. | 2 | 60 | 80 |
| Chamols | Jarrow .. | 1895 | 215 | 20·75 | 6·8 | 2 | 326 | 6,333 | 30·2 | 1-12 pr. 5-6 prs. | 2 | 60 | 91 |
| †Cheerful | Hebburn .. | 1897 | 210 | 21·0 | 8 | 2 | 308 | 6,000 | 30 | 1-12 pr. 5-6 prs. | 2 | 62 | 82 |
| †Coquette | Chiswick .. | 1898 | 210 | 19·5 | 7·2 | 2 | 285 | 5,800 | 30·31 | 1-12 pr. 5-6 prs. | 2 | 60 | 80 |
| Crane | Jarrow .. | 1896 | 215 | 20·7 | 6·8 | 2 | 324 | 6,338 | 30·3 | 1-12 pr. 5-6 prs. | 2 | 60 | 80 |
| †Cygnets | Chiswick .. | 1898 | 210 | 19·5 | 7·2 | 2 | 285 | 5,800 | 30·35 | 1-12 pr. 5-6 prs. | 2 | 60 | 80 |
| †Cynthia | Chiswick .. | 1898 | 210 | 19·5 | 7·2 | 2 | 285 | 5,800 | 30·2 | 1-12 pr. 5-6 prs. | 2 | 60 | 80 |
| †Desperate | Chiswick .. | 1895 | 210 | 19·6 | 7·2 | 2 | 275 | 5,800 | 30 | 1-12 pr. 5-6 prs. | 2 | 60 | 80 |
| †Dove | Hull .. | bldg. | 210·0 | 20·6 | 5·8 | 2 | 300 | 5,800 | 30 | 1-12 pr. 5-6 prs. | 2 | 60 | 80 |
| Earnest | Birkenhead .. | 1896 | 210·6 | 21·7 | 5·3 | 2 | 300 | 6,000 | 30·13 | 1-12 pr. 5-6 prs. | 2 | 58 | 80 |
| Electra | Clydebank .. | bldg. | 218 | 20·0 | 5·6 | 2 | 300 | 6,000 | 30 | 1-12 pr. 5-6 prs. | 2 | 58 | 80 |
| Express | Birkenhead .. | 1897 | 227·6 | 22·0 | 9 | 2 | 300 | 9,000 | 33 | 1-12 pr. 5-6 prs. | 2 | 60 | 80 |
| Fairy | Fairfield .. | 1897 | 227·6 | 22·0 | 9 | 2 | 300 | 6,000 | 30 | 1-12 pr. 5-6 prs. | 2 | 60 | 80 |
| †Falcon | Fairfield .. | bldg. | 220 | 21·3 | .. | .. | .. | 6,000 | 30 | .. | .. | .. | .. |
| †Fame | Chiswick .. | 1896 | 210·6 | 19·6 | 7·1 | 2 | 275 | 5,800 | 30·16 | 1-12 pr. 5-6 prs. | 2 | 60 | 80 |

* Built by Yarrow, fitted with Thornycroft W. T. boilers at Earle's. All Jarrow-built destroyers have Reed's boilers. Vessels marked † have Thornycroft W. T. boilers.

Great Britain and Dependencies—continued.

| Name or Number. | Where Built. | Launched. | Dimensions. | | | Number of Screws. | Displacement. | Indicated Horse-Power. | Mean Speed on Trial, or expected. | Armament. | Torpedo Tubes. | Complement. | Coal Capacity. |
|-------------------------------------|--------------------|-----------|-------------|----------|----------|----------------------|---------------|---------------------------|---|-------------------|----------------|-------------|----------------|
| | | | Length. | Breadth. | Draught. | | | | | | | | |
| TORPEDO BOAT DESTROYERS | | | | | | | | | | | | | |
| Fawn | Jarrow | 1897 | 215 | 20'7 | 6'8 | 2 | 325 | 6,581 | 30'5 | 1-12 pr. 5-6 prs. | 2 | 60 | 91 |
| Flirt | Jarrow | 1897 | 215 | 20'7 | 6'8 | 2 | 329 | 6,682 | 30 | 1-12 pr. 5-6 prs. | 2 | 60 | 91 |
| Flyingfish | Jarrow | 1897 | 215 | 20'7 | 6'8 | 2 | 323 | 6,416 | 30'4 | 1-12 pr. 5-6 prs. | 2 | 58 | 91 |
| † Foam | Chiswick | 1896 | 210 | 19'6 | 7'1 | 2 | 275 | 5,800 | 30'18 | 1-12 pr. 5-6 prs. | 2 | 58 | 80 |
| Gipsy | Fairfield | 1897 | 227'6 | 22'0 | 9 | 2 | 300 | 6,000 | 30 | 1-12 pr. 5-6 prs. | 2 | 60 | 80 |
| Greyhound | Hawthorn's | 1900 | 210 | 21 | 8'6 | 2 | 316 | 6,000 | 30 | 1-12 pr. 5-6 prs. | 2 | 60 | 90 |
| Griffon | Birkenhead | 1896 | 210'0 | 20 | 5'3 | 2 | 300 | 6,000 | 30'11 | 1-12 pr. 5-6 prs. | 2 | 58 | 80 |
| Kestrel | Clydebank | bldg. | 218 | 20'0 | 5'6 | 2 | 300 | 6,000 | 30 | 1-12 pr. 5-6 prs. | 2 | 60 | 80 |
| Kangaroo | Jarrow | bldg. | 215 | 20'75 | 6'8 | 2 | 335 | 6,500 | 30 | 1-12 pr. 5-6 prs. | 2 | 58 | 91 |
| † Lee | Sunderland | 1899 | 210'0 | 19'9 | 7'6 | 2 | 283 | 5,400 | 30 | 1-12 pr. 5-6 prs. | 2 | 58 | 80 |
| Leopard | Barrow | 1897 | 210 | 20'0 | 5'6 | 2 | 300 | 6,000 | 30 | 1-12 pr. 5-6 prs. | 2 | 60 | 80 |
| Leven | Fairfield | bldg. | 218'0 | 20'0 | 5'6 | 2 | 300 | 6,000 | 30 | 1-12 pr. 5-6 prs. | 2 | 58 | 80 |
| Lively | Clydebank | bldg. | 218 | 20'0 | 5'6 | 2 | 300 | 6,000 | 30 | 1-12 pr. 5-6 prs. | 2 | 58 | 80 |
| Locust | Birkenhead | 1896 | 210 | 21'7 | 6'3 | 2 | 300 | 6,000 | 30'16 | 1-12 pr. 5-6 prs. | 2 | 58 | 80 |
| † Mallard | Chiswick | 1896 | 210'6 | 19'6 | 7'1 | 2 | 275 | 5,800 | 30'11 | 1-12 pr. 5-6 prs. | 2 | 60 | 80 |
| Mermaid | Hebburn | 1898 | 210 | 21'0 | 8 | 2 | 308 | 6,000 | 30 | 1-12 pr. 5-6 prs. | 2 | 62 | 82 |
| † Myrmidon | Jarrow | bldg. | 215 | 20'75 | 6'8 | 2 | 335 | 6,500 | 30 | 1-12 pr. 5-6 prs. | 2 | 58 | 91 |
| Orwell | Birkenhead | bldg. | 218'0 | 20'0 | 5'6 | 2 | 300 | 6,000 | 30 | 1-12 pr. 5-6 prs. | 2 | 58 | 80 |
| Osprey | Fairfield | bldg. | 227'6 | 22'0 | 9 | 2 | 300 | 6,000 | 30 | 1-12 pr. 5-6 prs. | 2 | 60 | 80 |
| † Osirich | Fairfield | bldg. | 210 | 21'0 | | | | 6,000 | 30 | | | | |
| Otter | Barrow | 1896 | 210 | 20'0 | 5'6 | 2 | 300 | 6,000 | 30 | 1-12 pr. 5-6 prs. | 2 | 60 | 80 |
| Panther | Birkenhead | 1897 | 210'6 | 21'7 | 6'3 | 2 | 300 | 6,000 | 30'14 | 1-12 pr. 5-6 prs. | 2 | 58 | 80 |
| Peterel | Jarrow | 1899 | 215 | 20'75 | 6'8 | 2 | 334 | 6,500 | 30 | 1-12 pr. 5-6 prs. | 2 | 91 | |
| Quail | Birkenhead | 1895 | 213'6 | 21'6 | 5'3 | 2 | 300 | 6,000 | 30'38 | 1-12 pr. 5-6 prs. | 2 | 58 | 90 |
| Racehorse | Hawthorn's | 1900 | 210 | 21 | 8'6 | 2 | 316 | 6,000 | 30 | 1-12 pr. 5-6 prs. | 2 | 60 | 90 |
| Recruit | Glasgow | bldg. | 218'0 | 20'0 | 5'6 | 2 | 300 | 6,000 | 30 | 1-12 pr. 5-6 prs. | 2 | 58 | 80 |
| Roebuck | Hawthorn's | 1901 | 210 | 21 | 8'6 | 2 | 316 | 6,000 | 30 | 1-12 pr. 5-6 prs. | 2 | 60 | 90 |
| Seal | Birkenhead | 1897 | 218'0 | 20'0 | 5'6 | 2 | 300 | 6,000 | 30'15 | 1-12 pr. 5-6 prs. | 2 | 58 | 80 |
| Sparrowhawk | Birkenhead | 1896 | 210'6 | 21'7 | 5'3 | 2 | 300 | 6,000 | 30'13 | 1-12 pr. 5-6 prs. | 2 | 58 | 80 |
| Spitfire | Jarrow | 1898 | 215 | 20'75 | 6'8 | 2 | 334 | 6,500 | 30'1 | 1-12 pr. 5-6 prs. | 2 | 91 | |
| Sprightly | Clydebank | bldg. | 218 | 20'0 | 5'6 | 2 | 300 | 6,000 | 30 | 1-12 pr. 5-6 prs. | 2 | 58 | 80 |
| † Stag | Chiswick | 1899 | 210 | 19'75 | 7'2 | 2 | 285 | 5,800 | 30 | 1-12 pr. 5-6 prs. | 2 | 60 | 80 |
| Star | Jarrow | 1896 | 215 | 20'75 | 6'88 | 2 | 328 | 6,266 | 30'7 | 1-12 pr. 5-6 prs. | 2 | 58 | 91 |
| Success | Sunderland | bldg. | 210'0 | 21'0 | 9'24 | 2 | 350 | 6,000 | 30 | 1-12 pr. 5-6 prs. | 2 | 62 | 43 |
| † Sylvia | Sunderland | bldg. | 210 | 19'9 | 7'6 | 2 | 283 | 5,400 | 30 | 1-12 pr. 5-6 prs. | 2 | 58 | 80 |
| † Syren | Jarrow | bldg. | 215 | 20'75 | 6'8 | 2 | 335 | 6,500 | 30 | 1-12 pr. 5-6 prs. | 2 | 58 | 91 |
| Thrasher | Birkenhead | 1896 | 210'6 | 21'7 | 5'3 | 2 | 300 | 6,000 | 30'13 | 1-12 pr. 5-6 prs. | 2 | 58 | 80 |
| † Violet | Sunderland | bldg. | 210 | 20'75 | 6'88 | 2 | 283 | 5,400 | 30 | 1-12 pr. 5-6 prs. | 2 | 58 | 80 |
| † Viper | Hebburn | 1899 | 210 | 21 | 7 | 8 | 3124 | 10,600 | 35 | 1-12 pr. 5-6 prs. | 2 | 62 | 88 |
| Virago | Birkenhead | 1896 | 210'6 | 21'7 | 5'3 | 2 | 300 | 6,000 | 30'13 | 1-12 pr. 5-6 prs. | 2 | 58 | 80 |
| † Vixen | Barrow | bldg. | 210'0 | 20'0 | 5'8 | 2 | 327 | 6,000 | 30 | 1-12 pr. 5-6 prs. | 2 | 62 | 88 |
| Vulture | Clydebank | bldg. | 218 | 20'0 | 5'6 | 2 | 300 | 6,000 | 30 | 1-12 pr. 5-6 prs. | 2 | 58 | 80 |
| Whiting | Jarrow | 1896 | 215 | 20'75 | 6'88 | 2 | 330 | 6,239 | 30'2 | 1-12 pr. 5-6 prs. | 2 | 58 | 91 |
| Wolf | Birkenhead | 1897 | 218 | 20 | 5'6 | 2 | 300 | 6,000 | 30 | 1-12 pr. 5-6 prs. | 2 | 58 | 80 |
| † Cobra | Elswick | 1900 | 223'6 | 20'6 | 6'0 | 12 | 400 | | 34'9 | 1-12 pr. 5-6 prs. | 2 | 63 | 107 |
| TORPEDO BOATS— | | | | | | | | | | | | | |
| First Class— | | | | | | | | | | | | | |
| 1 (ex Lightning) | Chiswick | 1877 | 84'6 | 10'9 | 5 | 1 | 27 | 460 | 19 | .. | 1 | .. | |
| 2-9 (8 boats) | Chiswick | 1878-9 | 87 | 10'9 | 4 | 1 | 28 | 450 | 20 | .. | 1 | 15 | |
| 10 | Chiswick | 1880 | 90'5 | 10'9 | 4 | 1 | 28 | 450 | 21'7 | .. | 1 | 15 | |
| 11, 12 (2 boats) | Chiswick | 1880 | 87 | 10'9 | 4 | 1 | 28 | 450 | 20 | .. | 1 | 15 | 7 |
| 13 | Lambeth | 1878 | 87 | 10'9 | 4 | 1 | 28 | 460 | 21 | .. | 2 | 15 | 7 |
| 14 | Poplar | 1878 | 87 | 11 | 4'5 | 1 | 33 | 550 | 22 | .. | 2 | 15 | 7 |
| 15 | | | 87 | 10'9 | 4 | 1 | 28 | 450 | 21 | .. | 2 | 15 | 7 |
| 17, 18 (2 boats) | Poplar | 1877 | 86 | 11 | 4'5 | 1 | 33 | 450 | 21 | .. | 2 | 15 | 7 |
| 19 | East Cowes | 1879 | 87 | 10'9 | 4 | 1 | 28 | 460 | 21 | .. | 2 | 15 | 7 |
| 20 | | 1880 | 87 | 10 | 4 | .. | 28 | 360 | 16'9 | .. | 2 | 15 | |
| 21, 22 (2 boats) | Chiswick | 1885 | 113 | 12'5 | 5'7 | 1 | 63 | 730 | 20 | .. | 3 | .. | 10 |
| 23, 24 (2 boats) | Poplar | 1885-6 | 113 | 12'5 | 5'5 | 1 | 67 | 800 | 19'5 | 2-3 prs. | 3 | .. | |
| 25-29 (5 boats) | Chiswick | 1886 | 127'5 | 12'5 | 6'2 | 1 | 60 | 600 | 21 | .. | 4 | 15 | |
| 30-33 (4 boats) | Poplar | 1886 | 125 | 13 | 5'5 | 1 | 60-66 | 670 | 19'5 | 2-3 prs. | 5 | 15 | 20 |
| 34-38 (5 boats) | East Cowes | 1886 | 125 | 14'6 | 4 | 1 | 60-66 | 950 | 18-19 | .. | 5 | 15 | |
| 39, 40 (2 boats) | Poplar | 1885 | 100 | 12'5 | .. | .. | 40 | 500 | .. | .. | 1 | 15 | |
| 41-60 (20 boats) | Chiswick | 1886 | 127'5 | 12'5 | 6'2 | 1 | 60 | 700 | 21 | 2-3 prs. | 4 | 15 | |
| 61, 63-74, 76-78 (16 boats) | Poplar | 1886 | 125 | 13 | 5'5 | 1 | 75 | 700 | 19-20 | 2-3 prs. | 5 | 15 | 20 |
| 79 | Poplar | 1896 | 125 | 13 | 5'5 | .. | 75 | 1,000 | 22'4 | 2-3 prs. | .. | 15 | 20 |
| 80 | Poplar | 1887 | 135 | 14 | 6 | 1 | 105 | 1,540 | 23 | 4-3 prs. | 5 | 21 | 30 |
| 81 (ex Swift) | East Cowes | 1885 | 150 | 17'5 | .. | 1 | 125 | .. | .. | 6-3 prs. | 3 | 25 | 35 |
| 82-87 (6 boats) | Poplar | 1889 | 130 | 13'5 | 5'5 | 1 | 85 | 1,100 | 23 | 3-3 prs. | 3 | 19 | 20 |
| 88, 89 (2 boats) | Poplar | 1894 | 142 | 14'75 | 4'5 | 1 | 112 | 1,600 | .. | 3-3 prs. | 3 | 18 | 20 |
| 90 | Poplar | 1895 | 140 | 14'25 | 3'7 | 1 | 109 | 1,430 | .. | 3-3 prs. | 3 | 18 | 18 |
| 91, 92 (2 boats) | Chiswick | 1894 | 140 | 15'5 | 7'5 | 1 | 130 | 2,400 | 23'24 | 3-3 prs. | 3 | 18 | 25 |
| 93 | Chiswick | 1893 | 140 | 15'5 | 5'4 | 2 | 130 | 2,200 | 23'5 | 3-3 prs. | 3 | 18 | 25 |
| 94-96 (3 boats) | East Cowes | 1894 | 140 | 15'5 | .. | 1 | 130 | 2,000 | 23'2 | 3-3 prs. | 3 | 18 | 25 |
| 97 | Birkenhead | 1893 | 140 | 15'5 | .. | 1 | 130 | 2,690 | 23'35 | 3-3 prs. | 3 | 18 | 25 |
| 98 and 99 | | | | | | | | | | | | | |
| g (107 and 108) | Chiswick | bldg. | 160 | 17 | 8'4 | 1 | 178 | 2,850 | 25 | 3-3 prs. | 3 | 32 | 20 |

a This vessel is fitted with the Parsons compound steam turbine. b Fitted with Yarrow boilers made by R. and W. Hawthorn, Leslie & Co., c No. 34 is fitted with Laird W. T. boilers. d Has four Express W. T. boilers. e Programme 1900-1901. Nos. 51, 87 fitted with Earle's W. T. boilers. f Reed's W. T. boilers. g Water-tube boilers of Thornycroft type.

Great Britain and Dependencies—*continued.*

| Name or Number. | Where Built. | Launched. | Dimensions. | | | Number of Screws. | Displacement. | Indicated Horse-Power. | Maximum Trial Speed. | Armament. | Torpedo Tubes. | Complement. | Coal Capacity. |
|------------------------------------|------------------|-----------|-------------|-------|----------|-------------------|---------------|------------------------|----------------------|-----------|----------------|-------------|----------------|
| | | | Length. | Beam. | Draught. | | | | | | | | |
| | | | Feet. | Feet. | Feet. | | Tons. | | Knots. | | | | Tons. |
| TORPEDO BOATS.—<i>cont.</i> | | | | | | | | | | | | | |
| SECOND CLASS— | | | | | | | | | | | | | |
| 38-48 (10 boats) | Poplar | 1889 | 60 | 9·2 | 3·7 | 1 | 16·5 | 230 | 16·5 | 1 mach. | 1 | 9 | 11 |
| 49, 50 (2 boats) | Poplar | 1887 | 60 | 8·5 | 3 | 1 | 15 | 200 | 17 | 1 mach. | 1 | 9 | |
| 51-62 (12 boats) | Chiswick | 1878-9 | 60·5 | 7·5 | 3·5 | 1 | .. | .. | 16·5 | .. | 2 | 7 | |
| 63 | | 1879 | 60 | .. | .. | 1 | .. | .. | 15 | .. | 2 | 7 | |
| 64-73 (10 boats) | Chiswick | 1880-1 | 60·5 | 7·5 | 3·5 | 1 | .. | .. | 16-17 | .. | 2 | 7 | |
| 74, 75, 96, 97 (4 boats) .. | Poplar | 1883 | 62 | 7·6 | 3·6 | 1 | 12 | .. | 16 | 1 mach. | 2 | 7 | |
| 76-95 (20 boats) | Chiswick | 1882-3 | 63 | 7·5 | 3·5 | 1 | .. | .. | 16·5-17 | .. | 2 | 7 | |
| 98 | Chiswick | 1883 | 66·3 | 7·5 | 2·5 | hyd. | .. | 120 | 12·6 | .. | 2 | 7 | |
| 99, 100 (2 boats) | Chiswick | 1886 | 64 | 8 | 3·6 | 1 | .. | .. | 16-16·8 | .. | 2 | 7 | |
| 101 | | .. | 64 | .. | .. | .. | .. | .. | .. | .. | 2 | 7 | |
| 1-9 (9 boats) | East Cowes | .. | 56 | .. | .. | 1 | 12 | .. | 14·5 | 2 mach. | sp | .. | .. |
| COLONIAL, ETC.— | | | | | | | | | | | | | |
| <i>Victoria.</i> | | | | | | | | | | | | | |
| Childers | Chiswick | 1883 | 113 | 12·5 | 5·9 | 1 | 65 | 730 | 20 | 2-1 prs. | .. | 12 | 10 |
| One boat | Poplar | 1891 | 130 | 13·5 | 5·7 | 1 | 82 | 1,150 | 23 | 3-3 prs. | 3 | 19 | 20 |
| Nepean, Lonsdale (2 boats) | Chiswick | 1884 | 63 | 7·5 | 3·2 | 1 | 12 | 150 | 17·5 | .. | 1 | 7 | |
| <i>New South Wales.</i> | | | | | | | | | | | | | |
| Acheron, Avernus (2 boats) | | 1879 | .. | .. | .. | 1 | 16 | 300 | 16 | .. | .. | .. | .. |
| <i>Queensland.</i> | | | | | | | | | | | | | |
| Mosquito | Chiswick | 1884 | 63 | 7·5 | 3·2 | 1 | 12 | .. | 17 | .. | 1 | 7 | |
| Wasp | | .. | .. | .. | .. | .. | 12 | .. | .. | .. | .. | 7 | |
| <i>Tasmania.</i> | | | | | | | | | | | | | |
| One boat | Chiswick | 1884 | 63 | 7·5 | 3·2 | 1 | 12 | .. | 17 | .. | 1 | 7 | |
| <i>New Zealand.</i> | | | | | | | | | | | | | |
| Nos. 1-4 (4 boats) | Chiswick | 1884 | 63 | 7·5 | 3 | 1 | 12 | 170 | 17 | 1 mach. | Sp. | .. | .. |
| <i>India.</i> | | | | | | | | | | | | | |
| Nos. 1-3 (3 boats) | Chiswick | 1888 | 134·5 | 14·8 | 7·1 | 1 | 96 | 1,270 | 23·2 | 2 Q.F. | 5 | .. | .. |
| Nos. 4-6 (3 boats) | East Cowes | 1889 | 130 | 14·6 | .. | .. | 95 | 1,030 | 20 | .. | .. | .. | .. |
| No. 7 | Paisley | 1888 | 130·4 | 14 | .. | .. | 92 | 1,060 | 21 | .. | .. | .. | .. |

Argentine Republic.

| Name or Number. | Where Built. | Launched. | Dimensions. | | | Number of Screws. | Displacement. | Indicated Horse-Power. | Maximum Trial Speed. | Armament. | Torpedo Tubes. | Complement. | Coal Capacity. |
|------------------------|--------------|-----------|-------------|-------|----------|-------------------|---------------|------------------------|----------------------|--------------------------------------|----------------|-------------|----------------|
| | | | Length. | Beam. | Draught. | | | | | | | | |
| DESTROYERS— | | | Feet. | Feet. | Feet. | | Tons. | | Knots. | | | | Tons. |
| Corrientes | Poplar | 1896 | 190 | 19.6 | 7.4 | 2 | 280 | 4,000 | 27.4 t. | { *1 14-pr. 3 6-pr. Q.F., 2 m. | 3 | 54 | 80 |
| Misiones | Poplar | 1896 | 190 | 19.6 | 7.4 | 2 | 280 | 4,000 | 26.0 t. | | 3 | 54 | 80 |
| Entre Rios | Poplar | 1896 | 190 | 19.6 | 7.4 | 2 | 280 | 4,000 | 26.7 t. | | 3 | 54 | 80 |
| FIRST CLASS— | | | | | | | | | | | | | |
| 2 boats | Chiswick .. | 1890-1 | 150 | 14.5 | 5.2 | 2 | 110 | 1,500 | 24.52 | 3 3-prs. | 3 | 27 | 22 |
| 6 boats | Poplar | 1890 | 130 | 13.5 | 6 | 1 | 85 | 1,200 | 23-24 | 2 3-pr. Q.F. | 2 | 15 | 15 |
| 4 boats | Poplar | 1880-2 | 100 | 12.5 | 6 | 1 | 52 | 600 | 20 | 2 mach. | 3 | 14 | 10 |
| SECOND CLASS— | | | | | | | | | | | | | |
| Nos. 1-8 (8 boats) .. | Poplar | 1890 | 60 | 9.2 | 3 | 1 | 16 | 230 | 17 | 1 Q.F. | 1 | 10 | 1.25 |
| Nos. 9-10 (2 boats) .. | Chiswick .. | 1881 | 60 | 7.5 | 3.5 | 1 | 16 | 230 | 17 | .. | 1 | | |
| VEDETTE BOATS— | | | | | | | | | | | | | |
| Nos. 1-4 (4 boats) .. | .. | 1875 | 55 | 7 | .. | .. | .. | .. | .. | .. | sp. | | |

The two 150-ft. boats are named Comodoro Py and Murature.

The six 130-ft. boats are named Bithurst, Buchardo, Jorge, King, Pinedo, and Thorne. They have locomotive boilers.

The four 100-ft. boats are named Alerta, Centella, Ferre, and Py.

* 4-in. plating over entire engine and boiler space (Yarrow W.T. boilers).

Austria-Hungary.

| Name or Number. | Where Built. | Launched. | Dimensions. | | | Number of Screws. | Displacement. | Indicated Horse-Power. | Maximum Trial Speed. | Armament. | Torpedo Tubes. | Complement. | Coal Capacity. |
|-----------------------|---|-----------|-------------|-------|----------|-------------------|---------------|------------------------|-----------------------|--------------------------|----------------|-------------|----------------|
| | | | Length. | Beam. | Draught. | | | | | | | | |
| FIRST CLASS— | | | Feet. | Feet. | Feet. | | Tons. | | Knots. | | | | Tons. |
| Adler, Falke | Poplar | 1886 | 135 | 13.7 | 5.6 | 1 | 95 | 900 | 22.4 | 2 Nord. | 2 | 16 | 28 |
| 22 boats | { Elbing, Trieste, &c. } | 1896-9 | 128 | 15.9 | 6.9 | 1 | 83 | { 900 { 1,000 } | { 17.5 to { 21.5 } | 2 mach. | 2 | 15 | 28 |
| Boa | Poplar | 1898-9 | 152.6 | 15.3 | 7.6 | 1 | 133 | 2,000 | 24.3 | 2 3-pr. Q.F. | 3 | 24 | 30 |
| Cobra | | | | | | | | | | | | | |
| Kigyo | | | | | | | | | | | | | |
| Python | Poplar | 1896 | 147.6 | 14.9 | 7.6 | 1 | 130 | 2,000 | 26.5 | 2 3-pr. Q.F. | 2 | 26 | 30 |
| Viper | | | | | | | | | | | | | |
| Natter | | | | | | | | | | | | | |
| | Elbing .. | 1896 | 150 | 17.5 | 8.8 | 2 | 152 | 2,300 | 26.5 | 2 3-pr. Q.F. | 3 | .. | 30 |
| SECOND CLASS— | | | | | | | | | | | | | |
| Nos. 9, 10 (2 boats) | { Chiswick, Poplar, Pola and Elbing } | 1881 | 98.5 | 10.8 | 2.9 | 1 | 37 | 450 | 17 | { 1 Q.F. 2 Q.F. .. | 1 | | |
| Nos. 11-32 (22 boats) | | 1883-7 | 107 | 11.6 | 3.1 | 1 | 47 | 600 | 17 | | | | |
| Nos. 33-39 (7 boats) | | 1887-91 | 118.1 | 14.4 | 3.3 | 1 | 64 | 700 | 18 | | | | |
| Nos. 2-8 (7 boats) .. | | 1878-81 | 87.4 | 9.6 | 2.8 | 1 | 27 | 300 | 15 | | | | |

Brazil.

| Name or Number. | Where Built. | Launched. | Dimensions. | | | Number of Screws. | Displacement. | Indicated Horse-Power. | Maximum Trial Speed. | Armament. | Torpedo Tubes. | Complement. | Coal Capacity. |
|---------------------|--------------|-----------|-------------|------------|-----------|-------------------|---------------|------------------------|----------------------|-----------|----------------|-------------|----------------|
| | | | Length. | Beam. | Draught. | | | | | | | | |
| FIRST CLASS— | | | | | | | | | | | | | |
| Nos. 1-5 (5 boats) | Poplar.. .. | 1882 | Feet. 100 | Feet. 12.5 | Feet. 5.5 | 1 | Tons. 52 | 600 | Knots. 20 | 2 mach. | 2 | 16 | Tons. 20 |
| Araguary | Chiswick .. | 1891 | 150 | 14.5 | 5.2 | 2 | 150 | 1,550 | 25.1 | 2 Q.F. | 4 | 27 | 22 |
| Iguatemi | Chiswick .. | 1891 | 150 | 14.5 | 5.2 | 2 | 150 | 1,550 | 25.4 | 2 Q.F. | 4 | 27 | 22 |
| Marcilio Diaz .. | Chiswick .. | 1891 | 150 | 14.5 | 5.2 | 2 | 150 | 1,550 | 25.8 | 2 Q.F. | 4 | 27 | 23 |
| 5 boats | Elbing .. | 1892-3 | 152 | 17.2 | 7.9 | 2 | 130 | 2,200 | 28 | 2-1 prs. | 3 | 24 | 30 |
| Pirating | .. | .. | 130 | 12 | .. | .. | .. | .. | 10 | 2-1 pr. | 1 | .. | .. |
| Poty | .. | .. | 126 | 12 | 3 | .. | 30 | .. | 18 | 1-1 pr. | 1 | .. | .. |
| SECOND CLASS— | | | | | | | | | | | | | |
| Inhanhuay (wood) .. | New York.. | 1893 | 90 | 10 | 3 | .. | 17 | .. | 25 | 1-1 pr. | 1 | 10 | .. |
| 4 boats | .. | 1883-4 | .. | .. | .. | 1 | 17 | .. | 17 | .. | .. | .. | 2 |
| 1 boat | Chiswick .. | 1885 | 63 | 75 | 3.2 | 1 | .. | .. | 17 | .. | .. | .. | .. |
| 1 boat | Poplar.. .. | 1886 | 60 | 8 | 3 | 1 | 14 | 200 | 17 | .. | 1 | .. | .. |
| THIRD CLASS— | | | | | | | | | | | | | |
| Moxoto | Poplar.. .. | 1883 | 60 | 9.3 | .. | .. | .. | .. | 16 | 1-1 pr. | 1 | .. | .. |
| 5 boats | Chiswick .. | 1883 | 45 | 6 | 1.2 | 1 | 3.5 | .. | 12-13 | 1 mach. | sp. | .. | .. |

Chili.

| Name or Number. | Where Built. | Launched. | Dimensions. | | | Number of Screws. | Displacement. | Indicated Horse-Power. | Maximum Trial Speed. | Armament. | Torpedo Tubes. | Complement. | Coal Capacity. |
|---|--------------|--------------|-------------|------------|----------|-------------------|---------------|------------------------|----------------------|---------------|----------------|-------------|----------------|
| | | | Length. | Beam. | Draught. | | | | | | | | |
| DESTROYERS— | | | | | | | | | | | | | |
| Capitan Orella .. | Birkenhead. | 1896 | Feet. 210 | Feet. 21·6 | Feet. .. | 2 | Tons. 300 | 6000 | Knots. 30·17 | 1-12 pr. Q.F. | 2 | 65 | Tons. 90 |
| Capitan Munoz { | Birkenhead . | 1896 | 210 | 21·6 | .. | 2 | 300 | 6000 | 30·42 | 5-6 pr. | 2 | 65 | 90 |
| Gamero... .. | | | | | | | | | | 1-12 pr. Q.F. | | | |
| Teniente Serrano .. | Birkenhead . | 1896 | 210 | 21·6 | .. | 2 | 300 | 6000 | 30·35 | 1-12 pr. Q.F. | 2 | 65 | 90 |
| Guardia-Marina | Birkenhead . | 1896 | 210 | 21·6 | .. | 2 | 300 | 6000 | 30·09 | 5-6 pr. | 2 | 65 | 90 |
| Riquelme .. | | | | | | | | | | 1-12 pr. Q.F. | | | |
| FIRST CLASS— | | | | | | | | | | | | | |
| 3 boats | Poplar.. .. | 1881 | 86 | 12·5 | .. | 1 | 25 | 400 | 19-20 | .. | 4 | 15 | .. |
| 5 boats | Poplar.. .. | 1881 | 100 | 12·5 | .. | 1 | 35 | 400 | 18-19 | 4 mach. | 4 | 15 | 9 |
| Sarjento Aldea .. | Poplar.. .. | 1886 | 125 | 13·5 | 5·5 | 1 | 70 | 800 | 20 | 2 Q.F. | 4 | 18 | 15 |
| Injenerio Hyatt, Cirujano Videla, Injenerio Mutilla, Guardia-Marina Contreras, Capitan Thompson, and Teniente Rodriguez (Viper type) .. | Poplar.. .. | 1896 1898 | 152·6 | 15·3 | 7·9 | 1 | 140 | 2200 | 27·5 27·2 | 3-3 pr. Q.F. | 3 | 28 | 40 |
| Janequeo, Guala, Rucumilla, and Guacolda | Poplar.. .. | 1881 | 100 | 12·5 | .. | 1 | .. | 450 | .. | .. | .. | .. | .. |
| Tegualda, Quidora, and Fresia | Poplar.. .. | .. | 87 | 10·9 | .. | 1 | .. | 400 | .. | .. | .. | .. | .. |
| SECOND CLASS— | | | | | | | | | | | | | |
| 1 boat | East Cowes | 1887 | 50 | .. | .. | .. | .. | .. | 16 | .. | .. | .. | .. |
| 1 boat | East Cowes | 1892 | 60 | 9·6 | 5 | 1 | 15 | 270 | 19 | .. | 1 | .. | .. |
| 1 boat | La Seyne .. | 1895 | 42 | 8·6 | .. | 1 | .. | .. | .. | .. | 1 | .. | .. |

The Thompson and Rodriguez were sent out in sections, and put together at Talcahuano and Valparaiso.

China.

| Name or Number. | Where Built. | Launched. | Dimensions. | | | Number of Screws. | Displacement. | Indicated Horse-Power. | Maximum Trial Speed. | Armament. | Torpedo Tubes. | Complement. | Coal Capacity. |
|------------------|-----------------|-----------|-------------|-------|----------|-------------------|---------------|------------------------|----------------------|---------------------------|----------------|-------------|----------------|
| | | | Length. | Beam. | Draught. | | | | | | | | |
| | | | Feet. | Feet. | Feet. | | Tons. | | Knots. | | | | Tons. |
| FIRST CLASS— | | | | | | | | | | | | | |
| 1 boat | Elbing .. | 1886 | 144.3 | 16.4 | 7.5 | 1 | 128 | 1,400 | 24.2 | 4 1-pr. revs. | 2 | 20 | 15 |
| 1 boat | Poplar... .. | 1887 | 128 | 13 | 5 | 1 | 69 | 1,000 | 23.9 | { 3 Q.F., 4 Gatlings } | 3 | 28 | 15 |
| 25 boats | Stettin, &c. .. | 1886-87 | 110 | 13 | 4.9 | 1 | 65 | 1,000 | 19.5 | 1-pr. revs. | 3 | 16 | 10 |
| 2 boats | Stettin .. | 1883 | 86 | 10.4 | 3.4 | 1 | 28 | 650 | 18.2 | 1-pr. revs. | 2 | 16 | 12 |
| 1 boat | Stettin .. | 1884 | 123.5 | 21.7 | .. | .. | .. | .. | 19 | .. | 5 | 16 | .. |
| 2 boats | Elbing .. | 1895 | 128 | 15.8 | .. | .. | 120 | 1,250 | 24.5 | Q.F. | 2 | .. | .. |
| SECOND CLASS— | | | | | | | | | | | | | |
| 11 boats | Elbing .. | 1885-86 | 85 | 11.9 | 4.8 | 1 | 27 | 400 | 19 | .. | 1 | .. | 5 |
| 1 boat | Foochow .. | Bldg. | 88.6 | 6.7 | 3.3 | 1 | 30 | 550 | 20.5 | .. | .. | .. | .. |

About twenty boats only are said to be serviceable. The four destroyers built at Elbing in 1893-9 were captured by the Allies from the Chinese at Taku, 1900, and added to the navies of Great Britain, France, Germany and Russia.

Costa Rica.

Costa Rica has one 62-ft., 15-knot boat.

Denmark.

| Name or Number. | Where Built. | Launched. | Dimensions. | | | Number of Screws. | Displacement. | Indicated Horse-Power. | Maximum Trial Speed. | Armament. | Torpedo Tubes. | Complement. | Coal Capacity. |
|--------------------------|--------------|-----------|-------------|-------|----------|-------------------|---------------|------------------------|----------------------|--------------------------|----------------|-------------|----------------|
| | | | Length. | Beam. | Draught. | | | | | | | | |
| FIRST CLASS— | | | | | | | | | | | | | |
| Højen | Copenhagen | 1896 | | | | | | | | | | | |
| Havørnen | Copenhagen | 1897 | 154.3 | 15.4 | 7.9 | 2 | 142 | 2,317 | 22.9 | { 1 4.7-in. 1 1-pr. } | 3 | .. | .. |
| Søbjørnen | Copenhagen | 1898 | | | | | | | | | | | |
| Delfinen | Chiswick .. | 1883 | 111.5 | 12.6 | 6 | 1 | 59 | 620 | 20 | 1 mach. | 2 | 14 | 9 |
| Havhesten | Chiswick .. | 1888 | 137.9 | 14 | 7 | 1 | 94 | 1,200 | 22.8 | 2 1-pr. revs. | 4 | 20 | 15 |
| Hvalrossen | Chiswick .. | 1884 | 114 | 12.6 | 6.5 | 1 | 64 | 660 | 18.7 | 1 mach. | 2 | 14 | 10 |
| Makrelen | Copenhagen | 1893 | 140 | 14.2 | 7 | 2 | 112 | 1,200 | .. | .. | .. | .. | 16 |
| Narhvalen | Chiswick .. | 1888 | 137.9 | 14 | 7 | 1 | 94 | 1,200 | 22.3 | 2 1-pr. revs. | 4 | 20 | 15 |
| Nord Kaperen | Copenhagen | 1893 | 140 | 14.2 | 7 | 2 | 112 | 1,200 | .. | 2 1-pr. revs. | 4 | .. | 16 |
| Sølvøen | Chiswick .. | 1887 | 131 | 14.8 | 6.8 | 1 | 89 | 1,200 | 23.3 | 2 mach. | 4 | 20 | 14 |
| Sølvøen | Havre.. .. | 1880 | 94.8 | 10.9 | 3.9 | 1 | 37 | 450 | 18.1 | .. | 2 | 12 | 5 |
| Springeren | Copenhagen | 1891 | 119 | 13 | 4.9 | 1 | 81 | 800 | 18.3 | 2 1-pr. revs. | 2 | 20 | 14 |
| Støren | Chiswick .. | 1887 | 131 | 14.8 | 6.8 | 1 | 89 | 1,200 | 23 | 2 mach. | 4 | 20 | 14 |
| Sværdfisken | Chiswick .. | 1881 | 110 | 12 | 6 | 1 | 49 | 600 | 20.7 | 1 mach. | 2 | 14 | 9 |
| SECOND CLASS— | | | | | | | | | | | | | |
| Nos. 4, 5 (2 boats) .. | Chiswick .. | 1882 | 63 | 7.5 | 2.5 | 1 | 15 | 350 | 16.9 | 1 mach. | 2 | 6 | 1 |
| Nos. 6, 7 (2 boats) .. | Chiswick .. | 1884 | 66.8 | 8 | 4.2 | 1 | 16 | 170 | 15.4 | 1 mach. | 2 | 6 | 1.5 |
| Nos. 8, 9 (2 boats) .. | Chiswick .. | 1886 | 69.5 | 8.1 | 3.8 | 1 | 17 | 170 | 15.7 | 1 mach. | 2 | 6 | 1 |
| Nos. 10, 11 (2 boats) .. | Chiswick .. | 1888 | 70.2 | 8 | 4 | 1 | 18 | 180 | 15.8 | 1 mach. | 2 | 6 | 1 |
| Nos. 12, 13 (2 boats) .. | Chiswick .. | 1889 | 78.3 | 9 | 4.9 | 1 | 24 | 350 | 18 | 1 mach. | 2 | 8 | 3 |
| 1 boat | Chiswick .. | 1875 | 58 | 7.5 | 3 | 1 | .. | .. | 16 | .. | sp. | .. | .. |

Four destroyers and two boats are provided for.

France.

| Name or Number. | Where Built. | Launched. | Dimensions. | | | Number of Screws. | Displacement. | Indicated Horse-Power. | Maximum Trial Speed. | Armament. | Torpedo Tubes. | Complement. | Coal Capacity. |
|-------------------------|----------------|-----------|-------------|-------|----------|-------------------|---------------|------------------------|----------------------|----------------|----------------|-------------|----------------|
| | | | Length. | Beam. | Draught. | | | | | | | | |
| | | | Feet. | Feet. | Feet. | | Tons. | | Knots. | | | | Tons. |
| DESTROYERS— | | | | | | | | | | | | | |
| Arbalète | Normand | Bldg. | 183.9 | 20.11 | 10.3 | 2 | 300 | 6000 | .. | 1-9pr. 6-3prs. | 2 | .. | .. |
| Arquebuse | Normand | Bldg. | 183.9 | 20.11 | 10.3 | 2 | 300 | 6000 | .. | 1-9pr. 6-3prs. | 2 | .. | .. |
| Carabine | Rocheport | Bldg. | 183.9 | 20.11 | 10.3 | 2 | 300 | 6000 | .. | 1-9pr. 6-3prs. | 2 | .. | .. |
| Durandal | Normand | 1899 | 180.5 | 20.8 | 10.3 | 2 | 300 | 5000 | 27.4 | 1-9pr. 6-3prs. | 2 | 45 | 84 |
| Epée | Havre (F.&C.) | 1900 | 183.9 | 20.8 | 10.3 | 2 | 300 | 5700 | 26 | 1-9pr. 6-3prs. | 2 | 48 | 33 |
| Epéu | Havre (F.&C.) | Bldg. | 183.9 | 20.11 | 10.3 | 2 | 300 | 6000 | .. | 1-9pr. 6-3prs. | 2 | .. | .. |
| Escopette | Rocheport | 1900 | 183.9 | 20.8 | 10.3 | 2 | 300 | 5700 | 26 | 1-9pr. 6-3prs. | 2 | 45 | 48 |
| Espingole | Normand | 1900 | 183.9 | 20.8 | 10.3 | 2 | 300 | 5000 | 27.2 | 1-9pr. 6-3prs. | 2 | 45 | 84 |
| Fauconneau | Normand | 1900 | 183.9 | 20.8 | 10.3 | 2 | 300 | 5000 | 27.1 | 1-9pr. 6-3prs. | 2 | 45 | 84 |
| Flamberge | Rocheport | Bldg. | 183.9 | 20.8 | 10.3 | 2 | 300 | 5700 | 26 | 1-9pr. 6-3prs. | 2 | 45 | 48 |
| Framée* | Nantes | 1900 | 183.9 | 20.8 | 10.3 | 2 | 300 | 5700 | 26 | 1-9pr. 6-3prs. | 2 | 48 | 33 |
| Fronde | Bordeaux | Bldg. | 183.9 | 20.11 | 10.3 | 2 | 300 | 6000 | .. | 1-9pr. 6-3prs. | 2 | .. | .. |
| Hallebarde | Normand | 1899 | 180.5 | 20.8 | 10.3 | 2 | 300 | 5000 | 27.2 | 1-9pr. 6-3prs. | 2 | 45 | 84 |
| Harpon | Bordeaux | Bldg. | 183.9 | 20.11 | 10.3 | 2 | 300 | 6000 | .. | 1-9pr. 6-3prs. | 2 | .. | .. |
| Javeline | Nantes | Bldg. | 183.9 | 20.11 | 10.3 | 2 | 300 | 6000 | .. | 1-9pr. 6-3prs. | 2 | .. | .. |
| Mousquet | Nantes | Bldg. | 183.9 | 20.11 | 10.3 | 2 | 300 | 6.00 | .. | 1-9pr. 6-3prs. | 2 | .. | .. |
| Pertuisane | Rocheport | 1900 | 183.9 | 20.8 | 10.3 | 2 | 300 | 5700 | 26 | 1-9pr. 6-3prs. | 2 | 45 | 48 |
| Pique | Havre (F.&C.) | 1900 | 183.9 | 20.8 | 10.3 | 2 | 300 | 5700 | 26 | 1-9pr. 6-3prs. | 2 | 48 | 33 |
| Rapier | Rocheport | Bldg. | 183.9 | 20.8 | 10.3 | 2 | 300 | 5700 | 26 | 1-9pr. 6-3prs. | 2 | 45 | 48 |
| Sagaie | Havre (F.&C.) | Bldg. | 183.9 | 20.11 | 10.3 | 2 | 300 | 6000 | .. | 1-9pr. 6-3prs. | 2 | .. | .. |
| Sarbacane | Rocheport | Bldg. | 183.9 | 20.11 | 10.3 | 2 | 300 | 6000 | .. | 1-9pr. 6-3prs. | 2 | .. | .. |
| Takou† | Elbing | 1898 | 193.7 | 21.0 | .. | 2 | 280 | 6000 | 35 | 6-3 pr. q. f. | 2 | .. | 67 |
| Yatagan | Nantes | 1900 | 183.9 | 20.8 | 10.3 | 2 | 300 | 5700 | 26 | 1-9pr. 6-3prs. | 2 | 48 | 33 |
| M 22 to 31 | .. | Pro. | 183.9 | 19.6 | 10.3 | 2 | 303 | 4800 | 26 | 1-9 pr. | 2 | 48 | 37 |
| SEA-GOING— | | | | | | | | | | | | | |
| Agile | La Seyne .. | 1889 | 139 | 14.7 | 7.7 | 2 | 121 | 1,100 | 20.4 | 3-3 prs. | 2 | 26 | 14 |
| Alarme | St. Nazaire | 1889 | 151 | 15.7 | 8.3 | 2 | 169 | 1,400 | 20.5 | 2-3 prs. | 4 | 30 | 40 |
| Aquilon | Normand .. | 1895 | 137.8 | 14.6 | 7.9 | 2 | 127 | 2,000 | 23.17 | 2-3 prs. | 2 | 34 | 17 |
| Archer | Normand .. | 1893 | 138 | 14.7 | 6.5 | 2 | 131 | 1,250 | 21 | 2-3 prs. | 2 | 26 | 17 |
| Argonaute | St. Denis .. | 1893 | 141 | 16.4 | 9.3 | 2 | 133 | 1,500 | 25.1 | 2-3 prs. | 2 | 34 | 16 |
| Audacieux | Nantes .. | 1900 | 144.2 | 15.2 | 10.0 | 2 | 152 | 4,200 | 30 | 2-3 prs. | 2 | .. | 18 |
| Aventurier | St. Nazaire .. | 1889 | 151 | 15.7 | 8.3 | 2 | 174 | 1,400 | 20.5 | 2-3 prs. | 4 | 34 | 40 |
| Averne | Havre (F.&C.) | 1894 | 141 | 16.4 | 9.3 | 2 | 133 | 1,500 | 24.4 | 2-3 prs. | 2 | 27 | 16 |
| Borée | Bordeaux .. | Bldg. | 147.7 | 16.7 | 8.0 | 2 | 160 | 4,400 | 30 | 2-3 prs. | 2 | .. | 18 |
| Bourrasque | Normand .. | Bldg. | 147.7 | 16.7 | 8.0 | 2 | 160 | 4,400 | 30 | 2-3 prs. | 2 | .. | 18 |
| Cerbère | .. | 1899 | 137.8 | 14.6 | 7.9 | 2 | 127 | 2,000 | 25 | 2-3 prs. | 2 | 34 | 17 |
| Chevalier | Normand .. | 1893 | 144.3 | 15.7 | 6.8 | 2 | 131 | 2,700 | 27.2 | 2-1 prs. | 2 | 32 | 17 |
| Corsaire | St. Denis .. | 1893 | 160.5 | 15 | 5.4 | 2 | 171 | 2,500 | 25.5 | 4-1 prs. | 2 | 32 | 15 |
| Coureur | Chiswick .. | 1888 | 147.5 | 14.5 | 4.6 | 2 | 129 | 1,550 | 23.28 | 4 Nords. | 2 | 27 | 22 |
| Cyclone (ex-Tenare) .. | Normand .. | 1898 | 144.2 | 15.2 | 10.0 | 2 | 152 | 4,200 | 30 | 2-3 prs. | 2 | .. | 18 |
| Dauphin | Havre (F.&C.) | 1894 | 141 | 16.4 | 9.3 | 2 | 137 | 1,500 | 25.22 | 2-3 prs. | 2 | 34 | 16 |
| Défi | St. Nazaire .. | 1889 | 151 | 15.7 | 8.3 | 2 | 173 | 1,400 | 21 | 2-3 prs. | 4 | 30 | 40 |
| Dragon | Normand .. | 1892 | 138 | 14.7 | 8.2 | 2 | 129 | 1,400 | 25 | 2-3 prs. | 2 | 26 | 15.5 |
| Eclair | La Seyne .. | 1891 | 144.3 | 14.7 | 7.7 | 2 | 128 | 1,100 | 21.5 | 3-3 prs. | 2 | 26 | 17 |
| Flibustier | Normand .. | 1894 | 143 | 16.4 | 9.3 | 2 | 132 | 1,500 | 23.5 | 2-3 prs. | 2 | 34 | 16 |
| Forban | Normand .. | 1895 | 144.2 | 15.2 | 10 | 2 | 135 | 3,200 | 31.2 | 2-1 prs. | 2 | .. | .. |
| Grenadier | Normand .. | 1892 | 138 | 14.7 | 8.2 | 2 | 129 | 1,400 | 25.25 | 2-3 prs. | 2 | 26 | 15.5 |
| Grondeur | Havre (F.&C.) | 1892 | 147.5 | 14.5 | 5 | 2 | 130 | 1,550 | 24 | 2-3 prs. | 2 | 27 | 20 |
| Kabye | La Seyne .. | 1891 | 144.3 | 14.7 | 7.7 | 2 | 128 | 1,100 | 21.6 | 3-3 prs. | 2 | 27 | 17 |
| Lancier | Normand .. | 1893 | 138 | 14.7 | 8.2 | 2 | 128 | 1,400 | 25.79 | 2-3 prs. | 2 | 26 | 15.5 |
| Mangini | Nantes .. | 1896 | 117.6 | 14.8 | 7.9 | 2 | 129 | 2,100 | 27.5 | 2-3 prs. | 2 | 34 | 17 |
| Mistral | Normand .. | 1901 | 147.7 | 16.8 | 8.8 | 2 | 182 | 4,200 | 30 | 2-3 prs. | 3 | .. | 23 |
| Mousquetaire | Havre (F.&C.) | 1892 | 154 | 15.7 | 7 | 2 | 150 | 2,100 | 24.77 | 2-1 prs. | 2 | 32 | 18 |
| Orange | La Seyne .. | 1891 | 144.3 | 14.7 | 7.7 | 2 | 128 | 1,100 | 21.7 | 3-3 prs. | 2 | 26 | 17 |
| Ouralgan | Nantes .. | 1887 | 151 | 15.7 | 8.3 | 2 | 174 | 1,400 | 20 | 2-3 prs. | 4 | 30 | 40 |
| Rafale | Normand .. | Bldg. | 147.7 | 16.7 | 8.0 | 2 | 160 | 4,400 | 30 | 2-3 prs. | 2 | .. | 18 |
| Sarrasin | Bordeaux .. | 1893 | 139 | 14.7 | 7.7 | 2 | 131 | 1,100 | 20.5 | 3-3 prs. | 2 | 26 | 14 |
| Simoun | Havre (F.&C.) | 1901 | 144.2 | 15.2 | 10.0 | 2 | 152 | 4,200 | 30 | 2-3 prs. | 2 | .. | 18 |
| Sirocco | Normand .. | 1901 | 147.7 | 16.8 | 8.8 | 2 | 182 | 4,200 | 30 | 2-3 prs. | 3 | .. | 23 |
| Téméraire | St. Nazaire .. | 1899 | 151 | 15.7 | 8.3 | 2 | 174 | 1,400 | 21 | 2-3 prs. | 4 | 30 | 40 |
| Tourbillon | Bordeaux .. | 1892 | 139 | 14.7 | 7.7 | 2 | 131 | 1,100 | 20.5 | 3-3 prs. | 2 | 26 | 14 |
| Tourmente | St. Denis .. | 1893 | 141 | 16.4 | 9.3 | .. | 132 | 1,500 | 21.6 | 2-3 prs. | 2 | 25 | 15 |
| Tramontane | Bordeaux .. | Bldg. | 147.7 | 16.7 | 8.0 | 2 | 160 | 4,400 | 30 | 2-3 prs. | 2 | .. | 18 |
| Trombe | Nantes .. | 1900 | 144.2 | 15.2 | 10.0 | 2 | 152 | 4,200 | 30 | 2-3 prs. | 2 | .. | 18 |
| Turco | St. Denis .. | 1892 | 138 | 14.7 | 8.2 | 2 | 124 | 1,400 | 21.3 | 2-3 prs. | 2 | 26 | 15.5 |
| Typhon | Havre (F.&C.) | 1901 | 144.2 | 15.2 | 10.0 | 2 | 152 | 4,200 | 30 | 2-3 prs. | 2 | .. | 18 |
| Vélocé | Havre (F.&C.) | 1892 | 147.5 | 14.5 | 5 | 2 | 130 | 1,550 | 23.6 | 2-3 prs. | 2 | 27 | 20 |
| Zouave | St. Denis .. | 1892 | 138 | 14.7 | 8.2 | 2 | 124 | 1,400 | 21.3 | 2-3 prs. | 2 | 26 | 15.5 |
| FIRST CLASS— | | | | | | | | | | | | | |
| Bainy | Normand .. | 1886 | 134.5 | 11 | 7.2 | 1 | 66 | 700 | 20 | 2-1 pr. rev. | 2 | 21 | 12 |
| Bouff-Willamez | St. Denis .. | 1888 | 134.5 | 11 | 7.2 | 1 | 66 | 700 | 20 | 2-1 pr. rev. | 2 | 21 | 12 |
| Capt. Cuny | .. | 1886 | 134.5 | 11 | 7.2 | 1 | 66 | 700 | 20 | 2-1 pr. rev. | 2 | 21 | 12 |
| Capt. Mehli | .. | 1886 | 134.5 | 11 | 7.2 | 1 | 66 | 700 | 20 | 2-1 pr. rev. | 2 | 21 | 12 |
| Challier | .. | 1886 | 131.5 | 11 | 7.2 | 1 | 66 | 700 | 20 | 2-1 pr. rev. | 2 | 21 | 12 |
| Dehorter | St. Denis .. | 1886 | 134.5 | 11 | 7.2 | 1 | 66 | 700 | 20 | 2-1 pr. rev. | 2 | 21 | 12 |
| Deroulède | Normand .. | 1886 | 134.5 | 11 | 7.2 | 1 | 66 | 700 | 20 | 2-1 pr. rev. | 2 | 21 | 12 |
| Doudart de Lagrée | Normand .. | 1886 | 134.5 | 11 | 7.2 | 1 | 66 | 700 | 20 | 2-1 pr. rev. | 2 | 21 | 12 |
| Edmond Fontaine | St. Denis .. | 1888 | 134.5 | 11 | 7.2 | 1 | 66 | 700 | 20 | 2-1 pr. rev. | 2 | 21 | 12 |
| 126-129 (4 boats) | Normand .. | 1889-0 | 118 | 13.2 | 8.6 | 1 | 80 | 1,250 | 21 | 2-1 prs. | 2 | 21 | 10 |
| 145-149 (5 boats) | Normand .. | 1891-3 | 118 | 13.2 | 8.7 | 1 | 79 | 1,300 | 23.9 | 2-1 prs. | 2 | 21 | 10 |
| 152-154 (3 boats) | Normand .. | 1892-3 | 118 | 13.2 | 8.7 | 1 | 80 | 1,300 | 24.6 | 2-1 prs. | 2 | 21 | 10 |
| 155-157 (3 boats) | Bordeaux .. | 1893 | 118 | 13.2 | 8.7 | 1 | 80 | 1,300 | 23 | 2-1 prs. | 2 | 21 | 10 |
| 158-160 (3 boats) | Cail | 1893 | 118 | 13.2 | 8.7 | 1 | 80 | 1,300 | 23 | 2-1 prs. | 2 | 21 | 10 |

* Framée, lost.

† Captured from the Chinese at Faku, 1900.

N.B.—“F. & C.” “Forges et Chantiers.”

“Normand” means that the boat has been built at that firm's yard at Havre.

Six new boats at Havre, 9 at Chalon, 5 at Bordeaux, and 11 others; dimensions not known.

France—continued.

| Name or Number. | Where Built. | Launched. | Dimensions. | | | Number of Screws. | Displacement. | Indicated Horse-Power. | Maximum Trial Speed. | Armament. | Torpedo Tubes. | Complement. | Coal Capacity. |
|--------------------------------------|--------------------------------------|-----------|-------------|-------|----------|-------------------|---------------|------------------------|----------------------|-----------|----------------|-------------|----------------|
| | | | Length. | Bear. | Draught. | | | | | | | | |
| | | | Feet. | Feet. | Feet. | | Tons. | | Knots. | | | | Tons. |
| FIRST CLASS—continued. | | | | | | | | | | | | | |
| 161-163 (3 boats) .. | St. Nazaire .. | 1892 | 118 | 13·2 | 8·7 | 1 | 80 | 1,300 | 23 | 2-1 prs. | 2 | 21 | 10 |
| 164-166 (3 boats) .. | La Seyne .. | 1892 | 118 | 13·2 | 8·7 | 1 | 79 | 1,300 | 23 | 2-1 prs. | 2 | 21 | 10 |
| 167-169 (3 boats) .. | Creusot .. | 1892 | 118 | 13·2 | 8·7 | 1 | 81 | 1,300 | 23 | 2-1 prs. | 2 | 21 | 10 |
| 170, 171 (2 boats) .. | Normand .. | 1893 | 118 | 13·2 | 8·7 | 1 | 80 | 1,300 | 23-2 | 2-1 prs. | 2 | 21 | 10 |
| 172, 173 (2 boats) .. | Havre .. | 1893-4 | 118 | 13·2 | 8·7 | 1 | 89 | 1,390 | 23-24 | 2-1 prs. | 2 | 21 | 10 |
| 174-176 (3 boats) .. | Havre .. | 1893-5 | 118 | 13·2 | 8·7 | 1 | 94 | 1,390 | 23-24 | 2-1 prs. | 2 | 21 | 10 |
| 177-179 (3 boats) .. | Havre .. | 1893 | 118 | 13·2 | 8·7 | 1 | 79 | 1,300 | 23-24 | 2-1 prs. | 2 | 21 | 10 |
| 180-187 (8 boats) .. | Normand, etc. | 1894-5 | 118 | 13·2 | 8·6 | 1 | 80 | 1,500 | 25·7 | 2-1 prs. | 2 | 21 | 10 |
| 188-191 (4 boats) .. | Havre, etc. | 1893-4 | 118 | 13·2 | 8·6 | 1 | 80 | 1,500 | 24-2 | 2-1 prs. | 2 | 21 | 10 |
| 192-194 (3 boats) .. | Havre, etc. | 1894-5 | 118 | 13·2 | 8·7 | 1 | 82 | 1,300 | 23-55 | 2-1 prs. | 2 | 21 | 10 |
| 195-200 (6 boats) .. | Havre, etc. | 1894-5 | 319 | 13·2 | 8·7 | 1 | 80 | 1,300 | 23·5 | 2-1 prs. | 2 | 21 | 10 |
| 201-205 (5 boats) .. | Normand .. | 1897-8 | 121·4 | 13·4 | 8·6 | 1 | 84 | 1,700 | 25·9 | 2-1 prs. | 2 | 23 | 10 |
| 206-211 (6 boats) .. | Bordeaux .. | 1897-8 | 121·4 | 13·6 | 8·6 | 1 | 86 | 1,500 | 23·5 | 2-1 prs. | 2 | 23 | 10 |
| 212-215 (4 boats) .. | Normand .. | 1899 | 121·4 | 13·6 | 8·6 | 1 | 86 | 1,800 | 27 | 2-1 prs. | 2 | 23 | 10 |
| 216-226 (11 boats) .. | {Cherbourg, Toulon, etc.} | 1899 | 121·6 | 13·6 | 8·6 | 1 | 86 | 1,500 | 23·5 | 2-1 prs. | 2 | 23 | 10 |
| 227-235 (9 boats) .. | Bordeaux, etc. | Bldg. | 121·4 | 13·2 | 8·7 | 1 | 86 | 1,500 | 23·5 | 2-1 prs. | 2 | 23 | 10 |
| 236-255 (20 boats) | Bordeaux, etc. | Bldg. | 121·4 | 13·2 | 8·7 | 1 | 86 | 1,500 | 23·5 | 2-1 prs. | 2 | 23 | 10 |
| 256-257 (2 boats) .. | .. | 1900 | 121·4 | 13·2 | 3·7 | 1 | 86 | 1,500 | 23·5 | 2-1 prs. | 2 | 23 | 10 |
| 258-261 (4 boats) .. | Bordeaux .. | Bldg. | | | | | | | | | | | |
| 262-263 (2 boats) .. | Creusot .. | Bldg. | | | | | | | | | | | |
| 264-265 (2 boats) .. | Bordeaux .. | | | | | | | | | | | | |
| P. 96 | Sargon .. | | | | | | | | | | | | |
| SECOND CLASS— | | | | | | | | | | | | | |
| 26 | .. | 1878 | 108 | 11 | 5·6 | 1 | 45 | 400 | 19 | 2-1 prs. | 2 | 16 | 10 |
| 27 | .. | 1878 | 104·4 | 10·6 | 6·1 | 1 | 44 | 400 | 19 | 2-1 prs. | 2 | 16 | 10 |
| 28 | .. | 1878 | 111·5 | 11 | 5·6 | 1 | 44 | 400 | 19 | 2-1 prs. | 2 | 16 | 10 |
| 60-64 (5 boats) .. | Normand .. | 1883 | 108·2 | 10·3 | 6·1 | 1 | 45 | 400 | 19 | 2-1 prs. | 2 | 16 | 10 |
| 65, 66, 68 (3 boats) | Normand .. | 1884 | 108·2 | 10·7 | 6·4 | 1 | 49 | 500 | 20 | 2-1 prs. | 2 | 16 | 10 |
| 69-74 (6 boats) .. | Normand .. | 1885 | 108·2 | 10·7 | 6·5 | 1 | 50 | 500 | 20 | 2-1 prs. | 2 | 16 | 10 |
| 75, 82, 84-109 (34 boats) | Call, etc. .. | 1885-92 | 114·7 | 10·6 | 6 | 1 | 54 | 525 | 20 | 2-1 prs. | 2 | 16 | 10 |
| 111-125 (11 boats) | La Seyne, etc. | 1885-90 | 114·7 | 10·6 | 6 | 1 | 54 | 525 | 20 | 2-1 prs. | 2 | 16 | 10 |
| 130-132, 134-144 (14 boats)* | Normand .. | 1890-91 | 111·5 | 11·4 | 6 | 1 | 52·8 | 520 | 21 | 2-1 prs. | 2 | 16 | 10 |
| THIRD CLASS— | | | | | | | | | | | | | |
| 8, 10-16, 18, 19 (10 boats) | Various Firms in France and England. | 1871-82 | 86 | 10·2 | 5 | 1 | 27 | 200-450 | 16-19 | .. | .. | 10 | 10 |
| 20 | | | 87 | 10·8 | 5 | 1 | 33 | | | .. | .. | 10 | 10 |
| 22, 23 (2 boats) .. | | | 87·6 | 10·4 | 5·2 | 1 | 30 | | | .. | .. | 10 | 10 |
| 24, 25 (2 boats) .. | | | 88·5 | 10·4 | 6 | 1 | 30 | | | .. | .. | 10 | 10 |
| 31 | | | 85·5 | 10·4 | 3·8 | 1 | 27 | | | .. | .. | 10 | 10 |
| 33-36 (4 boats) .. | | | 89 | 10·4 | 6 | 1 | 32 | | | .. | .. | 10 | 10 |
| 37-40 (4 boats) .. | | | 87 | 10·8 | 5 | 1 | 32 | | | .. | .. | 10 | 10 |
| 41, 42 (2 boats) .. | | | 87 | 10·8 | 6 | 1 | 33 | | | .. | .. | 10 | 10 |
| 43, 44 (2 boats) .. | | | 89 | 10·4 | 5·7 | 1 | 32 | | | .. | .. | 10 | 10 |
| 47 | | | 87 | 10·8 | 5 | 1 | 33 | | | .. | .. | 10 | 10 |
| 48 | | | 89 | 10·4 | 5·8 | 1 | 32 | | | .. | .. | 10 | 10 |
| 49, 50, 53 (3 boats) .. | | | 87 | 10·8 | 5 | 1 | 32 | | | .. | .. | 10 | 10 |
| 54, 55 (2 boats) .. | | | 91 | 10 | 6·1 | 1 | 32 | | | .. | .. | 10 | 10 |
| VEDETTE BOATS— | | | | | | | | | | | | | |
| (1 boat) (aluminium) .. | Poplar .. | 1894 | 62·3 | 9·1 | .. | 1 | 14 | 210 | 20·5 | .. | 1 | 8 | .. |
| 29, 30 (2 boats) .. | Chiswick .. | 1876 | 67 | 8·5 | 3·5 | 1 | 16 | .. | 18 | .. | 1 | 8 | .. |
| 56, 57 (2 boats) .. | Chiswick .. | 1879 | 59 | 7·5 | 3·5 | 1 | 12 | 50 | 16 | .. | 1 | 8 | .. |
| 58, 59 (2 boats) .. | Chiswick .. | 1881 | 63 | 7·5 | 3·5 | 1 | 11 | 50 | 17 | .. | 1 | 8 | .. |
| A, B, C | Creusot .. | 1891 | 62·4 | 8·9 | 4·9 | 1 | 15 | 210 | 16·5 | .. | 1 | 9 | .. |
| D, E, F, G, H, I† .. | Creusot .. | 1900 | | | | | | | | | | | |
| SUBMARINE— | | | | | | | | | | | | | |
| Algérien | Cherbourg .. | 1901 | 48·8 | 9·2 | .. | 1 | 266 | 720 | 14 | .. | 1 | 8 | .. |
| Farfadet | Rocheport .. | 1900 | | | | | | | | .. | .. | 4 | .. |
| Français | Cherbourg .. | 1901 | 48·8 | 9·2 | .. | 1 | 39 | 60 | 4-6 | .. | .. | .. | .. |
| Gnome | Rocheport .. | Bldg. | | | | | | | | .. | .. | .. | .. |
| Gustave Zédé | Toulon .. | 1893 | 131 | .. | .. | 1 | 266 | 720 | 14 | .. | 1 | 8 | .. |
| Gymnote | Mourillon .. | 1888 | 59 | 5·9 | 5·9 | 1 | 39 | 60 | 4-6 | .. | .. | .. | .. |
| Korrigan | Rocheport .. | Bldg. | | | | | | | | .. | .. | .. | .. |
| Lutin | Rocheport .. | Bldg. | | | | | | | | .. | .. | .. | .. |
| Morse | Cherbourg .. | 1899 | 120 | 9·2 | .. | 1 | 146 | .. | 13 | .. | 1 | 9 | .. |
| Narval | Cherbourg .. | 1899 | 111·6 | 12·4 | 5·2 | 1 | 106 | 250 | 12 | .. | 2 | 11 | .. |
| Siluro | Cherbourg .. | Bldg. | | | | | | | | .. | .. | .. | .. |
| Espadon | Cherbourg .. | Bldg. | | | | | | | | .. | .. | .. | .. |
| Sirène | Cherbourg .. | Bldg. | 111·6 | 12·4 | 5·2 | 1 | 106 | 250 | 12 | .. | 2 | 11 | .. |
| Triton | Cherbourg .. | Bldg. | 111·6 | 12·4 | 5·2 | 1 | 106 | 250 | 12 | .. | 2 | 11 | .. |

* Second-class boat No. 83 lost off Cape de la Chèvre, 1897, and No. 133 near Algiers, 1898.

† For the torpedo-transport Foudre.

The Libellule, a turbine-motor torpedo boat, is in hand at Cherbourg. Twenty submarine boats are to be put in hand—10 at Toulon, 6 at Rocheport, and 4 at Cherbourg.

Germany.

| Name or Number. | Where Built. | Launched. | Dimensions. | | | Number of Screws. | Displacement. | Indicated Horse-Power. | Maximum Trial Speed. | Armament. | Torpedo Tubes. | Complement. | Coal Capacity. |
|----------------------|-----------------|-----------|--------------|--------------|------------|-------------------|------------------|------------------------|----------------------|---------------|----------------|-------------|----------------|
| | | | Length. | Beam. | Draught. | | | | | | | | |
| DESTROYERS— | | | | | | | | | | | | | |
| D 1, D 2 (2 boats) | Elbing .. | 1887 | 180.6 | 21.6 | 9.8 | 2 | 250 | 1,800 | 19 | 6 1-pr. revs. | 3 | 48 | 50 |
| D 3, D 4 (2 boats) | Elbing .. | 1888 | 184 | 21.8 | 9.6 | 2 | 300 | 2,000 | 20 | 4 6-pr. Q.F. | 3 | 48 | 90 |
| D 5, D 6 (2 boats) | Elbing .. | 1888-9 | 190.3 | 23 | 9.6 | 2 | 320 | 3,000 | 22½ | 2 1-pr. revs. | 3 | 48 | 90 |
| D 7, D 8 (2 boats) | Elbing .. | 1890 | 190.3 | 23 | 9.9 | 2 | 350 | 3,500 | 22½ | 4 6-pr. Q.F. | 3 | 48 | 90 |
| D 9 | Elbing .. | 1894 | 197.0 | 24.3 | 9.9 | 2 | 380 | 4,500 | 26 | 6 Q.F. | 3 | 52 | 80 |
| D 10 | Chiswick .. | 1898 | 211.9 | 19.6 | 8.1 | 2 | 310 | 5,800 | 28.5 | 5 3-pr. Q.F. | 3 | 52 | 80 |
| D 11, D 12 | Chiswick .. | 1900 | 218.6 | 20.9 | 8.7 | 2 | 333 | 7,000 | 31 | 1 12 pr. | 2 | 59 | 40 |
| S 96-101 | Elbing .. | 1900 | 206.8 | 23 | .. | 2 | 350 | 6,000 | 27.5 | 5 6 prs. | 3 | .. | .. |
| G 102-107 | Kiel (Germania) | Bldg. | 206.8 | 23 | .. | 2 | 350 | 6,000 | 27.5 | 3 3-pr. Q.F. | 3 | .. | .. |
| Taku * | Elbing .. | 1898 | 193.7 | 21.0 | .. | 2 | 280 | 6,000 | 35 | 6.3 prs. | 2 | .. | 67 |
| FIRST CLASS— | | | | | | | | | | | | | |
| S 1—S 65 (64 boats)† | Elbing .. | 1893-92 | 121 (15½) | 15.7 15.6 | 6.7 6.7 | .. | 85-88 (1,600) | 900 (1,600) | 20-22½ | 2 1-pr. revs. | 2 | .. | 17 |
| S 66—S 73 (10 boats) | Elbing .. | 1893 | 154.3 | 16.4 | .. | 2 | 110 (145) | 1,600 | .. | .. | 3 | .. | .. |
| S 74—S 81 (8 boats) | Elbing .. | 1894 | 154.3 | 16.4 | .. | 2 | 125 | 1,900 | 25 | .. | 3 | .. | .. |
| S 82—S 87 (6 boats) | Elbing .. | 1897-8 | 158.2 | 16.9 | 9.0 | 2 | 140 | 2,300 | 26 | 2 1-pr. revs. | 3 | .. | 32 |
| G 88—G 89 (2 boats) | Kiel (Germania) | 1898 | 154.3 | 16.5 | .. | .. | 160 | 2,500 | 26 | 2 mach. | 3 | 22 | .. |
| G 90—G 95 (6 boats) | Elbing .. | 1899 | 157.5 | 16.9 | 8.9 | 2 | 155 | .. | 25 | 1 Q.F., 1 m. | 3 | .. | 30 |
| V 1, V 2 (2 boats) | Stettin .. | 1884 | 124.6 | .. | .. | .. | 75 | 550 | .. | .. | 2 | .. | .. |
| V 3, V 4 (2 boats) | Stettin .. | 1884 | .. | .. | .. | .. | 90 | 1,000 | .. | .. | 2 | .. | .. |
| V 5—V 10 (6 boats) | Stettin .. | 1884 | .. | .. | .. | .. | .. | .. | 19 | .. | 2 | .. | .. |
| G 1, | Gaarden .. | 1885 | 124.6 | 15.7 | 6.6 | .. | 88 | 1,000 | 19 | 2 1-pr. revs. | 2 | 17 | .. |
| Y 1, | Poplar .. | 1884 | 120 | 12.5 | 5.5 | 1 | 65 | 650 | 19 | 2 1-pr. revs. | 2 | 15 | 25 |
| T 1, T 2 (2 boats) | Chiswick, &c. | 1884 | 117.7 | 12.5 | 6.2 | 1 | 80 | .. | 20 | 2 1-pr. revs. | 2 | 15 | 22 |
| H 1, | Kiel (Howaldt) | 1886 | .. | .. | .. | .. | 80 | 1,000 | 20.2 | 2 1-pr. revs. | 2 | .. | .. |
| K 1, | Kiel (Dockyard) | 1887 | 118.1 | 13.4 | 5.9 | .. | 85 | 1,000 | 22 | 2 1-pr. revs. | .. | 18 | .. |
| SECOND CLASS— | | | | | | | | | | | | | |
| 3 boats | .. | 1893 | .. | .. | .. | .. | 88 | .. | 22 | .. | .. | .. | .. |
| 2 boats | .. | 1893 | .. | .. | .. | .. | 90 | .. | 3 | .. | .. | .. | .. |
| VEDETTE BOATS— | | | | | | | | | | | | | |
| 13 boats | .. | .. | .. | .. | .. | .. | 13.5 | .. | 18 | .. | .. | .. | .. |
| 2 boats | .. | .. | .. | .. | .. | .. | .. | .. | 16 | .. | .. | .. | .. |
| 1 boat | Chiswick .. | 1884 | 63 | 8 | 4.3 | 1 | .. | .. | 15.5 | 1 mach. | 2 | .. | .. |

* Ex Hai Ching, captured from the Chinese at Taku, 1900. † S 41 lost 1895.

The Estimates of 1901 provide the initial expenditure for the building of a division of torpedo boats.

Greece.

| Name or Number. | Where Built. | Launched. | Dimensions. | | | Number of Screws. | Displacement. | Indicated Horse-Power. | Maximum Trial Speed. | Armament. | Torpedo Tubes. | Complement. | Coal Capacity. |
|------------------|--------------|-----------|-------------|-------|----------|-------------------|---------------|------------------------|----------------------|---------------|----------------|-------------|----------------|
| | | | Length. | Beam. | Draught. | | | | | | | | |
| 6 boats | Stettin .. | 1885 | 128 | 15.3 | 5.4 | 1 | 85 | 1,050 | 19 | 4 1-pr. revs. | .. | 20 | Tons. |
| 6 boats | Poplar .. | 1881 | 100 | 12 | 4.2 | 1 | 48 | 600 | 19 | 2 1-pr. revs. | 2 | 12 | 9 |
| 4 boats | La Seyne .. | 1880 | 72 | 13 | 5.5 | 1 | 52 | 225 | .. | .. | .. | .. | 10 |
| 5 boats | La Seyne .. | 1881 | 89 | 11 | 3.1 | 1 | 35 | 500 | 17.5 | .. | .. | .. | 5 |
| 2 boats | Poplar .. | 1878 | 75 | 10.8 | 2.5 | .. | 18 | 295 | 16.2 | .. | .. | .. | 1.5 |
| 8 boats | .. | .. | .. | .. | .. | .. | 21 | .. | 16 | .. | .. | .. | .. |
| 20 boats | Various .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | sp. | .. | .. |

Italy.

| Name or Number. | Where Built. | Launched. | Dimensions. | | | Number of Screws. | Displacement. | Indicated Horse-Power. | Maximum Trial Speed. | Armament. | Torpedo Tubes. | Complement. | Coal Capacity. | |
|---|------------------------------|-----------|-------------|-------|----------|-------------------|---------------|------------------------|----------------------|--|----------------|-------------|----------------|--|
| | | | Length. | Beam. | Draught. | | | | | | | | | |
| DESTROYERS— | | | | | | | | | | | | | | |
| Fulmine | Sestri (Odero) | 1898 | 200 | 20.4 | 5.4 | 2 | 298 | 4,800 | 28 | { 1 12-pr. 3 6-pr. Q.F. } | 3 | 43 | 60 | |
| Lampo | { Elbing (Schichau) } | 1899 | 196.8 | 21.3 | 5.8 | 2 | 320 | 6,000 | 30 | { 1 12-pr. Q.F., 5 6-pr. } | 2 | 53 | 60 | |
| Freccia | | 1901 | | | | | | | | | | | | |
| Dardo | { Naples (Pattison) } | Bldg. | 208 | 19.4 | 6.3 | 2 | 330 | 6,000 | 30 | { 1 12-pr. Q.F., 3 6-pr. } | 2 | 53 | 60 | |
| Strale | | | | | | | | | | | | | | |
| Euro | | | | | | | | | | | | | | |
| Ostro | | | | | | | | | | | | | | |
| Nembo | | | | | | | | | | | | | | |
| Turbine | | | | | | | | | | | | | | |
| Aquilone | | | | | | | | | | | | | | |
| Borea | | | | | | | | | | | | | | |
| Meteoro | | | | | | | | | | | | | | |
| Tuono | | | | | | | | | | | | | | |
| FIRST CLASS— | | | | | | | | | | | | | | |
| 5 boat- { Aquila .. Sparviero .. Nibbio .. Avvoltoio .. Falco .. } | Elbing .. | 1888 | 152 | 17.2 | 7.9 | 2 | 130 | 2,200 | 26.6 | { 2 3-pr. Q.F., 1 1-pr. Q.F., 1 1-pr. rev. } | 3 | 24 | 40 | |
| Nos. 78, 79 (2 boats) | Venice .. | 1887 | 135 | 14 | 5.3 | 2 | 110 | 1,600 | 24 | { 1 1-pr. Q.F., 1 1-pr. rev. } | 3 | 20 | 24 | |
| Pellicano | Sestri (Odero) | 1899 | 157.4 | 19 | 14.8 | 2 | 147 | 2,700 | 25 | 2 3-prs. | 2 | 28 | 24 | |
| Condore | Sestri (Ansaldo) | 1898 | 154.3 | 16.8 | 6.9 | 2 | 136 | 2,500 | 27 | 2 3-prs. | 2 | 27 | 16 | |
| SECOND CLASS— | | | | | | | | | | | | | | |
| Nos. 76, 77 (2 boats) | Poplar.. .. | 1887 | 140 | 14 | 5 | 2 | 100 | 1,600 | 25 | { 2 3-pr. Q.F., 1 1-pr. rev. } | 4 | 20 | 24 | |
| Nos. 78, 79 (2 boats) | Venice .. | 1896 | .. | .. | .. | .. | .. | .. | .. | .. | 3 | 20 | 24 | |
| Nos. 80-104, 106-111 (31 boats) | { Elbing and Italy .. } | 1887-88 | 127.7 | 15.6 | 6.8 | 1 | 85 | 1,000 | 22.5 | 2 1-pr. Q.F. | 2 | 17 | 17 | |
| Nos. 112-116, 118-135 (23 boats) | { Elbing and Italy .. } | 1889-92 | 127.7 | 15.6 | 6.8 | 1 | 85 | { 1,100 1,200 } | 23 | .. | 2 | 17 | 17 | |
| No. 117 | | 1895 | 131.2 | 16.4 | .. | 1 | 85 | 1,000 | .. | 2 1 pr. Q.F. | 2 | 17 | 17 | |
| Nos. 136-146 (11 boats) | Italy .. | 1893-94 | 131.2 | 16.4 | .. | 1 | 85 | 1,000 | 22 | 2 1-pr. Q.F. | 2 | 17 | 17 | |
| Nos. 147-153 (7 boats) | Italy .. | 1894-5 | 131.2 | 16.4 | .. | 1 | 85 | 1,000 | 22 | 2 1-pr. Q.F. | 2 | 17 | 17 | |
| Nos. 60-75 (15 boats) | { Elbing and Italy .. } | 1885-87 | 127.7 | 15.6 | 6.8 | 1 | 65 | 1,000 | 22.5 | 2 1-pr. Q.F. | 2 | 17 | 17 | |
| THIRD CLASS— | | | | | | | | | | | | | | |
| No. 22 | Poplar.. .. | 1882 | 100 | 12.5 | 5.5 | 1 | 40 | 620 | 22 | 1 1-pr. rev. | 2 | 11 | 7 | |
| No. 25 | Poplar.. .. | 1882 | 100 | 12.5 | 5.5 | 1 | 40 | 620 | 22 | 1 1-pr. rev. | 2 | 11 | 7 | |
| Nos. 26-59 (34 boats) | { Chiswick and Italy .. } | 1882-86 | 100 | 11.7 | 5.3 | 1 | 34 | 430 | 21.3 | 1 1-pr. rev. | 2 | 11 | 7 | |
| Nos. 23, 24 (2 boats) | Chiswick .. | 1881 | 92 | 10.5 | 4.9 | 1 | 33 | 470 | 21.8 | 1 1-pr. rev. | 2 | 11 | 7 | |
| FOURTH CLASS. | | | | | | | | | | | | | | |
| No. 1 | Chiswick .. | 1878 | 78.8 | 9.8 | 3 | 1 | 19 | 173 | 19 | .. | 2 | 10 | | |
| No. 2 | Poplar.. .. | 1879 | 86 | 11 | 4.5 | 1 | 25 | 420 | 21 | 1 1-pr. rev. | 2 | 10 | | |
| No. 18 | Chiswick .. | 1883 | 62.4 | 7.5 | 2.5 | 1 | 10 | 170 | 17 | 1 1-pr. rev. | 2 | 10 | | |
| No. 11 | Leghorn .. | 1883 | 75.6 | 9.9 | 3.8 | 1 | 31 | 250 | 19.2 | .. | 2 | 10 | | |
| SUBMARINE— | | | | | | | | | | | | | | |
| Delfino | Spezia | 1895 | 49.0 | .. | .. | .. | 95 107 | .. | 10.0 | 1 1-pr. rev. | 2 | 8 | | |

The new Italian destroyers have Thornycroft water-tube boilers.

Japan.

| Name or Number. | Where Built. | Launched. | Dimensions. | | | Number of Screws. | Displacement. | Indicated Horse-Power. | Maximum Trial Speed. | Armament. | Torpedo Tubes. | Complement. | Coal Capacity. |
|----------------------|----------------|-----------|-------------|-------|----------|-------------------|---------------|------------------------|--------------------------|---------------------------|----------------|-------------|----------------|
| | | | Length. | Beam. | Draught. | | | | | | | | |
| DESTROYERS— | | | Feet. | Feet. | Feet. | | Tons. | | Knots. | | | | Tons. |
| Murakumo | Chiswick .. | 1898 | 210·0 | 19·5 | 7·2 | 2 | 285 | 5,800 | { 30 to 30·55 } | { 1 12-pr., 5 6-prs. } | 2 | 54 | 80 |
| Shinonome | Chiswick .. | 1898 | | | | | | | | | | | |
| Yugiri | Chiswick .. | 1898 | | | | | | | | | | | |
| Shiranui | Chiswick .. | 1899 | | | | | | | | | | | |
| Kagerou | Chiswick .. | 1899 | | | | | | | | | | | |
| Usugumo | Chiswick .. | 1900 | 220·0 | 20·6 | 8·9 | 2 | 400 | 6,000 | { 31·03 to 31·38 } | { 1 12-pr., 5 6-prs. } | 2 | 55 | 95 |
| 2 unnamed | Chiswick Bldg. | 1898 | | | | | | | | | | | |
| Ikaduchi | Poplar .. | 1898 | | | | | | | | | | | |
| Inadsuma | Poplar .. | 1899 | | | | | | | | | | | |
| Akebono | Poplar .. | 1899 | | | | | | | | | | | |
| Sazanami | Poplar .. | 1899 | 220·3 | 20·6 | 7·6 | 2 | 307 | 5,770 | 31·62 | { 1 12-pr., 5 6-prs. } | 2 | .. | 90 |
| Oboro | Poplar .. | 1899 | | | | | | | | | | | |
| Niji | Poplar .. | 1899 | | | | | | | | | | | |
| 2 unnamed | Poplar .. | Bldg. | | | | | | | | | | | |
| FIRST CLASS— | Poplar .. | 1886 | 170 | 19·6 | 5 | 1 | 190 | 1,400 | 19 | 4 mach. | 6 | .. | .. |
| | | 1889 | 114·7 | 10·6 | 6 | 2 | 56 | 525 | 20 | 2 1-prs. | .. | 16 | 50 |
| | | 1889 | 114·7 | 10·6 | 6 | 1 | 56 | 525 | 20 | 2 1-prs. | .. | 16 | .. |
| | | 1879 | 100 | 12·5 | .. | 1 | 40 | 620 | 20 | .. | .. | .. | .. |
| | | 1891 | 118 | 13·1 | 6·9 | 1 | 80 | 1,200 | 23 | 2 1-prs. | 2 | 21 | 10 |
| | | Bldg. | .. | .. | .. | 1 | .. | .. | .. | .. | .. | .. | .. |
| | | 1898 | 121·4 | 13·6 | 8·6 | 1 | 86 | 1,800 | 27 | 1 3-pr. | 2 | .. | 10 |
| | | 1898 | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. |
| | | 1899 | 147·7 | 16·0 | 8·2 | 2 | 150 | 4,200 | 30 | 3 3-prs. | 3 | .. | 13 |
| | | 1899 | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. |
| SECOND CLASS— | Elbing .. | 1891-9 | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. |

* No. 16 lost off the Pescadores, 1895.

The ten years' programme includes 23 first-class, 31 second-class, and 35 third-class torpedo-boats, and a 6750-ton torpedo transport.

Mexico.

Mexico has five first-class boats building or projected.

Netherlands.

| Name or Number. | Where Built. | Launched. | Dimensions. | | | Number of Screws. | Displacement. | Indicated Horse-Power. | Maximum Trial Speed. | Armament. | Torpedo Tubes. | Complement. | Coal Capacity. |
|-------------------------------|----------------|-----------|--------------|-------|----------|-------------------|---------------|------------------------|----------------------|-----------|----------------|-------------|----------------|
| | | | Length. | Beam. | Draught. | | | | | | | | |
| FIRST CLASS— | | | Feet. | Feet. | Feet. | | Tons. | | Knots. | | | | Tons. |
| Ardjoeno | Poplar .. | 1886 | 125 | 13 | 6 | 1 | 83 | 80 | 21 | 2 1-prs. | 2 | 16 | 10 |
| Batok | Amsterdam | 1887 | 125 | 13 | 6·9 | 1 | 83 | 725 | 20 | 2 1-prs. | 2 | 16 | 10 |
| Cycloop | Amsterdam | 1887 | 125 | 13 | 6·9 | 1 | 83 | 680 | 20 | 2 1-prs. | 2 | 16 | 10 |
| Dempo | Amsterdam | 1887 | 125 | 13 | 6·9 | 1 | 83 | 760 | 20 | 2 1-prs. | 2 | 16 | 10 |
| Empong | Poplar .. | 1888 | 128 | 13 | 6·2 | 1 | 91 | 1,100 | 24·1 | 2 1-prs. | 3 | 16 | 15 |
| Etna | Poplar .. | 1882 | 100 | 12·6 | 5·6 | 1 | 45 | 550 | 21·5 | 2 1-prs. | 2 | 16 | 7 |
| Foka | Amsterdam | 1888 | 123 | 13 | 6·2 | 1 | 90 | 1,000 | 22·1 | 2 1-prs. | 3 | .. | .. |
| Goentoe | Amsterdam | 1888 | 123 | 13 | 6·2 | 1 | 90 | 950 | 21 | 2 1-prs. | 3 | .. | .. |
| Hubang | Amsterdam | 1888 | 123 | 13 | 6·2 | 1 | 90 | 930 | 21·7 | 2 1-prs. | 3 | .. | .. |
| Hekla | Poplar .. | 1882 | 100 | 12·6 | 5·6 | 1 | 45 | 550 | 21·5 | 2 1-prs. | 2 | 16 | 7 |
| Idjen | Amsterdam | 1889 | 123 | 13 | 6·2 | 1 | 90 | 840 | 20·6 | 2 1-prs. | 3 | .. | .. |
| Krakatau | Amsterdam | 1889 | 123 | 13 | 6·2 | 1 | 90 | 750 | 19·1 | 2 1-prs. | 3 | .. | .. |
| Lamongan | Amsterdam | 1890 | 104·5 | 13·3 | 5·2 | 1 | 50 | 790 | 20·7 | 2 1-prs. | 2 | .. | .. |
| Makjan | Amsterdam | 1890 | 104·5 | 13·3 | 5·2 | 1 | 50 | 790 | 20·7 | 2 1-prs. | 2 | .. | .. |
| Nobo | Amsterdam | 1890 | 104·5 | 13·3 | 5·2 | 1 | 50 | 790 | 20·7 | 2 1-prs. | 2 | .. | .. |
| Scylla | Poplar .. | 1900 | 130 | 13·6 | 6·0 | 1 | 77 | 1,200 | 24·3 | 2 1-prs. | 3 | 18 | 20 |
| Hydra | Poplar .. | 1900 | 130 | 13·6 | 6·0 | 1 | 77 | 1,200 | 24·4 | 2 1-prs. | 3 | 18 | 20 |
| Ophir | Poplar .. | 1901 | 152·6 | 15·3 | 7·8 | 1 | 130 | 18,000 | 23 | 2 3-prs. | 2 | 25 | 32 |
| Pangrango | Poplar .. | 1901 | 152·6 | 15·3 | 7·8 | 1 | 130 | 18,000 | 23 | 2 3-prs. | 2 | 25 | 32 |
| Rindjani | Poplar .. | Bldg. | 152·6 | 15·3 | 7·8 | 1 | 130 | 18,000 | 23 | 2 3-prs. | 2 | 25 | 32 |
| SECOND CLASS— | | | | | | | | | | | | | |
| Nos. 1, 2, 4-20 (19 boats) | Chiswick, etc. | 1878-86 | { 76 79 } | 10·3 | 5·2 | 1 | 29 | 250 | 18 | 1 1-pr. | 2 sp | .. | 3 |
| Nos. 3, 21, 2 (3 boats) | .. | 1890 | 83·6 | 10·5 | 5·1 | 1 | 37 | 460 | 17·9 | 1 1-pr. | 1 | .. | 2 |
| 1 boat | East Cowes | 1883 | 45·5 | 9·7 | .. | 1 | .. | .. | 12 | 1 mach. | 1 | .. | .. |
| INDIAN FLEET— | | | | | | | | | | | | | |
| Cerberus | Flushing .. | 1888 | 125 | 13 | 6·9 | 1 | 83 | 912 | 21·2 | 2-1 prs. | .. | 16 | .. |
| 1 boat | .. | 1891 | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. |
| 3 boats | .. | 1893-94 | 125 | .. | .. | .. | 83 | .. | 21·5 | .. | 2 | .. | .. |

All the Poplar destroyers have Yarrow Water-tube boilers.

Norway.

| Name or Number. | Where Built. | Launched. | Dimensions. | | | Number of Screws. | Displacement. | Indicated Horse-Power. | Maximum Trial Speed. | Armament. | Torpedo Tubes. | Complement. | Coal Capacity. |
|-------------------------------------|----------------|-----------|-------------|-----------|-----------|-------------------|---------------|------------------------|----------------------|----------------|----------------|-------------|----------------|
| | | | Length. | Beam. | Draught. | | | | | | | | |
| FIRST CLASS— | | | | | | | | | | | | | |
| Lyn | .. | 1882 | Feet. 94.2 | Feet. 9.7 | Feet. 2.5 | 1 | Tons. 36 | 430 | Knots. 18 | .. | 1 | .. | Tons. 3 |
| Od | .. | 1882 | 97.5 | 11 | 5.6 | 1 | 40 | 450 | 18 | .. | 1 | .. | 3 |
| Orm, Otter (2 boats) | .. | 1887 | 108.2 | 12.2 | 5.6 | 1 | 40 | 500 | 20 | .. | 2 | .. | 3 |
| Pil, Rask (2 boats) .. | .. | 1887 | 101.7 | 11.8 | 5.6 | 1 | 40 | 500 | 20 | .. | 2 | .. | 3 |
| Snar | .. | 1887 | 104.9 | 11.8 | 5.6 | 1 | 40 | 500 | 20 | .. | 2 | .. | 3 |
| Springer | .. | 1887 | 97.5 | 11.6 | 5.6 | 1 | 40 | 450 | 19 | .. | 2 | .. | 3 |
| Varg (8), Raket (9) | Christiania .. | 1894 | 111.5 | 12.4 | .. | 1 | 43 | .. | .. | .. | 2 | .. | .. |
| Hval, Delfin, Hal (3 boats) | Elbing .. | 1896 | 128.0 | 15.0 | .. | 1 | 84 | 1,100 | 24.5 | 2 1.4-in. Q.F. | 2 | .. | .. |
| Storm, Ovrand, Trods | Christiania .. | Bldg. | 128.0 | 15.0 | .. | 1 | 84 | 1,100 | 23 | 2 1.4-in. Q.F. | 2 | .. | .. |
| SECOND CLASS— | | | | | | | | | | | | | |
| Rasp | Chiswick .. | 1873 | 5.4 | 7.5 | 3.9 | 1 | 16 | .. | 18 | .. | 2 | .. | .. |
| Ulven | .. | 1878 | 56 | .. | .. | 1 | 16 | .. | 9 | .. | sp. | .. | .. |
| 2 boats | .. | .. | .. | .. | .. | .. | 20 | .. | 12 | .. | .. | .. | .. |

Portugal.

| Name or Number. | Where Built. | Launched. | Dimensions. | | | Number of Screws. | Displacement. | Indicated Horse-Power. | Maximum Trial Speed. | Armament. | Torpedo Tubes. | Complement. | Coal Capacity. |
|------------------------|--------------|-----------|-------------|-------|----------|-------------------|---------------|------------------------|----------------------|-----------|----------------|-------------|----------------|
| | | | Length. | Beam. | Draught. | | | | | | | | |
| | | | Feet. | Feet. | Feet. | | Tons. | | Knots. | | | | Tons. |
| 5 boats (5-9) | Elbing .. | 1890-92 | | | | | | | | | | | |
| Espadarte (1) | Poplar.. | 1881 | 8 | 11 | 5 | 1 | 31 | 450 | 19.7 | 2 mach. | 2 | 10 | 10 |
| Nos. 2, 3, 4 (3 boats) | Poplar.. | 1886 | 120 | 12.5 | 5.5 | 1 | 60 | 700 | 20 | 2 mach. | 2 | 16 | 18 |
| Fulminante | Blackwall .. | 1880 | 75 | 15 | 2.6 | 2 | 40 | 150 | 11.5 | 2 mach. | .. | .. | 8 |
| 1 boat | | | .. | .. | .. | .. | 25 | | | | | | |
| Mineiro | Lisbon .. | 1893 | .. | .. | .. | .. | .. | .. | 12 | | | | |
| SUBMARINE— | | | | | | | | | | | | | |
| Plongeur | .. | 1892 | 72.1 | 11.5 | .. | .. | .. | .. | 6 | | | | |

Roumania.

| Name or Number. | Where Built. | Launched | Dimensions. | | | Number of Screws. | Displacement. | Indicated Horse-Power. | Maximum Trial Speed. | Armament. | Torpedo Tubes. | Complement. | Coal Capacity. |
|------------------|--------------|----------|-------------|------------|-----------|-------------------|---------------|------------------------|----------------------|--------------|----------------|-------------|----------------|
| | | | Length. | Beam. | Draught. | | | | | | | | |
| FIRST CLASS— | | | | | | | | | | | | | |
| Naluka | Havre | 1888 | Feet. 120·7 | Feet. 11·3 | Feet. 6·9 | 1 | Tons. 55 | 500 | Knots. 21 | 1 1-pr. rev | 2 | .. | Tons. 12 |
| Sborul | Havre | 1888 | 120·7 | 11·3 | 6·9 | 1 | .. | 500 | 21 | 1 1-pr. rev. | 2 | .. | 12 |
| Smeul | Havre | 1888 | 120·7 | 11·3 | 6·9 | 1 | .. | 500 | 21 | 1 1-pr. rev. | 2 | .. | 12 |
| SECOND CLASS— | | | | | | | | | | | | | |
| Szimul | Poplar | 1882 | 63 | 8 | 3 | 1 | 15 | 150 | 16·5 | .. | .. | 8 | 1 |
| Vulturul | Poplar | 1882 | 63 | 8 | 3 | 1 | 15 | 150 | 16·5 | .. | .. | 8 | 1 |

Russia.

| Name or Number. | Where Built. | Launched. | Dimensions. | | | Number of Screws. | Displacement. | Indicated Horse-Power. | Maximum Trial Speed. | Armament. | Torpedo Tubes. | Complement. | Coal Capacity. |
|--|--------------------------|-----------|-------------|------------|-----------|-------------------|---------------|------------------------|----------------------|-----------------|----------------|-------------|----------------|
| | | | Length. | Beam. | Draught. | | | | | | | | |
| BALTIC SEA. | | | | | | | | | | | | | |
| DESTROYER— | | | | | | | | | | | | | |
| Sokol | Poplar | 1895 | Feet. 190 | Feet. 18'6 | Feet. 7'0 | 2 | Tons. 240 | 4,400 | Knots. 29.7 | 1 12-pr. 3 | 2 | | Tons. |
| Krechet, Korshun (2 boats) | Abo | 1898 | 198 10 | 18'6 | 7'0 | 2 | 240 | 3,800 | 27.5 | 6-pr. | | | |
| Iastreb | Ishora | 1898 | 196'9 | 18'4 | 11'5 | 1 | 240 | 3,800 | 27 | 1 2'8-in. | 2 | | |
| Nyrok | Ishora | 1898 | 196'9 | 18'4 | 11'5 | 1 | 240 | 3,800 | 27 | 3 1'8-in. | 2 | | |
| Berkout | Ishora | 1898 | 196'9 | 18'4 | 11'5 | 1 | 240 | 3,800 | 27 | 3 1'8-in. | 2 | | |
| Condor | Ishora | 1898 | 196'9 | 18'4 | 11'5 | 1 | 240 | 3,800 | 27 | 3 1'8-in. | 2 | | |
| 5 boats | Ishora | Bldg. | | | | | | | | | | | |
| Kit, Skat, Delphin, Kassatka (4 boats) | Elbing | 1899 | 196'9 | 18'4 | 11'5 | 1 | 350 | 6,000 | 27 | 1 12-pr, 5 3-pr | 2 | | |
| Ossetr, Kephall, Losos | Havre (F & C.) | 19 0-1 | 186'0 | 20'8 | 10'3 | 2 | 300 | 5,000 | 27 | 1 12-pr, 5 3-pr | 2 | 80 | |
| Forel, Sterliad | (Havre (Nor- mand)) | 1900-1 | 186'0 | 20'8 | 10'3 | 2 | 300 | 5,000 | 27 | 1 12-pr, 5 3-pr | 2 | 80 | |
| Gagara, Voron, Fillin, Sova | Nevsky | 1899 | .. | .. | .. | 1 | 240 | .. | 29 | 1 12-pr, 5 3-pr | .. | 55 | 53 |
| Som | Birkenhead | 1899 | 213 | 21'5 | 12'9 | 1 | 370 | 6,000 | 28 | | | | |
| Lebed, Pelikan, Pavlin, Fasan .. | Creighton .. | | | | | | | | | | | | |
| Drozd, Diatel, Baklan, Bekass, Gorlitz, Gratch, Kulik, Perepel, Skvoretz, Strige, Shchegol | Nevsky and Ishora .. | Bldg. | | | | | | | | | | | |
| †Taku | Elbing | 1898 | 193'7 | 21'0 | .. | 2 | 280 | 6,000 | 35 | 6 3-pr. Q.F. | 2 | 67 | |
| FIRST CLASS— | | | | | | | | | | | | | |
| Aspen | Ishora | 1895 | 127'9 | 15'7 | 6'9 | 1 | 98 | 1,250 | 21 | .. | 2 | 17 | |
| Abo | Elbing | 1886 | 128 | 15'7 | 7'5 | 1 | 87 | 900 | 22.2 | 4 1-pr. revs. | 2 | 13 | 17 |
| Bjerke | Putiloff .. | 1890 | 136'5 | 13 | 7'8 | .. | 81 | 1,100 | 21 | .. | | | |
| Dago | Abo | 1891 | 152 | 13 | 8'3 | .. | 100 | 1,000 | 19 | .. | | | |
| Domeness | Putiloff .. | 1895 | 127'9 | 15'7 | 6'9 | 1 | 98 | 1,250 | 21 | .. | 2 | 17 | |
| Eckness | Abo | 1890 | 136'5 | 13 | 7'8 | .. | 81 | 1,100 | 21 | .. | | | |
| Hapsal | Putiloff .. | 1891 | 126 | 13 | 8'5 | 1 | 81 | 1,100 | 21 | 2 1-pr. revs. | 2 | 13 | |
| Hogland | Ishora | 1894 | 128 | 16 | 6'9 | 1 | 85 | 1,200 | 22 | 2 1-prs. | 2 | 13 | 17 |
| Kotka | Abo | 1891 | 152 | 13 | 8'3 | .. | 100 | 1,000 | 19 | .. | | | |
| Kotlinj | St. Petersburg | 1885 | 124'2 | 12'9 | 5'9 | 2 | 67 | 500 | 16.5 | 2 1-pr. revs. | 2 | 16 | 15 |
| Kronschlot | Ishora | 1891 | 152 | 13 | 8'3 | .. | 100 | 1,000 | 19 | .. | | | |
| Lachta | Elbing | 1886 | 128 | 15'7 | 7'5 | 1 | 87 | 900 | 20 | 4 1-pr. revs. | 2 | 13 | 17 |
| Libawa | Elbing | 1886 | 128 | 15'7 | 7'5 | 1 | 87 | 1,000 | 22 | 4 1-pr. revs. | 2 | 13 | 17 |
| Louga | Elbing | 1886 | 128 | 15'7 | 7'5 | 1 | 87 | 900 | 20 | 4 1-pr. revs. | 2 | 13 | 17 |
| Moonsund | Putiloff .. | 1891 | 126 | 13 | 8'5 | 1 | 81 | 1,100 | 21 | 2 1-pr. revs. | 2 | 13 | |
| Nargen | Ishora | 1894 | 128 | 16 | 6'9 | 1 | 85 | 1,200 | 22 | 2 1-prs. | 2 | 13 | 17 |
| Narwa | Elbing | 1886 | 128 | 15'7 | 7'5 | 1 | 87 | 900 | 20 | 4 1-pr. revs. | 2 | 13 | 17 |
| Nyrok | Ishora | 1898 | | | | | | | | | | | |
| Pernoff | Normand .. | 1892 | 137'9 | 14'9 | 6'8 | 2 | 120 | 1,600 | 25 | 2 3-prs. | 2 | 26 | 16 |
| Rochensalm | Putiloff .. | 1890 | 136'5 | 13 | 7'8 | .. | 81 | 1,100 | 21 | .. | | | |
| Seskar | Ishora | 1891 | 152 | 13 | 8'3 | .. | 100 | 1,000 | 19 | .. | | | |
| Sestoretzsk | Normand .. | 1894 | 118 | 13'2 | 8'6 | 1 | 80 | 1,300 | 24 | 2 1-prs. | 2 | 21 | 10 |
| Tosna | Putiloff .. | 1893 | 127'9 | 15'7 | 6'9 | 1 | 98 | 1,250 | 21 | .. | 2 | 13 | 17 |
| Transund | Ishora | 1895 | 127'9 | 15'7 | 6'9 | 1 | 98 | 1,250 | 21 | .. | 2 | 17 | |
| Viborg | Clydebank .. | 1886 | 144'5 | 17 | 8'1 | 2 | 126 | 1,400 | 20 | 2 3-pr. revs. | 3 | 24 | 45* |
| Vindawa | Elbing | 1886 | 128 | 15'7 | 7'5 | 1 | 87 | 900 | 21 | 4 1-pr. revs. | 2 | 13 | 17 |
| Vzriw | St. Petersburg | 1877 | 118 | 16 | 10'9 | 1 | 160 | 800 | 14.5 | 4 Q.F. | 1 | 18 | 16 |
| 8 boats | St. Petersburg | 1894 | 128 | 16 | 6'9 | 1 | 85 | 1,200 | 22 | 2 1-prs. | 2 | 13 | 17 |
| 2 boats | Putiloff .. | 1894 | 138 | 14'7 | 9'9 | 2 | 118 | .. | 25 | 2 mach. | 2 | 26 | |
| 2 boats | St. Petersburg | 1896 | 128 | 16 | 6'9 | 2 | 85 | 1,200 | 22 | 2 1-prs. | 2 | 13 | 17 |
| 6 boats | St. Petersburg | 1897 | 138 | 14'7 | 9'9 | 2 | 120 | .. | 25 | .. | 2 | 26 | |
| 8 boats | St. Petersburg | 1898 | .. | .. | .. | .. | 118 | .. | .. | .. | | | |
| 3 boats | Nicolajeff .. | 1898 | .. | .. | .. | .. | .. | .. | .. | .. | | | |
| 5 boats | Nicolajeff .. | Pro. | .. | .. | .. | .. | 150 | .. | .. | .. | | | |
| 5 boats | Abo | Pro. | .. | .. | .. | .. | 150 | .. | .. | .. | | | |
| SECOND CLASS— | | | | | | | | | | | | | |
| 21 boats (Galka class) | { Elbing and Russia } | 1880 &c. | 74'7 | 8'9 | 5 | 1 | 30 | 220 | 16 | .. | 2 | 14 | 3 |
| 21 boats (Woron class) | { Elbing and Russia } | .. | 66 | 11'1 | .. | 1 | .. | 260 | 17 | .. | | | |
| 1 boat | Poplar | 1888 | 60 | 8'5 | 3 | 1 | 16 | 240 | 17.5 | .. | 2 | .. | 1 |
| BLACK SEA. | | | | | | | | | | | | | |
| FIRST CLASS— | | | | | | | | | | | | | |
| A. B. C. (3 boats) .. | Nicolajeff .. | 1893 | 126 | .. | .. | .. | 81 | .. | 21 | .. | | | |
| Adler | Elbing | 1890 | 152'0 | 17'2 | 7'9 | 2 | 130 | 2,200 | 27.4 | 2 1-prs. | 3 | 24 | 40 |
| Anakria | Elbing | 1890 | 128'0 | 16 | 6'9 | 1 | 85 | 1,200 | 22 | 2 1-prs. | 2 | 13 | 17 |
| Anapa | Odessa | 1891 | 126 | 13 | 8'5 | 1 | 81 | 1,100 | 21 | 2 1-pr. revs. | 2 | 13 | |
| Aitodorj | Odessa | 1891 | 126 | 13 | 8'5 | 1 | 81 | 1,100 | 21 | 2 1-pr. revs. | 2 | 13 | |
| Batoum | Poplar | 1880 | 100 | 12'5 | 5'5 | 1 | 40 | 500 | 22 | 2 1-pr. revs. | 2 | 12 | 9 |
| D. E. (2 boats) | Sebastopol .. | 1893 | 128 | .. | .. | .. | 85 | .. | 22 | .. | | | |
| Gagri | Claparède .. | 1883 | 120'6 | 13'3 | 7 | 1 | 78 | 600 | 18 | 2 1-pr. revs. | 2 | 13 | 12 |
| Gelendshik | La Seyne .. | 1883 | 122'7 | 12'4 | 6'2 | 1 | 73 | 560 | 18 | 2 1-pr. revs. | 2 | 13 | 11 |
| Ismail | Nicolajeff .. | 1886 | 128 | 15'7 | 7'5 | 1 | 87 | 900 | 20 | 2 1-pr. revs. | 2 | 13 | 17 |
| Itzvar | Odessa | 1891 | .. | .. | .. | .. | 81 | 1,100 | 21 | .. | | | |
| Kodor | Elbing | 1886 | 128 | 15'7 | 7'5 | 1 | 87 | 900 | 21 | 4 1-pr. revs. | 2 | 13 | 17 |

* Has received liquid fuel apparatus. † Of the Pernoff type, building on the Neva. ‡ Captured from the Chinese at Taku, 1900

Russia—continued.

| Name or Number. | Where Built. | Launched. | Dimensions. | | | Number of Screws. | Displacement. | Indicated Horse-Power. | Maximum Trial Speed. | Armament. | Torpedo Tubes. | Complement. | Coal Capacity. |
|------------------------------|----------------|-----------|-------------|-------|----------|-------------------|---------------|------------------------|----------------------|---------------|----------------|-------------|----------------|
| | | | Length. | Beam. | Draught. | | | | | | | | |
| | | | Feet. | Feet. | Feet. | | Tons. | | Knots. | | | | Tons. |
| BLACK SEA—contd. | | | | | | | | | | | | | |
| FIRST CLASS—contd. | | | | | | | | | | | | | |
| Kilia | Elbing .. | 1886 | 128 | 15.7 | 7.5 | 1 | 87 | 900 | 22 | 4 1-pr. revs. | 2 | 13 | 17 |
| Novorossisk | Elbing .. | 1886 | 128 | 15.7 | 7.5 | 1 | 87 | 900 | 22 | 4 1-pr. revs. | 2 | 13 | 17 |
| Poti | Normand .. | 1883 | 124.8 | 11.0 | 7.0 | 1 | 62 | 550 | 18 | 2 1-pr. revs. | 2 | 13 | 10 |
| Reni | Elbing .. | 1886 | 128 | 15.7 | 7.5 | 1 | 87 | 900 | 22 | 4 1-pr. revs. | 2 | 13 | 17 |
| Sookhoum | Chiswick .. | 1883 | 113 | 12.5 | 6 | 1 | 64 | 700 | 19.5 | 2 Nords. | 2 | 13 | 10 |
| Tchardak | Elbing .. | 1886 | 128 | 15.7 | 7.5 | 1 | 87 | 900 | 20 | 4 1-pr. revs. | 2 | 13 | 17 |
| Yalta | Elbing .. | 1886 | 128 | 15.7 | 7.5 | 1 | 87 | 900 | 22 | 4 1-pr. revs. | 2 | 13 | 17 |
| 3 boats | Elbing .. | 1886 | 128 | 15.7 | 7.5 | 1 | 87 | 900 | 22 | 4 1-pr. revs. | 2 | 13 | 17 |
| 4 boats | Nicolaieff .. | Bldg. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. |
| SECOND CLASS— | | | | | | | | | | | | | |
| Ischeritza | Sebastopol .. | 1878 | 62.3 | 9.7 | 3.9 | 1 | 24 | 220 | 15 | .. | .. | 10 | .. |
| Karabin | Elbing .. | 1877 | 64.3 | 8.4 | 2 | 1 | 11 | 120 | 15 | .. | .. | 8 | .. |
| Kefal | Chiswick .. | 1880 | 60.5 | 7.5 | 3.5 | 1 | .. | .. | 16.8 | .. | .. | 8 | .. |
| Schegiensk | Sebastopol .. | 1878 | 59.3 | 9.5 | 3.9 | 1 | 24 | 220 | 15 | .. | .. | 10 | .. |
| Schchouka | Sebastopol .. | 1878 | 59.3 | 9.5 | 3.9 | 1 | 24 | 220 | 15 | .. | .. | 10 | .. |
| Scoombia | Odessa .. | 1878 | 61.3 | 10 | 4 | 1 | 25 | 220 | 15 | .. | .. | 10 | .. |
| Soroka | St. Petersburg | 1878 | 62.3 | 9.7 | 3.9 | 1 | 24 | 220 | 15 | .. | .. | 10 | .. |
| Soulin | .. | 1877 | 60 | 9.7 | 3.9 | 1 | 24 | 210 | 15 | .. | .. | 10 | .. |
| Sultanka | Odessa .. | 1878 | 64.3 | 10 | 4 | 1 | 25 | 220 | 15 | .. | .. | 10 | .. |
| 1 boat | Poplar .. | 1877 | 75 | 10 | .. | .. | .. | .. | .. | .. | .. | .. | .. |
| 50 boats (Woron Class) | Elbing, etc. | .. | 66 | 11.1 | .. | 1 | .. | 260 | 17 | .. | .. | .. | .. |
| SIBERIAN FLOTILLA. | | | | | | | | | | | | | |
| Borgo | Abo | 1890 | 136.5 | 13 | 7.8 | .. | 81 | 1,100 | 21 | .. | .. | .. | .. |
| Forel | .. | .. | 71.5 | 6.5 | 3.3 | 1 | 23 | 220 | 16 | .. | .. | .. | .. |
| Jantchiche | Elbing .. | 1887 | 128 | 15.7 | 11.5 | .. | 87 | 970 | 19 | 4 1-pr. revs. | 2 | 13 | 17 |
| N. | .. | 1893 | 152.5 | 16.8 | .. | .. | 140 | 2,200 | 26.5 | 2 1-pr. revs. | 3 | 24 | 40 |
| N. | .. | 1893 | 152.5 | 16.8 | .. | .. | 140 | 2,200 | 26.5 | 2 1-pr. revs. | 3 | 24 | 40 |
| Podorosnik | .. | .. | 71.5 | 6.5 | 3.3 | 1 | 23 | 220 | 16 | .. | .. | .. | .. |
| Revel | Normand .. | 1886 | 151 | 12.5 | 8.4 | 1 | 102 | 800 | 20 | 2 1-pr. revs. | 2 | 23 | 15 |
| Sisik | .. | .. | 71.5 | 6.5 | 3.3 | 1 | 23 | 220 | 16 | .. | .. | .. | .. |
| Skorpion | .. | .. | 71.5 | 6.5 | 3.3 | 1 | 23 | 220 | 16 | .. | .. | .. | .. |
| Sootchena | Elbing .. | 1887 | 128 | 15.7 | 11.5 | .. | 87 | 970 | 19 | 4 1-pr. revs. | 2 | 13 | 17 |
| Sterliad | .. | .. | 71.5 | 6.5 | 3.3 | 1 | 23 | 220 | 16 | .. | .. | .. | .. |
| Strauss | .. | .. | 71.5 | 6.5 | 3.3 | 1 | 23 | 220 | 16 | .. | .. | .. | .. |
| Sunguri (<i>ex</i> Hogland) | Abo | 1890 | 152 | 16 | 7.9 | 2 | 140 | 1,800 | 22 | .. | .. | .. | .. |
| Sweaborg | Normand .. | 1886 | 151 | 12.5 | 8.4 | 1 | 102 | 800 | 20 | 2 1-pr. revs. | 2 | 23 | 15 |
| Ussuri (<i>ex</i> Nargen) | Abo | 1890 | 152 | 16 | 7.9 | 2 | 140 | 1,800 | 22 | .. | .. | .. | .. |
| 2 Unnamed | Ochtenski .. | Bldg. | 152 | 16 | 7.9 | 2 | 140 | 1,800 | 22 | .. | .. | .. | .. |

Spain.

| Name or Number. | Where Built. | Launched. | Dimensions. | | | Number of Screws. | Displacement. | Indicated Horse-Power. | Maximum Trial Speed. | Armament. | Torpedo Tubes. | Complement. | Coal Capacity. |
|-----------------------|--------------|-----------|-------------|-------|----------|-------------------|---------------|------------------------|----------------------|-------------------|----------------|-------------|----------------|
| | | | Length. | Beam. | Draught. | | | | | | | | |
| | | | Feet. | Feet. | Feet. | | Tons. | | Knots. | | | | Tons. |
| DESTROYERS— | | | | | | | | | | | | | |
| Terror | Clydebank .. | 1896 | 220 | 22 | 5.6 | 2 | 300 | 6,000 | 28 | { 2 12-pr. 2 } | 2 | 67 | 100 |
| Audaz | .. | .. | .. | .. | .. | .. | .. | .. | .. | { 6-pr. 2 1-pr. } | .. | .. | .. |
| Osado | Clydebank .. | 1897 | 225 | 25.6 | 5.8 | 2 | 400 | 7,500 | 30 | { 2 14-pr. 2 } | 2 | 70 | 90 |
| Proserpina | .. | .. | .. | .. | .. | .. | .. | .. | .. | { 6-pr. 21-pr. } | .. | .. | .. |
| FIRST CLASS— | | | | | | | | | | | | | |
| Acevedo | Chiswick .. | 1885 | 117.7 | 12.5 | 6.2 | 1 | 63 | 660 | 20.1 | 2 mach. | 2 | .. | .. |
| Ariete | Chiswick .. | 1887 | 147.5 | 14.6 | 4.9 | 2 | 97 | 1,600 | 26.1 | 4 3-pr. Q.F. | 2 | .. | 25 |
| Azor | Poplar .. | 1887 | 134.5 | 14 | 6 | 1 | 108 | 1,600 | 24 | 4 3-pr. Q.F. | 3 | 23 | 25 |
| Bustamante | Normand .. | 1887 | 126 | 10.9 | .. | .. | 63 | 800 | .. | 3 3-prs. | 2 | .. | .. |
| Ejercito | Kiel | 1887 | 111.5 | 13 | 3.3 | .. | 60 | 1,000 | 25 | 2 mach. | 2 | .. | .. |
| Habana | Chiswick .. | 1887 | 127.5 | 12.5 | 6 | 1 | 59 | 730 | 21.3 | 1 mach. | 2 | .. | .. |
| Halcon | Poplar .. | 1887 | 134.5 | 14 | .. | 1 | 108 | 1,600 | 24 | 4 3-pr. Q.F. | 3 | 23 | 25 |
| Julian Ordoñez | Chiswick .. | 1885 | 117.7 | 12.5 | 6.2 | 1 | 65 | 660 | 20.1 | 2 1-in. Nord. | 2 | .. | .. |
| Orion | Gaarden .. | .. | 125 | 15.5 | 3.5 | 1 | 85 | 1,000 | 21.5 | 2 1-pr. revs. | 2 | 18 | 16 |
| Rayo | Chiswick .. | 1887 | 147.5 | 14.6 | 4.9 | 2 | 97 | 1,600 | 25.5 | 4 3-pr. Q.F. | 2 | .. | 25 |
| Retamosa | Poplar .. | 1886 | 118 | 12.5 | 5.5 | 1 | 70 | 700 | 20.5 | 2 1-in. | 2 | 17 | 20 |
| Rigel | Bremen .. | 1883 | 105 | 12.3 | 3.3 | 1 | 57 | .. | 19 | 1 1-pr. rev. | 2 | 18 | 13 |
| Seza | Ferrol .. | 1885 | 126 | .. | .. | .. | 85 | .. | 14 | .. | .. | .. | .. |
| 4 boats | Bldg. | 147 | 43.0 | 5 | .. | .. | 98 | 1,600 | 25 | .. | .. | 25 | 25 |
| 2 boats | Clydebank .. | Bldg. | .. | .. | .. | .. | .. | .. | 28 | .. | .. | .. | .. |
| SECOND CLASS— | | | | | | | | | | | | | |
| Aire | Spain | 1883 | 43.4 | 10.2 | 3 | 2 | 25 | 175 | 8 | 1 3.1-in. | .. | 16 | 1 |
| Castor | La Seyne .. | 1878 | 76.2 | 9.7 | 2.3 | .. | 23 | 265 | 19 | .. | .. | 14 | 1.5 |
| Pollux | Poplar .. | 1879 | 84.5 | 10.7 | 4.6 | .. | 33 | 450 | 19.5 | .. | 2 | 14 | 9 |
| VEDETTE BOATS— | | | | | | | | | | | | | |
| 3 boats | East Cowes | 1892 | 60 | 9.3 | .. | .. | .. | .. | 18.3 | .. | .. | .. | .. |
| Peral | Carraca .. | 1889 | 70 | 8.5 | .. | 2 | 87 | 60 | 10 | .. | .. | .. | .. |

It is stated that the Ejercito, Retamoso, Rigel, and Castor have been condemned.

Sweden.

TORPEDO BOATS.

| Name or Number. | Where Built. | Launched. | Dimensions. | | | Number of Screws. | Displacement. | Indicated Horse-Power. | Maximum Trial Speed. | Armament. | Torpedo Tubes. | Complement. | Coal Capacity. |
|--|--------------|----------------------|-------------|-------|----------|-------------------|---------------|------------------------|----------------------|----------------|----------------|-------------|----------------|
| | | | Length. | Beam. | Draught. | | | | | | | | |
| FIRST CLASS— | | | Feet. | Feet. | Feet. | | Tons. | | Knots. | | | | Tons. |
| Komet | Elbing .. | 1896 | 128 | 15.9 | 6.11 | 1 | 92 | 1,056 | 23.0 | 2 1.9-in. Q.F. | 2 | 16 | 17 |
| Blixt | Carlskrona.. | 1898 | 128 | 15.9 | 6.11 | 1 | 92 | 1,260 | 23.5 | 2 1.9-in. Q.F. | 2 | 18 | 17 |
| Meteor | Carlskrona.. | 1899 | 128 | 15.9 | 6.11 | 1 | 92 | 1,330 | 23.8 | 2 1.9-in. Q.F. | 2 | 18 | 17 |
| Stjerna | Carlskrona.. | 1899 | 128 | 15.9 | 6.11 | 1 | 92 | 1,250 | 23.4 | 2 1.9-in. Q.F. | 2 | 18 | 17 |
| Orkan | Carlskrona.. | 1900 | 128 | 15.9 | 6.11 | 1 | 92 | 1,250 | 23.5 | 2 1.5-in. Q.F. | 2 | 18 | 17 |
| Vind | Carlskrona.. | 1900 | 128 | 15.9 | 6.11 | 1 | 92 | 1,250 | 23.5 | 2 1.5-in. Q.F. | 2 | 18 | 17 |
| Bris | Carlskrona.. | 1900 | 128 | 15.9 | 6.11 | 1 | 92 | 1,250 | 23.5 | 2 1.5-in. Q.F. | 2 | 18 | 17 |
| 2 boats (A and B) .. | Carlskrona.. | Bldg. | 128 | 15.9 | 6.11 | 1 | 92 | 1,250 | | 2 1.5-in. Q.F. | 2 | 18 | 17 |
| No. 1. | Chiswick .. | 1884 | 113.2 | 12.2 | 6.3 | 1 | 65 | 620 | 18.5 | 1 mach. | 2 | 16 | 11 |
| 2 boats (3 and 5) .. | Stockholm .. | 1887 | 114.2 | 12.6 | 6.7 | 1 | 67 | 620 | 18.5 | 1 mach. | 2 | 16 | 15 |
| No. 7. | Stockholm .. | 1887 | 114.2 | 12.6 | 6.7 | 1 | 67 | 620 | 18.7 | 1 mach. | 2 | 16 | 15 |
| 2 boats (9 and 11) .. | Carlskrona.. | 1894 | 126.8 | 13.11 | 7.7 | 1 | 86 | 850 | 19.5 | 2 mach. | 2 | 16 | 15 |
| SECOND CLASS— | | | | | | | | | | | | | |
| No. 61 | Stockholm .. | 1882 | 91.6 | 11.8 | 5.7 | 1 | 40 | 350 | 16.0 | 1 mach. | 1 | 14 | 9 |
| No. 63 | Chiswick .. | 1893 | 100.1 | 11.10 | 5.11 | 1 | 45 | 420 | 19.0 | 1 mach. | 2 | 14 | 7 |
| No. 65 | Stockholm .. | 1885 | 100.1 | 11.10 | 5.11 | 1 | 45 | 420 | 19.0 | 1 mach. | 2 | 14 | 9 |
| No. 67 | Stockholm .. | 1886 | 100.9 | 11.10 | 6.1 | 1 | 46 | 430 | 19.2 | 1 mach. | 2 | 14 | 9 |
| No. 69 | Stockholm .. | 1886 | 100.9 | 11.10 | 6.1 | 1 | 46 | 450 | 19.9 | 1 mach. | 2 | 14 | 9 |
| No. 71 | Stockholm .. | 1887 | 103.4 | 11.10 | 6.7 | 1 | 53 | 460 | 18.6 | 1 mach. | 2 | 14 | 9 |
| No. 73 | Stockholm .. | 1887 | 103.4 | 11.10 | 6.7 | 1 | 58 | 460 | 18.6 | 1 mach. | 2 | 14 | 9 |
| No. 75 | Stockholm .. | 1892 | 100.5 | 11.6 | 6.3 | 1 | 49 | 460 | 18.9 | 1 mach. | 2 | 14 | 9 |
| No. 77 | Carlskrona.. | 1891 | 100.5 | 11.6 | 6.3 | 1 | 49 | 460 | 18.9 | 1 mach. | 2 | 14 | 9 |
| No. 79 | Stockholm .. | Bldg. | 104.0 | 12.5 | 6.1 | 1 | 49 | | | 1 1.5-in. Q.F. | 2 | 14 | |
| No. 81 | Stockholm .. | Bldg. | 104.0 | 12.5 | 6.1 | 1 | 49 | | | 1 1.5-in. Q.F. | 2 | 14 | |
| THIRD CLASS— | | | | | | | | | | | | | |
| Nos. 141, 143, 145, 147, } 149 (5 boats) .. | Stockholm .. | { 1879 } { 1890 } | 55.0 | 10.7 | 4.1 | 2 | 21 | 80 | 10 | | 2 | | 1.5 |

Turkey.

| Name or Number. | Where Built. | Launched. | Dimensions. | | | Number of Screws. | Displacement. | Indicated Horse-Power. | Maximum Trial Speed. | Armament. | Torpedo Tubes. | Complement. | Coal Capacity. |
|---------------------|-----------------------------|-----------|-------------|-------|----------|-------------------|---------------|------------------------|----------------------|---------------|----------------|-------------|----------------|
| | | | Length. | Beam. | Draught. | | | | | | | | |
| DESTROYERS— | | | Feet. | Feet. | Feet. | | Tons. | | Knots. | | | | Tons. |
| Berk-Efshan | Gaarden .. | 1894 | 187 | | | 2 | 270 | 200 | 25 | 6 1-pr. revs. | 2 | | |
| Tajjar | Gaarden .. | 1894 | 187 | 21.6 | | 2 | 270 | | 25 | 6 1-pr. revs. | 2 | | |
| FIRST CLASS— | | | | | | | | | | | | | |
| A. B. | Sestri Ponente | 1901 | 166 | 18.6 | 4.0 | 2 | 145 | 2,400 | 26 | 2.1 pr. | 2 | | 16 |
| Edjder (No. 10) .. | Gaarden .. | 1890 | 152.7 | 18.9 | 7.4 | 2 | 150 | 2,200 | 23 | 5 3-prs. Q.F. | 2 | | |
| 1 boat | Constantinople | 1889 | 140 | 16 | 6.9 | 2 | 120 | 1,800 | 23 | 5 1-pr. revs. | 2 | | |
| 5 boats | Gaarden .. | 1889-90 | 126.7 | 15.4 | 8.6 | 1 | 85 | 1,300 | 22 | 2 1-pr. revs. | 2 | 21 | 8 |
| Timsah | London .. | 1887 | 126 | 15 | | | | | 21.7 | | | | |
| 5 boats | Elbing .. | 1886 | 120.3 | 16.2 | | | 85 | 900 | 21 | 2 Nords. | 2 | 20 | 10 |
| 4 boats | Constantinople | 1886-89 | 100.3 | 11.8 | 5.5 | 1 | 42 | 550 | 19.5 | 2 mach. | | | |
| Tewfik | Normand .. | 1885 | 100.7 | 13 | 5.5 | 1 | 42 | 550 | 20 | | | | |
| 2 boats | La Seyne and Constantinople | 1885 | 100.7 | 13 | 5.5 | 1 | 42 | 550 | 20.3 | 2 Nords. | | | |
| 2 boats | Teddington | 1887 | 124 | 15 | | | | | 22 | | | | |
| 2 boats | Kiel | 1892 | 127 | | | | | | 22 | | | | |
| SUBMARINE— | | | | | | | | | | | | | |
| Abdul Hamid | Chertsey .. | 1886 | 100 | 12 | | 3 | 160 | 250 | 10 | 2 mach. | 1 | | 8 |
| Abdul Mejid | Chertsey .. | 1886 | 100 | 12 | | 3 | 160 | 250 | 10 | 2 mach. | 1 | | 8 |

United States.



| Name. | Where Built. | Launched. | Dimensions. | | | | Number of Screws. | Displacement. | Indicated Horse-Power. | Maximum Trial Speed. | Armament. | | | |
|-----------------|----------------------|-----------|-------------|---------|----------|-------|-------------------|---------------|------------------------|----------------------|----------------|-------------|------------------------|-------|
| | | | Length. | Beam. | Draught. | Guns. | | | | | Torpedo Tubes. | Complement. | Maximum Coal Capacity. | |
| | | | ft. in. | ft. in. | ft. in. | | Tons. | | | Knots. | | | | Tons. |
| DESTROYERS— | | | | | | | | | | | | | | |
| Bainbridge .. | Philadelphia | 1900 | 245 0 | 23 7 | 6 6 | 2 | 420 | 8,000 | 29 | 2 12-pr., 5 6-pr.* | 2 | 64 | 139 | |
| Barry | Philadelphia | 1900 | 245 0 | 23 7 | 6 6 | 2 | 420 | 8,000 | 29 | 2 12-pr., 5 6-pr. | 2 | 64 | 139 | |
| Chauncey .. | Philadelphia | 1900 | 245 0 | 23 7 | 6 6 | 2 | 420 | 8,000 | 29 | 2 12-pr., 5 6-pr. | 2 | 64 | 139 | |
| Dale | Richmond .. | 1900 | 245 0 | 23 7 | 6 6 | 2 | 420 | 8,000 | 28 | 2 12-pr., 5 6-pr. | 2 | 64 | 139 | |
| Decatur .. . | Richmond .. | 1900 | 245 0 | 23 7 | 6 6 | 2 | 420 | 8,000 | 28 | 2 12-pr., 5 6-pr. | 2 | 64 | 139 | |
| Hopkins .. . | Wilmington | 1900 | 244 0 | 24 6 | 6 0 | 2 | 408 | 7,200 | 29 | 2 12-pr., 5 6-pr. | 2 | 64 | 150 | |
| Hull | Wilmington | 1900 | 244 0 | 24 6 | 6 0 | 2 | 408 | 7,200 | 29 | 2 12-pr., 5 6-pr. | 2 | 64 | 150 | |
| Lawrence .. | Weymouth, Mass. . . | 1900 | 242 3 | 22 3 | 6 2 | 2 | 400 | 8,400 | 30 | 2 12-pr., 5 6-pr. | 2 | 64 | 115 | |
| Macdonough .. | Weymouth, Mass. . . | 1900 | 242 3 | 22 3 | 6 2 | 2 | 400 | 8,400 | 30 | 2 12-pr., 5 6-pr. | 2 | 64 | 115 | |
| Paul Jones .. | San Francisco | 1900 | 245 0 | 23 7 | 6 6 | 2 | 420 | 7,000 | 29 | 2 12-pr., 5 6-pr. | 2 | 64 | 139 | |
| Perry | San Francisco | 1900 | 245 0 | 23 7 | 6 6 | 2 | 420 | 7,000 | 29 | 2 12-pr., 5 6-pr. | 2 | 64 | 139 | |
| Preble | San Francisco | 1901 | 245 0 | 23 7 | 6 6 | 2 | 420 | 7,000 | 29 | 2 12-pr., 5 6-pr. | 2 | 64 | 139 | |
| Stewart .. . | Morris Heights | 1900 | 245 0 | 23 7 | 6 6 | 2 | 420 | 8,000 | 29 | 2 12-pr., 5 6-pr. | 2 | 64 | 139 | |
| Truxtun .. . | Baltimore .. | 1900 | 248 0 | 23 3 | 6 0 | 2 | 433 | 8,300 | 30 | 2 12-pr., 5 6-pr. | 2 | 64 | 232 | |
| Whipple .. . | Baltimore .. | 1900 | 248 0 | 23 3 | 6 0 | 2 | 433 | 8,300 | 30 | 2 12-pr., 5 6-pr. | 2 | 64 | 232 | |
| Worden .. . | Baltimore .. | 1900 | 248 0 | 23 3 | 6 0 | 2 | 433 | 8,300 | 30 | 2 12-pr., 5 6-pr. | 2 | 64 | 232 | |
| | | | | | | | | | | | | | | |
| Bagley | Bath | 1900 | 157 0 | 17 0 | 4 7 | 2 | 167 | .. | 28 | 3 3-pr. | 3 | 29 | .. | |
| Bailey | Morris Heights | 1899 | 205 0 | 19 0 | 6 0 | 2 | 235 | 5,000 | 30 | 4 6-pr. | 2 | .. | 20 | |
| Barney | Bath | 1900 | 157 0 | 17 0 | 4 7 | 2 | 167 | .. | 28 | 3 3-pr. | 3 | 29 | .. | |
| Biddle | Bath | 1900 | 157 0 | 17 0 | 4 7 | 2 | 167 | .. | 28 | 3 3-pr. | 3 | 29 | .. | |
| Blakely .. . | Boston .. . | 1900 | 175 0 | 17 6 | 4 8 | 2 | 165 | 3,000 | 26 | 3 3-pr. | 3 | 29 | 70 | |
| De Long .. . | Boston .. . | 1900 | 175 0 | 17 6 | 4 8 | 2 | 165 | 3,000 | 26 | 3 3-pr. | 3 | 29 | 70 | |
| Du Pont .. . | Bristol, R.I. | 1897 | 175 0 | 17 8 | 4 8 | 2 | 165 | 3,400 | 28.58 | 4 1-pr. | 3 | 32 | 76 | |
| Farragut .. . | San Francisco | 1898 | 213 6 | 20 8 | 6 0 | 2 | 273 | 5,000 | 30 | 4 6-pr. | 2 | .. | 76 | |
| Foote | Baltimore .. | 1896 | 160 0 | 16 1 | 5 0 | 2 | 142 | .. | 24.5 | 3 1-pr. | 3 | 24 | 44 | |
| Goldsborough .. | Portland, Ore. | 1899 | 194 8 | 20 5 | 5 0 | 2 | 247.5 | .. | 30 | 4 6-pr. | 2 | .. | 131 | |
| Nicholson .. | Elizabethport | 1900 | 174 6 | 17 0 | 4 6 | 2 | 174 | .. | 26 | 3 3-pr. | 3 | 29 | .. | |
| O'Brien .. . | Elizabethport | 1900 | 174 6 | 17 0 | 4 6 | 2 | 174 | .. | 26 | 3 3-pr. | 3 | 29 | .. | |
| Porter | Bristol, R.I. | 1896 | 175 0 | 17 8 | 4 8 | 2 | 165 | .. | 28.63 | 4 1-pr. | 3 | 32 | 76 | |
| Rodgers .. . | Baltimore .. | 1896 | 160 0 | 16 1 | 5 0 | 2 | 142 | 2,000 | 24.5 | 3 1-pr. | 3 | 24 | 44 | |
| Rowan | Seattle, Wash. | 1898 | 170 0 | 17 0 | 5 11 | 2 | 182 | 3,200 | 26 | 4 1-pr. | 3 | 32 | 60 | |
| Shubrick .. . | Richmond .. | 1899 | 175 0 | 17 6 | 4 8 | 2 | 165 | 3,000 | 26 | 3 3-pr. | 3 | 29 | 70 | |
| Stockton .. . | Richmond .. | 1899 | 175 0 | 17 6 | 4 8 | 2 | 165 | 3,000 | 26 | 3 3-pr. | 3 | 29 | 70 | |
| Stringham .. | Wilmington | 1899 | 225 0 | 22 0 | 6 6 | 2 | 340 | 7,200 | 30 | 7 6-pr. | 2 | .. | 120 | |
| Thomson .. . | Richmond .. | 1900 | 175 0 | 17 6 | 4 8 | 2 | 165 | 3,000 | 26 | 3 3-pr. | 3 | 29 | 70 | |
| Tingey | Baltimore .. | Bldg. | 175 0 | 17 6 | 4 8 | 2 | 165 | 3,000 | 26 | 3 3-pr. | 3 | 29 | 70 | |
| Wilkes | Morris Heights Bldg. | Bldg. | 175 0 | 17 6 | 4 8 | 2 | 165 | 3,000 | 26.25 | 3 3-pr. | 3 | 29 | 70 | |
| Winslow .. . | Baltimore .. | 1897 | 160 0 | 16 1 | 5 0 | 2 | 142 | 2,000 | 24.5 | 3 1-pr. | 3 | 24 | 44 | |
| SEA-GOING— | | | | | | | | | | | | | | |
| Cushing .. . | Bristol, R.I. | 1890 | 138 9 | 14 3 | 4 11 | 2 | 105 | 1,720 | 22.5 | 3 1-pr. | 3 | 23 | 36 | |
| Davis | Portland, Ore. | 1898 | 146 0 | 15 4 | 5 4 | 2 | 132 | 1,750 | 22.5 | 3 1-pr. | 3 | .. | .. | |
| Dahlgren .. . | Bath | 1899 | 147 0 | 16 4 | 4 7 | 2 | 146 | 4,200 | 30.5 | 4 1-pr. | 2 | .. | 32 | |
| Ericsson .. . | Dubuque, Iowa | 1894 | 149 7 | 15 6 | 4 9 | 2 | 120 | 1,800 | 24 | 4 1-pr. | 3 | 23 | 35 | |
| Fox | Portland, Ore. | 1898 | 146 0 | 15 4 | 5 4 | 2 | 132 | 1,750 | 22.5 | 3 1-pr. | 3 | .. | .. | |
| Manly | Yarrow .. . | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | |
| Morris | Bristol, R.I. | 1898 | 138 3 | 15 6 | 4 1 | 2 | 105 | 1,750 | 24 | 3 1-pr. | 3 | .. | 28 | |
| Somers | Schichau, Elbing .. | .. | 149 3 1/2 | 17 5 | .. | 2 | 145 | .. | .. | .. | .. | .. | .. | |
| T. A. M. Craven | Bath | 1899 | 147 0 | 16 4 | 4 7 | 2 | 146 | 4,260 | 30.5 | 4 1-pr. | 2 | .. | 32 | |
| THIRD CLASS— | | | | | | | | | | | | | | |
| Gwin | Bristol, R.I. | 1897 | 99 6 | 12 6 | 3 3 | 1 | 46 | 850 | 20.88 | 1 1-pr. | 2 | .. | 8 | |
| Mackenzie .. | Philadelphia | 1898 | 99 3 | 12 9 | 4 3 | 1 | 65 | 850 | 20 | 1 1-pr. | 2 | .. | 15.3 | |
| McKee | Philadelphia | 1898 | 99 3 | 12 9 | 4 3 | 1 | 65 | 850 | 19.82 | 2 1-pr. | 2 | .. | .. | |
| Talbot | Bristol, R.I. | 1897 | 99 6 | 12 6 | 3 3 | 1 | 46 | 850 | 21.15 | 1 1-pr. | 2 | .. | 8.8 | |
| Stiletto (wood) | Bristol, R.I. | .. | 88 6 | 11 0 | 3 0 | 1 | 31 | 359 | 18.22 | .. | 2 | .. | 4 | |
| SUBMARINE— | | | | | | | | | | | | | | |
| Adder | Elizabethport | Bldg. | 63 4 | 11 9 | .. | 1 | 120 | 160 | 8 | .. | 1 | .. | .. | |
| Grampus .. . | S. Francisco | Bldg. | 63 4 | 11 9 | .. | 1 | 120 | 160 | 8 | .. | 1 | .. | .. | |
| Holland .. . | Elizabethport | 1896 | 54 0 | 10 3 | .. | 1 | 74 | 45 | 8 | 1 dynamite | 1 | 5 | .. | |
| Moccasin .. . | Elizabethport | Bldg. | 63 4 | 11 9 | .. | 1 | 120 | 160 | 8 | .. | 1 | .. | .. | |
| Pike | S. Francisco | Bldg. | 63 4 | 1 9 | .. | 1 | 120 | 160 | 8 | .. | 1 | .. | .. | |
| Plunger .. . | Baltimore .. | 1898 | 85 3 | 11 6 | .. | 1 | 168 | 70 | 8 | .. | 2 | .. | .. | |
| Porpoise .. . | Elizabethport | Bldg. | 63 4 | 11 9 | .. | 1 | 120 | 160 | 8 | .. | 1 | .. | .. | |
| Shark | Elizabethport | Bldg. | 63 4 | 11 9 | .. | 1 | 120 | 160 | 8 | .. | 1 | .. | .. | |

* Guns of Destroyers of this class are Driggs Semi-Automatic Quick-Firers.

The Barcelo and some other Spanish torpedo-boats were captured during the war.

With the exception of the Lawrence Macdonough and Stewart, all the destroyers in the first alphabetical list have Thornycroft water-tube boilers. The Farragut, Goldsborough and Stringham have also boilers of this type.

PLANS
OF
BRITISH AND FOREIGN SHIPS.




GREAT BRITAIN.

"Eolus"
"Andromache"
"Apollo"
"Brilliant"
"Indefatigable"
"Intrepid"
"Iphigenia"
"Latona"
"Melampus"
"Naiad"
"Rainbow"
"Retribution"


2ND CLASS CRUISER, PROTECTED
"Apollo" (Class)

"Sappho"
"Scylla"
"Sirius"
"Spartan"
"Sybille" wrecked
"Terpsichore"
"Thetis"
"Tribune"



"Astræa"
"Bonaventure"
"Cambrian"
"Charybdis"
"Flora"
"Forte"
"Fox"
"Hermione"



2ND CLASS PROTECTED CRUISERS
"Astræa" (Class)






Scale 100 ft = 1 in.
Midship Section



GREAT BRITAIN

"Arrogant" Class.
2nd Class Cruiser







GREAT BRITAIN



"Crescent" "Grafton"
"Edgar" "Hawke"
"Endymion" "Royal Arthur"
"Gibraltar" "S. George"
"Theseus"

FIRST CLASS PROTECTED CRUISERS

"Edgar" Class





Note. The Crescent and Royal Arthur have two 6 in guns forward in place of the 22 ton gun.

GREAT BRITAIN

'Diadem'(Class)
1st CLASS CRUISERS



"Adromeda" "Amphitrite"
"Diadem" "Ariadne"
"Europa" "Argonaut"
"Niobe" "Spartiate"

Scale 100 Feet to 1 in





FIRST CLASS ARMOURD CRUISERS
"Drake" Class

"Drake"
"King Alfred"
"Good Hope"
"Leviathan"





GREAT BRITAIN

FIRST CLASS ARMOURD CRUISERS OF THE
 "CRESSY" CLASS
 "Cressy," "Aboukir," "Hogue",
 "Euryalus," "Sutlej," "Bacchante"




"FORMIDABLE" CLASS

"Formidable," "Irresistible," "Implacable",
 "Bulwark," "London," "Venerable"



Technical drawing of the USS Oregon (BB-3). The drawing includes a side elevation, a cross-section, and a plan view. The side elevation shows the ship's profile with masts and gun turrets. The cross-section shows the internal structure and the gun turrets. The plan view shows the hull shape and the gun turrets. The drawing is labeled "Oregon" and "BB-3".




GREAT BRITAIN



FIRST CLASS BATTLE SHIPS.

"Duncan" Class

"Duncan"
"Cornwallis"
"Russell"
"Exmouth"
"Montagu"
"Albemarle"





GREAT BRITAIN.





GREAT BRITAIN.

"Powerful"
"Terrible"
First Class Cruisers


Scale 100 Ft to in.



GREAT BRITAIN
FIRST CLASS BATTLESHIP
"Renown"




GREAT BRITAIN




Pelorus Class



| | |
|------------------|--------------------|
| <i>Pelorus.</i> | <i>Pumona.</i> |
| <i>Pactolus.</i> | <i>Prometheus.</i> |
| <i>Pegasus.</i> | <i>Proserpine.</i> |
| <i>Perseus.</i> | <i>Pyramus.</i> |
| <i>Pandora</i> | <i>Psyche</i> |

Pioneer






GREAT BRITAIN





"Majestic" Class
 "Majestic" "Victorious"
 "Magnificent" "Mars"
 "Hannibal" "Illustrious"
 "Prince George" "Cæsar"
 "Jupiter"



GREAT BRITAIN

"Royal Sovereign" Class
14,150 tons 13,000 I.H.P.


"Empress of India"
"Ramillies"
"Repulse"
"Resolution"
"Revenge"
"Royal Oak"
"Royal Sovereign"





GREAT BRITAIN

"Hood"



TURRET SHIP WITH REDOUBTS







On Special Scale




GREAT BRITAIN.






ARGENTINA.

"Garibaldi"
 "General Belgrano"
 "Pueyrredon"
 "San Martin"
 "This ship has 46 in guns at the angles of the
 Upper Deck battery"
 "This ship has two 6 in guns in each barbette"





"Libertad" & Independencia"







AUSTRIA-HUNGARY.

ARMoured CRUISER.
Kaiser Karl VI.







Zenta







AUSTRIA-HUNGARY.





AUSTRIA-HUNGARY

Kronprinz Erzherzog Rudolph.






Habsburg.




BRAZIL.

Marshal Deodoro
Marshal Floriano.





Plan of Upper Deck





CHILI.


"Blanco Encalada"




"Capitan Prat"



CHILI
Armoured Cruiser
"Esmeralda"





Length between Perpendiculars





CHILI.

Protected Cruiser
"Ministro Zenteno"





O' Higgins





DENMARK.

"Helgoland"




"Iver Hvitfeldt"



DENMARK.



Herluf Trolle.



FRANCE.




Amiral Baudin.

Formidable.





Note. "Amiral Baudin" has only four 6.4" guns

"Amiral Duperré"





FRANCE.









FRANCE.

"Bruix"
 "Chanzy"
 "Charner"
 "Latouche Tréville"




"Calman"
 "Indomptable"
 "Requin"
 "Terrible"






FRANCE.



Devastation.

Courbet.


Redoutable.




Note. In the Redoutable, the 4 10.6 guns in the central redoubt are replaced by 9.4 guns and the 6 5.5 guns by an equal number of 3.9 guns.

FRANCE.



Descartes.





D'Estrées



FRANCE.
"Dupuy de Lôme"




D'ENTRECASTEAUX.




FRANCE.

"Châteaurenault"




"Desaix"
"Kléber"
"Dupleix"




ARMOURED CRUISERS.


France.

"Condé"
"Gloire"
"Sully"




"Gueydon"
"Du Petit-Thouars"
"Montcalm"







Hoche



FRENCH SHIPS.


"Jauréguiberry."



FRANCE.


PROTECTED CRUISERS

"Jean-Bart"
"Alger"
"Isly"





BATTLE-SHIPS.

"Magenta"
"Marceau"
"Neptune"





BATTLE-SHIP
Suffren

France




Pothuau



FRANCE.


PROTECTED CRUISERS

"Jean-Bart"
"Alger"
"Isly"




BATTLE-SHIPS.

"Magenta"
"Marceau"
"Neptune"




BATTLE-SHIP
Suffren

France




Pothuau




Germany.

"Freya"
"Hansa"
"Hertha"
"Victoria Louise"
"Vineta"




"Fürst Bismarck"




GERMANY.


Protected Cruiser
"Gefion"




"Kaiserin Augusta"



Germany.





Prinz Heinrich.




GERMANY

*Kurfurst Friedrich Wilhelm.
Brandenburg.
Weissenburg.
Wörth*




*Note. The Odin & Aegir are 16 feet
longer than the earlier ships and
have a larger armament which is in
some respects better protected.*





GREECE.

Hydra. Psara. Spetsaj.





ITALY.

Andrea Doria.
Francesco Morosini.
Ruggiero di Lauria.





ITALY.



"Dulio" (not rearmed)
"Dandolo" (As refitted and rearmed)



ITALY,
Vittorio Emanuele
Regina Elena.




Benedetto Brin.
Regina Margherita.





"Giuseppe Garibaldi"
 "Varese"
 "Francesco Ferruccio."

ITALY





ITALY.

Italia.
Lepanto.





Marco Polo.





ITALY.


Ammiraglio Di St. Bon.
Emanuele Filiberto




"Carlo Alberto"
"Vettor Pisani"





"Sardegna"
 "Re Umberto"
 "Sicilia"





Note. *Sardegna* is 9' 10" longer
 and 3' 3" broader than the
other two.



JAPAN.
Asama and Tokiwa




TAKASAGO.








JAPAN.

Chin Yuen.




Itsukushima.
Hashidate.





BATTLE-SHIP.
 "Hatsuse."
 15000 Tons. 14,500 H.P.


Japan.



ARMoured CRUISER.



"Idzumo."

JAPAN.





JAPAN.



"Yoshino"





Kasagi.



NETHERLANDS.






Koningin Wilhelmina de Nederlanden.





NETHERLANDS.

"Reinier Claesen"




Holland.





NORWAY.

ARMOUR-CLADS.
"Norge"
"Eidsvold"




RUSSIA.


ARMoured CRUISER "Admiral Nachimoff"



"Alexander II"





RUSSIA.
 "Catherine II."
 "Tchsmé."
 "Sinope."





RUSSIA.

Bayan.




Tsarevitch



ARMoured CRUISER.

"Gromoboi."

Russia.




FIRST CLASS BATTLE-SHIPS

"Oslabya"

"Peresviet"


Russia.



RUSSIA.


BATTLE SHIP

"Nicolai I"





ARMoured CRUISER

"Pamyat Azova."





RUSSIA.





PETROPAVLOVSK
POLTAVA
SEVASTOPOL



Pallada







RUSSIA.





N.B. All Armour treated
by Krupp Process

RUSSIA.




RUSSIA.
"Tria Sviatitelia."






SPAIN

"Emperador Carlos V."




"Cataluña."
 "Cardenal Cisneros"
 "Princesa de Asturias"

Midship Section.





SPAIN

"Pelayo"





COAST DEFENCE SHIPS.
"A," "B" AND "C."





UNITED STATES.

Alabama
Illinois
Wisconsin





"Brooklyn"
(Armoured Cruiser)





UNITED STATES.

ARKANSAS





Maine
Missouri.
Ohio.





UNITED STATES.

Columbia.
Minneapolis





Note - Minneapolis has only two funnels.

California.
Pennsylvania
West Virginia.
Colorado.
Maryland.
South Dakota.





"Iowa." (Battle Ship)

UNITED STATES.




Nº 5 (Kearsage)
" 6 (Kentucky)
(Battle ships)

L. W. L.




UNITED STATES


Coast Defence Ship "Monterey"



Midship Section.





On Special Scale



UNITED STATES



BATTLE SHIPS.

"Oregon"
"Massachusetts"
"Indiana"





ARMoured CRUISER.
"New York"

UNITED STATES





UNITED STATES.



Charleston.
Milwaukee.
St. Louis





Georgia
Nebraska
New Jersey
Rhode Island
Virginia



UNITED STATES "Texas"




Main & Hurricane Decks



UNITED STATES.

SUBMARINE TORPEDO BOAT.
 Adder. Moccasin. Porpoise.
 Grampus. Pike. Shark.

On Special Scale.



PART III.

ARMOUR AND ORDNANCE.

PART III.

Armour and Ordnance.

CHAPTER I.

ARMOUR.

FOR more than a decade the section of the *Naval Annual* devoted to armour and ordnance has been most ably edited by the late Captain Orde Browne, R.A., whose untimely death is a great loss, not only to those who have read with much pleasure from year to year the excellent articles that proceeded from his pen, but also to all who are connected with the manufacture and use of guns, ammunition, and armour plates. And as an insular nation, depending under God on the protection which our Navy affords, where is the man who should not be concerned in the excellence of those means of offence and defence on which the Navy must mainly rely?

Captain Orde Browne added to an excellent judgment and great critical capacity such fairness of mind and absolute integrity, that he was constantly entrusted with information which was withheld from others, who had not his practically world-wide reputation for discretion and fairness. On many occasions he was thus enabled to speak with great authority, and was one of the first to predicate the many and important changes and improvements that have taken place in recent years in the armour and armament of our ships. Patriotic as he was, he never hesitated to point to any evidence that clearly showed that we were dropping behind our rivals abroad in the race for excellence of *matériel*; thus an appreciation of a home product endorsed by him was worth far more than if it had emanated from one who could see nothing good in that which had its origin abroad.

The Editor has determined that, for this year at any rate, the Ordnance Section shall retain its old form; the valuable tables and other data due to Captain Orde Browne are retained, with the few corrections necessary, whilst, according to custom, particulars of some of the most important trials of armour plates are also included.

Immense progress in armour in the last decade.

Although year by year the *Annual* has called attention to the advances made in ordnance *matériel* and armour, it is doubtful whether outside a comparatively narrow circle of experts it is fully realised what a complete revolution has taken place within the last decade—more especially in armour. We propose, therefore, to briefly review the progress made. Nor is this merely an interesting retrospect into past history; it intimately concerns the battleships—the first-class battleships—of the present day. All authorities are agreed in admitting the claims of the Royal Sovereign class to be placed in the category of First-Class Battleships. They still form the backbone of our Mediterranean Fleet. But these ships are protected by compound armour, armed with 13·5-in. guns, have only four quick-firing guns mounted behind armour, and carry no hoods over their barbette guns. The question of the guns will be dealt with later on, but let us first look at the armour.

Compound and ordinary or mild steel armour.

From 1880 to 1890 compound armour reigned supreme in England, whilst abroad compound and steel were used indifferently. Many were the comparative trials that took place between compound and steel armour; but, on the whole, the two systems of armouring gave very similar protection for the same weight, and there was so little to choose between the two that some nations, notably the French, had ships built at the same period, some of which were protected by compound armour and some by steel. When compound armour was first introduced, about the year 1880, the armour-piercing projectiles commonly in use were made of cast iron, chilled by the Palliser or some similar process. The comparatively hard steel face of the compound plate had such resisting power that the inferior metal forming the head of the Palliser projectile was completely crushed up and no deep penetration was effected, unless the energy and piercing power of the projectile was very great as compared with the resistance of the plate; when this happened, though the projectile was crushed, a piece of plate was punched out.

Improvements in projectiles.

About the year 1886 the appearance of chrome steel projectiles, made by Holtzer and other French firms, completely altered the aspect of the case. The material of which these projectiles were made was so superior in combined hardness and toughness to the face metal of the best plates, that complete perforation was effected without deformation of the projectile, and, as a result, the piercing power of guns went up fully 20 per cent. In 1885 a good compound plate 10 inches thick might have been considered equal in resisting power to some 15 or 16 inches of wrought iron; but in 1886 this figure was reduced to 12½ inches of wrought iron, when the plates were attacked by chrome steel shot in lieu of Palliser.

For some five years the projectiles triumphed over the plates, passing through them without deformation, and though the steel and compound armour used was much superior to the wrought iron with which all ships built in the seventies were plated, the plate makers failed to produce a plate which could be counted upon to crush up the hardened points of the chrome steel shell.

But the plate makers did not stand still. In 1890 Captain Orde Browne remarks on some trials that took place the previous year:— "*On Brown's plate the Krupp projectiles broke up like chilled iron.*" In Brassey's *Annual* of 1890 there is also an account of a most extraordinary result said to have been obtained by a plate made in America by the Redemann-Tilford process, when a 6-in. plate defeated a 100 lb. 6-in. projectile, striking with a velocity of 2,103 ft. secs., and having a piercing power of 15 inches of wrought iron. Such an unprecedented trial, in which a 6-in. plate resisted an attack which would have defeated a compound plate nearly 12 inches thick, scarcely aroused so much attention as should have been the case, owing possibly to a certain amount of incredulity. And though this took place before a single plate had been made for the Royal Sovereign, not only that ship herself, but her seven sisters, the latest built of which, the Revenge, was not completed till 1895, were all armoured with compound plates. Nor is there any blame to be imputed to our authorities for their apparent remissness.

The plates
once more
gain the
ascen-
dancy.

As a matter of fact, they were extremely alert and took up the new process immediately it was established as a practical success, which success was demonstrated by the repeated production of cemented plates not only hard but tough. But a new process means new manufacturing plant, which takes years before it is in thorough working order and capable of turning out large quantities of plates—so that it must always happen, as occurred in this instance, that though a new process may have been discovered, ships cannot be supplied with better quality plates for some time to come.

Cemented
plates
establish
their supe-
riority.

The first plates with cemented faces tried in England were manufactured by Sir John Brown & Co., and were made by a process patented by Captain Tresidder; the trials took place in 1891 and are given in the *Annual* for 1892. At the same time, trials of the Harvey process were being carried out at Indian Head, and are given in the same volume. The most satisfactory result was that a 10½-in. Harvey plate just succeeded in stopping an 8-in. Carpenter steel shot weighing 250 lb., the velocity being 1,700 ft. secs., and perforating power 14·8 inches of wrought iron. This plate, therefore, had a figure of merit somewhat above 1·4, and was some 20 per cent. better than the steel and compound plates then

Particulars of trials of Harveyed Schneider nickel steel plates, 1891.

being supplied to the Royal Sovereign and other ships building. About the same period, namely July, 1891, a nickel steel plate of Schneider's, of 10·43 inches, was just pierced by projectiles with perforating power of 13·35 wrought iron. Its figure of merit was 1·28—some 10 per cent. less than that of the Harveyed plate; but it was greatly superior to the compound plates of the Royal Sovereign class. The Tresidder plates were decidedly superior to the Schneider nickel steel, but were not quite equal to the Harveyed plates, and the latter process was adopted by all the great Sheffield firms.

The first ships for which it was decided to adopt the Harvey process were the U.S. ships Brooklyn and Indiana, begun in 1892, completed in 1896. A sample 6-in. plate for the latter had the remarkable figure of merit of 2·25 far eclipsing anything in the way of iron cemented plates, or of any other process hitherto tried. But, although the Americans had a considerable start, owing to the enterprise of our Sheffield firms and the energy with which the work was pushed on in England, the Majestic, though begun some time after the Indiana, was the first ship actually completed which had the great advantage of having Harveyed plates. No trials can be quoted as showing the exact resistance of her plates, but the 6-in. plates may be considered as having a figure of merit equal to those tried on board the Nettle towards the latter part of 1893, when the average figure of merit was about 2·0. The thicker plates may be considered equal to the 10½-in. plates tried at Shoeburyness with a figure of merit of 1·9.

Enormous advantage of Harveyed over compound plates.

The advantage gained by using Harveyed, as compared with compound, plates was enormous. A 10½-in. plate which, if made on the compound system as supplied to the Royal Sovereign, could have been pierced by a 6-in. 6-ton gun, was able to resist successfully a shot from the 9·2-in. 25-ton gun fired under similar conditions. The extra resistance given to the armour would force an opponent to increase the weight of the attacking gun four-fold. Or, if the resistance of the Royal Sovereign's armour be considered adequate, it was possible in the Majestic class to increase the area protected by armour more than 50 per cent. without adding to the weight. A great gulf, therefore, exists between the Royal Sovereign and Majestic classes, and from this point of view it may scarcely be fair, considering the great improvements made since the former were built, to classify them as first-class battleships.

Progress in Foreign Countries.

At the time that the Majestic class were being plated in England, viz. from 1893 to 1897, the French were applying nickel steel (non-Harveyed) armour to the ships coming forward, and the following

ships are all plated with nickel steel, non-cemented, the figure of merit of which is about 1·4:—

| | Completed in |
|--------------------------|--------------|
| Carnot. | 1897 |
| Jauréguiberry | 1897 |
| Charles Martel | 1897 |
| Masséna | 1898 |

The Bouvet, completed in the summer of 1898, was the first French ship with cemented armour, but advantage was not taken of the increased resisting power of the armour to reduce its thickness and increase the area protected, so that the belt is a very narrow one, 16 inches thick, and the turrets have the same thickness, which is equivalent in resisting power to that of some 29 inches of wrought iron, a somewhat unnecessary amount of protection at the date it was provided, but useful now in view of the increase of power in heavy guns. In Russia the Petropavlovsk and Poltava, completed in 1897, have Harveyed armour on their turrets, but their belts are not Harveyed; the Rossia, however, finished about the same time, had a 10-in. Harveyed belt. The first German ship to reap the benefit of the cementing process was the Aegir, completed in 1897, and since then all German ships have had either Harveyed or Krupp process plates.

As early as 1895, when there were not more than half a dozen ships in the world which had benefited by the Harvey process, Krupp came forward with a rival method of cementing or face-hardening plates, which for some time stood unrivalled, and has only recently been equalled by other processes, which are probably generally similar in principle. The Krupp process has been adopted in all countries save in France and Italy, but both in the great French steel works and at Terni they now use cementing processes which produce equally good results; so that from the point of view of the user of the plate it may be said without serious error that the Krupp process has been universally adopted, and that all ships building at the present time are being furnished with Krupp plates.

The
Krupp
process
plates.

Like the Harveyed plates, the Krupped plates depend for their efficiency on the intense hardness of the face, which destroys the point and head of an ogival-headed projectile. The Krupped plates also possess extreme toughness, so that their resistance to punching and cracking is extraordinarily great. We give particulars below of a plate exhibited at the Paris Exhibition made at Terni which resisted a blow which would have pierced nearly three times its thickness of wrought iron. It is possible that this was an exceptional result, but

Figure,
of merit, of
Krupp
plates.

the average figure of merit for Krupp plates may be put somewhat as under :—

| Thickness of Plate. | Equivalent to Wrought Iron. | Figure of Merit. |
|------------------------|--------------------------------|------------------|
| Inches. | Inches. | |
| 4 | 9 | 2·25 |
| 6 | 16 | 2·67 |
| 8 | 20 | 2·5 |
| 10 | 24 | 2·4 |
| 12 | 28 | 2·33 |

The figure of merit for the thinnest plate, viz., the 4-in., is lower than the others, since hitherto plates of this thickness have not equalled thicker ones in resisting power. The Terni Company, however, exhibited at the Paris Exhibition a 9 cm. (3·54-in.) plate with a figure of merit exceeding 2·5, and a second plate of 11 cm. (4·33-in.) which had the remarkable figure of merit of just over 2·85, as it resisted a 4·7-in. projectile, weight 45 lb., velocity 2,198, penetrating power 12·3 inches wrought iron.

The results already obtained with Krupp plates justify us in considering the resistance of a Krupp plate as being equal to that of a compound plate of double its thickness. Thus the 17-in. barbette plates of the Royal Sovereign might be replaced to-day by 8½-in. Krupp plates, thus saving an immense deal of weight. Our latest battleships, the Duncan class, will have no plates thicker than 11 inches, and so far as we are aware 12 inches is about the thickest armour that is being made; moreover, it is quite possible that the French battleships which are said to be going to receive plates of this thickness may be content with thinner ones.

The gun
beaten by
the plate.

The fact that the plates are being reduced in thickness shows that on all hands it is considered that the plate has completely beaten the gun. Nor is this remarkable, for the plate has an immense advantage over the gun which is not generally understood or appreciated. The fact is that the addition of weight to the plate in order to obtain increased resisting power is as nothing to the corresponding increase in weight of the gun made necessary in order to cope with a plate of increased thickness. At present a 12-in. gun of 50 tons fairly matches a 12-in. plate. If the plate were doubled in thickness—and the Inflexible actually carries 24-in. plates—the gun would have to be increased in weight to 400 tons, whilst a

single projectile would weigh nearly 3 tons. Such a gun is, of course, out of the question.

The following table shows the resisting power of the plates of typical first class battleships:—


TABLE I.
ARMOUR OF TYPICAL FIRST-CLASS BATTLESHIPS.

| SHIP. | Date of Completion. | Actual thickness of Armour. | | | Resisting power of Armour. | | | Remarks. |
|-----------------------------|---------------------|-----------------------------|-----------------------|----------------------|----------------------------|-----------------------|-----------------------|---|
| | | Belt. | Heavy Gun Protection. | Q.F. Gun Protection. | Belt. | Heavy Gun Protection. | Q.F. Gun Protection. | |
| | | Inches. | Inches. | Inches. | Inches, wrought iron. | Inches, wrought iron. | Inches, wrought iron. | |
| Inflexible | 1881 | 24 w.t. | 17 c. | Nil. | 24 | 21 | Nil. | w.t. = wrought iron s. = steel. c. = compound. n.s. = nickel steel. h.s. = Harvey steel. k.s. = Krupp steel. |
| Formidable (French) | 1885 | 21½ s. | 16 s. | Nil. | 26 | 20 | Nil. | |
| Royal Sovereign | 1892 | 18 c. | 17 c. | 6 c. | 22½ | 21½ | 7½ | |
| Brennus | 1894 | 18 s. | 18 s. | 4 s. | 22½ | 22½ | 5 | |
| Charles Martel | 1897 | 18 n.s. | 14½ n.s. | 4 s. | 24 | 19 | 5 | |
| Indiana | 1896 | 18 h.s. | 17 h.s. | 6 h.s. | 29 | 27 | 13 | |
| Majestic | 1895 | 9 + 4 h.s. | 14 h.s. | 6 h.s. | 27* | 24½ | 12 | |
| Three Saints | 1896 | 16 h.s. | 16 h.s. | 5 s. | 26 | 26 | 6½ | |
| Bouvet | 1898 | 16 h.s. | 16 h.s. | 5 s. | 29 | 29 | 6½ | |
| Sevastopol | 1899 | 14½ h.s. | 14 h.s. | 5 s. | 28 | 27 | 6½ | |
| Implacable | 1901 | 12 k.s. | 12 k.s. | 6 k.s. | 28 | 28 | 15 | |
| <i>New Designs—</i> | | | | | | | | |
| England | 1904? | 11 k.s. | 11 k.s. | 6 to 7 k.s. | 27 | 27 | 16 to 18 | |
| France | | | | | | | | |
| America | | | | | | | | |

* Resistance of sloping deck included.

From the above it appears that whereas ten years ago the standard resistance sought for in the thick armour was from 22 to 26 inches wrought iron, it has now slightly increased and stands at 27 to 28 inches. Theoretically, this scarcely seems sufficient, for the 13.5-in. guns of the Royal Sovereign or 14.5-in. of the Formidable pierce some 25 inches wrought iron at 3,000 yards, and the 12-in. guns of the Implacable or Bouvet pierce 29 inches at the same

range. But this assumes that the projectile strikes direct, which only about one in four will do when the target is a circular turret.



Chances of hitting direct or otherwise.

The following table is made out for a circular turret, but it may be applied without much error to the case of belt armour, for it seems probable that ships will usually engage broadside to broadside in order to bring the greatest number of guns to bear, and therefore under ordinary circumstances at least 60 per cent. of the rounds fired will strike within 37° of the normal whether the target be a curved turret or a wall-sided battery.

TABLE II.

TABLE SHOWING EXCESS OF PIERCING POWER TO OBTAIN PERFORATION ON OBLIQUE IMPACT ON CIRCULAR TURRET IF NORMAL RESISTANCE = 100.

Extra
piercing
power
required
when
hitting
obliquely

| Piercing power. | Angle with normal at which perforation is obtained. | Percentage of Hits striking within this angle. |
|-----------------|---|--|
| 104 | 15° | 25 |
| 110 | 20° | 34 |
| 120 | 25° | 43 |
| 130 | 30° | 50 |
| 140 | 34° | 56 |
| 150 | 37° | 60 |
| 175 | 45° | 70 |
| 200 | 53° | 78 |

Example
of propor-
tion of
piercing
hits.

Let us suppose an engagement between the Royal Sovereign and the Brennus, the Implacable and the Bouvet, the piercing power of their guns being as under:—

TABLE III.

| SHIP. | GUN. | Piercing power in Wrought Iron at ranges as under. | | | |
|-----------------------|---------|--|-----------------|------------|-----------------|
| | | 1,000 yds. | 2,000 yds. | 3,000 yds. | 4,000 yds. |
| | Inches. | | | | |
| Royal Sovereign . . . | 13.5 | $30\frac{1}{2}$ | $27\frac{1}{2}$ | 25 | 23 |
| Brennus | 13.4 | 36 | 32 | 29 | 26 |
| Implacable | 12 IX. | $35\frac{1}{2}$ | 32 | 29 | 26 |
| Bouvet | 12 | 33 | 29 | 26 | $24\frac{1}{2}$ |

The resistance of the Royal Sovereign's barbette is equal to $21\frac{1}{2}$ inches, and that of the Brennus' turrets $22\frac{1}{2}$ inches wrought iron.

Then we see that the percentage of piercing hits out of the total number striking the target is as under :—

TABLE IV.

| TARGET. | Piercing Hits per cent. | | | |
|---|-------------------------|------------|------------|------------|
| | 1,000 yds. | 2,000 yds. | 3,000 yds. | 4,000 yds. |
| Royal Sovereign (barbette) } fired at by Brennus . . } | 66 | 59 | 53 | 44 |
| Brennus (turret) fired at by } Royal Sovereign . . . } | 53 | 44 | 35 | 15 |

At 3,000 yards about half the armour-piercing shot striking the Royal Sovereign's barbette will do no harm, whilst two-thirds of her hits on the Brennus' turrets will be equally harmless. At 4,000 yards the Brennus gets in nearly three times the number of piercing hits obtained by her opponent. But even at 3,000 yards it will be good practice if 10 per cent. of the rounds fired strike the barbette or turret at which they are aimed, so that at this range the Brennus would have to fire nineteen rounds before getting a piercing hit, and the Royal Sovereign twenty-nine, whilst at 4,000 yards the numbers would be thirty-eight and one hundred and ten. At 2,000 yards, however, where the hits should be one in five, the Brennus would only have to fire eight rounds and the Royal Sovereign ten. In the above case the guns most decidedly overmatch the armour; but in a duel between the Bouvet and Implacable the figures would be for every 100 shot striking the target :—

TABLE V.

| Target. | Piercing Hits per cent. | | | |
|---|-------------------------|------------|------------|------------|
| | 1,000 yds. | 2,000 yds. | 3,000 yds. | 4,000 yds. |
| Implacable (barbette) } fired at by Bouvet . . } | 40 | 20 | Nil. | Nil. |
| Bouvet (turret) fired at } by Implacable . . . } | 45 | 30 | 15 | Nil. |

Here, at 3,000 yards, the Implacable's barbette is impenetrable, and some six hits out of seven would fail to pierce the Bouvet's turret; or, assuming as before that one-tenth of the rounds fired hit the turret, it would take sixty-seven rounds to disable it, far more

15.8
270


than the number of armour-piercing shot carried. If the ships closed to 2,000 yards one shot in five might hit turret or barbette, therefore at this range seventeen rounds from the Implacable should give one piercing hit, whilst the Bouvet would require to fire twenty-five.

Should
heavy
guns fire
armour
piercers or
common
shell?

It is often objected that it would be out of the question to devote the services of a heavy gun for perhaps half an hour (25 rounds per half-hour is a good record for a single gun) to silencing an opposing gun protected by turret or barbette. Shot ought not to be fired, say these objectors; shell should be resorted to. But if a heavy gun takes to firing shell, it at once puts itself into competition with the quick-firing guns, which are infinitely superior for this purpose. For example, a 12-in. gun fires in one minute one 850-lb. shell with bursting charge 80 lb. Eight 6-in. guns weigh about the same as one 12-in.; they can fire in one minute shells aggregating 3,200 lb. with some 300 lb. of bursting charge. Moreover, the 6-in. shells will hit the enemy in thirty-two places, the 12-in. shell in only one. Nor is it in the least clear how even a 12-in. shell bursting outside the armour is going to damage anyone or anything inside. All trials have shown that shells breaking up on the face of armour plates which they are too weak to pierce do no harm. It is perfectly evident from the fact that the battleships of all nations carry nothing between the heaviest quick-firing gun and the lightest big gun capable of piercing their opponent's thick armour, that the rôle of the heavy gun is essentially armour-piercing, and that all nations intend to use quick-firing guns for shell fire, heavy guns for attacking armour.

There are, of course, many heavy guns mounted which can be more readily silenced by shot or even shell from quick-firing guns than by the comparatively slow process of pounding at the armour with heavy shot, but this is due to errors which will not be repeated in new ships. The guns of the Majestic and Royal Sovereign classes are unfortunate cases in point. These guns are loaded fore and aft, but the end-on fire of the ships is so weak, and the broadside fire so strong, that they must needs bring an enemy to bear on the beam or nearly so. This exposes the chase of the gun when loading, and in the case of the 13.5-in. much of the breech as well, broadside on to the enemy's fire. A gun end on to the enemy's fire runs little or no risk; the target is extremely small and extremely invulnerable. Many guns have been hit in this position without being put out of action. But broadside on the target is very large (see sketch), and even a 4-in. shell will disable a 12-in. gun striking it in this position. As the target afforded by a 12-in. gun in the

loading position is more than one-sixth the size of the prize-firing target, which at 1,500 yards is hit six times in five minutes by a single 6-in. Q.F. and about twice as often by a 4-in. Q.F., one 6-in. gun firing for five minutes, or one 4-in. firing for two and a half minutes, could, at 1,500 yards, disable a 12-in. gun in the Majestic class, supposing the latter was always in the loading position. If half the time was spent in the loading position the periods would be: 6-in. gun ten minutes; 4-in. gun five minutes. The Royal Sovereign would be worse off, as the target is larger, and the time spent in the loading position relatively longer. Of course all this is at the comparatively short range of 1,500 yards. Still at 3,000 yards a single 6-in. gun should not take more than half an hour to disable a 12-in. gun loading from a fore and aft fixed position, and a quarter of an hour



Chance of
disabling
heavy gun
without
piercing
armour.

should suffice for the 13.5-in. of the Royal Sovereign class. A modern armoured cruiser, say the Japanese Asama, would make exceedingly short work of the Royal Sovereign. The only guns in the battleship which can silence the Asama's four 8-in. and ten 6-in. Q.F. guns, all protected by 6 inches of Harveyed steel, are the 13.5-in. guns, and these, as shown above, would be quickly silenced if, say three 6-in. Q.F. were devoted to the task, all firing at the barbette which happened to be loading. The Asama, having the speed, would close in to 2,000 yards or so, where the three quick-firers would finish their work in three or four minutes. Even at 4,000 yards both 13.5-in. barbettes ought to be out of action in a quarter of an hour or twenty minutes. In the meantime the Asama's four 8-in. Q.F. and

Royal
Sovereign
v.
Asama.

Dangers
of the
Royal
Sovereign
class.

the remaining two protected 6-in. Q.F. would, with the two unprotected 6-in. Q.F., make short work of the five 6-in. Q.F. on the Royal Sovereign's broadside, only two of which are protected, and that by but 6 inches of compound armour, which would be riddled with great ease by armour-piercing shell from the 8-in. guns or by shot from the Asama's 6-in., which are themselves protected by armour impenetrable to the 6-in. shot of the Royal Sovereign. Once the Royal Sovereign's guns were silenced, the threat of a torpedo must bring her flag down. A far smaller ship than the Asama, such as the Italian Varese, of 7,400 tons, would indeed suffice to capture the Royal Sovereign; all that is needed is ten or a dozen 6-in. Q.F. protected by 5 inches of Krupp steel, and with water-line similarly protected. The only remedy for the Royal Sovereign appears to be to give her new barbettes with 11-in. Krupp armour and 12-in. IX. guns, the weight saved being put into 6-in. Krupp armour for the protection of six 7.5-in. guns to take the place of the six 6-in. Q.F. on the upper deck. But is the ship worth it, looking at her inferior speed? If the answer is No, the alternative is to build eight new battleships to replace the Royal Sovereign and her seven sisters. Such ships as these latter, which, owing to improvements in armour, cannot face modern ships of half their size, and which, owing to their 15 knot speed, must act as a serious drag on a fleet of Russells, Formidables, or Oceans, all good for $17\frac{1}{2}$ knots, should not be retained in our list of first-class battleships.

TABLE VI.

PIERCING POWER IN WROUGHT IRON OF TYPICAL Q.F. GUNS NOW AFLOAT IN BATTLESHIPS.

| GUNS. | PIERCING POWER.—WROUGHT IRON. | | | |
|------------------------------------|-------------------------------|--------------|--------------|--------------|
| | 1,000 Yards. | 2,000 Yards. | 3,000 Yards. | 4,000 Yards. |
| | Inches. | Inches. | Inches. | Inches. |
| 6-in. VII. | 17 | 14 | 11 | 9 |
| 6.46 French | 16 | 13 | 10 | 8 |
| 5.46 French | 14 | 11 | 8 | 6 |
| 6-in. Q.F. | 13 | 10 | 8 | 6 |
| 5.46 French earlier patterns . . . | 10 | 7 | 5 | 4 |

Looking back at Table I. it is apparent that since the adoption of cemented plates the protection of the heavy quick-firing guns

used as the secondary armament has been enormously increased. For the last twelve years British and American ships have taken the lead in this important matter, so that whilst nearly all ships built on the Continent had only such armour for the protection of their secondary armament as could easily be penetrated by the quick-firing guns carried by their rivals, British ships were being furnished with casemate armour well nigh or quite impenetrable except by the heavy guns.

Armour
for the
protection
of
secondary
arma-
ments.

In her day the Royal Sovereign's casemate armour, with resistance equal to $7\frac{1}{2}$ inches wrought iron, was absolutely impenetrable by the old pattern 5.46 gun at 2,000 yards, but her 6-in. Q.F. would even at 4,000 yards (see Table II.) send 43 per cent. of the shot which hit through the Charlemagne's turrets (equal to 5 inches wrought iron), and at 2,000 yards 78 per cent. The improvement of the 5.46 gun and the adoption of the 6.46 has made the Royal Sovereign's armour penetrable at 3,000 and 4,000 yards respectively; but the Majestic's casemates (equal to 12 inches wrought iron) are perfectly safe from the 5.46 at 2,000 yards, and only some 30 per cent. of the 6.46 hits pierce at the same moderate range.

In the case of all new ships with 6-in. Krupp armour, equal to from 15 to 18 inches of wrought iron and quite impenetrable to our best 6-in. at quite short ranges, such as 1,500 yards, it is evident that more powerful guns are required, having a penetration of from 18 to 20 inches of wrought iron at 2,000 yards. Even if 3,000 ft. secs. muzzle velocity could be attained *with a service charge* from the 6-in. as has been promised by some sanguine prophets, this would not suffice, and a more powerful gun is an absolute necessity.

The Americans claim the following velocities and energies from their latest guns, which correspond to penetrations as under:—

Power of
latest
Q.F.
guns.

TABLE VII.

| GUN. | Muzzle Velocity. | Weight of Projectile. | Muzzle Energy. | PENETRATION. | | | | | | | |
|------------|------------------|-----------------------|----------------|--------------|-------|------------|-------|------------|-------|------------|----------------|
| | | | | 1,000 Yds. | | 2,000 Yds. | | 3,000 Yds. | | 4,000 Yds. | |
| | | | | W. I. | K. S. | W. I. | K. S. | W. I. | K. S. | W. I. | K. S. |
| | f. s. | lbs. | ft. tons. | | | | | | | | |
| 6-in. Q.F. | 2,900 | 100 | 5,838 | 19 | 7 | 16 | 6 | 18 | 5 | 10 | 4 |
| 8-in. Q.F. | 2,800 | 250 | 13,602 | 27 | 11 | 23 | 9 | 20 | 8 | 17 | $6\frac{1}{2}$ |

But the 8-in. is not a quick-firer. The British 7·5-in., with a rate of fire of four rounds per minute, has the following power, which fairly meets the case, a cordite charge being used :—

TABLE VIII.

| Gun. | Muzzle Velocity. | Weight of Projectile. | Muzzle Energy. | PENETRATION. | | | | | | | |
|--------------------------|------------------|-----------------------|--------------------|--------------|-------|------------|-------|------------|-------|------------|-------|
| | | | | 1,000 Yds. | | 2,000 Yds. | | 3,000 Yds. | | 4,000 Yds. | |
| | | | | W. I. | K. S. | W. I. | K. S. | W. I. | K. S. | W. I. | K. S. |
| 7·5-in. Q.F. of 14 tons. | f. s. 2,600 | lbs. 200 | ft. tons. 9,388 | 22 | 8½ | 19 | 7 | 16 | 6 | 13 | 5 |

With such a powder as that used in America, which gives a higher velocity than cordite, a 6-in. Krupp plate would be pierced at 3,000 yards by some 40 per cent. of the shot striking, and this should be sufficient; but nothing less than a 14-ton gun will at all meet the case, and it almost looks as if the old duel between guns and plates is to be repeated with quick-firers, and we may soon see 9·2-in. quick-firers pitted against 9-in. plates.

Recent trials of armour plates.

There is nothing very remarkable to record this year in connection with armour plate trials. Plates treated by the Krupp and similar processes have attained such a degree of excellence that it is difficult to see how they can improve. Still there is no doubt that the plates exhibited by the Terni Company at the Paris Exhibition, if not an improvement on what has hitherto been obtained, were extremely good, and we therefore give the results of trials of two of them.

5·9-in. Terni special plate.

"Terni Special" plate: 7·9 ft. by 5·25 ft. by 5·9 in., tried at Muggiano (Spezia), 23rd May, 1899. Gun 6-in.; projectile, Krupp armour-piercing shot, weight 100 lbs.

| Round. | Striking Velocity. | Effect on Plate. | By Tressider's Formula. | |
|--------|--------------------|---|----------------------------|------------------|
| | | | Penetration. Wrought Iron. | Figure of Merit. |
| 1 | f. s. 1,936 | Projectile broke up on the face of the plate. Greatest penetration 4·3 inches. No cracks. | 13·2 | 2·26 |
| 2 | " | | " | " |
| 3 | " | | " | " |
| 4 | " | | " | " |
| 5 | " | | " | " |
| 6 | 2,313 | Plate just pierced, the point of the projectile remained in the backing without injuring the inner skin. No cracks. | 17·2 | 2·92 |

The first five rounds are evidently of a similar character to the standard rounds fired for the test of plates at Whale Island, and it was only to be expected that the plate would defeat with ease projectiles capable of piercing a wrought-iron plate two and a quarter times its thickness. But the sixth round is a very severe test; it struck comparatively close to the edge and to the points of impact of three other rounds. Nevertheless, it was stopped by the backing, and did no material harm, so that this plate attains the very remarkable figure of merit of 2.92, which has scarcely been exceeded anywhere.

The next plate to which we would call attention is also a Terni plate, but only 4.3 inches (11 cm.) in thickness. Plates of this thickness are of great interest at the present time, as they are being supplied to the smaller type of armoured cruisers, such as our "Essex" class, and until recently it was an exceedingly moot point if the cementing process could be applied with advantage to such thin plates. It would have been more interesting if, in addition to the rounds fired by the 4.7-in., a round had also been fired from the 6-in. gun at the Terni plate. Our own 6-in. Q.F. has only a penetrating power of 10 inches of wrought iron at 2,000 yards, and this is the sort of blow that a 4-in. or 4½-in. plate is likely to get on service.

"Terni Special" plate: 6.5 ft. by 5.25 ft. by 4.3 in., tried at Muggiano (Spezia), 20th February, 1900. Gun 4.7-in.; projectile, Terni armour piercing; weight 45 lb.

Other
Terni
special
plates.

| Round. | Striking Velocity. | Effect on Plate. | By Tresidder's Formula. | |
|--------|--------------------|---|----------------------------------|---------------------|
| | | | Penetration. Wrought Iron. | Figure of Merit. |
| 1 | f. s. 1,887 | Penetration 2.75 ins. Point of projectile left in plate | 9 5 | 2 2 |
| 2 | " | Penetration 2.64 ins. Projectile broken as before | | |
| 3 | " | Projectile broken. Penetration not measured | 11.3 | 2.62 |
| 4 | 2,116 | Projectile broken. Penetration not measured | | |
| 5 | 2,198 | Projectile broken. Penetration not measured. Bulge at back, 2.4 ins. high, 3 radial cracks | 12.0 | 2.77 |

There were no cracks. The resistance to the last round was most remarkable. A figure of merit of 2.77 is excellent for a 6-in. plate, but for a plate as thin as 4.3 inches it is, so far as we are aware, quite unprecedented, and the Terni works may be congratulated at obtaining such a very good result, more especially since their

experience as manufacturers of armour plates is not very extensive. The Terni firm also exhibited a 3.54-in. plate, which was just matched by a 12-pdr. shot with piercing power of 9-in. wrought iron, giving the excellent figure of merit of 2.55, and a 3-in. plate which was only just pierced by a 12.2-lb. shot, velocity = 2,306 ft. sec., piercing power 8.4 ins., figure of merit 2.8 nearly (see Fig. 1).




FIG. 1.—TERNI 3-IN. PLATE WITH FIGURE OF MERIT 2.8 (NEARLY).

Non-
cemented
plate.

One of the last articles written by Captain Orde Browne (see *Engineer*, August 3rd, 1900) described the trial of a 4-in. K.N.C. (Krupp non-cemented) plate made by Messrs. Cammell and Co., when a 4-in. plate completely defeated a 4.7-in. shot with velocity of 1,813 ft. sec. and penetrating power 9 inches, the corresponding figure of merit being 2.25. The British plate was not tested up to its limit of resistance, so there is no evidence whether it was or was not up to the very high standard of the Italian plates; but we have had

no published results of trials of 4-in. plates in England where the figure of merit rises above 2·25, and 2·2 has generally been considered a good figure for plates of this thickness.

But even with a figure of merit of 2·5 or 2·7, a 4-in. plate is not a sufficient safeguard against 6-in. projectiles from the most recent guns, for at 3,000 yards such a plate can be perforated by the 6-in. VII. gun; from 25 to 35 per cent. of the hits piercing, whilst at 2,000 yards 50 per cent. would perforate.

But little progress has been made this year with caps for armour-piercing projectiles. There is no doubt that when the cap acts it is most efficacious, increasing the piercing power from 10 to 15 or even 20 per cent.; but it does not always act with direct fire, and does not act at all with oblique fire beyond, say, 20° from the normal. Still a cap may be very useful when a gun is barely up to piercing a plate. Take, for example, the case of a French 5·46 gun trying at 2,000 yards to silence a 6-in. Q.F., in one of the Majestic's casemates, with protection equal to 12 inches wrought iron, whilst the 5·46 is only good for 11 inches. The French ship might not like to close in to 1,500 yards for fear of torpedoes, but the use of capped shot would cause most of the projectiles striking within 20° of the normal to penetrate; these would amount to (see Table II.) some 30 per cent. of all the hits on the casemates. On the other hand, if the gun had sufficient power to penetrate 13 inches without a cap, which it would have at 1,300 yards, some 30 per cent. would pierce in any case. And the use of a cap would not increase this percentage at the short range, for it would not assist these rounds that struck at more than 20° to the normal. Or let us consider the case of the 12-in. Mark IX. gun attacking one of the Bouvet's turrets, which has a resistance equal to 29 inches wrought iron. We get the following results:—

Caps for
armour-
piercing
projectiles.

12-IN. B.L. MARK IX. *v.* TURRET OF BOUVET, 16-IN.
HARVEYED STEEL.

PERCENTAGE OF PIERCING HITS AT RANGES AS UNDER.

| | 1,000 yds. | 1,500 yds. | 2,000 yds. | 2,500 yds. | 3,000 yds. | 3,500 yds. | 4,000 yds. | 4,500 yds. |
|-----------------|------------|------------|------------|------------|------------|------------|------------|------------|
| Uncapped shot . | 45 | 39 | 32 | 26 | 15 | Nil. | Nil. | Nil. |
| Capped shot . . | 45 | 39 | 36 | 32 | 30 | 25 | 25 | Nil. |

The same proportion of piercing hits can be obtained with the cap at 4,000 yards as without it at 2,500, in each case some 25 per cent. of the shot which strike the turret will pierce; the remainder will fail. But it may not be considered desirable to fire shot at all

at 4,000 yards, because the chance of hitting a small object like a turret is but slight. Say that eleven rounds out of twelve miss the turret, then forty-eight will have to be fired for one piercing hit. Some one or two of the rounds missing the turret might, however,




FIG. 2.—BETHLEHEM KRUPP PLATE FOR RETVIZAN ATTACKED BY CAPPED AND UNCAPPED SHOT.

land on the belt or on one of the secondary turrets; the latter would be destroyed and the former pierced. If shell were used in lieu, the chance of piercing belt or large turret would be surrendered, a small turret might equally be wrecked, but there would be somewhat more effect where there is no armour to balance against the chance of a piercing hit. The guns mounted without armour in the Bouvet

are eight 4-in. Q.F., four firing on each broadside; it can scarcely be contended that it is desirable to fire shell from four 12-in. guns in the hope of disabling four 4-in. guns. Above the water-line a 12-in. shell will smash in the upper (4-in.) belt, but a shot would do the same.




FIG. 3.—BETHLEHEM KRUP PLATE FOR RETVIZAN ATTACKED BY CAPPED AND UNCAPPED SHOT.

Therefore the 4-in. guns can well be left to the 6-in. and 12-pdrs., and the 12-in. would profit by having capped shot supplied, so as to be capable of piercing the turrets and silencing the heavy guns of an opponent at as long a range as possible.

Caps are certainly being issued in America, France, and Russia, but it is not known whether they have been adopted in Germany or

Capped
shot used
at trials of
plate for
the
Retvizan.

Italy. It is, however, a notable fact that all supplies of armour plates are tested by firing uncapped projectiles. The photographs reproduced (see figs. 2 and 3) are principally interesting as showing the advantage gained by using a cap when attacking a Krupp plate direct. The plate, though nominally 9 inches, was actually 9·3 inches thick. It was the proof plate for the acceptance of the turret armour of the Retvizan. It was first subjected to four rounds from the 8-in. gun. For the seventh round a so-called "decapping device" was placed in front of the plate. This consisted of an ordinary thin plate about $\frac{5}{8}$ -in. thick, backed by 4 inches of wood. Whether it actually assisted the projectile cannot be stated with certainty, for capped projectiles often give capricious results, but there is no doubt that the sixth round, which had the same velocity, was easily stopped, whilst the seventh went clean through. Whether or no the perforation was due to the cap, the decapping device, or both combined, the photograph shows clearly enough that the projectile held together and was but little deformed, and thus easily tore its way through. On the other hand, the first four projectiles were all mushroomed out to nearly twice their original diameter, whilst the fifth and sixth were also set up and broken, but to nothing like the extent of the first four.

9·3-INCH BETHLEHEM KRUPP PLATE FOR THE TURRET OF RETVIZAN.

| Round. | Weight of Shot. | Striking Velocity. | By Tresidder's Formula. | | Effect on Plate and Shot. |
|--------|-----------------------|--------------------|----------------------------|------------------|---|
| | | | Penetration. Wrought Iron. | Figure of Merit. | |
| | | ft. sec. | inches. | | |
| 1 | 252½ | 2,088 | 20·3 | 2·17 | Projectile crushed, penetration small. |
| 2 | " | 2,065 | 20·0 | 2·14 | |
| 3 | " | 1,991 | 19·0 | 2·04 | |
| 4 | " | 1,968 | 18·6 | 2·0 | |
| 5 | { 258½ with cap. } | 1,907 | 17·9 | 1·93 | Projectile held together fairly, penetration evidently more than previous rounds. Complete perforation. |
| 6 | | 1,951 | 18·6 | 2·0 | |
| 7 | | 1,947 | 18·6 | 2·0 | |

An alternative proposal to protecting the points of armour-piercing projectiles with caps is to make the shot flat-headed. If the plate attacked is hard enough to crush the point of the shot, the destruction of the whole projectile is easily attained, and the only chance the projectile then has is to punch out a piece of plate at least equal in diameter to the crushed-up shot. But if from the first it is decided to attempt punching rather than piercing, there is no doubt that a flat head must be superior to a pointed one. This was

established by some trials which recently took place with a 6-in. gun against a modern Krupp process plate 7 inches in thickness. Two flat-headed projectiles, with energy sufficient for piercing some 14 inches wrought iron, penetrated to a depth of 6 inches each, whilst a third, with energy corresponding to a penetration of 16 inches of wrought iron, went through easily. Thus a plate which against pointed projectiles might have been expected to show a figure of merit of 2·65, had considerably less than 2·3 when attacked by flat-heads.

Question of blunt heads v. sharp points for piercing hardened plates.

The objection to flat-heads is that they are decidedly inferior to pointed projectiles when attacking non-cemented plates, but as ships with non-cemented plates are already in a minority amongst first-class ships, the adoption of either caps or flat-heads seems to be most desirable. Caps if equally efficacious, as seems to be the case, have one most important advantage, that they can be applied to existing projectiles, whereas the adoption of flat-headed projectiles would entail the condemnation of a most costly stock of pointed armour-piercers.

Summary and Conclusion.

No great advance has taken place in the manufacture of either plates or projectiles in 1900; the cementing process is now applied to all thicknesses of plates down to 4 inches with great success. If the toughening processes initiated by Krupp are not in universal use, similar results are at any rate obtained in nearly all armour factories, and the production of excellent plates is proceeding at a great rate all the world over.* Hitherto the very best projectiles have entirely failed to tear a clean hole in plates as now produced. In all cases the point of an uncapped shot is crushed. Caps have been used with some success to prevent the utter destruction of the shot on striking, but their action is uncertain, and they fail when striking obliquely.

General conclusion as to plates and projectiles in 1900.

The improvements in the quality of armour allow a given weight to be spread over a wider area, and the protection of the quick-firing guns is now very efficient, and water-line armour has been much extended. The modern ship should require a great deal of hammering to bring her to terms, and seeing that the improvement of torpedoes conduces to long range fire, a large amount of ammunition, especially of armour-piercing projectiles, will be needed.

* Three 4-inch non-cemented plates, manufactured by Sir W. G. Armstrong, Whitworth & Co. at their Openshaw works, were tested at Whale Island in April, 1901, these being the first plates of the class submitted by this firm. The gun was the 4·7-in. with 45 lb. armour-piercing projectiles, striking velocity about 1,633 f.s. Three shots were fired at each plate. The *maximum* penetration was just over 1 inch, and, when the plates were taken down, there was no appearance of any bulge or cracks on the backs, and as far as the appearance of the backs was concerned, it was impossible to tell that they had ever been fired at. All the projectiles were shattered by the impact on the surface of the plates. Previous trials of 6-inch plates made by the same firm had given excellent results.

CHAPTER II.

SHELL FIRE.

THE BELLEISLE EXPERIMENTS.

DURING the early summer of 1900 it was announced that the Admiralty had determined to carry out certain experiments, using the old Belleisle as a target ship for various kinds of shell, the experiments having special reference to the risk of fire entailed on ships going into action without removing the multitudinous wood fittings with which every ship built before 1895, and most of those built since, have been only too liberally provided.

The account which follows is mainly taken from the pages of the *Engineer*, whose representative seems to have obtained a fuller history of what happened than most of the other representatives of the press. In some instances, however, information has been culled from other public prints, especially from the *Times*, and where two or more independent accounts agree in traversing the narrative as given in the *Engineer* or *Times*, these independent accounts have been followed.


The general aspect of the Belleisle can be gathered from the sketches and photographs. She had a complete belt, with an armoured battery amidships, the armour (wrought iron) varying in thickness from 6 to 12 inches. The deck in line with the top of the belt had from 3 inches to 1 inch of armour. That covering in the battery was 1 inch thick. She carried four 12-inch R.M.L. guns in the battery, and six 6-pdr. quick-firers, and six machine guns on the top of battery.

Conditions
of the ex-
periments.

The Belleisle was moored head and stern with some three or four feet of water under her bottom, and was attacked by the *Majestic*, which steamed in an elliptical course round the doomed ship. Fire was opened from the starboard broadside when the *Majestic* was right astern of the Belleisle and 1,700 yards off. From this position she gradually closed until she passed the port beam of the Belleisle at 1,300 yards and was about 1,700 yards off on the port bow of the Belleisle, when fire ceased after a period variously reported as being

from six to eight minutes. The speed of the *Majestic* was about ten knots. The *Majestic* fired, as far as can be ascertained—eight rounds 12-in. common shell, seven rounds 12-in. A.P. shot, about 100 6-in. lyddite at bow and battery, about 100 6-in. common at stern, about 400 12-pdr. common, and about 750 3-pdr. A.P. shell. Full charges were used throughout for all guns.

Roughly speaking, about thirty or forty per cent. of the projectiles fired were said to be effective, but there is no evidence to show that any of the 12-in. armour piercers struck the armour. This projectile has a penetrating power of 30 inches of wrought iron, so that it should easily have gone in at one side and out at the other (see diagram showing thickness of armour). It is therefore



pretty clear that either none were fired, or that if they did not miss altogether, they passed harmlessly through the light upper works. The projectiles that hit were, therefore, all shells. With regard to the condition of the ship for resisting the inflammatory effect of shells, not only was nothing removed in the way of splinter-making or inflammable material, but the men's kits, hammocks and mess gear, officers' bedding and furniture, and all the ordinary woodwork of cabins and living places, was left *in situ*. Boats were all in their places, some on the upper deck, others in crutches, some little height above the deck, and others again at the davits. Some spare spars were on deck stowed under the boats. On the other hand, the ordinary precautions against fire were taken as far as the circumstances allowed. The decks were well flooded beforehand, and the

The
Belleisle
before the
firing.

The ship
not set on
fire.

pumps were kept going, delivering a stream of water on to the various decks whilst the ship was being battered. In addition to the ordinary wood fittings, a crew of 130 wooden dummies were placed at the various guns and for passing ammunition. The guns' crews of the 6-prs. were all exposed on the upper deck, those at the 12-in. guns were protected by the battery armour. But, notwithstanding the numbers of shells that struck and burst, the *Belleisle* was not set on fire. It was stated by Mr. Goschen in the House that there was only a little smouldering fire in one of the cabins amongst some clothes, and this notwithstanding that the woodwork was shattered in all directions, and the whole of the interior of the ship was filled with wreckage. But the *Times* and other reporters who gave account of the firing all believed that the ship was on fire, and spoke of the immense volumes of smoke that rose from the fated ship. This smoke must have been entirely due to the bursting shell. Nor is it remarkable that this should entirely hide the ship, and stream out at every orifice in dense clouds, seeing that the bursting charges of shells estimated to hit were about as under :—


| | Bursting Charges. | |
|------------------------------|-------------------|----------|
| | Gunpowder. | Lyddite. |
| | lbs. | lbs. |
| 5 12-in. shells | 405 | — |
| 75 6-in. „ | 380 | 500 |
| 140 12-pdr. shells | 180 | — |
| 200 3-pdr. „ | 35 | — |
| | 1,000 | 500 |

A battleship in the present day uses some 20 lb. of powder for a twenty-one gun salute, and even in the old days of big smooth bores 100 lb. sufficed. No wonder then that powder sufficient for some fifty salutes on the new scale, and for ten on the old scale, to say nothing of half as much lyddite, produced clouds of dense smoke, through which the gunners of the *Majestic* could scarcely perceive their target, and which must have considerably affected the accuracy of their fire.

The
damage
inflicted.


As to the effect of the shells, the armour only seems to have been penetrated in three places, twice by 12-in. shells and once by 6-in. One 12-in. shell, described by the *Times* as a gallery shot, caught the upper corner of the citadel on the port after angle; checked by the massiveness of the target (6-in. wrought iron), it exploded, wrecking

Stars show shells which broke up without penetration; holes where penetration was effectual.



SKETCH SHOWING THE GENERAL EFFECT OF SHELL FIRE ON THE BELLE ISLE AS VIEWED FROM OUTBOARD.
(From the Engineer.)


the platform on which the conning tower stands, and doing immense damage inside the battery, though the guns themselves and heavier parts of mountings were uninjured. It seems to have been this shell which caused the wreckage of all the dummies, described by the *Engineer*, inside the battery, where it is also said that the sights and "gear" of the guns sustained such damage that, though the guns themselves were uninjured, they could have been, of no



MARK OF LYDDITE SHELL ON ARMOUR OF BELLEISLE.

use. Several small shells, from 3-pdrs. and 12-pdrs., may have passed through the ports and have contributed to this damage. Another 12-in. shell struck on, or just below, the water-line amidships, where the plating varies from 12 inches to 8 inches in thickness. It made a large hole, and, though it did not send anything down into the engine room, was undoubtedly the cause of the sinking of the ship, which took place some minutes after the completion of the practice.

Another entered the unarmoured lower deck forward, and cut the spindle of the capstan, whilst a fourth is reported to have cut down the funnel and utterly wrecked the funnel casing.




HOLE PUNCHED BY 6-INCH SHELL, 10 INCH IN DIAMETER.

With regard to the effect of the 6-in. shells, only one punched its way through the armour; a sketch of the hole is reproduced from the *Engineer*. As is usual where an inferior projectile is used, the hole is much larger than the original diameter of the shell, showing that the head of the shell was crushed and the body expanded, but just succeeded in punching its way through, probably assisted by the lack of toughness of the plate, which was 6 inches thick at the spot struck. All the rest

of the 6-in. shells which struck the citadel or belt broke up harmlessly against the armour, with the one exception—pointed out by the *Times*—that several lyddite shells which struck the plating forward, near the water-line, had so hammered it as to cause a dangerous leakage. A 6-in. shell appears to have grazed the edge of one of the gun-ports of the battery, bursting as it did so, but the gun beside the burst was not damaged.


A writer in the *Engineer* argues from the slight effect of the 6-in. common shell, notwithstanding their pointed heads, that, for efficiency, projectiles should either be made of hardened steel with strong tough heads, and if necessary reduced bursting charges, for dealing either with armoured or unarmoured parts, or should be made with the view of holding the largest possible bursting charge; and that the best shell exclusively for the attack of the unprotected structure is a nose-fuzed shell filled with lyddite.

The unarmoured parts of the ship before and abaft the central citadel were simply riddled by the bursting shells, both 6-in., 12-pdrs., and 3-pdrs., but there was a marked difference between



MARK OF 6-INCH SHELL WHICH GRAZED EDGE OF PORT.

the effect of the powder-filled 6-in. fired at the after part of the ship and that of the lyddite shell fired at the fore part. Between the damage done by one and the other there was no comparison. While the 6-in. common destroyed as one might destroy a wood box with an axe, lyddite completely pulverised the wood, acting in a moment much as dry rot acts in a score or two of years. Moreover, where 6-in. common shell burst between the decks, the deck above shewed no sign of it; but it was quite another thing with lyddite. Not only were huge holes blown upwards, but the entire deck was bulged up. These holes are well shown in the sketches taken from the *Engineer*.




THE ONLY BOAT LEFT ON BOARD THE BELLEISLE.

Some claim that the funnel was cut down by 12-in. common, others that a 6-in. lyddite shell did the damage; possibly both contributed. One of these shells also cut a steam pipe down below, a fragment having passed through the gratings of the funnel. The 6-pdrs. on the top of the battery were all disabled, and all the dummies stationed round them were "killed." Those on the port side were said to have been disabled by the upward radiating action of lyddite shell striking the armour below them, which radiating action is well shown in the sketch. The *Times* correspondent argues from this fact that light guns should be somewhat recessed back from

the armoured side in order to avoid this contingency. The lyddite shell smashed up and overturned the unarmoured structure on the fore-castle used as a seaman's head, but the masts, though riddled, stood, although most of the rigging was shot away. The conning tower does not appear to have been hit, though the dummies inside it were broken by the concussion of one of the shells striking the boats and bridge close to it.

The only boat left was the steam pinnace, of which a sketch is given. It is not hard to understand from this sketch why the others disappeared.

The armoured deck does not appear to have been pierced. A correspondent of the *Engineer* states that several lyddite shells burst close to the deck where it was 2 inches thick without injuring it at all. At least one 12-in. shell also burst close to the



Port after corner of Battery ,
showing damage to thin plating .

deck without causing serious injury, and generally the gas from the shells seems to have sought the line of least resistance, which in the case of the *Belleisle* was usually upwards.

In fact, there was nothing to show that a shell bursting between decks under the floor plates of a turret or barbette in ships like our Admiral class would do any damage on the other side of the plating. Moreover, the almost prohibitive difficulty of getting a shell to burst where required, namely, exactly under and close to the floor plating of a barbette, is sufficiently obvious.

The 12 and 3-pdrs. did well as regards riddling all unprotected structures, but the difference of effect of the hard steel 3-pdr. shell which pierced deeply into the armour, and the soft steel 12-pdrs. which splashed harmlessly against it, was very noticeable. But the general destruction of unarmoured parts was such as to make it impossible to identify the damage caused by each individual shell of small calibre. All was swallowed up in a general ruin, which is well shown in the sketches reproduced from the *Engineer*. It

seems possible, if not probable, that the 3-pdrs. and 12-pdrs. alone would have fully sufficed to wreck and destroy all the unarmoured parts of the ship, and to put out of action the unprotected guns, so that a large proportion of the 6-in. guns might have advantageously fired armour-piercing projectiles for piercing the battery and water-line. But the object of the experiment being apparently to ascertain the effect of shell and not to sink or destroy the *Belleisle*, ordinary shells were naturally fired in lieu of armour piercers.


Possibilities of torpedo attack.

It was remarked by many observers than an attack by torpedo craft, if supported by even half or a quarter of the shell fire directed against the *Belleisle*, would have considerable chance of success. The smoke alone which was poured out by the bursting shells in dense volumes would act as a screen for the torpedoists, and the fire of guns quite unprotected by armour would be very wild and slow under a shower of bursting shells. It certainly appears an open question, whether in our larger battleships and cruisers some protection should not be given to the men actually fighting the light quick-firing guns on which we must mainly rely to beat off a torpedo attack, and which might be assailed by the quick-firing guns of supporting ships.

Lyddite shells.

No very exact information is to hand as to the destruction of the unarmoured side by lyddite shells. But judging by the photograph given in the *Engineer* showing the ship being towed into harbour, the damage must have been most extensive, and it bodes anything but well for the water-line of our very numerous protected cruisers. In this connection the effect of a single shell, apparently a 6-in., gives serious grounds for reflection. This shell blew away a large piece of plating, said by the *Engineer* to measure 10 ft. square; which happened in this way.

The shell entered some feet abaft the junction between the thin plating of the lower deck and the armour of the casemate, passed



Section of Port Aft Corner of Battery, shewing damage to thin plating by 6" shell.


through the outer plating, and burst against the casemate bulkhead. The gases caused by its explosion, unable to affect the casemate armour or armoured deck, rebounded and blew an enormous hole in the ship's side. If the rough sketch be looked at sideways it will be seen that the bulkhead might be taken to represent the sloping armoured deck in, say, the Diadem or Terrible. The object of this sloping armour is to stop shells which strike about the water-line. In doing this there seems a great liability that very large gaps will be blown in the ship's side. The only remedy would seem to be to give the gases free scope upwards inside the ship in some direction where they would be harmless, by no means a simple matter.

It is perfectly obvious that shells will burst after entering the unprotected parts of all ships, whether battleships or cruisers, but it seems extremely doubtful whether we are in the habit of so building our ships that the gases may do as little destruction as possible. Much might certainly be done to give shells which burst between decks, &c., a chance of discharging their gases comparatively innocuously. Large hatches, somewhat after the fashion of the old skids, might be made between main deck casemates; whilst on the other hand, in unarmoured cruisers, bulkheads or screens should be arranged so as to protect the men between decks from the blast of shells bursting before or abaft them.

Provision
for the
escape of
gases.


Conclusion.

The Belleisle experiments demonstrated most forcibly that armour gives most efficient protection against shell fire, and that the unarmoured parts of a ship are hopelessly untenable under the fire of a number of quick-firing guns.



THE BELLE ISLE BEING TOWED INTO HARBOUR AFTER BEING FLOATED.

(From the *Engineer*.)



SKETCH OF THE BELLEISLE IN DOCK.

(From the Engineer.)

CHAPTER III.

GUN MOUNTINGS.—ACCURACY AND RAPIDITY OF FIRE.

Rapidity
of hitting
an impor-
tant test of
efficiency.

THE efficiency of a gun depends to a far greater extent than is generally admitted on the rapidity of its fire, or, to put the matter correctly, on the rapidity with which it can hit.

In the days of old, when the rapidity of fire of all guns was fairly equal, the power of a ship naturally depended on the number of her guns, for, the more guns the more hits. This simple state of affairs has completely passed away, and though we still place after a ship's name the number of her guns, no one but a simpleton supposes that the ship with most guns must necessarily be the strongest. Within the last dozen years the rate of fire of both heavy and light guns has increased from three to fivefold, whilst the accuracy has also improved, so that a ship of the present day, say the *Cressy*, with two 9·2-in. and twelve 6-in., would have no difficulty at all if opposed to the *Orlando* with her original armament of two 9·2-in. and ten 6-in. (slow-firers), in putting in four hits to the latter's one.

Improve-
ment in
gun
mount-
ings.


The improvement of gun mountings has contributed far more than anything else to the improved rate of hitting, especially with heavy guns.

Our earlier mountings for heavy B.L. guns, as mounted in the turrets of the *Colossus*, and subsequently in the barbettes of the *Admiral* class, barely admitted of one round in three minutes, nor was the rate of fire of their contemporaries across the Channel any greater; indeed, it was probably less.

In the Royal Sovereign class the rate of fire for the heavy guns has increased, and stands at 2 min. 10 secs. (average of some 400 rounds fired under prize-firing conditions), whilst in the *Majestic* class it stands at 1 min. 9 secs. Across the Channel there has evidently been a similar improvement. An officer of the *Bouvet*, in a paper contributed to the *Revue Maritime*, claims that the heavy guns of that ship fire a round per minute.



The rate of fire of the heavy American guns at Santiago was very slow, not more than one round in four minutes, if that; but in their latest designs of battleships the Americans claim that they will attain one round per minute from the 8-in. turret guns and nearly the same rate from the heavier guns. The Germans

PERFORATIONS - STRIKING DIRECT



BRITISH B.L. GUNS


PERFORATIONS-STRIKING DIRECT



The 12-IN-VIII-WIRE nets through 28 inches up to 2430 yards

The 12" N. X. has much greater perforation
THICKNESS OF FRONT PLATE IN INCHES STEEL
EQUIVALENT OF STEEL & BACKING IN WROUGHT IRON

VESSLS CARRYING
FOUR NEARLY EQUIVALENT
TO SECTIONS SHOWN
ABOVE THEIR NAMES.



DEUTSCH

-BURG
 OATHER-
 SISSO
 VELIKY

OLDENBURG

-BURG
 OATHER-
 SISSO
 VELIKY

(RUSSIAN) SEVASTOPOL. (INC.) VELOCITY.



A HOLE WITHOUT FIGURES MEANS PERFORATION UP TO 3000 YARDS. MAXIMUM RANGES OF PERFORATION, LESS THAN 3000 YARDS, ARE MARKED IN FIGURES.

SHARP GUNS ARE CORRECT IN GENERAL OUTLINE.

ALL BACKING IS 18 IN. OF WOOD WITH 1/2 IN. SKIN.
NOTE THE 29 TON 10 IN. GUN PERFORATES THE 18-8 IRON (TONNANT) SHIELD AT 1800 YARDS AND ALL THINNER SHIELDS AT ALL RANGES
WHILE GUN IS TAKEN FROM ELISWICK OF GUN TABLE. †† PERFORATIONS CALCULATED BY TRESIDGERS' FORMULA

FRENCH GUNS PERFORATIONS-STRIKING DIRECT.

BACKING-POWER
MUZZLE-ENERGY
FOOT- TONS.



THICKNESS OF FRONT PLATE IN INCHES STEEL
EQUIVALENT OF STEEL & BACKING IN WROUGHT IRON

FRENCH
ITALIAN
GERMAN
RUSSIAN

VESSELS CARRYING
ARMOUR NEARLY EQUIVALENT
TO SECTIONS SHOWN
ABOVE THEIR NAMES

SEVASTOPOL.
DUELO
ITALIA
DOIRA
MAISER
FRIEDRICH III.
SARDINIA
FURST
BAGEN
BISMARCK
BURGO
POSIEDA.
OTHER
VELIKY.

OLDENBURG
FRIEDLAND
DEUTSCH-
LAND
A-NACH-
MOFF.

A HOLE WITHOUT FIGURES MEANS PERFORATION UP TO 3000 YARDS, MAXIMUM RANGES OF PERFORATION LESS THAN 3000 YARDS, ARE MARKED IN FIGURES.

SCALE-20 FEET TO AN INCH. SHADED GUNS ARE CORRECT IN GENERAL OUTLINE.

ALL BACKING IS 18 IN. OF WOOD WITH 1/2 IN SKIN

† PERFORATIONS CALCULATED BY TRESIDERS FORMULA.

PERFORATIONS—STRIKING DIRECT.

RACKING-POWER
MUZZLE-ENERGY
FOOT-TONS

† Q.F. 15 C.M. (5.9 IN.)
6.55 TONS

† Q.F. 15 C.M. (6.3 IN.)
7.38 TONS


24 C.M. (9.45 IN.)
18.7 TONS

26 C.M. (10.3 IN.)
21.7 TONS

30.3 C.M. (12 IN.)
35.4 TONS

30.5 C.M. (12.10 IN.)
51.5 TONS

40 C.M. (15.75 IN.)
119 TONS.



THICKNESS OF FRONT PLATE IN INCHES STEEL
EQUIVALENT OF STEEL & BACKING IN WROUGHT IRON

VESSLS CARRYING
ARMOUR NEARLY EQUIVALENT
TO SECTIONS SHOWN
ABOVE THEIR NAMES

FRENCH
ITALIAN
GERMAN
RUSSIAN

ABRUIN CATTAN
GAULOIS JAUREGUIRY
JENA
DULIO
ITALIA
DORIA
KAISER
FRIEDRICH III.
SEVASTOPOL.
RUSSIAN

19.8
25.7
23.6
23.2
17.8
17.4
22.5
20.7
15.8
14.2
12.6
12.0
11.2
10.4
8
7
6.8
6.2

ABRUIN CATTAN
GAULOIS JAUREGUIRY
JENA
DULIO
ITALIA
DORIA
KAISER
FRIEDRICH III.
SEVASTOPOL.
RUSSIAN

ABRUIN CATTAN
GAULOIS JAUREGUIRY
JENA
DULIO
ITALIA
DORIA
KAISER
FRIEDRICH III.
SEVASTOPOL.
RUSSIAN

A HOLE WITHOUT FIGURES MEANS PERFORATION UP TO 3000 YARDS. MAXIMUM RANGES OF PERFORATION LESS THAN 3000 YARDS, ARE MARKED IN FIGURES.
SCALE—20 FEET TO AN INCH. SHADED GUNS ARE CORRECT IN GENERAL OUTLINE.

ALL BACKING IS 18 IN. OF WOOD WITH 1 1/2 IN. SKIN
† TAKEN FROM KRUPP Q.F. GUN TABLE.

NOTE IT IS ALMOST CERTAIN THAT THE GERMAN 24 C.M. HAS MADE MORE ENERGY, IT IS PROBABLY EQUAL TO FRENCH 24 C.M.

have for some time trusted to rapidity of fire, and are content with 9·4-in. guns in the Brandenburg class in order to obtain rapidity. What their rapidity of fire is has never been announced, but in a pamphlet by Lieutenant B. Weyer, published at Munich in 1901, the following rate of fire is claimed for Krupp guns of 1899 model:— 9·4-in.: two to three rounds per min.; 11-in.: one to two rounds per min.; 12-in.: one round per min. These figures, however, have all the appearance of being merely estimates, and are evidently compiled without any reference to actual performances of guns as mounted on board ship.

In some trials that have recently taken place at sea the following rates of fire have been attained with mountings manufactured by the great Armstrong firm: Turret mounting for 9·2-in. B.L. Mark X. for Cressy; charge, 100 lb.; weight of shell, 380 lb.; interval between rounds, 32 secs. Turret mounting for 8·3-in. B.L. for Norwegian coast-defence ship Eidsvold; charge, 52 lb.; projectile, 308 lb.; charge from below, projectile from the turret. (1) Gun horizontal and empty, loaded and fired in 15 secs.; (2) gun horizontal and empty, loaded and fired in 27 secs., the turret being trained 30° and gun elevated to extreme elevation after loading. (3) Gun empty, two rounds fired in 38 secs.

Lieutenant Dawson, in a paper read before the Society of Arts, claims a rate of fire of nearly six rounds per minute for the 7·5-in. gun. We believe that four rounds per minute have been fairly easily attained under service conditions, but the 7·5-in. has a projectile only weighing 200 lb., which can be handled by two men, and does not come under the same category as the heavier guns, where the projectile has to be lifted and rammed home by hydraulic or electric power.

Lieutenant Dawson also claims a rate of fire of two rounds per minute for the 12-in. guns mounted on the Vickers system, but his statement, like that of Lieutenant Weyer, appears rather to be a hopeful estimate than the result of a trial under service conditions.

We give designs of turret mountings for (a) one 9·2-in. gun, (b) two 6-in. guns, by Vickers & Co. These mountings may be said to be based, as regards their general features, on the designs which have been in use in France for many years, but they embody many excellent features presumably never before combined. The object to be attained is to get great offensive power and good protection with a moderate weight and a small gun's crew.

Let us take first the design for the 9·2-in. gun, which represents the mounting to be supplied to the Hogue. The turret is 6 inches thick, and is rotated by hydraulic power, the engine being placed in the

Turret
mount-
ings for
medium
guns.

shallow barbette just below the gun. Hand power is available as an alternative. The recoil is checked by hydraulic buffers of the normal type. The gun is run out by springs. Elevation is given either by hydraulic power or by hand. Thirty-two projectiles are carried in the shallow barbette under the gun. When these are exhausted, projectiles have to be hoisted into the barbette by bringing the rear of the gun platform over one of the two hoists in the deck. The charge is hoisted by hand up the central tube as shown. In loading, the shell is lifted by hydraulic power from the carrier into the loading tray, and rammed home by hand. A rate of fire of two rounds per minute is expected to be attained with considerable ease.*

Turret for
twin 6-in.
guns.

The turret for twin guns is essentially British, but we have never before built a turret for a smaller gun than a 9·2-in. Foreign nations, especially the French, have shown great fondness for placing one or two quick-firers in small turrets, but we have always preferred casemates. That a turret like the one shown allows of a considerable saving of weight over a two-decked casemate, with which it may well be compared, there is no manner of doubt. It also presents a much smaller target, and the arc of fire is far greater, whilst the protection is somewhat superior, owing to the smallness of the parts.


In nearly all the latest designs of ships, turrets are a great feature. The new Italian battleships have all their large quick-firers in turrets. Turrets for the secondary armament form a prominent feature in American, German and Russian designs, and possibly we may follow suit.

The main objection to turrets for light guns is that they are supposed to reduce the rate of fire. Whether this is so we shall now be able to determine. In the heavier guns the rate of fire depends more than anything else on the loading arrangements, but for lighter guns it is more a question of the rate of laying. A 4·7-in. gun can readily be loaded and fired ten times a minute, but when firing at a small target on the move, as at prize firing, five rounds per minute is a fair rate of fire, and six rounds is excellent. The ease of laying and facility of rapid movement allowed by the mounting is therefore of the first importance, and whether the twin turret with its moving weight of nearly 80 tons can be laid as quickly as the guns can be loaded, can only be determined by trial.

Descrip-
tion of the
6-in.
turret.


The 6-in. turret is 4 inches thick, as is also the shallow barbette in which it stands, which shelters the electric motor and other parts of the training gear. 132 projectiles are also stored in the barbette.

* Trials have just taken place at sea in which a rate of fire of three rounds per minute was attained.



TURRET FOR 9.2-INCH GUNS OF THE HOGUE.

VICKERS, CONNOR & MAXIM LTD.



TURRET FOR 9.2-INCH GUNS OF THE HOGUE.

The charges are brought up the central tube by an endless band hoist worked by a motor at the foot of the hoist. The main hoist delivers its cartridges to the lift, but by an ingenious arrangement of an auxiliary band hoist running at higher speed every alternate cartridge is delivered to the right. If desirable, projectiles may be placed in the hoist alternately with, or in lieu of, cartridges. The cartridges and projectiles are loaded independently by hand.

Each gun has an independent sighting position with handles conveniently placed for working the training switch to electric training gear and for elevating by hand. Hand training gear can be used if necessary. With electric training the turret can be trained 360° in 30 seconds, and with the hand gear 360° in 1 minute. The guns can be elevated, loaded and fired independently, but must of course be trained together. The total weights are approximately as under with 200 rounds per gun.


| | |
|---|----------|
| 2 guns | 15 tons. |
| 132 projectiles in barbette | 6 " |
| Gun mountings, turret and gear | 60 " |
| Barbette and armoured ammunition tube | 25 " |
| Ammunition in magazine—400 charges, 268 | } 20 " |
| projectiles | |
| | 126 " |

Two 6-in. guns mounted in the open would weigh with ammunition some 52 tons. Looking at the excellent protection given, the extra weight appears to be fully justified.

The *Naval and Military Record* has devoted several articles to the results of prize firing up to and including the year 1899, from which the following particulars are completed and extracted:—

Accuracy
of fire as
judged by
"prize
firing."

The conditions of firing vary according to the nature of guns, which are placed in three classes: (a) 16·25-in., 13·5-in., 12-in. (old pattern), 10-in., 9·2-in. (old pattern); (b) 12-in. Mark VIII. (Majestic, &c.), 9·2-in. Mark VIII. (Powerful and later ships); (c) quick-firing guns, 6-in. to 4-in. The (a) guns fire for twelve minutes, the ship steaming 8 knots, and the range varying from 1,400 to 2,000 yards; target as shown for 9·2-in. gun in diagram; height, 15 ft.; breadth, top 20 ft., bottom 50 ft.; area, 525 sq. ft. The (b) guns fire for six minutes only at the same target as above. The (c) guns fire for two minutes, the ship steaming 12 knots, and the range varying from 1,400 to 1,600 yards; target as shown for 6-in. guns in diagram: height, 15 ft.; breadth, 20 ft.; area, 300 sq. ft.



TURRET FOR TWIN 6-IN. Q.F. GUNS.

The heavy guns have the disadvantage of firing at a longer range than the quick-firing guns. Moreover, the distance varies a good deal, often 100 yards or more between successive rounds, whilst with the quick-firing guns 30 yards is a large variation. On the other hand, the target is 70 per cent. larger for the heavy guns, and the speed 4 knots less. The range is known in all cases.

As a comparison it may be stated that a turret or barbette for two heavy guns is usually some 25 ft. high (measuring from water-line) and 32 ft. in diameter, area of target 800 sq. ft., or 50 per cent. bigger than heavy gun target.

A turret or casemate for quick-firing guns may be taken as presenting a target of about 150 sq. ft. in area, about half that of the prize-firing target for quick-firing guns.

The following table gives a summary of the performances of the various heavy guns during the years 1898-99:—

TARGET, 15 FEET HIGH. AREA, 525 SQUARE FEET. RANGE, 1,400-2,000.

SPEED, 8 KNOTS.

| GUN. | Rounds per Gun per Minute. | Hits per Gun per Minute. | Percentage of Hits to Rounds Fired. | Time required to make one Hit. | Weight of Metal Hitting per Gun per Minute. | Remarks. |
|--|-------------------------------------|--------------------------------|--|---|---|--|
| | | | | minutes. | lbs. | |
| 16·25-in. | 0·25 | 0·04 | 16 | 52 | 72 | These guns fire for twelve minutes |
| 13·5-in. | 0·40 | 0·12 | 30 | 8 | 150 | |
| 12-in., old pattern | 0·36 | 0·11 | 31 | 9 | 79 | |
| 10-in. | 0·69 | 0·22 | 32 | 4½ | 110 | |
| 9·2-in., old pattern | 0·70 | 0·29 | 41 | 3½ | 110 | |
| 12-in. Mark VIII., Majestic, etc. | 0·90 | 0·27 | 30 | 3½ | 230 | Fires for six minutes |

The rapidity of fire depends mainly on the mounting, the slow rate of fire of the 16·25-in. and old-pattern 12-in. being mainly due to inferior mountings. On the other hand, the 12-in. guns of Majestic class, with their improved mountings, beat even the 9·2-in. guns in rate of fire.

The inaccuracy of the 16·25-in. gun is probably due to the old-fashioned mounting. The 9·2-in. guns are nearly all on hand-worked mountings with light shields, and are apparently easier to lay accurately than the guns with heavy armour protection, but owing to their exposure their fire in action must needs be inferior.

The performance of the quick-firing guns is given below for 1898-1899:—

TARGET, 15 FEET HIGH. AREA, 300 SQUARE FEET. RANGE, 1,400-1,600.
SPEED, 12 KNOTS.

| Gun. | Rounds per Gun per Minute. | Hits per Gun per Minute. | Percentage of Hits to Rounds Fired. | Weight of Metal Hitting per Gun per Minute. |
|-----------------|-------------------------------------|--------------------------------|--|---|
| 6-in. | 3·8 | 1·07 | 28 | lbs. 107 |
| 4·7-in. | 5·2 | 1·65 | 32 | 74 |
| 4-in. | 5·7 | 1·75 | 31 | 42 |

Although the 4-in. gun can be loaded more than twice as fast as the 6-in., the gain in rate of fire is only a bare 50 per cent. The accuracy of all three calibres is very similar.

Seeing that the heavy and quick-firing guns fire at different targets, under different conditions, an exact comparison cannot be made, but if heavy guns are used for firing shell at unarmoured parts, as is sometimes advocated, they naturally come in for comparison with the quick-firers, when it is evident from the column, "Weight of metal hitting," etc., that for this kind of work the quick-firer beats the heavy gun quite out of the field. Thus a single 4·7-in. gun of $2\frac{1}{2}$ tons gets in more metal per minute than the gigantic 16·25-in. of 110 tons, while the 6-in. Q.F. beats the old-pattern 12-in., and (with due allowance made for different size of targets in prize firing) is decidedly superior to the 10-in. or 9·2-in. Of all the heavy guns the 12-in. Mark VIII. is the only one that does respectably with shell, and this gun is barely equal to a pair of 6-in. Q.F., weighing together about one-quarter of the 12-in.

The function of the heavy guns is essentially to pierce the armour which stops the quick-firing projectiles; thus, given the necessary penetrating power, they must mainly be judged by the number of hits, in which the 9·2-in. and 12-in. Mark VIII. do best. As explained in the section on armour, if a gun has a considerable reserve of piercing power more *effective* hits will be obtained, as the oblique hits will pierce in lieu of glancing off. Thus the 12-in. would always be superior to the 9·2-in., even against armour which the latter could penetrate.


It is evident that there is a wide field for improvement in heavy guns by increasing the rate of fire, and if, as promised, the rate of fire of 9·2-in. and 12-in. can be doubled, it will be a very great advance.

What the lighter guns need is greater penetration, so that the numerous hits which they deliver may go home, and may not glance off harmlessly.

We reproduce a diagram, published by the *Naval and Military Record*, which shows that there is still ample scope for improvement in shooting which can be attained by diligent training and constant practice. It shows the targets made by the *Terrible* under Captain P. M. Scott, C.B. It is not easy to compare the results obtained by the *Terrible's* 9·2-in. guns with that attained in the service generally, because the *Terrible's* mountings stand alone, but it appears to be about twice as good as the average. The rate of hitting by the 6-in. gun is just three times the average rate.

Possible improvement in accuracy.

The *Terrible's* record.



TARGETS MADE BY TERRIBLE AT PRIZE FIRING, 1900.

ABSTRACT OF RESULT OF PRIZE-FIRING PRACTICE, H.M.S. TERRIBLE, 1900.

| GUN. | Rounds per Gun per Minute. | Hits per Gun per Minute. | Percentage of Hits to Rounds Fired. | Time required to make one Hit. | Weight of Metal Hitting per Gun per Minute. |
|--|----------------------------|--------------------------|-------------------------------------|--------------------------------|---|
| 9-in. Mark VIII. | 1·16 | 0·75 | 60 | minutes. 1·3 | lbs. 285 |
| 6-inch Q.F. | 4·3 | 3·33 | 77 | 0·3 | 333 |
| Average figures for 6-in. Q.F. throughout the Service. | 3·8 | 1·07 | 28 | 0·9 | 107 |

These excellent results were obtained in a ship which had been two and a half years in commission, and in which aiming practice took place almost daily on a principle worked out by Captain Scott himself. There is every reason that similar hard work and untiring diligence should produce equal results in other ships. The *Majestic* in the Channel and the *Cæsar* in the Mediterranean attained a rate of hitting of 2·2 shells per minute with the 6-in. gun, and there is no doubt that far more attention is now paid to gunnery practice than ever before.

Long
range
fire.

It is perfectly obvious that two cruisers, or indeed two battle-ships, which fired with anything like the accuracy attained at prize firing, would, if they closed to 1,500 yards, make a very speedy end of the affair. This is also borne out by the Belleisle experiments. But the history of all fighting, both afloat and ashore, tends to show that a range will be taken up at which there will be an immense deal of missing, at least on one side, and that an action will take some time to fight out, and will not be finished in five minutes or so, as must be the case if ships close in at once. It is very important to know at what range to open fire, and at what range it may be expected that fire will become really efficient.

Long
range
practice.

Various trials have taken place during the past year, especially in the Channel and Mediterranean, both with the range altering quickly and fairly constant. Practice has been carried out at all ranges between 3,000 and 7,000 yards.

So far as can be ascertained the result of the practice has been distinctly promising. Without crediting all that has been published of cruisers making 30 per cent. of hits at a target supposed to represent another cruiser at 5,000 yards, it is certain that good practice has been made at ranges never before dreamt of, at any rate for real fighting. If even 10 per cent. of hits can be made at 5,000 yards, and 5 per cent. at 7,000, as has been stated, it is most decidedly worth opening fire at the latter range in a chase, and very possibly at the opening of a regular engagement, whilst practice at long ranges will in future form part of the regular exercise of every ship in commission.

Method of
increasing
power of
guns.

It was stated above that owing to the increase of armour protection, more piercing power is required for the quick-firing guns. When greater power is aimed at, three courses are open: (a) To substitute guns of larger calibre; (b) To substitute guns of greater length; (c) To increase the charge.

(a) Is a radical step scarcely feasible, as a rule, without almost reconstructing the ship. It entails entirely new ammunition, and may so increase the weight of projectile as to be a

very serious matter when the loading by hand of a quick-firing gun is in question.

- (b) Utilises the old projectiles, and possibly the old charges, which, however, may have to be increased. It may entail new mountings, and in many ships is out of the question owing to lack of room.
- (c) Is a comparatively simple matter at first sight, but is liable to entail all kinds of difficulties, of which prohibitive stress to the mounting comes first, closely followed by increased erosion to the bore, the erosion being very serious if cordite be used.

Owing mainly to the great erosion which appears inevitable when large charges of cordite are used, proposals have been made to substitute for cordite some other propellant which it is said will give the necessary power without undue erosion. But whether the increase of power can be attained by improvements in the propellant without countervailing disadvantages has yet to be demonstrated.

Increase of
power by
giving
more
velocity.

It is claimed for the new nitro-cellulose powders that they give higher velocities than cordite for the same erosion, or less erosion for the same velocity. But for similar velocities some 25 per cent. more powder is required, and if the velocity is to be increased the weight of the nitro charge may rise to 50 per cent. above that of cordite, and the bulk will increase in a higher proportion, entailing serious difficulty in loading arrangements. There has been much exaggerated talk about erosion. If a gun can last through an action without serious loss of efficiency, it can easily be changed when the ship gets her necessary refit. Cordite is very cheap, charge for charge, as compared with nitro powder. The money saved by using cordite should be put into reserve guns and plant for quickly renewing eroded barrels, then we can wear away our inner tubes with a light heart. It has taken us ten years to supply all our guns with cordite; even now some are using brown powder. We shall therefore have to do with cordite for many years to come, and it is absolutely essential that our guns should have sufficient power with cordite charges. If nitro-cellulose comes in and increases their power they will have something to spare, but guns of increased power are required at once, and since the 6-in. falls short of what is needed, the best policy is to go in boldly for the 7·5-in. in new ships, and where possible replace 6-in. guns in the older ships, at the same time pushing on the work of improving the rate of fire of the 9·2-in.

Cordite
versus
nitro-
cellulose
powders.

NOTES ON TABLES OF ORDNANCE.

THE authorities on which the data in the Ordnance Tables are based are as follows:—

Speaking generally, the British and United States Tables contain figures from official sources. The Tables for the Continental powers are mainly taken from the *Austrian Marine Almanack*. The energies and perforations, however, are worked out independently, as explained below. The Ordnance Tables of Elswick, Vickers, Schneider-Canet, and Krupp guns are obtained directly from the manufacturers, and the data in them are given on their authority. In justice to British manufacturers, the compiler would call special attention to the fact that the very high velocities, 2,740 ft.-secs. and over, which occur often in the foreign tables, are very rarely found in the guns marked with an asterisk, that is, existing guns, and when actually achieved with new guns cannot be long maintained. In the course of time lower velocities are generally substituted. Elswick explains the possibility of obtaining such velocities in a footnote, but limits the columns to existing guns, except one 12-in. gun under manufacture. The fact is, that just as it has been found injudicious to work a boiler with forced draught, so it has hitherto been found undesirable to use so large a charge as to give more than 2,600 to 2,700 ft.-secs. in a 45-calibre gun with projectiles of the British or American type ($\frac{w}{d^2} = .49$). A 50-calibre gun should give another 80 ft.-secs., and with some of the nitro-cotton powders now coming forward it may be possible to reach 2,800 to 2,900 ft.-secs., but it will be some time yet before any guns with such very high velocities are actually mounted afloat. Such enormous charges as 360 lb. of smokeless powder, which is said to be the charge of the 12-in. gun in America, to give a velocity of 2,900 ft.-secs., never seem likely to be adopted.

There are very few alterations this year in the British and foreign service Tables. The Russian Table is the best obtainable, but is certainly not up to date, and readers are cautioned not to be misled by it. The particulars given in the margin are fairly well authenticated. The German Navy also possesses more powerful 24-cm. guns than those shown.

Tresidder's formula being now recognised and used in official papers, and this even for velocities below 2,000 ft.-secs., it has been concluded that it is best to follow the course indicated in the *Annual* for 1896, p. 363, that is to say, to employ Fairbairn's or Maitland's formula only for velocities up to 1,580 ft.-secs. For these low velocities they have been thoroughly tested and found good, and for these it would be a mistake to alter the existing tables based on them. About 1,580 ft.-secs. the formulæ of De Marre, Krupp, Tresidder, Maitland and Fairbairn all agree fairly well. At this point, then, it is convenient to "shunt," as it were, from the Fairbairn, on to the Tresidder curve, for British Tables. Krupp's formula gives nearly the same results as Tresidder's, and it makes little difference which of the two is employed, and in some foreign Tables where Krupp's formula has been used it is left undisturbed, Tresidder's being often added to enable a comparison to be made. In Krupp's formula weight tells more in comparison to velocity than in Tresidder's. The actual formula used is nearly always stated on the face of the Table.

BRITISH RIFLED ORDNANCE—continued.

(Compiled from the official "List of Service Ordnance, 1893." Supplemented by subsequent information.)

| ORDNANCE. | | | | | | | | | | Projectile. | | | | | | Ballistics (with full charges). | | | | | | | | |
|---------------------------|-----------------|----------|---------------------------------|-------------------------|---------------------------------------|-----------|-------------------------------|-------------------|------------------|----------------|--------------------|----------|-----------|------------------|----------------------------------|---------------------------------|----------------------------|------------------|----------------------|-----------------------|------------------------------|-------|---------------|------|
| NATURE. | | Weight. | Mark and Service.* | Total length in inches. | Length of Chamber, including Chamber. | CHAMBER. | | RIFLING. | | Charge (full). | Charge (cordite). | | Diameter. | Weight. δ | Bursting Charge of Common Shell. | Value of $\frac{w}{d^2}$. | Value of $\frac{w}{d^3}$. | Muzzle velocity. | Total muzzle energy. | Muzzle energy per ton | Perforation of wrought iron. | | | |
| Calibre or Pr. | | | | | | Diameter. | Length to base of projectile. | Twist one turn in | Least at breech. | | Greater at muzzle. | System.† | | | | | | | | | Weight. | Size. | ins. | lbs. |
| QUICK-FIRING GUNS. | | | | | | | | | | | | | | | | | | | | | | | | |
| 7.5 in. | .. | 14 tons | I. & III. II. (Wire) | 319 | 45 | ins. | ins. | cala. | cala. | lbs. | lbs. ozs. | .. | ins. | 200.0 | .. | 0.2810 | 0.474 | 2700 | 10,120 | 723 | 27.4 | 23.0 | 19.3 | |
| 6.0 in. | .. | 7 tons | I. to VI. | 249.25 | 40 | .. | .. | 60 | 30 | .. | 13 | 4 | 30 | 100 0 | .. | 0.3600 | 0.463 | 2200 | 3356 | 479 | 15.9 | 12.7 | 10.2 | |
| 6.0 in. converted | .. | 5 " | "BL. VII." | 169.1 | 26.2 | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | 1913 | 2537 | 362 | 13.0 | 10.3 | 8.2 | |
| 6.0 in. (Vickers) †† | .. | 7.5 tons | I. II. III. & IV. Wire | 163.6 | 26.6 | .. | .. | 100 | 34.4 | .. | .. | .. | .. | 100.0 | .. | 0.3600 | 0.463 | 2642 | 44840 | 654 | 21.0 | 16.7 | 13.4 | |
| 4.7 in. | .. | 41 cwt. | I. II. III. Wire converted guns | 191.1 | 40 | .. | .. | 0 | 30 | .. | 5 | 7 | 20 | 4.72 | 45.0 | .. | 0.4950 | 0.428 | 2188 | 1491 | 711 | 12.4 | 9.2 | 6.6 |
| 4 in. | .. | 42 " | I. II. III. Wire converted guns | 165.25 | 40 | .. | .. | .. | .. | .. | 3 | 9 | 15 | .. | 25.0 | .. | 0.6400 | 0.390 | 2300 | 917 | 705 | 10.5 | 6.9 | 4.9 |
| 12-pr. | .. | 26 cwt. | I. | 120 | 28 | .. | .. | 120 | 28 | .. | 1 | 15 | 10 | 3.0 | 12.5 | .. | 0.6570 | 0.500 | 2177 | 821 | 569 | 9.5 | 6.5 | 4.6 |
| 12-pr. | .. | 12 cwt. | I. | 123.6 | 40 | .. | .. | 60 | 28 | .. | 13 | 10 | 3.0 | 12.5 | .. | 0.6570 | 0.500 | 2210 | 423 | 677 | 8.1 | 5.3 | 3.5 | |
| Hotchkiss | 6-pr. | 8 cwt. | I. & II. | 87.6 | 28 | .. | .. | 0 | 30 | .. | 13 | 10 | 3.0 | 12.5 | .. | 0.6570 | 0.500 | 1607 | 223.8 | 544 | 4.9 | 3.2 | 2.4 | |
| Nordenfält | 6-pr. | 6 cwt. | I. II. & III. | 97.63 | 40.0 | .. | .. | 180 | 29.9 | .. | 67 | 5 | 2.24 | 6.0 | .. | 0.8360 | 0.534 | 1818 | 137.5 | 344.8 | 4.8 | 2.8 | .. | |
| Hotchkiss | 3-pr. | 5 cwt. | I. & II. | 104.4 | 42.3 | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | 1.0370 | 0.521 | 1873 | 80.3 | 321.2 | 4.1 | 2.1 | .. | |
| Nordenfält | 3-pr. | 4 cwt. | I. L. | 80.63 | 40 | .. | .. | 25 | 25 | .. | 66 | 3 | 5 | 1.85 | 3.3 | .. | .. | 1920 | 84.3 | 337.2 | 4.3 | 2.2 | .. | |
| MACHINE GUNS. | | | | | | | | | | | | | | | | | | | | | | | | |
| Nordenfält | 2 bar 1-in. | 180 lbs. | I. | 52 | 45.4 | .. | .. | 35 | 35 | 625 M.G. | .. | .. | 1.0 | 74 | 0 | .. | 2.2070 | 0.453 | .. | .. | .. | 4-in. | at 200 yards. | |
| " | 4 bar 1-in. | 447 lbs. | III.** | 57.0 | .. | .. | .. | 35 | 35 | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | |
| " | 5 bar 0.45-in. | 160 lbs. | I. G. G. | 46.0 | .. | .. | .. | 22 | 22 | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | |
| Gardner | 1 bar 0.45-in. | 76 lbs. | II. G. G. | 42.25 | .. | .. | .. | 22 | 22 | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | |
| " | 2 bar 0.45-in. | 120 lbs. | I. G. G. | 47.0 | .. | .. | .. | 22 | 22 | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | |
| " | 5 bar 0.45-in. | 268 lbs. | I. G. G. | 47.0 | .. | .. | .. | 22 | 22 | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | |
| Gatling | 10 bar 0.65-in. | 787 lbs. | I. G. G. | 53.5 | .. | .. | .. | 22 | 22 | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | |
| " | 10 bar 0.45-in. | 402 lbs. | I. G. G. | 66.5 | .. | .. | .. | 30 | 30 | 270 R.F.G. | .. | .. | .. | 0.65 | 1422 | .. | 2.1090 | 0.730 | .. | .. | .. | .. | .. | |
| " | (Acclesfeed) | 266 lbs. | I. G. G. | 59.0 | .. | .. | .. | 22 | 22 | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | |
| Maxim | 1 bar 0.45 in. | 63 lbs. | I. G. G. | 43.75 | .. | .. | .. | 22 | 22 | 85 R.F.G. | .. | .. | .. | 0.450 | 480 | .. | 2.9520 | 0.751 | .. | .. | .. | .. | .. | |
| Maxim, converted | 4.5 | .. | I. G. G. | 45.0 | .. | .. | .. | 10 | 27 | 31 Cordite | .. | .. | .. | 0.450 | 480 | .. | 2.9520 | 0.751 | .. | .. | .. | .. | .. | |
| Maxim, converted | 4.5 | .. | I. G. G. | 42.38 | .. | .. | .. | 10 | 25.6 | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | |

* L. Land-service only, but might concern navy when serving on land.
 H. Henry; E.X.F., Experimental letter F.
 ** I. and II. differ chiefly in being 7 lbs. lighter; I. has a pitch of rifling of 1 in 60 in.; G.G., Gardner Gatling; H., Henry. b With 4 lbs. I.F.G. † With 4 lbs. I.F.G. †† There is a Gardner and also a Nordenfält 303 bore gun for L.S.
 ‡ The Roman numeral is the number of the pattern given.
 § For the higher numbers the weight of projectile given is for full shot; for the lower numbers it is for filled common shell.
 ¶ This gun has no metal cartridge.
 †† This gun has no metal cartridge.

AUSTRIAN NAVAL ORDNANCE.

| Designation by Calibre, in centimetres . . . | Krupp Steel B.L. Guns. | | | | | | | | | | Uchatius. St., Br. | | | Cast Iron BL. | | Q.F. Krupp. | | | Q.F. Skoda. | |
|--|------------------------|----------------------|----------------------|----------------------|-------------|----------------------|----------------------|---------------------|---------------------|----------------------|----------------------|----------------------|----------------------|---------------|-------------|-------------|-------------|-------------|-------------|-------------|
| | 30.5 L. 35 C. 80 | 26 L. 22 C. 86 | 24 L. 22 C. 86 | 24 L. 22 C. 86 | 21 L. 20 | 15 L. 35 C. 86 | 15 L. 35 C. 80 | 15 L. 26 K.Z. | 15 L. 26 P.Z. | 12 L. 35 C. 80 | 12 L. 35 C. 87 | 15 L. 25 L. 37 | 12 L. 35 L. 24 | 7 L. 15 | 15 L. 21 | 24 L. 40 | 15 L. 40 | 15 L. 35 | 12 L. 35 | 12 L. 40 |
| Calibre, in inches . . . | 12.01 | 10.24 | 9.45 | 9.27 | 8.24 | 5.87 | 5.87 | 5.87 | 5.87 | 4.72 | 4.72 | 4.72 | 4.72 | 3.43 | 5.87 | 9.45 | 5.87 | 5.87 | 4.72 | 4.72 |
| (Total, in Feet . . .) | 35.11 | 18.77 | 27.60 | 17.16 | 13.73 | 17.13 | 17.13 | 12.63 | 12.63 | 13.8 | 13.8 | 12.19 | 14.38 | 3.28 | 10.13 | 31.5 | 19.55 | 17.13 | 13.85 | 19.55 |
| Length . . . | 314.8 | 148.4 | 237.7 | 135.9 | 105.0 | 151.4 | 153.6 | 106.8 | 112.4 | 128.5 | 126.3 | 111.4 | 123.2 | 23.8 | 91.1 | 287.8 | 182.8 | 153.6 | 128.2 | 182.8 |
| Powder Chamber . . . | 69.9 | 46.1 | 65.2 | 41.7 | 37.0 | 37.3 | 35.4 | 28.3 | 22.6 | 24.0 | 26.3 | 22.8 | 36.6 | 11.0 | 15.7 | 63.8 | 35.7 | 35.7 | 28.5 | 35.7 |
| (Of bore in calibres . . .) | 35 | 19.0 | 35 | 22.0 | 20.0 | 35 | 35.0 | 25.8 | 25.8 | 35.0 | 35.0 | 24.9 | 37 | 15.0 | 18.4 | 40 | 40 | 35 | 35 | 40 |
| No. of Grooves . . . | 68 | 32 | 25 | 32 | 30 | 36 | 36 | 24 | 36 | 32 | 32 | 36 | 32 | 23 | 30 | 72 | 44 | 44 | 36 | 44 |
| Twist in calibres . . . | 45.25 | 70 | 26.9 | 70 | 49 | 45.25 | 25 | 68.4 | 45 | 25 | 25 | 45 | 45.25 | 45 | 63.2 | 25 | 45.25 | 45.25 | 45.25 | 45.25 |
| (Gun, tons . . .) | 47.2 | 21.7 | 26.6 | 14.5 | 8.68 | 5.7 | 4.69 | 3.94 | 3.94 | 2.25 | 2.31 | 3.35 | 3.15 | 0.85 | 2.81 | 27.8 | 4.43 | 3.75 | 1.97 | 4.33 |
| Breach Block, in lbs. . . | 3306.9 | 1951 | 1776.9 | 1422 | 1080 | 445.3 | 463.0 | 321.9 | 321.9 | 253.5 | 211.6 | 209.4 | 211.6 | 55.1 | 176.4 | 1450.6 | 328.5 | 328.5 | 521.1 | 6291.0 |
| Steel Shell . . . | 1003.1 | 1395.7 | 474.0 | 292.1 | 206.6 | 112.5 | 86.0 | 72.8 | 84.9 | 57.3 | 57.3 | 84.9 | 57.3 | .. | .. | 474.0 | 100.3 | 100.3 | 352.4 | 100.3 |
| Weight . . . | 1003.1 | 1354.2 | 474.0 | 263.5 | 172.0 | 112.5 | 69.9 | 67.2 | 69.4 | 57.3 | 57.3 | 69.45 | 57.3 | 14.02 | 6.11 | 474.0 | 100.3 | 100.3 | 352.4 | 100.3 |
| Common Shell . . . | .. | .. | .. | .. | .. | 112.4 | 71.9 | 67.2 | 69.4 | 57.3 | 57.3 | 69.45 | 57.3 | 15.76 | 6.79 | 474.0 | 100.3 | 100.3 | 352.4 | 100.3 |
| Shrapnel Shell . . . | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. |
| Case Shot . . . | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. |
| Steel Shell . . . | 10.6 | 8.8 | 5.1 | 6.6 | 4.4 | 1.3 | 1.76 | 1.65 | 2.09 | 0.55 | 0.55 | 2.09 | 0.53 | 0.55 | 38.4 | 5.07 | 2.0 | 2.0 | 1.1 | 2.0 |
| Common Shell . . . | 97.7 | 20.3 | 17.9 | 15.0 | 15.0 | 5.29 | 3.86 | 3.86 | 5.07 | 2.2 | 2.2 | 5.07 | 2.20 | 2.21 | 1.87 | 4.72 | 8.82 | 8.82 | 4.6 | 8.82 |
| Shrapnel Shell . . . | .. | .. | .. | .. | .. | 1.26 | 1.10 | 1.08 | 1.08 | 0.57 | 0.57 | 1.08 | 0.57 | 0.57 | 0.90 | .. | 1.0 | 1.0 | 0.53 | 1.0 |
| Steel Projectile, in lbs. . . | 155.5 | 89.3 | 93.2 | 76.1 | 50.7 | 22.5 | 15 cm. N | 38.8* | 21.6 | 20.9 | 19.8 | 20.9 | 19.8 | 19.8 | .. | 91.5 | 18.3 | 17.9 | 9.7 | 18.3 |
| Common Shell, in lbs. . . | 24 cm. N | 155.5 | 93.2 | 76.1 | 50.7 | 22.5 | 15 cm. N | 38.8* | 21.6 | 20.9 | 19.8 | 20.9 | 19.8 | 19.8 | .. | 91.5 | 18.3 | 17.9 | 9.7 | 18.3 |
| Shrapnel, in lbs. . . | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. |
| Exercising, in lbs. . . | 154.3B | 59.5 | .. | 44.1 | 30.9 | 28.7 | 19.6 | 21.6 | 20.9 | 11.0 | 6.6 | 20.9 | 19.8 | 12.13 | 4740 | 63.9 | 11.9 | 11.9 | 4.6 | 11.9 |
| Saluting . . . | 19.8 | 19.8 | 15.4 | 15.4 | 15.4 | 15.4 | 15.4 | 15.4 | 15.4 | 15.4 | 15.4 | 15.4 | 15.4 | 15.4 | .. | .. | .. | .. | .. | .. |
| Muzzle Velocity, in feet . . . | 1969 | 1575 | 2100 | 1587 | 1519 | 2133 | 1969 | 1641 | 1562 | 1755 | 2133 | 1562 | 1755 | 1470 | 1017 | 2264 | 2264 | 2133 | 2133 | 2264 |
| (Total, foot-tons . . .) | 25,970 | 6808 | 14,500 | 5104 | 3306 | 3549 | 2312 | 1358 | 1435 | 1215 | 1808 | 1435 | 1224 | 1224 | .. | 11,850 | 3565 | 3163 | 1647 | 3565 |
| Muzzle . . . | 714.8 | 211.6 | 488.3 | 175.3 | 127.7 | 192.5 | 125.4 | 73.7 | 77.9 | 82.5 | 122.2 | 77.9 | 82.5 | 82.5 | .. | 567.6 | 193.3 | 171.6 | 111.1 | 193.3 |
| Energy . . . | 28.08 | 15.08 | 27.4 | 13.78 | 11.68 | 14.58 | 11.78 | 8.88 | 9.18 | 9.48 | 11.68 | 9.18 | 9.58 | 9.58 | .. | 25.0 | 14.6 | 13.7 | 11.1 | 14.6 |
| Thickness of Iron, perforated inches at Muzzle . . . | 30.1 | 14.7 | 25.8 | 13.4 | .. | 16.1 | 12.6 | 8.9 | 8.9 | 9.7 | 12.9 | 8.9 | 9.7 | 9.7 | .. | 29.0 | 17.0 | 15.5 | 12.5 | 17.0 |
| Ditto by Tresidder's formula . . . | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. |

NOTE.—C for cube powder; * prismatic powder; O, ordinary powder; B, brown prismatic.
 † By Krupp's formula. § By Fairbairn's formula.
 There are also q.f. Skoda 7 cm., Skoda and Hotchkiss 47 mm., another 47 mm. and Hotchkiss 37 mm.
 It is believed that guns with at least 2500 M.V. are under construction.

DANISH NAVAL ORDNANCE.

| Krupp B.L. Guns designated. | | | | | | | | | | | | | Armstrong M.L. | | | | Flase- pong. |
|---|----------|----------|-----------------|------------------|--------|-----------------|-------------------|------------------|-----------------|------------------|---------|--------|----------------|-------|--------|-------|-----------------|
| Designation by Calibre | 35.5 cm. | 30.5 cm. | 26 cm. long. | 26 cm. short. | 21 cm. | 15 cm. long. | 15 cm. medium. | 15 cm. short. | 12 cm. long. | 12 cm. short. | 8.6 cm. | 10 in. | 10 in. | 9 in. | 8 in.† | 6 in. | |
| Calibre, in inches | 13.98 | 12.01 | 10.24 | 10.24 | 8.24 | 5.91 | 5.91 | 5.91 | 4.72 | 4.72 | 3.43 | 10.0 | 10 in. | 9.0 | 8.0 | 6.04 | |
| Total length, in feet | 29.1 | 22.0 | 32.8 | 18.77 | 24.04 | 17.1 | 12.63 | 10.7 | 11.8 | 9.6 | 6.9 | 17.0 | 14.5 | 13.0 | 10.8 | 9.5 | |
| Length of Bore, including Powder Chamber { in inches | 304.7 | 227.2 | 327.6 | 194.5 | 264.5 | 190.3 | 135.0 | 112.9 | 128.8 | 102.4 | 73.6 | 175.5 | 145.5 | 140.0 | 104.2 | 100.8 | |
| Number of Grooves | 21.8 | 18.9 | 32.0 | 19.0 | 35 | 32.2 | 22.8 | 19.1 | 27.3 | 21.7 | 21.3 | 17.5 | 14.55 | 14.0 | 13.3 | 16.7 | |
| Twist of Rifling, in calibres | 80 | 68 | 60 | 60 | 48 | 36 | 36 | 36 | 32 | 32 | 24 | 7 | 7 | 6 | 6 | 6 | |
| Total weight, including Breech-gear, tons | 45 | 45 | 70.25 | 45 | 70.25 | 70.25 | 45 | 45 | 25 | 40 | 45 | 40 | 40 | 40 | 50 | 40 | |
| Breech Block, lbs. | 51.3 | 35.4 | 27.6 | 21.6 | 13.3 | 4.7 | 4.4 | 3.5 | 2.13 | 1.39 | 0.49 | 20.0 | 18.5 | 18.0 | 12.5 | 8.65 | |
| Steel Shell, " | 4695.8 | 2910 | 2006 | 1940 | 903.9 | 330.2 | 330.7 | 324.1 | 229.2 | 176.4 | 101.4 | .. | .. | .. | .. | .. | |
| Chilled Shell, " | 1157.4 | 725.3 | 451.9 | 451.9 | 238.1 | 112.4 | .. | 86.0 | .. | 44.1 | .. | 400 | 400 | 400 | .. | .. | |
| Common Shell, " | 1157.4 | 725.3 | 451.9 | 451.9 | 238.1 | 112.4 | 69.4 | 69.4 | 57.3 | 36.2 | 15.2 | 400 | 400 | 400 | 250.2 | 165.3 | |
| Shrapnel Shell, " | 1157.4 | 725.3 | 451.9 | 451.9 | 238.1 | 112.4 | 86.0 | 86.0 | 57.3 | 44.1 | .. | .. | .. | .. | .. | 55.1 | |
| Case Shot, " | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | 191.8 | .. | 154.3 | 127.9 | 15.4 | |
| Weight of Bursting Charge { | 57.3 | 39.7 | 25.4 | 25.4 | 12.8 | 6.2 | 3.0 | 3.0 | 1.7 | 1.4 | 0.44 | 26.5 | 26.5 | 18.5 | 7.5 | 5.0 | |
| Common Shell, " | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | |
| Weight of Firing Charge { Steel or Chilled Shell, lbs. | 330.7 | 180.2 | 191.8 | 101.4 | 105.8 | 41.9 | 19.3 | 21.8 | 17.4 | 8.8 | .. | 71.7 | 71.7 | 44.1 | 29.8 | .. | |
| Common Shell, " | 330.7 | 180.2 | 191.8 | 112.4 | 105.8 | 41.9 | 19.3 | 21.8 | 17.4 | 8.8 | 3.3 | 71.7 | 71.7 | 44.1 | 19.8 | 60.6 | |
| Muzzle Velocity { Armour-piercing Projectile, feet | 1762 | 1675 | 2018 | 1640 | 2021 | 1800 | 1565 | 1542 | .. | 1416 | .. | 1457 | 1368 | 1368 | 1378 | .. | |
| Common Shell, " | 1762 | 1675 | 2018 | 1640 | 2021 | 1890 | 1683 | 1690 | 1720 | 1549 | 1457 | 1457 | 1368 | 1368 | 1320 | 1076 | |
| Muzzle Energy { Total foot-tons | 24910 | 14110 | 12770 | 8428 | 6745 | 2784 | 1461 | 1418 | .. | 6130 | .. | 5889 | 5192 | 5192 | 3246 | 2177 | |
| Per inch circumference, foot-tons . | 568.3 | 374.1 | 396.8 | 262.0 | 260.6 | 150.0 | 78.7 | 73.0 | .. | 32.8 | .. | 189.0 | 165.3 | 165.3 | 115.8 | 86.9 | |
| Perforation at Muzzle, in ins. by Fairbairn's forma. | 24.8 | 20.0 | 20.1 | 16.7 | 16.9 | 12.8 | 9.1 | 8.8 | .. | 5.8 | .. | 14.1 | 13.1 | 13.1 | 10.9 | 9.5 | |
| ditto ditto Tresidder's forma. | 25.6 | 20.1 | 22.9 | 16.8 | 18.5 | 15.6 | 12.6 | .. | .. | .. | .. | .. | .. | .. | .. | .. | |

NOTE.—Chilled projectiles will gradually be replaced by steel.

† There is another Armstrong gun differing very little from this one. Krupp has supplied 12-cm. and 8.7-cm. Q.-F. guns, and Bofors's Q.-F. piece have been adopted and manufactured. No more of these guns will be made; the most recent guns have undoubtedly higher velocity.

DUTCH NAVAL ORDNANCE.

| | Krupp Breech Loading. | | | | | | Armstrong Muzzle Loading. | | | Dutch Breech Loading. | | |
|---|-------------------------|----------------------|-------|-------|---------------------|--------------------|---------------------------|----|----|------------------------------|-----------------|-------|
| | 28 | 21 | 17 | 15 | No. 1. No. 2. | No. 1. No. 2. | 28 | 23 | 18 | 12 No. 2. | 121 | 7-5 |
| Designation by Calibre, in centimetres . . . | | | | | | | | | | | | |
| Calibre, in inches . . . | 11-02 | 7-91 | 6-80 | 5-87 | 4-72 | 4-72 | | | | 4-72 | 4-72 | 2-95 |
| Total Length, in feet . . . | 20-01 | 24-04 | 13-94 | 12-63 | 17-13 | 13-78 | | | | 6-89 | 13-78 | 7-87 |
| Length of Rifled Portion of bore, in inches . . . | 170-8 | 222-2 | 112-7 | 111-8 | 151-4 | 128-5 | | | | 61-4 | .. | 43-2 |
| Length of Powder Chamber . . . | 36-4 | 42-4 | 36-0 | 23-2 | 37-7 | 24-0 | | | | 13-0 | .. | 6-7 |
| Length of bore, in Calibres . . . | 18-8 | 35 | 21-9 | 23-0 | 35 | 35 | | | | 15-8 | 35 | 17-5 |
| Number of Grooves . . . | 64 | $\frac{48}{61}$ | 42 | 36 | 44 | 32 | | | | 12 | 32 | 20 |
| Depth of Grooves, inches . . . | 0-069 | 0-059 | 0-118 | 0-118 | .. | .. | | | | 0-118 | 0-06 | 0-049 |
| Twist of Rifling in Calibres . . . | 45 | $\frac{25}{12-79}$ | 45 | 40 | 25 | 25 | | | | 40 | $\frac{45}{30}$ | 30 |
| Total Weight, in tons . . . | 27-21 | $\frac{13-93}{99-2}$ | 5-51 | 3-94 | 4-72 | 2-26 | | | | 0-93 | 2-31 | 0-21 |
| Firing Charge { Armour-piercing Projectile, in lbs. | 121-3 | 99-2 | 27-6 | 20-9 | 49-6 | .. | | | | .. | 19-5 | .. |
| Common Shell | 121-3 | 99-2 | 27-6 | 20-9 | 49-6 | 2-43 | | | | 2-43 | 19-8 | 0-82 |
| Weight { Armour-piercing Projectile | 560-0 | 308-6 | 132-3 | 86-0 | 112-2 | 41-0 | | | | .. | 57-3 | .. |
| Common Shell | 476-2 | 308-6 | 112-4 | 69-4 | 112-2 | 29-5 | | | | 29-5 | 57-3 | 9-5 |
| Case Shot | 273-4 | .. | 63-9 | 41-9 | .. | 26-5 | | | | 26-5 | .. | 9-3 |
| Bursting Charge { Armour-piercing Projectile | 6-6 | 4-6 | 2-2 | 1-1 | .. | 0-44 | | | | .. | .. | .. |
| Common Shell | 26-5 | 12-3 | 6-6 | 6-6 | .. | 2-0 | | | | 1-8 | .. | 0-44 |
| Muzzle Velocity, feet . . . | 1558 | 1739 | 1558 | 1558 | 2001 | 971 | | | | 951 | 1804 | 958 |
| Muzzle { Total, in foot-tons . . . | 9423 | 6471 | 2226 | 1447 | 3115 | .. | | | | .. | 1264 | .. |
| Energy { Per inch Circumference, foot-tons | 272 | 260-7 | 104 | 84 | 169-0 | .. | | | | .. | 85-2 | .. |
| Perforation at Muzzle, in inches . . . | 17-0 | $\frac{16-8}{17-1}$ | 10-5 | 9-1 | $\frac{13-6}{14-8}$ | $\frac{9-4}{10-1}$ | | | | .. | 9-6 | .. |
| Metal employed or system of construction . . . | Steel Jacket and Hoops. | | | | | | Steel-hooped. | | | Steel Tube and Wrought Iron. | | |
| | | | | | | | Steel-hooped. | | | Bronze. | | |
| | | | | | | | Steel-hooped. | | | | | |
| | | | | | | | Steel-hooped. | | | | | |

NOTE.—The 23-cm. M.L. guns also discharge 113-Kg. (249-1 lbs.) steel shells and 119-Kg. solid shot. The 18-cm. M.L. guns discharge steel shells of 51-Kg. (112-4 lbs.) and segment shells of 53-Kg. (116-8 lbs.). The 7-5-cm. B.L. guns discharge ring-shells of 4-3 Kg. (9-5 lbs.). Of the older guns there are yet extant three sorts—rifle-16-cm. muzzle-loader (mostly bronze), and rifled bronze 7-cm. and 5-cm.
 † By Tresidder's formula.
 The newer ships have undoubtedly more powerful guns, including 9-4-in., 8-2-in., 5-9-in., and 4-7-in. Q.F.s.

FRENCH NAVAL ORDNANCE.

| Date and Pattern of Gun. | Model 1893. | | | | | Model 1887. | | | | | 1870-81. 70-84. | | 1884. | | | | | 1881. | | | | | | | | | |
|--|-------------|-------|-------|-------|-------|-------------|-------|-------|-------|-------|--------------------|-------|-------|-------|-------|-------|------|-------------|--------------|-------|-------|--------------|--------------|-------|-------|------------|------|
| | | | | | | | | | | | 27 | 32 | 34 | 27 | 24 | 16 | 14 | 34 long. | 34 short. | 27 | 24 | 16 heavy. | 16 light. | 14 | 10 | mm. mm. | |
| | 34-0 | 30-5 | 27-44 | 24-0 | 19-4 | 34 | 30-5 | 27 | 19 | | 27 | 32 | 34 | 27 | 24 | 16 | 14 | | | | | | | | | | |
| Design by Calibre, in cms. . | 13-39 | 12-0 | 10-8 | 9-45 | 7-6 | 13-39 | 12-0 | 10-8 | 7-6 | | 10-80 | 12-6 | 13-39 | 10-80 | 9-45 | 6-49 | 5-45 | 13-39 | 13-39 | 10-8 | 9-45 | 6-49 | 6-49 | 5-46 | 3-9 | 3-5 | 2-57 |
| Calibre, in inches . | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | 23-97 | 27-93 | .. | 23-47 | 24-89 | 17-04 | .. | .. | .. | .. | .. | .. | .. | 14-3 | 8-6 | 7-1 | 3-58 |
| Total length, in feet . | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | 269-0 | 313-8 | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | 162-6 | 102-6 | 77-9 | 41-2 |
| Length of Bore, in inches . | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | 25 | 25 | 30 | 30 | 30 | 30 | 30 | 30 | 28-5 | 28-5 | 28-5 | 28 | 28 | 26 | 22 | 16 | |
| Length of Bore, in calibres | 35 | 40 | 45 | 40 | 40 | 42 | 45 | 45 | 45 | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | 42 | 30 | 28 | 20 |
| Number of Grooves . | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. |
| Depth of Grooves, inches . | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | 0-059 | 0-059 | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. |
| Rifling Twist . | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | 7° | 7° | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. |
| Total weight, in tons . | 52-9 | 45-9 | 34-9 | 22-4 | 10-6 | 60-0 | 49-2 | 37-1 | 10-6 | 24-6 | 42-3 | 282-2 | 388-0 | 200-6 | .. | 42-5 | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. |
| Weight of { Armour-piercing Firing Projectile lbs. Charge { Common Shell " | 220-5 | 198-4 | 114-6 | 110-2 | 44-1 | 220-5 | 198-4 | 114-6 | 44-1 | 154-3 | 249-1 | 282-2 | 388-0 | 200-6 | .. | 42-5 | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. |
| { Armour - piercing Projectile * lbs. Weight { Common Shell " { Case Shot . " | 925-9 | 648-8 | 476-2 | 317-5 | 165-3 | 925-9 | 648-8 | 476-2 | 165-3 | 476-2 | 760-6 | 925-9 | 648-8 | 476-2 | 317-5 | 99-2 | 99-2 | 925-9 | 648-8 | 476-2 | 317-5 | 99-2 | 99-2 | .. | .. | .. | .. |
| Muzzle Velocity, in ft.-sec. . | 2400 | 2625 | 2625 | 2625 | 2625 | 2560 | 2625 | 2625 | 2625 | 1887 | 1804 | 1985 | 1969 | 1969 | 1969 | 1969 | 1969 | 1969 | 1804 | 1969 | 1969 | 1969 | 1969 | 1821 | 1986 | 1673 | 1493 |
| Muzzle { Total, in foot-tons . Energy { Per in. circ., foot-tons | 36850 | 30750 | 22750 | 15170 | 7898 | 42040 | 30750 | 22750 | 7898 | 11760 | 17160 | 20780 | 24900 | 12800 | 8539 | 2668 | 1777 | 24900 | 20880 | 12800 | 8539 | 2668 | 2080 | .. | .. | .. | .. |
| Perforation at Muzzle, inches | 36-8 | 37-3 | 33-7 | 29-4 | 13-4 | 40-8 | 37-3 | 33-7 | 23-7 | 20-6 | 22-6 | 26-6 | 21-1 | 18-4 | 12-4 | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. |

* Steel or chilled iron.

† By Tresidder's formula.

‡ By Krupp's formula.

NOTE.—M. Claidmon stated in March, in the French Chamber of Deputies, that France has a 12-in. (30-5 cm.) gun with a muzzle energy of 12,200 metre tons or 39,395 ft. tons. This for a projectile of 643-8 lbs. implies a velocity of 2971 ft.s.

GERMAN NAVAL ORDNANCE.

| Krupp Steel Breech-loading Guns, designated by calibre. | | | | | | | | | | | | | | | | | | | | | Bronze E.L. | |
|--|-----------------|--------|--------|------------------------|--------------|-------------------|-------------|--------------|-------------|-------------|-------------|-------------|------------------------|-------------------------|-------------------------|--------------------------|-------|-------|-------|-------|----------------|--|
| Designation in centimetres | 30.5 jack'd. | 28 | 28 | 26 long. jack'd. | 26 short. | 26 long. ** | 24 long. | 24 short. | 24 long. | 21 long. | 21 long. | 17 long. | 15 long. jack'd. | 15 short. jack'd. | 15 short. jack'd. | 12.5 hoop'd. long. | 10.5 | 8.7 | 6.7 | 8 | | |
| Calibre, in inches | 12.01 | 11.02 | 11.02 | 10.33 | 10.33 | 10.33 | 9.45 | 9.45 | 9.45 | 8.24 | 8.24 | 6.80 | 5.87 | 5.87 | 5.87 | 4.92 | 3.96 | 3.43 | 2.36 | 3.19 | | |
| Total, in feet | 21.98 | 36.75 | 32.15 | 18.77 | 17.77 | 17.06 | 31.50 | 27.56 | 23.63 | 15.45 | 24.02 | 20.61 | 13.94 | 14.67 | 10.73 | 9.60 | 12.08 | 6.89 | 4.1 | 5.15 | | |
| Length | 181.9 | {407.9 | {352.8 | 149.8 | 150.0 | 129.3 | 349.6 | 302.4 | 201.6 | 116.2 | 221.8 | 217.5 | 117.1 | 128.5 | 93.3 | 87.1 | 85.7 | 113.6 | 62.7 | 44.3 | | |
| Rifled portion, in ins. | 45.3 | {407.9 | {352.8 | 44.7 | 44.4 | 44.7 | .. | .. | .. | 53.5 | 40.9 | 75.3 | 46.7 | 31.5 | 31.1 | 19.0 | 25.1 | 16.7 | 19.5 | 10.7 | | |
| Powder Chamber, | 18.9 | 40 | 35 | 18.8 | 18.8 | 16.8 | .. | .. | .. | 26.1 | 16.8 | 35.6 | 27.1 | 21.9 | 27.2 | 19.1 | 19.1 | 20.8 | 33.6 | 21.4 | | |
| Bore, in calibres | 72 | .. | .. | 36 | 48 | 36 | .. | .. | .. | 56 | 48 | 48 | 30 | 36 | 36 | 36 | 32 | 24 | 24 | 12 | | |
| Number of Grooves | .. | .. | .. | 0.077 | 0.079 | 0.077 | .. | .. | .. | 0.059 | 0.061 | 0.059 | 0.059 | 0.061 | 0.061 | 0.059 | 0.049 | 0.049 | .. | 0.051 | | |
| Depth of Grooves, in inches | .. | .. | .. | 50 | 50 | 50 | .. | .. | .. | 25* | 45 | 25* | 45 | 25* | 45 | 45 | 40* | 25* | 40* | 46 | | |
| Twist, in calibres | 35.4 | 43.4 | 43.2 | 21.7 | 18.7 | 17.7 | 25.4 | 21.7 | 18.7 | 14.6 | 13.03 | 12.3 | 5.51 | 4.04 | 3.44 | 3.44 | 1.38 | 1.15 | 0.44 | 0.23 | | |
| (Gun, including Breech Gear, tons Breech Block, in lbs. | 2954 | .. | .. | 2050 | 1973 | 1973 | .. | .. | .. | 1378831 | 1908.3 | 496.0 | 390.2 | 324.1 | 324.1 | 324.1 | 163.1 | 149.9 | 86.0 | 55.1 | | |
| Weight | 725.3 | 562.2 | 562.2 | 412.3 | 412.3 | 412.3 | 474.0 | 474.0 | 474.0 | 474.0 | 474.0 | 474.0 | 474.0 | 474.0 | 474.0 | 474.0 | 474.0 | 474.0 | 474.0 | 474.0 | | |
| Armour - piercing projectile, in lbs. | 7.7 | .. | .. | 5.3 | 5.3 | 5.3 | 7.05 | 7.05 | 6.6 | 3.2 | 5.5 | 5.5 | 1.3 | 1.5 | 0.8 | 0.8 | 0.8 | 0.8 | 0.8 | 0.8 | | |
| Common Shell, in lbs. | 19.8 | 25.4 | 25.4 | 14.3 | 14.3 | 22.0 | 16.5 | 16.5 | 15.4 | 15.4 | 12.1 | 12.1 | 5.1 | 4.3 | 4.2 | 4.2 | 2.4 | 0.9 | 0.4 | 0.6 | | |
| Weight of Bursting Charge | 202.8 | 352.7 | 297.6 | 105.8 | 105.8 | 125.7 | .. | .. | 152.1 | 67.2 | 103.6 | 103.6 | 30.9 | 33.1 | 14.3 | 17.1 | 17.1 | 17.1 | 17.1 | 17.1 | | |
| Armour - piercing Shell, in lbs. | 202.8 | 352.7 | 297.6 | 105.8 | 105.8 | 125.7 | .. | .. | 152.1 | 67.2 | 103.6 | 103.6 | 30.9 | 33.1 | 14.3 | 17.1 | 17.1 | 17.1 | 17.1 | 17.1 | | |
| Common Shell, in lbs. | 1713 | 2362 | 2133 | 1588 | 1588 | 1578 | 2067 | 1903 | 1657 | 1493 | 1739 | 1657 | 1608 | 1624 | 1463 | 1463 | 1463 | 1463 | 1463 | 1463 | | |
| Armour - piercing projectile, ft.-sec. | 1713 | .. | .. | 1641 | 1641 | 1654 | 2067 | 1903 | 1657 | 1891 | 1739 | 1657 | 1654 | 1624 | 1555 | 1555 | 1545 | 1526 | 1545 | 1545 | | |
| Initial Velocity | 14,750 | 21,750 | 17,740 | 7211 | 7211 | 7119 | 14050 | 11910 | 9024 | 4736 | 6471 | 5876 | 2112 | 2055 | 1131 | 1131 | 1131 | 1131 | 1131 | 1131 | | |
| Muzzle Energy | 391 | 628.4 | 512.4 | 223 | 223 | 220 | 473.3 | 401.2 | 304 | 161 | 250.0 | 227 | 98.9 | 111.5 | 61.3 | 61.3 | 61.3 | 61.3 | 61.3 | 61.3 | | |
| Perforation at Muzzle, in ins. | 20.5 | 130.7 | 26.7 | 15.4 | 15.4 | 15.3 | 26.8 | 21.0 | 18.1 | 13.0 | 16.4 | 15.6 | 10.3 | 11.0 | 8.0 | 8.0 | 8.0 | 8.0 | 8.0 | 8.0 | | |
| Ditto by Tresidder's formula | 20.8 | 30.6 | 26.7 | 15.1 | 15.1 | 15.0 | 25.3 | 22.2 | 18.0 | .. | 16.8 | 15.6 | 10.2 | .. | .. | .. | .. | .. | .. | .. | | |

NOTE.—There are also quick-firing guns; see Table of Krupp Q.-F. guns, but M.V. does not probably exceed 2400 to 2500 f.s. * Maximum twist. † Including taper entrance into bore.
 ‡ In most cases steel shells. § Length including powder chamber. || Iron by Krupp's formula. ¶ Boat gun for landing and working ashore.
 ** The 9.45 Q.-F., which is being mounted in all the latest ships, probably has M.V. about 2500 f.s. Pen.: 33.5" and 25.4" at 2000 yds.

ITALIAN NAVAL ORDNANCE.

| Designation by Calibre, in centimètres. | Armstrong Breech Loading. | | | B.L. | | Armstrong Muzzle Loading. | | | | | | | Muzzle Loading, Old Pattern. | | Breech Loading. | | Armstrong Quick Firing. | | | |
|---|---------------------------------|-----------------------------------|--------|-------|-------|---------------------------|------------------------------------|---------------------|----------------------|----------------|-------|-------|------------------------------|---------|-----------------|---------------|-------------------------|------------|-------|-------|
| | 43-11† New Pattern. 1882. | 43-11† Early Pattern. 1882. | 34-3 | 12-0 | 12-0 | 45-0 | 27-9 New Pattern. | 25-4 No. 1 Long. | 25-4 No. 2 Short. | 25-4 No. 2. | 22-8 | 20-3 | 16 | 16 | 7-5 No. 1. | 7-5 No. 2. | 15-2† | 14-9 | 12-0* | 12-0§ |
| Calibre, in inches | 17 | 17 | 13-5 | 4-72 | 4-72 | 17-72 | 11 | 10 | 10 | 10 | 9 | 8 | 6-5 | 6-5 | 3 | 3 | 6-0 | 5-87 | 4-7 | 4-7 |
| Length | 40-75 | 39 | 36-09 | 8-5 | 9-25 | 32-7 | 14-4 | 14-4 | 14 | 13-8 | 13-8 | 10-8 | 11-8 | 10-6 | 5-8 | 3-3 | 13-8 | 13-87 | 16-2 | 13-0 |
| Rifled Bore, in inches | 34-8 | 315-7 | .. | 75 | 88 | 302 | 121 | 120 | 114 | 112 | 106 | 89 | 96 | 87 | 52 | 27 | 126 | .. | 189 | .. |
| Powder Chamber, in inches | 84-5 | 98 | .. | 10-8 | 22 | 56-5 | 24-5 | 26-0 | 26-0 | 14-0 | 19-5 | 15-7 | 21-3 | 21-3 | 10-2 | 7-9 | 28 | .. | 40 | 35 |
| Bore, in Calibres | 27 | 26 | .. | 20-2 | 23-5 | 20-5 | 13-2 | 14-6 | 14-0 | 12-6 | 13-9 | 13-1 | 16-8 | 15-5 | 20-7 | 11-7 | 26 | .. | 22 | 22 |
| No. of Grooves | 82 | 82 | 56 | 37 | 36 | 28 | 9 | 7 | 7 | 8 | 6 | 6 | 6 | 6 | 12 | 12 | 28 | 28 | 34-4 | .. |
| Twist of Rifling, in Calibres | 50 | 50 | .. | 40 | 42 | 50 | 35 | 40 | 40 | 55 | 45 | 45 | 42-5 | 27-3 | 48 | 48 | 40 | 40 | .. | 1-69 |
| Total Weight, in tons | 104-3 | 101-5 | 67-9 | 1-20 | 1-38 | 100 | 25-0 | 18-0 | 18-1 | 12-1 | 12-6 | 6-99 | 5-12 | 3-54 | 0-29 | 0-095 | 4 | 4-2 | 2-05 | .. |
| Firing Charge | 900-0 | 725 | 630-5 | 5-5 | 9-9 | 551 | 95-2 | 77-6 | 63-9 | 59-7 | 37-7 | 37-7 | 19-8 | .. | .. | .. | 39-7 | 26-5 | 12-0 | .. |
| Armour-piercing projectile, lbs. | 600 | 480 | .. | 5-5 | 9-9 | 63-0 | 66-6 | 52-9 | 41-9 | 37-7 | 26-7 | 191-8 | 103-6 | .. | .. | .. | 80 | about 80-0 | 45-0 | 36-0 |
| Common Shell, | 2000 | 2000 | 1250 | 52-0 | 52-2 | 2000 | 540-1 | 451-9 | 331-8 | 315-3 | 180-0 | 180-0 | 64-6 | 65-7 | 9-4 | 9-4 | 80 | .. | .. | 36-2 |
| Shrapnel | 2000 | 2000 | 1250 | 31-7 | 36-8 | 2000 | 526-9 | 399-0 | 284-4 | 250-0 | 180-0 | 180-0 | 68-3 | .. | 9-4 | 9-4 | 80 | .. | .. | 29-8 |
| Case Shot | 2017 | 2017 | 1250 | 37-3 | 37-37 | 2180 | 533-5 | 399-0 | 284-4 | 250-0 | 180-0 | 180-0 | 33-1 | 33-1 | 9-0 | 9-0 | 70 | .. | .. | .. |
| Armour-piercing projectile, | .. | .. | .. | 32-4 | 35-9 | .. | 200-1 | 188-1 | 135-6 | 99-6 | 79-4 | 3-8 | .. | .. | .. | .. | 1-5 | .. | .. | 1-83 |
| Common Shell, | 32 | 32 | 17-4 | 2-31 | 2-31 | 32-2 | 15-0 | 12-3 | 8-4 | 6-5 | 3-8 | 9-7 | 2-87 | 2-87 | 0-31 | 0-31 | 5 | .. | .. | 3-02 |
| Shrapnel | 60 | 60 | 87-1 | 2-2 | 2-2 | 78-2 | 26-0 | 23-8 | 18-2 | 1-96 | 1-80 | 1-17 | 0-55 | .. | 0-03 | 0-03 | 0-16 | .. | .. | 0-35 |
| Muzzle Velocity, in feet | 5 | 5 | 4-25 | 0-35 | 0-35 | 5-2 | 2-2 | 2-20 | 1-96 | 1-80 | 1-80 | 1-17 | 0-55 | .. | 0-03 | 0-03 | 0-16 | .. | .. | .. |
| Muzzle Energy | 1992 | 1935 | 2016 | 134-5 | 1591 | 1700 | 1353 | 1388 | 1373 | 1284 | 1311 | 1290 | 1024 | 1335 | .. | .. | 1946 | .. | 1786 | .. |
| Total, foot-tons | 55,030 | 51,930 | 35,230 | 650-4 | 916-4 | 40,060 | 6857 | 6035 | 4369 | 3604 | 2286 | 1195 | .. | .. | .. | .. | 2100 | .. | 995-4 | .. |
| Per inch circumference, foot-tons | 1035 | 976-3 | 830-8 | 43-9 | 61-8 | 753-4 | 198-5 | 192-2 | 139-1 | 127-6 | 91-0 | 58-5 | .. | .. | .. | .. | 114-1 | .. | 67-1 | .. |
| Perforation at Muzzle, inches of iron | 33-7 | 32-8 | 30-2 | 6-7 | 8-1 | 27-8 | 14-3 | 14-1 | 12-0 | 11-4 | 9-6 | 7-7 | .. | .. | .. | .. | **11-4 | .. | **8-8 | .. |
| by Tresidder's formula | 36-7 | 35-0 | 33-0 | .. | 8-3 | 28-2 | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | 11-8 | .. | 9-2 | .. |
| Metal employed in structure | St. | I & St. | St. | St. | St. | St. | Steel tube in Wrought Iron jacket. | | | | | | | I & St. | Cast I. | Br. | Br. | St. | St. | St. |

* For Piemonte.

St. stands for steel, I. for iron, Br. for Bronze.

† For Piemonte, Fieramosca, Re Umberto, Ancona, Doria.

‡ There are four types of these boxes, viz.—types Lauria, Lepanto, Italia, Valente.

§ For Duilio, Dandolo, Formidabile. The Piemonte has a 40-calibre gun.

Note.—See also Table of Elswick Quick-Firing Guns. Ships built since 1899 probably have guns with about 2500f.s. M.V.

RUSSIAN NAVAL ORDNANCE.

448

| Obukhoff Steel Breech Loading Hooped Guns. | | | | | | | | | | | | | | | Steel B.L. Guns. | | NEW PATTERN RUSSIAN NAVAL GUNS. | | | |
|--|-----|----------|-----------|-----------|------------------|------|------------|------|------|----------|-------|------|------|-------|------------------|-------------|------------------------------------|------|------|---|
| Designation by Calibre, in inches. | 12 | 12 Long. | 12 M. 77. | 11 M. 67. | 11 Pat. term 17. | 9 | a 9 M. 67. | b 9 | 8 | 8 M. 67. | Long. | 6 | 6 | Long. | 6 | Long 9-pdr. | 4-pdr. | 3-43 | 8-70 | |
| Calibre in centimetres | 30 | 48 | 30 | 48 | 27 | 94 | 22 | 86 | 22 | 86 | 22 | 86 | 22 | 86 | 22 | 86 | 22 | 86 | 22 | |
| Total Length, in feet | 30 | 30 | 20 | 18 | 3 | 20 | 0 | 26 | 25 | 15 | 0 | 13 | 26 | 25 | 15 | 0 | 13 | 26 | 25 | |
| Length of Rifled Portion of Bore, in inches | .. | .. | 165 | 0 | 152 | 0 | 158 | 0 | .. | .. | .. | 128 | 0 | .. | .. | 118 | 7 | 106 | 0 | |
| Length of Powder Chamber, in inches | .. | .. | 38 | 5 | 35 | 0 | 50 | 4 | .. | .. | .. | 23 | 0 | .. | .. | 30 | 5 | 22 | 4 | |
| Length of Bore in calibres, including Powder Chamber | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | |
| Chamber | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | |
| Number of Grooves, in ins. | .. | .. | 36 | 36 | 64 | .. | 32 | 32 | .. | .. | 30 | .. | .. | .. | .. | 24 | 24 | 24 | 24 | |
| Depth of Grooves, in ins. | .. | .. | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| Twist of Rifling in calibres | .. | .. | 73 | 5 | 70 | .. | 60 | 60 | .. | .. | 70 | .. | .. | .. | .. | 68 | 68 | 68 | 68 | |
| Total Weight, in tons | 55 | 7 | 50 | 45 | 39 | 9 | 28 | 2 | 28 | 2 | 13 | 64 | 12 | 7 | 4 | 9 | 9 | 9 | 9 | |
| (Steel Shell, in lbs.) | .. | .. | 665 | 8 | 515 | 9 | .. | .. | .. | .. | 172 | 0 | .. | .. | .. | 97 | 688 | 0 | .. | |
| Weight of Chilled Shell, " of Common Shell, " | 626 | 4 | .. | .. | .. | .. | .. | .. | .. | .. | 193 | 1 | 169 | 8 | .. | 119 | 0 | 86 | 0 | |
| Case Shot, " | .. | .. | 293 | 2 | 216 | 1 | .. | .. | .. | .. | 134 | 5 | .. | .. | .. | 57 | 3 | 57 | 3 | |
| Steel Shell, " | .. | .. | 144 | 4 | 115 | 3 | .. | .. | .. | .. | 31 | 5 | .. | .. | .. | 14 | 3 | 18 | 1 | |
| of Firing Chilled Shell, " | .. | .. | 246 | 9 | 144 | 6 | 90 | 6 | 132 | 2 | 72 | 0 | 29 | 3 | 39 | 6 | 14 | 3 | 18 | 1 |
| Charge of Common Shell, " | .. | .. | 117 | 3 | 81 | 6 | 132 | 2 | 180 | .. | 88 | 2 | 72 | 0 | 28 | 4 | 10 | 8 | 14 | 3 |
| Muzzle Velocity, in feet | .. | .. | 1942 | 1470 | 1486 | 1516 | 2376 | 1463 | 1260 | 1925 | 1796 | 1352 | 2080 | 1739 | 1206 | 1463 | 1225 | .. | .. | |
| (Total, foot-tons) | .. | .. | 19140 | 9974 | 7903 | 8960 | 10500 | 4095 | 3035 | .. | 4321 | 2180 | 2682 | 1905 | 982 | 1276 | .. | .. | .. | |
| Muzzle Per Inch Circumference, ft.-tons | .. | .. | 508 | 4 | 264 | 6 | 228 | 8 | 253 | 3 | 371 | 4 | 144 | 7 | 107 | 4 | .. | .. | .. | |
| Perforation at Muzzle, in inches | .. | .. | 23 | 6 | 16 | 7 | 15 | 5 | 16 | 5 | 20 | 2 | 12 | 3 | 10 | 5 | .. | .. | .. | |
| Perforation at Muzzle, by Tresidder's formula | .. | .. | 25 | 3 | .. | .. | .. | .. | .. | .. | 15 | 7 | 14 | 2 | .. | .. | .. | .. | .. | |

| | | | | | | |
|------------------------------|-----------|-----------|-----------|-----------|-----------|-----------|
| Length | 40 cal. | 45 cal. | 45 cal. | 45 cal. | 45 cal. | 45 cal. |
| Projectile | 720 lbs. | 488 lbs. | 403 lb. | 188 lbs. | 188 lbs. | 188 lbs. |
| Muzzle Velocity | 2600 f.s. | 2600 f.s. | 2500 f.s. | 2800 f.s. | 2800 f.s. | 2800 f.s. |
| Perf. (Muzzle) | 38 ins. | 35 ins. | 32 ins. | 27 ins. | 27 ins. | 27 ins. |
| Wt. Ir (2000 yds.) | 30 " | 27 " | 24 " | 20 " | 20 " | 20 " |

| | | | |
|------------------------------|-----------|-----------|-----------|
| Q.F. GUNS. | | | |
| 6-in. | 4-7-in. | 13-pdr. | |
| Length | 45 cal. | 35 cal. | 45 cal. |
| Projectile | 89 lbs. | 46 lbs. | 13 lbs. |
| Muzzle Velocity | 2700 f.s. | 2600 f.s. | 2430 f.s. |
| Perf. (Muzzle) | 20 ins. | 15 ins. | 9 ins. |
| Wt. Ir (2000 yds.) | 12 " | 9 " | 4 " |

** It is doubtful if this refers to the total length of gun or of bore.
 † With pyroxilline.
 * Maximum of increasing twist.
 † There exist also 15 and 10.7-cm. Krupp guns.
 ‡ The weight of the projectile is uncertain.

SPANISH NAVAL ORDNANCE.

| Designation by Calibre Calibre, in inches (Total length, in feet Rifled Portion, in inches Powder Chamber, in inches (Bore, in calibres No. of Grooves . . . Depth of Grooves, in ins. Twist of Rifling, in cal. Total Weight, in tons Armour piercing projectile, in lbs Common Shell, in lbs. Ring Segment, in lbs. Firing Charge (Armour-piercing projectile, in lbs. Other projectiles Muzzle Velocity, in feet Muzzle Energy (Total, in ft.-tons Per inch circumference, ft.-tons Perforation at Muzzle, in inches Metal and Construction | Hontoria, Pattern 79. | | Hontoria, Pattern 83. | | | | | | | | | | Armstrong. | | Krupp. | | | | Converted. | | Garcia de Loma. | | | |
|---|-----------------------|---------------|-----------------------|--------|--------|--------|--------|--------|--------|--------|--------|---------------|-----------------|-----------|----------------|-----------------|--------|--------|------------|------------|-----------------|---------------|---------------|--------------|
| | B.L. | | Breech Loading. | | | | | | | | | | Muzzle Loading. | | Pattern. B.L. | Breech Loading. | | | | Q.F. guns. | | | | |
| | 18-cm. No. 1. | 16-cm. No. 2. | 32-cm. No. 3. | 24-cm. | 20-cm. | 18-cm. | 16-cm. | 14-cm. | 12-cm. | 15-cm. | 12-cm. | 8.7-cm. long. | 7.5-cm. | 22.86-cm. | 20.3-cm. | 6-in. | 15-cm. | 12-cm. | 8.7-cm. | 7.5-cm. | | 14-cm. M. 83. | 12-cm. M. 83. | 7-cm. M. 79. |
| | 7.09 | 6.30 | 12.60 | 11.02 | 9.45 | 7.87 | 6.34 | 5.51 | 4.72 | 6.00 | 4.72 | 3.4 | 2.95 | 9.00 | 8.00 | 6.00 | 5.87 | 4.72 | 3.43 | 2.95 | 5.51 | 4.7 | 2.76 | |
| | 15.57 | 13.8 | 33.7 | 33.8 | 29.0 | .. | 21.75 | 19.3 | 16.91 | 14.5 | 16.97 | 13.75 | 7.9 | 7.50 | 13.0 | 11.0 | 14.5 | 17.13 | 11.81 | 6.9 | 6.6 | 17.4 | 3.71 | |
| | 141.2 | 125.6 | 352.4 | 309.1 | .. | .. | 170.6 | 149.1 | 126.0 | 158.3 | 135.8 | 75.0 | 70.7 | 104.0 | 102.0 | 126.9 | .. | .. | 57.6 | .. | .. | .. | .. | |
| | 31.9 | 17.3 | 86.8 | 77.1 | .. | .. | 49.8 | 53.9 | 39.4 | 31.4 | 19 | 13 | 13 | .. | .. | 29.7 | .. | .. | .. | .. | .. | .. | .. | |
| | 25 | 17 | 50 | 50 | 30 | .. | 30 | 35 | 35 | 32 | 33 | 27 | 28.7 | 14 | 14.75 | 26.1 | 35* | 30* | 24* | 25.8* | .. | .. | .. | |
| | 42 | 38 | 80 | 70 | 60 | 50 | 45 | 40 | 35 | 28 | 22 | 20 | 18 | 6 | 4 | 28 | 36 | 32 | 24 | 24 | .. | .. | .. | |
| | 0.06 | 0.06 | 0.06 | 0.06 | 0.05 | 0.06 | 0.04 | 0.04 | 0.04 | 0.037 | 0.03 | 0.03 | 0.03 | 0.18 | 0.18 | .. | 0.06 | 0.06 | 0.05 | 0.05 | .. | .. | .. | |
| | 56 | 56 | From 0 to 30. | | | | | | | | | | 45 | 40 | 100 | 25 | 25 | 40 | 36 | .. | .. | .. | .. | .. |
| | 7.37 | 5.6 | 48.0 | .. | .. | 11.5 | 8.71 | 6.1 | 4.1 | 5.0 | 2.2 | 0.45 | 0.35 | 12.0 | 9.0 | 4.0 | 4.7 | 2.1 | 0.44 | 0.30 | 4.23 | .. | 0.98 | |
| | 135.6 | 93.7 | 1041 | 694.3 | 438.7 | 253.5 | 187.4 | 130.1 | 86.0 | 97.0 | 39.2 | .. | .. | 250.0 | 180.0 | 78.3 | 84.9 | 43.65 | .. | .. | 154.3 | 112.4 | 32.4 | |
| | 113.8 | 83.6 | 879.6 | 536.4 | 370.4 | 213.8 | .. | 112.4 | 75.0 | 92.6 | 36.4 | 14.1 | 11.5 | 250.0 | 180.0 | 73.6 | 65.5 | 34.61 | 14.6 | 9.48 | 145.5 | 108 | 7.3 | |
| | .. | 83.8 | 886.3 | 590.8 | 370.4 | 211.6 | .. | 112.4 | 75.0 | .. | 38.6 | 15.4 | 11.7 | .. | .. | 83.6 | .. | 34.61 | 14.6 | 9.04 | 145.5 | 108 | 8.2 | |
| | .. | 26.5 | 435.0 | 352.7 | 220.5 | 112.4 | 94.8 | 66.1 | 44.1 | 48.5 | 16.0 | .. | .. | 50.0 | 35.0 | 34.0 | 37.48 | 19.29 | .. | .. | .. | .. | 17.2 | |
| | .. | 24.3 | 463.0 | 319.7 | 220.5 | .. | .. | 61.7 | .. | 30.0 | 11.9 | 4.0 | 4.0 | 33.0 | 21.0 | 24.9 | 25.4 | .. | 10.3 | 10.4 | .. | .. | .. | |
| | .. | 1631 | 2034 | 2034 | 2034 | 2034 | 2051 | 2001 | 1988 | 2070 | 2000 | 1625 | 1709 | 1339 | 1339 | 1929 | 2001 | 1887 | 1539 | 1552 | .. | .. | 1136 | |
| | .. | 1550 | 29830 | 24030 | 12580 | 7271 | 5374 | 3806 | 2386 | 2882 | 1087 | 258 | 233 | 3105 | 2239 | 2018 | 2357 | 1076 | .. | .. | .. | .. | .. | |
| | .. | 87.4 | 73.2 | .. | .. | .. | 141.4 | 191.1 | 137.8 | 101.9 | 153.3 | 73.3 | .. | 110.0 | 89.1 | 1071 | 127.8 | 72.6 | .. | .. | .. | .. | .. | |
| | .. | 49.3 | 8.8 | .. | .. | .. | 14.4 | 19.3 | 14.4 | 19.3 | 14.4 | 19.3 | .. | 10.6 | 9.6 | 11.0 | 12.7 | 7.9 | 7 | .. | .. | .. | .. | |
| | St. & Cast Iron. | | St. Jacket and Hoops. | | | | | | | | | | St. | | St. and Wt. I. | | | St. | | | St. | | | |

18 and 16-cm. Palliser guns and 16 and 13-cm. Parrot guns also exist, and some bronze muzzle loaders. St. stands for Steel; I. for Iron.
 There is also a 20-cm. (7.87-in.) B.L. Hontoria, Pattern 79, weighing 10.8 tons, firing an armour-piercing projectile weighing 180.8 lbs. with a charge of 61.73 lbs.
 * Total length, the length of bore not being supplied. † By Krupp's formula.
 ‡ These weights include the charge and case.

NAVAL ORDINANCE OF SWEDEN AND NORWAY.

| SWEDEN. | | | | | | | | | | NORWAY. | | | | | | | | | | | | |
|-----------------|----|----|-----------|----|-----------|----|-----------|---|--------|---------|--------|-------|--------------|----|----|----|------------------|------|------|--|-----------------|--|
| Breach Loaders. | | | Model 76. | | Model 81. | | Model 83. | | M. 85. | M. 86. | M. 89. | M. L. | Krupp, B. L. | | | | Armstrong, M. L. | | | | Palliser, M. L. | |
| 27 | 24 | 17 | 27 | 24 | 27 | 12 | 15 | 8 | 25 | 6.5 | 15 | 12 | 26 | 26 | 15 | 12 | 26.7 | 26.7 | 26.7 | No. 2, No. 1, No. 3, No. 2, No. 1, No. 2 | | |

Sweden.—The breech-loaders have breech screw-stoppers. The whole of the guns which do not fire shrapnel discharge case-shot.

Nr. 1 — Besides the chilled shell, there are chilled solid shot for the 26-7-cm. and the 20-2-cm. guns, and for all muzzle-loaders case-shot also, besides steel shrapnel for some Krupp guns.

* Maximum rate of increasing twist.

ding 8.2 Elswick guns, 5.9

UNITED STATES NAVAL ORDNANCE.

| NATURE OF GUN. | Calibre. | Weight. tons. | Total Length. feet. | Total Length of Bore. inch. | Length of Rifling. inch. | Twist of Rifling. | Length of Chamber. inch. | Weight of Service-charge (not Smokeless Powder.) lbs. | Weight of Projectile. lbs. | Muzzle Velocity (Service). ft.-seconds. | Muzzle Energy. ft.-tons. | Perfora- tion of Wrought Iron at Muzzle.† inch. |
|---------------------------------------|----------|------------------|---------------------------|--------------------------------------|--------------------------------|----------------------------|--------------------------------|---|----------------------------------|--|--------------------------------|--|
| | | | | | | | | | | | | |
| 3-in. (14 pr.) | 3 | 0.87 | 12.5 | 149.7 | 125.5 | zero to 1 in 25 | 21.3 | 12 to 14 | 14 | 3000 | 874 | 13.5 |
| 4-in. Q.-F., Mark I. | 4 | 1.3 | 13.7 | 157.3 | 130.3 | .. | 24.7 | .. | 33 | 2000 | 915 | 9.8 |
| 4-in. Q.-F. Gun | 4 | 1.5 | 13.7 | 157.5 | 128.1 | .. | 25.4 | .. | 33 | 2000* | .. | 9.8 |
| 4-in. Q.-F., Mark VII., of 50 Cals. | 4 | 2.56 | 17.0 | 200.0 | 168.4 | .. | 31.6 | .. | 32 | 3000† | 1,939 | 17.6 |
| 5-in. Q.-F., Mark I. | 5 | 2.8 | 13.5 | 150.3 | 120.8 | { 1 in 180 to } 1 in 30 | 27.1 | 26 to 29 | 60 | 2000 | 1,660 | 11.8 |
| 5-in. Q.-F. Gun | 5 | 3.1 | 17.4 | 191.5 | 164.4 | zero to 1 in 25 | 32.0 | 28 to 30 | 50 | 2300 | 1,834 | 13.2 |
| 5-in. Q.-F., Mark V. | 5 | 4.46 | 21.3 | 250 | 212.9 | .. | 37.2 | .. | 60 | 2500† | 3,503 | 20.5 |
| 6-in. B.L.R., Mark I. | 6 | 4.8 | 15.8 | 176.0 | 136.7 | { 1 in 180 to } 1 in 30 | 36.9 | 50 | 100 | 2000 | 2,773 | .. |
| 6-in. B.L.R., Mark II. | 6 | 4.9 | 16.1 | 180.1 | 144.9 | .. | 32.7 | 45 to 48 | 100 | 2000 | .. | 13.8 |
| 6-in. B.L.R., Mark III., of 30 Cals. | 6 | 4.8 | 16.3 | 183.8 | 147.3 | zero to 1 in 25 | 34.0 | 44 to 47 | 100 | 2000 | .. | .. |
| 6-in. B.L.R., Mark III., of 35 Cals. | 6 | 5.2 | 18.8 | 213.8 | 177.3 | .. | 34.0 | .. | 100 | 2080 | 2,990 | 14.7 |
| 6-in. B.L.R., Mark III., of 40 Cals. | 6 | 6.0 | 21.3 | 243.8 | 207.3 | .. | 34.0 | .. | 100 | 2150 | 3,204 | 15.4 |
| 6-in. B.L.R., Mark III., of 40 Cals. | 6 | 6.0 | 21.3 | 243.8 | 204.3 | .. | 37.0 | 44 to 47 | 100 | 2150 | 3,200 | 15.4 |
| 6-in. Q.-F. Gun | 6 | 8.17 | 25.0 | 293.7 | 245.3 | .. | 48.4 | .. | 100 | 2900† | 5,898 | 24.2 |
| 6-in. Q.-F., Mark VI. | 6 | (12.3) | 21.5 | 239.9 | 195.2 | { 1 in 180 to } 1 in 30 | 42.1 | 105 to 115 | { 250 } { 250 } | 2000 | 6,932 | 19.0 |
| 8-in. B.L.R., Mark I. | 8 | 13.0 | 21.5 | 239.9 | 195.2 | .. | 42.1 | .. | .. | 2080 | 7,498 | 19.0 |
| 8-in. B.L.R., Mark II. | 8 | 13.1 | 25.4 | 290.5 | 242.8 | zero to 1 in 25 | 45.1 | .. | 250 | 2150 | 8,011 | 20.1 |
| 8-in. B.L.R., Mark III., of 35 Cals. | 8 | 15.2 | 28.7 | 330.5 | 282.8 | .. | 45.1 | .. | 250 | 2800† | 13,602 | 21.1 |
| 8-in. B.L.R., Mark V., of 40 Cals. | 8 | 18.0 | 28.6 | 335.0 | 271.0 | .. | 61.0 | .. | 250 | 2800† | .. | 31.4 |
| 8-in. B.L.R., Mark V., of 45 Cals. | 8 | 18.0 | 28.6 | 335.0 | 271.0 | { 1 in 180 to } 1 in 35 | 57.2 | 225 to 240 | 500 | 2000 | 13,864 | 24.0 |
| 10-in. B.L.R., Mark I., of 30 Cals. | 10 | 25.7 | 27.4 | 306.3 | 247.3 | zero to 1 in 25 | 57.2 | .. | 500 | 2060 | 14,709 | 25.0 |
| 10-in. B.L.R., Mark I., of 35 Cals. | 10 | (27.1) (28.2) | 30.5 | 343.8 | 283.7 | { zero to } 1 in 26.8 | 57.2 | .. | 500 | 2000 | 13,864 | 24.0 |
| 10-in. B.L.R., Mark II., of 30 Cals. | 10 | 25.1 | 27.4 | 307.3 | 247.3 | zero to 1 in 25 | 57.2 | .. | 500 | 2100 | 15,285 | 25.8 |
| 10-in. B.L.R., Mark II., of 35 Cals. | 10 | 27.6 | 31.2 | 354.9 | 294.9 | .. | 57.2 | .. | 500 | 2800† | 27,204 | 42.0 |
| 10-in. B.L.R., Mark III., of 40 Cals. | 10 | 33.4 | 33.3 | 389.0 | 313.4 | .. | 75.6 | .. | 850 | 2100 | 25,985 | 30.8 |
| 12-in. B.L.R., Mark I. | 12 | 43.2 | 36.8 | 419.2 | 343.1 | .. | 71.1 | 425 | 850 | 2800† | 46,246 | 47.2 |
| 12-in. B.L.R., Mark III., of 40 Cals. | 12 | 52 | 41.8 | 480.1 | 388.1 | .. | 91.9 | .. | 1100 | 2100 | 33,627 | 33.5 |
| 13-in. B.L.R., Mark I. | 13 | 60.5 | 40.0 | 451.5 | 370.5 | .. | 80.9 | 550 | .. | .. | .. | .. |

NOTE.—The weight of fixed ammunition for Q.-F. 4-in. and 5-in. guns is 58 and 65 lbs. respectively.
 10" = 2200, 12" = 2300. The charges are kept down to suit the eight bars.
 † It should be pointed out that these high velocities cannot be fairly compared with the velocities on the British table, because the former are obtained with new guns, while the latter are purposely taken as what might be expected on service after the gun has fired a considerable number of rounds.
 ‡ By Trevellick's formula.

VICKERS, SONS AND MAXIM'S Q.F. GUNS AND MOUNTINGS.

This Table is supplied by the Manufacturers.

| Gun. | Gun. | | | | | | | | | | | | | | | | | | Mounting. | |
|--|-------------------|-------------------|-------------------|-------------------|-------------------|----------------------------|----------------------------|------------------------------|----------------------------|----------------------|----------------------|-------------------|-------------------|----------------------|----------------------|---------------------|---------------------|----------------------|-------------|--|
| | * 37 m.m. 30 cal. | * 47 m.m. 40 cal. | * 47 m.m. 42 cal. | * 57 m.m. 42 cal. | * 57 m.m. 50 cal. | * Naval. 76-2 m.m. 45 cal. | * Naval. 76-2 m.m. 50 cal. | * Field. 76-2 m.m. 23-5 cal. | * Mount. 75 m.m. 10-7 cal. | * 101-6 m.m. 45 cal. | * 101-6 m.m. 50 cal. | * 12 c.m. 40 cal. | * 12 c.m. 45 cal. | * 15-24 c.m. 40 cal. | * 15-24 c.m. 45 cal. | * 20-3 c.m. 45 cal. | * 25-4 c.m. 42 cal. | * 30-48 c.m. 40 cal. | | |
| Diameter of Bore (in ins.) | 1-457 | 1-85 | 1-85 | 2-244 | 2-244 | 3 | 3 | 3 | 2-953 | 4 | 4 | 4-724 | 4-724 | 6 | 6 | 8 | 9-2 | 10 | 12 | |
| Length of Bore (in ins.) | 43-5 | 82-0 | 73-72 | 81-34 | 95 | 112-2 | 135 | 150 | 31-6 | 180 | 200 | 188-98 | 212-58 | 240 | 270 | 360 | 414 | 405-15 | 480 | |
| Total length of Gun (in ins.) | 73-75 | 94-0 | 77-95 | 91-5 | 104-4 | 116-4 | 140 | 155 | 35-85 | 186-1 | 206 | 193-28 | 217 | 249-2 | 279-2 | 372-1 | 426-8 | 420 | 496-5 | |
| Diameter of Chamber | 1-44 | 1-6 | 2-04 | 2-04 | 2-45 | 2-8 | 3-6 | 3-6 | 3-0 | 5 | 5 | 5-1 | 5-5 | 6-8 | 8-5 | 11 | 13-5 | 11-5 | 17-5 | |
| Length of Chamber | 3-73 | 12-93 | 13 tons | 13 tons | 15 tons | 14-2 | 15-4 | 15-4 | 4-575 | 21-2 | 21-2 | 25-5 | 25-75 | 32-5 | 33 | 43 | 67 | 63-35 | 872 | |
| Maximum pressure in Chamber | 13 tons | 14 tons | 13 tons | 13 tons | 15 tons | 16 tons | 16 tons | 16 tons | 8 tons | 17 tons | 17 tons | 16 tons | 17 tons | 16 tons | 17 tons | 17 tons | 17 tons | 17 tons | 17 tons | |
| Nature of Charge | Corlitz | Corlitz | Corlitz | Corlitz | Corlitz | Corlitz | Corlitz | Corlitz | Corlitz | Corlitz | Corlitz | Corlitz | Corlitz | Corlitz | Corlitz | Corlitz | Corlitz | Corlitz | Corlitz | |
| Weight of Charge | oz. grs. 110 | oz. grs. 30 | oz. grs. 30 | oz. grs. 110 | oz. grs. 110 | lb. oz. 14 | lb. oz. 14 | lb. oz. 14 | ozs. 6-25 | lbs. 6 | lbs. 6 | lbs. 8-3 | lbs. 9 | lbs. 19 | lbs. 25 | lbs. 50 | lbs. 94-5 | lbs. 100 | lbs. 207 | |
| Weight of Projectile | 1 lb. | 1-25 lbs. | 3-3 lbs. | 6 lbs. | 6 lbs. | 12-5 lbs. | 12-5 lbs. | 12-5 lbs. | 12-5 lbs. | 25 lbs. | 25 lbs. | 45 lbs. | 45 lbs. | 100 lbs. | 100 lbs. | 250 lbs. | 380 lbs. | 450 lbs. | 850 lbs. | |
| Total weight of Gun, including Breech Mechanism | 1800 | 2350 | 2125 | 2400 | 2380 | 2500 | 2500 | 2500 | 918 | 2700 | 2800 | 2494 | 2600 | 2530 | 2775 | 2625 | 2750 | 2580 | 2600 | |
| Muzzle Velocity in feet per second | 4000 | 48 | 103 | 132 | 220 | 260 | 586 | 632 | 73 | 1263 | 1359 | 1940 | 2109 | 4437 | 5310 | 11945 | 19927 | 20811 | 39813 | |
| Muzzle Energy in foot tons | 1-9 | 3-3 | 4-5 | 5-3 | 6-2 | 7 | 9-2 | 9-7 | .. | 11-6 | 12-3 | 13-3 | 14-1 | 18-5 | 21-1 | 27-6 | 34-3 | 32-3 | 42-3 | |
| Penetration of Wrought Iron Plate at Muzzle by Gavre's formula | 1-5 | 2-6 | 3-5 | 4-1 | 4-8 | 5-4 | 7-1 | 7-5 | .. | 9 | 9-5 | 10-3 | 10-9 | 14-4 | 16-4 | 21-4 | 26-6 | 25-0 | 32-8 | |
| Penetration of Steel Plate at Muzzle by Gavre's formula | .. | .. | .. | .. | 7-1 | 7-9 | 10-25 | 10-8 | 5-4 | 13-3 | 14-0 | 14-6 | 15-5 | 19-8 | 22-6 | 28-5 | 32-7 | 33-4 | 42-4 | |
| + Perforation of Wrought Iron at Muzzle (Lieber's formula) | 300 | 300 | 300 | 300 | 28 | 28 | 20 | 20 | 14 | 15 | 15 | 12 | 12 | 8 | 8 | 5 | .. | .. | .. | |
| Rounds per minute | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | |
| Weight of Mounting complete with Shield | c. q. l. 30 | c. q. l. 30 | c. q. l. 30 | c. q. l. 30 | c. q. l. 30 | c. q. l. 30 | c. q. l. 30 | c. q. l. 30 | c. q. l. 30 | c. q. l. 30 | c. q. l. 30 | c. q. l. 30 | c. q. l. 30 | c. q. l. 30 | c. q. l. 30 | c. q. l. 30 | c. q. l. 30 | c. q. l. 30 | c. q. l. 30 | |
| Thickness of Shield (in ins.) | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | .. | |
| Weight of Shield | c. q. l. 30 | c. q. l. 30 | c. q. l. 30 | c. q. l. 30 | c. q. l. 30 | c. q. l. 30 | c. q. l. 30 | c. q. l. 30 | c. q. l. 30 | c. q. l. 30 | c. q. l. 30 | c. q. l. 30 | c. q. l. 30 | c. q. l. 30 | c. q. l. 30 | c. q. l. 30 | c. q. l. 30 | c. q. l. 30 | c. q. l. 30 | |
| Angle of Elevation | 16° | 13° | 18° | 18° | 20° | 20° | 20° | 20° | 26° | 20° | 20° | 20° | 20° | 20° | 20° | 15° | 15° | 15° | 15° | |
| Angle of Depression | 25° | 25° | 15° | 15° | 20° | 20° | 20° | 20° | 10° | 7° | 7° | 7° | 7° | 7° | 7° | 5° | 5° | 5° | 5° | |

Older types of 9-2-in., 10-in., 12-in. and 13-5-in. guns, as manufactured by Vickers, Sons & Maxim, Limited, are not enumerated in the table, but only modern guns making use of smokeless powders.
 * Existing guns.
 † The perforations through wrought iron (Lieber's) are added by the compiler for purposes of comparison.
 ‡ Depending on type of mounting used.

SCHNEIDER - CANET QUICK - FIRE GUNS.

This Table is supplied by the Manufacturers.

* Guns in actual use.

| Calibre, in centimètres Calibre, in inches | 24 9.45 | 20 7.87 | 152.4 6 | 15 5.91 | 14 5.5 | 12 4.72 |
|---|------------|------------|------------|------------|-----------|------------|
| Length, in calibres | 40 | 45 | 50 | 45 | 45 | 40 |
| Length, in feet | 31.5 | 32.7 | 25 | 22.2 | 24.6 | 15.7 |
| Weight of Gun, in tons | 21.45 | 13.18 | 5.65 | 4.72 | 6.20 | 1.61 |
| Weight of Projectile, in lbs. | 331 | 198 | 94.9 | 88.2 | 88.2 | 39.7 |
| Muzzle Velocity, in ft.-secs. | 2690 | 2860 | 2750 | 2560 | 2740 | 2530 |
| Muzzle Energy, in ft.-tons | 16312 | 17338 | 11258 | 4000 | 4590 | 2030 |
| Velocity at 2000 metres, in ft.-secs. | 2075 | 2147 | 1860 | 1744 | 1858 | 1114 |
| Energy at 2000 metres, in ft.-tons | 9900 | 10600 | 2254 | 1860 | 2150 | 1581 |
| Perforation at muzzle, Gavre formula, in ins. | 34.1 | 36.04 | 22.2 | 19.6 | 21.8 | 15.1 |
| " Tresidder formula, | | | | | | |
| through wrought-iron, in ins. | 31.3 | 25.6 | 21.0 | 19.1 | 21.0 | 15.2 |
| Perforation at 2000 metres, in ins. | 22.9 | 17.2 | 12.7 | 10.9 | 12.1 | 6.3 |
| Calibre, in centimètres | 10 | 9 | 7.5 | 6.5 | 5.7 | 4.7 |
| Calibre, in inches | 3.94 | 3.5 | 2.95 | 2.57 | 2.24 | 1.85 |
| Length, in calibres | 45 | 30 | 50 | 50 | 60 | 60 |
| Length, in feet | 14.8 | 8.8 | 12.3 | 10.65 | 12.8 | 9.24 |
| Weight of Gun, in tons | 1.69 | 0.71 | 0.88 | 0.54 | 0.68 | 0.26 |
| Weight of Projectile, in lbs. | 28.6 | 16.7 | 13.2 | 9.8 | 9.8 | 3.3 |
| Muzzle Velocity, in ft.-secs. | 2490 | 1970 | 2530 | 2439 | 2721 | 2688 |
| Muzzle Energy, in ft.-tons | 1235 | 451 | 587 | 372 | 455 | 167 |
| Velocity at 2000 metres, in ft.-secs. | 1475 | 1020 | 1337 | 1167 | 1327 | 826 |
| Energy at 2000 metres, in ft.-tons | 439 | 121 | 155 | 83.5 | 108 | 25 |
| Perforation at muzzle, Gavre formula, in ins. | 12.6 | 7.4 | 9.99 | 7.75 | 9.4 | 6.4 |
| " Tresidder formula, | | | | | | |
| through wrought-iron, in ins. | 12.7 | 7.2 | 10.1 | 8.5 | 10.5 | 8.7 |
| Perforation at 2000 metres, in ins. | 5.06 | 3.10 | 3.75 | 2.62 | 3.9 | 2.3 |
| Calibre, in centimètres | 37 | 37 | 37 | 37 | 37 | 37 |
| Calibre, in inches | 1.46 | 1.46 | 1.46 | 1.46 | 1.46 | 1.46 |

KRUPP QUICK-FIRE GUNS, Model 1897.

Table supplied by Manufacturers.

LIGHT GUNS.

| Calibre, in centimetres | 7.5 | 10.5 | 12 | 15 | 21 | 24 | 28 | 30.5 |
|-------------------------------------|--------|--------|--------|--------|--------|--------|--------|--------|
| Calibre, in inches | 2.95 | 4.13 | 4.72 | 5.91 | 8.27 | 9.45 | 11.02 | 12.01 |
| Total Length of Gun, in cal. | 40 | 40 | 40 | 40 | 40 | 40 | 40 | 40 |
| Total Length, in feet | 9.84 | 11.07 | 12.30 | 15.75 | 17.7 | 19.69 | 22.00 | 24.44 |
| Length of Bore, in inches | 108.66 | 123.43 | 138.19 | 153.55 | 174.21 | 194.89 | 222.45 | 247.78 |
| Weight of Piece, in lbs. | 1488.2 | 1710.8 | 1935.7 | 4078 | 5401 | 7055 | 9324 | 11707 |
| Weight of Piece, in tons | 0.66 | 0.76 | 0.86 | 1.82 | 2.12 | 2.41 | 2.73 | 3.15 |
| Weight of Steel Projectile, in lbs. | 11.5 | 11.5 | 11.5 | 30.86 | 30.86 | 30.86 | 46.30 | 46.30 |
| Weight of Charge, in lbs. | 14.6 | 14.6 | 14.6 | 39.68 | 39.68 | 39.68 | 59.52 | 59.52 |
| Muzzle Velocity, in ft.-secs. | 2349 | 2589 | 2703 | 2862 | 2956 | 2726 | 2907 | 2969 |
| Muzzle Energy, in ft.-tons | 2083 | 2254 | 2402 | 2087 | 2254 | 2402 | 2608 | 2664 |
| Perforation through Steel, in ins. | 438.6 | 512.1 | 581.5 | 1197 | 1430 | 1588 | 2121 | 2465 |
| Perforation through Iron, in ins. | 5.87 | 6.58 | 7.20 | 8.4 | 9.37 | 10.28 | 13.4 | 18.7 |
| Tresidder's formula | 8.1 | 9.1 | 10.0 | 11.4 | 12.5 | 13.8 | 18.0 | 22.1 |

HEAVY GUNS.

| Calibre, in centimetres | 7.5 | 10.5 | 12 | 15 | 21 | 24 | 28 | 30.5 |
|-------------------------------------|--------|--------|--------|--------|--------|--------|--------|--------|
| Calibre, in inches | 2.95 | 4.13 | 4.72 | 5.91 | 8.27 | 9.45 | 11.02 | 12.01 |
| Total Length of Gun, in cal. | 40 | 40 | 40 | 40 | 40 | 40 | 40 | 40 |
| Total Length, in feet | 9.84 | 11.07 | 12.30 | 15.75 | 17.7 | 19.69 | 22.00 | 24.44 |
| Length of Bore, in inches | 108.66 | 123.43 | 138.19 | 153.55 | 174.21 | 194.89 | 222.45 | 247.78 |
| Weight of Piece, in lbs. | 1860.7 | 2094.4 | 2325.9 | 5115 | 5732 | 6393 | 7628 | 8598 |
| Weight of Piece, in tons | 0.83 | 0.94 | 1.04 | 2.28 | 2.56 | 2.85 | 3.41 | 3.84 |
| Weight of Steel Projectile, in lbs. | 11.5 | 11.5 | 11.5 | 30.86 | 30.86 | 30.86 | 46.30 | 46.30 |
| Weight of Charge, in lbs. | 14.6 | 14.6 | 14.6 | 39.68 | 39.68 | 39.68 | 59.52 | 59.52 |
| Muzzle Velocity, in ft.-secs. | 2448 | 2635 | 2805 | 2658 | 2845 | 3104 | 2667 | 2864 |
| Muzzle Energy, in ft.-tons | 2172 | 2336 | 2490 | 2349 | 2510 | 2684 | 2392 | 2566 |
| Perforation through Steel, in ins. | 476.6 | 551.5 | 625 | 1519 | 1736 | 1984 | 2361 | 2720 |
| Perforation through Iron, in ins. | 6.22 | 6.93 | 7.56 | 9.96 | 10.94 | 12.0 | 11.8 | 13.07 |
| Tresidder's formula | 8.5 | 9.5 | 10.5 | 13.3 | 14.7 | 16.4 | 15.7 | 17.6 |

NOTE.—Every one of the Guns included in the Tables has been actually constructed and can be supplied on order. Fresh orders are all executed according to model 1899.

KRUPP QUICK-FIRE GUNS, Model 1899.

Table supplied by Manufacturers.

LIGHT GUNS.

| Calibre, in centimetres. | 7.5 | 10.5 | 12 | 15 | 21 | 24 | 28 | 30.5 |
|-------------------------------------|--------|--------|--------|--------|--------|--------|--------|--------|
| Calibre, in inches. | 2.95 | 4.13 | 4.72 | 5.91 | 8.27 | 9.45 | 11.02 | 12.01 |
| Total Length of Gun, in cal. | 40 | 40 | 40 | 40 | 40 | 40 | 40 | 40 |
| Total Length, in feet. | 9.84 | 10.5 | 10.5 | 10.5 | 10.5 | 10.5 | 10.5 | 10.5 |
| Length of Bore, in inches. | 108.66 | 138.19 | 138.19 | 138.19 | 138.19 | 138.19 | 138.19 | 138.19 |
| Length of Bore, in feet. | 9.06 | 11.5 | 11.5 | 11.5 | 11.5 | 11.5 | 11.5 | 11.5 |
| Weight of Piece, in lbs. | 1488.2 | 1710.8 | 1935.7 | 2170.7 | 2425.4 | 2692.1 | 2968.8 | 3245.5 |
| Weight of Piece, in tons. | 10.6 | 12.3 | 13.8 | 15.5 | 17.2 | 19.2 | 21.2 | 23.2 |
| Weight of Steel Projectile, in lbs. | 14.6 | 14.6 | 14.6 | 14.6 | 14.6 | 14.6 | 14.6 | 14.6 |
| Weight of Charge, in lbs. | 2.78 | 3.13 | 3.55 | 3.97 | 4.39 | 4.81 | 5.23 | 5.65 |
| Weight of Charge, in tons. | 0.002 | 0.002 | 0.002 | 0.002 | 0.002 | 0.002 | 0.002 | 0.002 |
| Muzzle Velocity, in ft.-secs. | 2690 | 2720 | 2750 | 2780 | 2810 | 2840 | 2870 | 2900 |
| Muzzle Velocity, in ft.-secs. | 2388 | 2395 | 2403 | 2411 | 2419 | 2427 | 2435 | 2443 |
| Muzzle Velocity, in ft.-secs. | 575.7 | 581.8 | 587.9 | 594.0 | 600.1 | 606.2 | 612.3 | 618.4 |
| Muzzle Velocity, in ft.-secs. | 7.12 | 7.12 | 7.12 | 7.12 | 7.12 | 7.12 | 7.12 | 7.12 |
| Perforation through Steel, in ins. | 9.8 | 11.0 | 11.8 | 12.6 | 13.4 | 14.2 | 15.0 | 15.8 |
| Perforation through Iron, in ins. | 9.8 | 11.0 | 11.8 | 12.6 | 13.4 | 14.2 | 15.0 | 15.8 |
| Tresidder's formula | 9.8 | 11.0 | 11.8 | 12.6 | 13.4 | 14.2 | 15.0 | 15.8 |

HEAVY GUNS.

| Calibre, in centimetres. | 7.5 | 10.5 | 12 | 15 | 21 | 24 | 28 | 30.5 |
|-------------------------------------|--------|--------|--------|--------|--------|--------|--------|--------|
| Calibre, in inches. | 2.95 | 4.13 | 4.72 | 5.91 | 8.27 | 9.45 | 11.02 | 12.01 |
| Total Length of Gun, in cal. | 40 | 40 | 40 | 40 | 40 | 40 | 40 | 40 |
| Total Length, in feet. | 9.84 | 10.5 | 10.5 | 10.5 | 10.5 | 10.5 | 10.5 | 10.5 |
| Length of Bore, in inches. | 108.66 | 138.19 | 138.19 | 138.19 | 138.19 | 138.19 | 138.19 | 138.19 |
| Length of Bore, in feet. | 9.06 | 11.5 | 11.5 | 11.5 | 11.5 | 11.5 | 11.5 | 11.5 |
| Weight of Piece, in lbs. | 1860.7 | 2094.3 | 2325.9 | 2557.5 | 2789.1 | 3020.7 | 3252.3 | 3483.9 |
| Weight of Piece, in tons. | 13.3 | 15.0 | 16.6 | 18.3 | 19.9 | 21.6 | 23.2 | 24.9 |
| Weight of Steel Projectile, in lbs. | 14.6 | 14.6 | 14.6 | 14.6 | 14.6 | 14.6 | 14.6 | 14.6 |
| Weight of Charge, in lbs. | 3.0 | 3.35 | 3.77 | 4.19 | 4.61 | 5.03 | 5.45 | 5.87 |
| Weight of Charge, in tons. | 0.002 | 0.002 | 0.002 | 0.002 | 0.002 | 0.002 | 0.002 | 0.002 |
| Muzzle Velocity, in ft.-secs. | 2792 | 2805 | 2817 | 2830 | 2843 | 2856 | 2869 | 2882 |
| Muzzle Velocity, in ft.-secs. | 2476 | 2481 | 2486 | 2491 | 2496 | 2501 | 2506 | 2511 |
| Muzzle Velocity, in ft.-secs. | 619.6 | 620.5 | 621.4 | 622.3 | 623.2 | 624.1 | 625.0 | 625.9 |
| Muzzle Velocity, in ft.-secs. | 7.52 | 7.52 | 7.52 | 7.52 | 7.52 | 7.52 | 7.52 | 7.52 |
| Perforation through Steel, in ins. | 10.5 | 11.4 | 12.3 | 13.2 | 14.1 | 15.0 | 15.9 | 16.8 |
| Perforation through Iron, in ins. | 10.5 | 11.4 | 12.3 | 13.2 | 14.1 | 15.0 | 15.9 | 16.8 |
| Tresidder's formula | 10.5 | 11.4 | 12.3 | 13.2 | 14.1 | 15.0 | 15.9 | 16.8 |

NOTE.—Every one of the guns included in the Tables has been actually constructed and can be supplied on order.

TABLE RELATING TO CONVERSION OF MEASURES.

Length.

METRIC TO ENGLISH.

ENGLISH TO METRIC.

| I. Mètres. | II. Yards. | III. Feet. | IV. Inches. | V. Yards. | VI. Mètres. | VII. Feet. | VIII. Mètres. | IX. Inches. | X. Centimètres. |
|---------------|---------------|---------------|----------------|--------------|----------------|---------------|------------------|----------------|--------------------|
| 1 | 1.0936 | 3.2809 | 39.37 | 1 | 0.91438 | 1 | 0.30479 | 1 | 2.5400 |
| 2 | 2.1873 | 6.5618 | 78.74 | 2 | 1.82877 | 2 | 0.60959 | 2 | 5.0799 |
| 3 | 3.2809 | 9.8427 | 118.11 | 3 | 2.74315 | 3 | 0.91438 | 3 | 7.6199 |
| 4 | 4.3745 | 13.1236 | 157.48 | 4 | 3.65753 | 4 | 1.21918 | 4 | 10.1598 |
| 5 | 5.4682 | 16.4045 | 196.85 | 5 | 4.57192 | 5 | 1.52397 | 5 | 12.6998 |
| 6 | 6.5618 | 19.6854 | 236.22 | 6 | 5.48630 | 6 | 1.82877 | 6 | 15.2397 |
| 7 | 7.6554 | 22.9663 | 275.60 | 7 | 6.40068 | 7 | 2.13356 | 7 | 17.7797 |
| 8 | 8.7491 | 26.2472 | 314.97 | 8 | 7.31507 | 8 | 2.43836 | 8 | 20.3196 |
| 9 | 9.8427 | 29.5281 | 354.34 | 9 | 8.22945 | 9 | 2.74315 | 9 | 22.8596 |

EXPLANATION.—To convert any number from one measure to the other, take the values of the different multiples of 10 by shifting the position of the decimal point, and add together. Thus, find the number

| | | | | | |
|--|--|--|---|---|--|
| of yards in 2354 mètres (see cols. I. & II.). mètres. yards. 2000=2187.3 300=328.09 50=54.68 4=4.37 ∴ 2354=2574.44 | of feet in 12.4 mètres (see cols. I. & III.). mètres. feet. 10=32.809 2=6.562 0.4=1.312 ∴ 12.4=40.633 | of inches in 30.5 centimètres (see cols. I. & IV.). Note, 1 m.=100 cm. cms. inches. 30.0=11.811 .5=.197 ∴ 30.5=12.008 | of mètres in 1026 yards (see cols. V. & VI.). yards. mètres. 1000=914.38 20=18.29 6=5.49 ∴ 1026=938.16 | of mètres in 1742 feet (see cols. VII. & VIII.). feet. mètres. 1000=304.79 700=213.36 40=12.19 2=0.61 ∴ 1742=530.95 | of centimètres in 17.72 ins. (see cols. IX. & X.). inches. cms. 10.0=25.400 7.0=17.780 0.7=1.778 .02=.051 ∴ 17.72=45.009 |
|--|--|--|---|---|--|

NOTE.—A ready way of approximately converting all French measures into English inches is to multiply by 4 and apply the decimal point by common sense—Thus for a 15-cm. gun; $15 \times 4 = 60$. Now this Calibre cannot be 60 inches, nor can it be 0.6 inch; therefore it must be 6 inches. (The exact value is 5.906 in.)

Weight.

METRIC TO ENGLISH.

ENGLISH TO METRIC.

| I. Kilo-grammes. | II. Tons. | III. Pounds Avoirdupois. | IV. Grains Troy. | V. Tons. | VI. Milliers. | VII. Pounds Avoirdupois. | VIII. Kilo-grammes. | IX. Grains. Troy. | X. Gramme. |
|---------------------|--------------|--------------------------------|------------------------|-------------|------------------|--------------------------------|------------------------|-------------------------|---------------|
| 1 | .000984 | 2.2046 | 15432.3 | 1 | 1.016 | 1 | 0.4536 | 1 | .0648 |
| 2 | .001968 | 4.4092 | 30864.7 | 2 | 2.032 | 2 | 0.9072 | 2 | .1296 |
| 3 | .002953 | 6.6139 | 46297.0 | 3 | 3.048 | 3 | 1.3608 | 3 | .1944 |
| 4 | .003937 | 8.8185 | 61729.4 | 4 | 4.064 | 4 | 1.8144 | 4 | .2592 |
| 5 | .004921 | 11.0231 | 77161.7 | 5 | 5.080 | 5 | 2.2680 | 5 | .3240 |
| 6 | .005905 | 13.2277 | 92594.1 | 6 | 6.096 | 6 | 2.7216 | 6 | .3888 |
| 7 | .006889 | 15.4323 | 108026.4 | 7 | 7.112 | 7 | 3.1751 | 7 | .4536 |
| 8 | .007874 | 17.6370 | 123458.8 | 8 | 8.128 | 8 | 3.6287 | 8 | .5184 |
| 9 | .008858 | 19.8416 | 138891.1 | 9 | 9.144 | 9 | 4.0823 | 9 | .5832 |

EXPLANATION.—To convert any number from one measure to the other, take the values of the different multiples of 10 by shifting the position of the decimal point, and add together. Thus, find the number

| | | | | | |
|---|--|--|---|---|--|
| of tons in 35 milliers (see cols. I. & II.). Note, 1000 kg. =1 millier). milliers. tons. 30=29.53 5=4.92 ∴ 35=34.45 | of pounds in 56.3 kilo-grammes. (see cols. I. & III.). kgms. lbs. 50=110.231 6=13.228 0.3=.661 ∴ 56.3=124.120 | of grains in 120 grammes (see cols. I. & IV.). Note, 1000 grms. =1 kg.) grammes. grains. 100=1543.23 20=308.65 ∴ 120=1851.88 | of milliers in 38 tons (see cols. V. & VI.). tons. milliers. 30=30.48 8=8.13 ∴ 38=38.61 | of kilogrammes in 68 pounds (see cols. VII. & VIII.). lbs. kgs. 60=27.216 8=3.629 ∴ 68=30.845 | of grammes in 85 grains (see cols. IX. & X.). grains. grammes. 80=5.184 5=0.324 ∴ 85=5.508 |
|---|--|--|---|---|--|

NOTE.—7000 grains troy=1 pound avoirdupois.

PRESSURE.

| METRIC TO ENGLISH. | | | ENGLISH TO METRIC. | | | ATMOSPHERIC TO ENGLISH. | | | ENGLISH TO ATMOSPHERIC. | |
|-------------------------------------|-------------------------|-----------------------|-------------------------|-------------------------------------|-----------------------|-------------------------------------|---------------|-----------------------|-------------------------|---------------|
| I. | II. | III. | IV. | V. | VI. | VII. | VIII. | IX. | X. | XI. |
| Kilo-grammes per square centimètre. | Pounds per square inch. | Tons per square inch. | Pounds per square inch. | Kilo-grammes per square centimètre. | Tons per square inch. | Kilo-grammes per square centimètre. | Atmo-spheres. | Tons per square inch. | Tons per square inch. | Atmo-spheres. |
| 1 | 14.223 | .00635 | 1 | .07031 | 1 | 157.49 | 1 | .00656 | 1 | 152.38 |
| 2 | 28.446 | .01270 | 2 | .14062 | 2 | 314.99 | 2 | .01313 | 2 | 304.76 |
| 3 | 42.668 | .01905 | 3 | .21093 | 3 | 472.48 | 3 | .01969 | 3 | 457.14 |
| 4 | 56.891 | .02540 | 4 | .28124 | 4 | 629.97 | 4 | .02625 | 4 | 609.52 |
| 5 | 71.114 | .03175 | 5 | .35155 | 5 | 787.47 | 5 | .03281 | 5 | 761.91 |
| 6 | 85.337 | .03810 | 6 | .42186 | 6 | 944.96 | 6 | .03938 | 6 | 914.29 |
| 7 | 99.560 | .04445 | 7 | .49217 | 7 | 1102.45 | 7 | .04594 | 7 | 1066.67 |
| 8 | 113.783 | .05080 | 8 | .56248 | 8 | 1259.95 | 8 | .05250 | 8 | 1219.05 |
| 9 | 128.005 | .05715 | 9 | .63279 | 9 | 1417.44 | 9 | .05906 | 9 | 1371.43 |

NOTE.—One atmosphere is taken to be 14.7 lbs. per square inch.

EXPLANATION.—To convert any number from one measure to the other, take the values of the different multiples of 10 by shifting the position of the decimal point, and add together. Thus, find the number

| of pounds per square inch in 32.1 kilogrammes per square centimetre (see cols. I. & II.). | of tons per square inch in 3210 kilogrammes per square centimetre (see cols. I. & III.). | of kilogrammes per square centimetre in 15 lbs. per square inch (see cols. IV. & V.). | of kilogrammes per square centimetre in 18.3 tons per square inch (see cols. VI. & VII.). | of tons per square inch in 3254 atmospheres (see cols. VIII. & IX.). | of atmospheres in 14.6 tons per square inch (see cols. X. & XI.). |
|---|--|---|---|--|---|
| kgs. per sq. in. | kgs. per sq. in. | lbs. per sq. in. | tons per sq. in. | atmospheres per sq. in. | tons per sq. in. |
| 30 = 426.68 | 3000 = 19.05 | 10 = .7031 | 10 = 1574.9 | 3000 = 19.69 | 10 = 1523.8 |
| 2 = 28.45 | 200 = 1.27 | 5 = .3516 | 8 = 1259.95 | 50 = .33 | 4 = 609.5 |
| 0.1 = 1.42 | 10 = .06 | | 0.3 = 47.25 | 4 = .03 | 0.6 = 91.4 |
| 32.1 = 456.55 | ∴ 3210 = 20.38 | ∴ 15 = 1.0547 | ∴ 18.3 = 2382.10 | ∴ 2254 = 21.36 | ∴ 14.6 = 222.7 |

ENERGY.

| METRIC TO ENGLISH. | | ENGLISH TO METRIC. | |
|--------------------|------------|--------------------|-------------|
| I. | II. | III. | IV. |
| Mètre-tons. | Foot-tons. | Foot-tons. | Mètre-tons. |
| 1 | 3.2291 | 1 | 0.3097 |
| 2 | 6.4581 | 2 | 0.6194 |
| 3 | 9.6872 | 3 | 0.9291 |
| 4 | 12.9162 | 4 | 1.2388 |
| 5 | 16.1453 | 5 | 1.5484 |
| 6 | 19.3743 | 6 | 1.8581 |
| 7 | 22.6034 | 7 | 2.1678 |
| 8 | 25.8324 | 8 | 2.4775 |
| 9 | 29.0615 | 9 | 2.7872 |

1 mètre-ton is termed a "dinamode" in Italy.

EXPLANATION.—To convert any number from one measure to the other, take the values of the different multiples of 10 by shifting the position of the decimal point, and add together. Thus find the number

| of foot-tons in 4367 mètre-tons (see cols. I. & II.). | of mètre-tons in 3592 foot-tons (see cols. III. & IV.). |
|---|---|
| mètre-tons. | foot-tons. |
| 4000 = 12916.2 | 3000 = 929.1 |
| 300 = 968.72 | 500 = 154.84 |
| 60 = 193.74 | 90 = 27.87 |
| 7 = 22.60 | 2 = .62 |
| ∴ 4367 = 14101.26 | ∴ 3592 = 1112.43 |

PERFORATION THROUGH IRON AND STEEL WITH THE FACE NOT HARDENED.

To obtain perforation through steel equivalent to a given perforation through iron, and *vice versa*.

1 inch steel = 1½ inches iron ;
that is, 4 inches steel = 5 inches iron.

Thus, given 9.4 inches perforation through iron,


$$9.4 \times \frac{4}{5} = 7.52 \text{ inches steel;}$$

or, given 5.2 inches steel,

$$5.2 \times \frac{5}{4} = 6.5 \text{ inches iron.}$$

PART IV.

STATISTICS, OFFICIAL STATEMENTS AND
PAPERS.



Statement of the First Lord of the Admiralty explanatory of the Navy Estimates for 1901-1902.

The Navy Estimates for 1901-1902 amount to a net total of £30,875,500; being an increase of £2,083,600 beyond the amount of £28,791,900 voted for the year 1900-1901.

The Manning Vote (Vote 1) shows an increase of £233,000, due in the main to the increased number of men last year and this year.

Vote 8, Shipbuilding, &c., shows a net increase of £1,274,900.

Vote 9, Armaments, is increased by £161,800.

Vote 10, Works, is increased by £137,300.

The remaining Votes show a net increase of £276,600.

The comparison in every case is with the original estimates of 1900-1901 plus the additional estimates voted in July, 1900.

NUMBERS.

The total number of Officers, Seamen and Boys, Coastguard, and Royal Marines proposed for the year 1901-1902 is 118,635, being an increase of 3,745.

The additions proposed are to meet the needs of the Fleet, and are made up of

- 287 Officers.
- 1,150 Seamen.
- 500 Stokers.
- 398 Miscellaneous.
- 310 Artizans (including 100 Electricians.)
- 1,000 Marines.
- 100 Apprentices (Shipwrights and Coopers).

MOBILISATION.

The plans for strengthening and developing the system of Reserves, referred to in last year's statement as under consideration, have been given effect to by the passing of an Act of Parliament

to establish a new Reserve force, to be called the Royal Fleet Reserve. It will consist partly of men who have served in the Navy or Royal Marines and left without taking pension (Class B), and partly of men who have been pensioned (Class A). The Seaman Pensioner Reserve will be superseded eventually by the new Royal Fleet Reserve, but the present Royal Naval Reserve is not affected.

The first entries in the new force will be made from the first of March of this year, and it is hoped to eventually raise the numbers of Class B to 15,000. The men in the new Royal Fleet Reserve will undergo periodical drill.

In order further to facilitate mobilisation another Act of Parliament was also passed, enabling the Admiralty, when the Royal Naval Reserve is called by Royal Proclamation into actual service, to limit the numbers to be called out to such as may from time to time appear desirable.

The Coast Guard and Port Guard Ships, which heretofore have had only a portion of their crews on board, are now kept fully manned. An additional Coast Guard ship has been commissioned and established at Rathmullen, in Ireland.

THE ROYAL MARINES.

2,630 Recruits were raised for the Corps during the year 1900, the Artillery branch receiving 616 of this number, the remainder going to the Infantry Divisions.

For the Artillery branch the mean height was 5 feet 8 inches, for the Infantry 5 feet 6 inches.

The twelve months produced a wastage of 2,165, the largest for some years. More than half of this number were men time expired, pensioned, purchased, and invalided, most of whom will be eligible for entry in the new Reserve, and will probably join it.

During the past year directions have been given for the training in Gunnery of the young officers Royal Marine Light Infantry to take place in the Gunnery School at Whale Island instead of at their Divisional Headquarters in the same manner as the young officers Royal Marine Artillery, whereby uniformity of instruction is ensured.

A fuller recognition has been made of the eligibility of Marines for employment as Captains of Guns in H.M. Ships. A proportion of Marine Captains of Guns will in future be allowed in the complements of all Battleships and such First Class Cruisers as are Flagships; and a new auxiliary rating of Second Captain of Gun

has been established by Order in Council for men of the Marine Infantry with an additional allowance of one penny per diem while borne on ships' books for the duty.

Musketry.—Twenty per cent. of the men on shore qualified as marksmen, 75 per cent. reaching the next stage of efficiency.

Reserve of Officers.—During the past year attention was directed to the fact that no specific regulation existed under which Retired Marine Officers could be recalled for service in case of emergency. A scheme has been prepared for the creation of a "Reserve of Officers, Royal Marines." It makes all officers who voluntarily retire liable to serve in this Reserve, those already on the Retired List or who may be retired compulsorily having the option of joining if under 50.

Reserve of Men.—Taking advantage of the powers given to the Admiralty by the Naval Reserve Act of 1900, to raise and keep up a new Division of Reserves in addition to the men already authorised under the Act of 1859, steps were taken to incorporate in the new force a reserve of Royal Marines, and the raising of this Reserve is now in course of operation.

NAVAL RESERVES.

Executive Officers.—The establishment is fixed at 1,500, and there are now borne 436 Lieutenants, 517 Sub-Lieutenants, and 547 Midshipmen. Vacancies for Executive Officers are filled up as soon as they occur. There are no vacancies at present, and 330 qualified candidates are on the list of applicants for appointment.

The total number of Executive Officers now on the Active List who have served for 12 months or more in the Navy, or are now undergoing 12 months' training, is 295, an increase of 28 since last year.

Engineers.—The establishment of Engineer Officers is fixed at 400 and is complete. There are 15 candidates on the list of applicants for appointments.

The Instructional Courses for Engineers in the Home Dockyards, commenced in 1898, have been continued. Three courses of six Officers have been held each year, and arrangements are now being made to increase the number to 18 Officers for each course, or a total of 54 per annum. Thirty-two Officers have been through the courses, and they have been satisfactorily reported on for conduct and attention. These Officers appreciate the instruction and experience afforded.

Seamen.—On the 31st December last the total number of seamen borne, as compared with the numbers voted, was:—

| Class. | Number Voted, 1900-1. | Numbers Borne. | |
|-------------------------------|--------------------------|----------------|-----------|
| | | 31.12.00. | 31.12.99. |
| Qualified Seamen. | 11,700 | 2,937 | 2,080 |
| 1st Class, old system | | 7,978 | 8,921 |
| Seamen | 11,300 | 4,218 | 3,406 |
| 2nd Class, old system | | 5,996 | 7,555 |
| Totals | 23,000 | 21,129 | 21,962 |

| | 1900. | 1899. |
|---|-------|-------|
| Numbers embarked for six months' Naval training | 784 | 980 |

The falling off in numbers borne and in those embarking for naval training, is attributed to the unpopularity of this compulsory training owing to insufficient pay as compared with what the men earn at their proper vocations (fishing, yachting, merchant ships, &c.), and the length of time required to serve, which interferes with their employment. Arrangements are being made to readjust the pay and to reduce the period of training from six to three months, which it is hoped will induce more men to embark. Further, this embarkation will not be compulsory, except as regards earning promotion and future pension, and men who do not qualify for promotion to "Qualified Seamen" will be allowed to re-enrol as "Seamen" for a second and third period of five years, which at present is not allowed. We regret this unavoidable diminution of the training period; but it is believed that a readjustment of the system of instruction will go far to neutralise the loss of time.

The negotiations for the establishment of a branch of the Royal Naval Reserve in the North American Colonies, to which reference was made in last year's Statement, have been proceeded with, and 50 seamen from Newfoundland have been embarked in His Majesty's ships on the Station for six months' training.

Firemen.—During the year 1900 there were 337 Firemen enrolled as compared with 544 in 1899, being a decrease of 207.

The numbers borne as compared with the numbers voted are:—

| | | | |
|-------------------------------|-------|-----------|--------|
| Borne, 31st December 1900 . . | 3,530 | Voted . . | 3,600. |
| " " 1899 . . | 3,494 | " . . | 3,500. |

Drill Ships and Batteries.—The process of replacing the old M.L. guns by modern Q.F. guns is being continued, and arrangements are in hand to supply several 5-in. B.L. (converted to Q.F.) and Maxim guns during the forthcoming financial year.

CHANGES IN COMPOSITION OF FLEETS.

China.—The China Fleet has been considerably increased during the past 12 months. The Dido, Isis, and Astraea from the Mediterranean, the Arethusa from the Pacific, the Wallaroo, Mohawk, and Lizard from Australia, and the Marathon from the East Indies, were all sent to that Station during the disturbances last year for temporary service. Of these, the Marathon has returned to her Station, the Dido and Isis have been replaced by other Cruisers in the Mediterranean, and will remain in China; the Mohawk has been replaced in Australia, and is now returning home. The Glory, Argonaut, and two Destroyers (Otter and Janus) have been added to the Fleet in Chinese waters, and the Ocean left Malta 2nd February to join them. The Robin, River Gunboat, has been commissioned for service in the West River, and the steamer Pioneer has been purchased and will be fitted as a gunboat for service on the Yangtse Kiang.

Mediterranean.—Eight Destroyers and four first-class Torpedo Boats have been added to the Mediterranean Fleet. The Hood has replaced the Ocean sent to China.

Home.—A Torpedo Gunboat (fitted with water-tube boilers) has been attached to each Home Port for the instruction of Engine Room Ratings in water-tube boilers.

The additions to the sea-going Fleet in Commission, enumerated above, involved complements to the extent of 7,269 Officers and Men.

It is worthy of note that these ships have been commissioned without reducing the personnel at Home below the strength required for mobilisation of the Ships in Reserve, without any interruption or diminution of the work of the various Schools and Training Establishments, and without drawing upon any of the Naval Reserve Forces. The ordinary reliefs on foreign stations, which were due during the latter portion of the year 1900, had unavoidably to be delayed, but are all now either being or about to be carried out.

Naval Brigades.—All Naval Brigades serving on shore in South Africa had returned to their ships by October, 1900.

A Naval Brigade participated in the International advance to Peking, and, on the occupation of the city, returned to their ships.

The Government of South Australia offered the services of the South Australian Gunboat Protector for service in China during the disturbances of last year. The offer was accepted for four months, and the Protector served in China from September till the end of November. The Commander-in-Chief reported that the Protector was most useful, being an efficient and well kept man-of-war, reflecting credit on captain, officers, and men.

The Governments of New South Wales and Victoria similarly offered the services of Colonial Naval Brigades, consisting respectively of 300 and 200 officers and men for service in China. These offers were accepted, and the Brigades have been employed on shore under the General where they did good service. They will return home by the end of March.

Losses.—The Second Class Cruiser Sybille went ashore at Lambert's Bay, in Cape Colony, on 16th January, and is reported to be a total wreck. One life was lost. The Report of the Court Martial has not yet arrived. The Hind, Coast Guard Cruiser, was wrecked on the East Coast of England in November. No lives were lost. The River Gunboat Sandpiper sank during a typhoon at Hong Kong in November, but was successfully raised. One life was lost.

Manœuvres.—The annual Manœuvres took place, 49 ships and torpedo boats being specially commissioned for the purpose. Altogether 115 ships and vessels took part in the Manœuvres, and over 30,000 officers and men. The total number of Coast Guard embarked was 45 officers and 1,711 men, and of Royal Naval Reserves, 35 officers and 390 men.

COALING OF THE FLEET.

In order to facilitate the departmental administration of this service a slight change has been made in the Navy Estimates, whereby all incidental expenses, including craft, machinery, &c., are provided for under the same subhead as the cost of the coal and its conveyance (Vote 8, Section 2, Subhead K). The works and buildings connected with coaling have also been grouped in one subhead of Vote 10.

Steps are in progress to organise and improve the coaling facilities at the several Naval Stations to ensure that the requirements of the Fleets can at all times be amply met. It is proposed to include the provision for the necessary expenditure in the forthcoming Naval Works Loan Bill.

Additions have been made to the coaling craft, and provision is included in the Estimates for 1901-2 for further floating craft to be

equipped with modern appliances. Provision is also made for the increase of reserve stocks of coal at certain Naval Stations abroad. The supervision of coaling duties at certain of the Naval Depôts has been strengthened.

The system of supplying coal to Fleets and Naval Stations by colliers under Admiralty control or under the orders of the Commanders-in-Chief is working well, and will be extended as far as circumstances permit.

The experiments with Patent Fuel have been satisfactorily concluded, and suitable quantities will be stored to form adequate reserves at foreign stations.

Schemes for further trials with Liquid Fuel have been considered, and some manufacturers have undertaken to submit designs and particulars of trials. Two of these plans are about to be tried, one with a marine water-tube boiler on shore, and one, if the arrangements are suitable, on board H.M.S. Surly.

NAVAL TRAINING.

The training of officers and men has received and is receiving much attention from the Board.

The report of a Committee on the Training and Examination of Junior Officers, which was appointed in 1897, and the circular in which its recommendations have been embodied and issued to the Fleet, will be laid before Parliament. Sufficient time has not elapsed to show the result of the changes introduced, but any modifications shown to be necessary by experience will be adopted.

Special encouragement is being given to the better study of foreign languages; the seamanship examination has been revised by the Council of Education to meet the present conditions obtaining on modern warships; promotion to the rank of Lieutenant will not in future depend only upon success in examinations, but a certificate will be required to be obtained by every Sub-Lieutenant from his Commanding Officer after six months' service in a ship of war at sea as to his fitness to take charge of a watch at sea and to perform efficiently his other duties as a Lieutenant.

A Naval Strategy course, including therein Strategy, Tactics, Naval History, and International Law, has been commenced at Greenwich for the benefit of the Senior Officers at the Royal Naval College, and is being conducted by the Captain of the College. The Tactical courses at Portsmouth are being continued. All the officers going through these courses have been placed on full pay.

The Council of Naval Education has been directed to carefully scrutinise the Greenwich course with a view to ascertaining whether the matter and period of study of the Gunnery and Torpedo Lieutenants is that most adapted to the efficiency of the Service.

The system of training the men of the Navy is being constantly watched and revised with a view to increased efficiency. Great stress is being laid on efficiency in coaling; special arrangements have been made for training the stokers in the depôts in the stoking of water-tube boilers. A scheme has been matured, and is now under consideration for transferring a large proportion of the instruction in gunnery from the Gunnery Schools to the sea-going Fleet, and for confining the further education in the Gunnery Schools to those seamen who show special aptitude, and who may, therefore, be selected for the advanced ratings of Captains of Guns and Captains of Turrets, or for the higher Torpedo ratings. There is no doubt but that the standard of proficiency in gunnery is steadily rising in the Navy. A large addition of practice ammunition for the Fleet was sanctioned in 1899, and a seagoing gunnery ship has been allotted to each of the Gunnery Schools, and will be attached as soon as ready.

NEW CONSTRUCTION.

There has been no relaxation of activity in shipbuilding and engineering operations generally during the past year, better progress having been made than in recent years with the ships under construction for the Royal Navy, and it is anticipated that the aggregate expenditure on new construction will closely approach the provision made in the Estimates, and will largely exceed that of any previous year.

The steps taken by the various contractors to increase the output of armour and machinery have begun to show their effect, and the rate of progress has greatly increased during the latter half of the year. This is especially the case with armour, the total output of which for Admiralty use in the present year will be from 45 to 50 per cent. greater than last year. The rate of delivery during the latter half of this year indicates that the new plant is now in effective working order. Moreover, a fifth firm has undertaken armour manufacture, and has advanced considerably with the necessary plant. The outlook in regard to the future supply of armour is, therefore, favourable.

The total output of new construction in the financial year now drawing to a close will probably exceed that of 1899-1900, which was previously the greatest on record, by about a million.

Battleships.

The *Glory* has been completed and commissioned. The *Albion* has been delivered, and has commenced her trials, but I regret to say that defects in her machinery have been discovered which have postponed her completion.

The *Vengeance*, the last ship of the *Canopus* class, has been detained at Barrow in consequence of an accident to the entrance of the dock in which the ship was being completed. It is now reported that the works on the dock entrance are being rapidly pushed forward, and that they will probably be sufficiently advanced to permit the ship to pass out during April. Her trials and completion will be accelerated as much as possible after delivery.

The six battleships of the *Formidable* class, which were in hand in the dockyards at the beginning of the present financial year, have been considerably advanced, and two similar ships (the *Queen* and *Prince of Wales*) have been commenced. The *Implacable* has commenced her steam trials, and will be practically completed by the end of the financial year; her gunnery trials will probably be made rather later. It is anticipated that the *Formidable* and *Irresistible* will be completed early in the next financial year, and the *Bulwark* about December next. The *London* and *Venerable* will probably be finished about May 1902.

The six vessels of the *Duncan* class have also been well advanced. Of the four building by contract, the *Russell* has been launched and the *Duncan* will be launched on March 21st, and the other two are very nearly in the same stage of progress. The *Albemarle* and *Montagu*, building in the dockyards, are to be launched on the 5th of March. All these vessels should be completed in 1902-3.

Armoured Cruisers.

Twenty vessels are now in course of construction; six of the *Cressy* class, four of the *Drake* class, and ten of the *Monmouth* class.

The *Cressy* has been delivered within the contract date, and has satisfactorily completed her steam trials, exceeding her estimated maximum speed by nearly half a knot. Satisfactory preliminary trials have been made with the new type of mounting for her 9·2-in. guns, and the ship is now being prepared for service. Her gunnery trials will be carried out early in the next financial year.

The *Sutlej* has been delivered and the *Aboukir* will be delivered during the present financial year. Both ships will be made ready for trials immediately.

The completion of the Hogue at Barrow has been delayed by the same accident that has affected the delivery of the Vengeance. The contractors are now making special arrangements to press forward the work on the ship.

The Bacchante has been launched, and the Euryalus is the only vessel of the class remaining on the building slips. Her launch has been deferred in consequence of the accident to the dock entrance at Barrow.

One vessel of the Drake class (the Good Hope) has been launched, and the Drake is to be launched before the present financial year closes. Equally satisfactory progress has not been made hitherto on the other two vessels of this class building by contract, but the contractors have been urged to make greater efforts, and have undertaken to do so.

Four of the vessels of the Monmouth class which were commenced last year have been considerably advanced. The first of these (the Kent) will have been launched before the close of this financial year, and two others will probably be launched about May next, and the fourth about August.

The remaining six vessels have been commenced recently and the work on them will be advanced, before the present financial year closes, to a stage which will enable rapid progress to be made on them next year.

It will be seen from the above that four battleships and four armoured cruisers are expected to be launched during the last two months of this financial year.

Protected Cruisers.

The contractors' steam trials of the first-class cruiser Spartiate were not satisfactory, and the completion of the ship has been delayed by the necessity for replacing a condemned crank shaft.

The two second-class cruisers of improved Hermes type (Challenger and Encounter) referred to in the Statement of last year have been commenced in the Dockyards. They are not sheathed with wood and copper, and are about a knot faster than the Hermes class. One of these classes is to be fitted with Babcock & Wilcox boilers.

Only one third-class cruiser (the Pandora) has been in hand during the year. Her steam trials have still to be completed, but it is anticipated she will be practically ready for service at the close of the present financial year.

Sloops and Gunboats.

Eight sloops have been under construction during the year, six in the Dockyards and two by contract. The delivery of the latter has been considerably delayed, and they will not be completed as was anticipated this financial year. Two of the dockyard-built vessels will be completed this year, and two others will be finished next summer, when the contract-built ships should also be finished.

The remaining two vessels (Odin and Merlin) have been commenced at Sheerness during the present year.

Two gunboats of extremely light draught (the Teal and Moorhen) have been begun this year and are now well advanced. The work has been hindered by difficulties with material for boiler tubes, but it is anticipated that the vessels will be finished early in the next financial year.

Torpedo-boat Destroyers.

The total number of vessels in this class is now 113. Forty-two have trial speeds of 26 to 27 knots, and the whole of these have been completed and accepted. Four of this type, which were originally completed with locomotive boilers, have now been fitted with water-tube boilers, and the whole of the 113 torpedo boat destroyers now have water-tube boilers of the small tube or Express type.

Of the 30-knot vessels 58 have been delivered, of which two have not yet passed their trials, and the eight still remaining in the builders' hands are well advanced, one having passed her official trials and two others being now under trial.

Of the five Destroyers with trial speeds of over 30 knots, two have been delivered and have completed their trials, viz., the Albatross, which attained $31\frac{1}{2}$ knots speed on trial, and the Viper, fitted with Parsons' Steam Turbine, which attained on trial a speed of over $33\frac{1}{4}$ knots, combined with an almost entire absence of vibration. The Cobra, which has similar machinery to that in the Viper, was tried with a load on board largely in excess of that usually carried on speed trials by Destroyers, and maintained for three hours a speed slightly above 30 knots.

A fourth vessel, of 32 knots' speed, is expected to commence her preliminary steam trials about June next.

The fifth vessel (of 33 knots' contract speed) has undergone a very long series of trials with propellers of varying dimensions, but the builders have not up to the present succeeded in attaining the guaranteed speed, and consequent delay in completion has resulted.

At the close of this financial year there will be 10 Destroyers ordered previously to 1900-1901 still undelivered, but five additional

vessels, not included in the original Estimates for the year, were purchased under an additional Estimate while in course of construction, and these will be delivered this financial year.

Torpedo Boats.

The two Torpedo Boats of 25 knots trial speed, ordered in 1899, are well advanced. The first will shortly commence her preliminary trials. The further two of the same type ordered this year are also well advanced, and it is expected that all four will have been delivered and tried by September next.

Royal Yacht.

The alterations in this vessel which were mentioned as necessary in last year's Statement have been made, and she has satisfactorily completed her steam trials during the year. These trials included three of 48 hours each, one at 5,000 horse-power, and two at 7,500 horse-power; and one trial of eight hours at 11,000 horse-power. All the trials were carried out with complete success, the engines working with great smoothness and an almost complete absence of vibration. The maximum speed obtained was $20\frac{1}{2}$ knots, instead of the 20 knots promised in the design; and on two occasions the vessel ran at a speed of about $18\frac{1}{2}$ knots for 48 hours continuously.

Experiments made since the alterations show that the vessel will have ample stability, and her behaviour during her trials when experiencing a very strong breeze and considerable sea was very satisfactory.

The work of completing her internal decoration and fittings is now in hand.

Fleet Auxiliaries.

The provision of fleet auxiliaries is under the careful consideration of the Board. Three colliers are now working with the Fleet; a repairing and distilling ship has been purchased and is now being fitted up; provision is made in the Estimates for another distilling ship and for a depôt ship, while it is expected that the *Maine* will, with the kind assistance of the Committee of American ladies and the owner, be secured for service as a hospital ship in the Mediterranean during the ensuing summer.

Royal Naval Reserved Merchant Cruisers.

During the year a new arrangement has been made with nearly all the great steamship companies, by which their finest vessels are held at the disposition of the Admiralty for employment as Armed

Cruisers when required. Under the previous agreements only the Cunard, White Star, Peninsular and Oriental, and Canadian Pacific Railway Companies were included. To these have now been added the Orient, Royal Mail, and Pacific Companies. Eighteen of the largest and swiftest passenger steamers belonging to these companies will receive an annual subvention, and thirty steamers in addition are held at the disposition of the Admiralty without further subsidy. In the main features the new agreements will be similar to former agreements, but in some particulars, modifications have been made based on experience.

Experiments.

During the year a number of experiments have been made on armour plates with a view to improvements in manufacture, or to the selection of the quality of armour best adapted for particular services.

An important firing trial was also carried out against H.M.S. Belleisle, and much valuable information was obtained which will be of service in future naval construction.

Submarine Boats.

Five submarine vessels of the type invented by Mr. Holland have been ordered, the first of which should be delivered next autumn.

What the future value of these boats may be in naval warfare can only be a matter of conjecture. The experiments with these boats will assist the Admiralty in assessing their true value. The question of their employment must be studied, and all developments in their mechanism carefully watched by this country.

MACHINERY AND BOILERS.

Between the preparation of last year's Statement and 31st March, 1900, the battleship Glory and the sloop Condor completed their contractors' trials, and the former vessel is now on the China station.

The following vessels have completed their contract steam trials during the present financial year:—

First-class cruiser—Cressy. Sloops—Vestal and Shearwater. Torpedo-boat destroyers—16 in number. Royal yacht—Victoria and Albert.

In addition, the battleships Albion, Implacable, the first-class cruiser Spartiate, the third-class cruiser Pandora, the sloop Mutine, and four torpedo-boat destroyers have commenced their trials.

The battleships Bulwark and Formidable and armoured cruiser Sutlej will be ready for trials early in the next financial year.

The third-class cruiser *Blanche* has been re-boilered, the double-ended cylindrical boilers being replaced by water-tube boilers of the small-tube type. She has completed her trials satisfactorily, and is now on foreign service. The sister vessel *Blonde* is now in hand for similar alterations.

The torpedo-gunboats *Niger* and *Gossamer* are being re-engined and re-boilered, with small-tube water-tube boilers, associated with light quick-running engines. This is following on a similar course to that adopted last year with *Skipjack* and *Speedwell*, and provides an increase in the I.H.P. developed in the vessels from 3,500 to 6,000.

The torpedo-boat destroyers *Havock*, *Hasty*, and *Charger* have had their locomotive boilers replaced by small-tube water-tube boilers, and the *Havock* has satisfactorily completed her trials with the new boilers.

The torpedo-gunboat *Seagull*, recently fitted with water-tube boilers of the *Niclausse* type, has satisfactorily completed an exhaustive series of sea-going trials similar to those carried out in the *Sharpshooter* (*Belleville*) and *Sheldrake* (*Babcock and Wilcox*) during the preceding year.

These comparative trials in three similar ships have furnished valuable information regarding the different types of boilers; and as a result it has been decided to continue them on a larger scale, and boilers of the *Babcock and Wilcox* pattern have accordingly been ordered for the new second-class cruiser *Challenger* and the sloop *Odin*; the sloop *Espiègle* was ordered to be fitted with these boilers in 1899-1900, and she will be ready to commence her steam trials early in the ensuing financial year; and *Niclausse* boilers are to be fitted in the first-class cruiser *Suffolk* and in the sloop *Merlin*.

The second-class cruisers *Highflyer* (*Belleville* boilers) and *Minerva* (cylindrical boilers) carried out a series of comparative trials; the results of which were embodied in a Parliamentary Return.

The Boiler Committee appointed by Lord Goschen commenced their sittings in September last, but their experiments have not been concluded. The *Minerva* and the second-class cruiser *Hyacinth* (*Belleville* boilers) have been placed at the disposal of the Boiler Committee for comparative experiments. The *Minerva's* trials have commenced.

At the special request of the Board, an ad interim report has just been presented by the Committee in reply to certain specific questions specially addressed to it. This report will be laid before Parliament, and all outstanding orders for boilers will be immediately reconsidered, and, if necessary, revised in the light of the information afforded by this report.

The torpedo-boat destroyers Viper and Cobra, whose propelling machinery is of the turbine type, have completed their contract trials, obtaining high speeds. They will be further tested on service as soon as practicable. There are still many points connected with this system of propulsion which require experimental investigation.

DOCKYARDS.

Satisfactory progress has, on the whole, been made during the current year on New Construction in the dockyards. It is anticipated that, despite some delays which have occurred in deliveries of armour, and work on propelling machinery, and the large amount of repairing work performed on ships in reserve, the amounts voted for labour and issue of ordinary materials will in almost every respect be fully realised. Every endeavour is being made to attain this result.

The number of men employed in the dockyards has been gradually increased during the year to meet the additional work thrown on them by the growth of the fleet.

The number of workmen borne in the home dockyards on the 1st April, 1900, and on the 1st January, 1901, are as follows:—

| | |
|-------------------------|--------|
| April, 1900 | 28,833 |
| January, 1901 | 30,330 |
| Increase | 1,497 |

This increased number includes about 690 dockyard and naval artificer apprentices who were entered in July, 1900.

LARGE REPAIRS DURING 1900-1901 AT HOME DOCKYARDS.

The following ships have been or will be completed in the yards:—

| | |
|-------------|--------------|
| Amphion. | Immortalité. |
| Anson. | Impérieuse. |
| Beagle. | Iphigenia. |
| Blanche. | Lapwing. |
| Camperdown. | Narcissus. |
| Eclipse. | Nymphe. |
| *Garnet. | Pallas. |
| Grafton. | Pegasus. |
| Harrier. | Rattler. |
| Hawke. | Revenge. |
| Hazard. | *Ruby. |
| Hebe. | Sparrow. |
| Hood. | Talbot. |
| Hussar. | *Tourmaline. |

* Converting into coal hulks.

The following ships are now in hand, or their refit will be commenced during 1900-1901 :—

| | |
|-----------|---|
| Barrosa. | Melpomene (if decided to proceed with refit). |
| Blonde. | |
| Doris. | Peacock. |
| Europa. | Pearl. |
| Fearless. | Pheasant. |
| Hecate. | Powerful. |
| Hermes. | Swallow. |
| Leander. | Venus. |

The details of the repairs and refits to be carried out in 1901-1902 appear in the Appendix to the Navy Estimates. The principal items of work to be undertaken in this section are :—

| | |
|--------------|------------|
| *Audacious. | Mohawk. |
| Barfleur. | Porpoise. |
| Centurion. | Spider. |
| Howe. | Tartar. |
| *Invincible. | Undaunted. |

* Conversion into bases for Torpedo Boat Destroyers.

NEW SHIPBUILDING PROGRAMME.

We propose to lay down in the coming financial year—

- 3 Battleships.
- 6 Armoured Cruisers.
- 2 Third Class Cruisers.
- 10 Torpedo Boat Destroyers.
- 5 Torpedo Boats.
- 2 Sloops.
- 5 Submarine Boats (ordered and work commenced in 1900).

Of these 2 Battleships, 1 Armoured Cruiser, and 2 Sloops will be built in the Royal dockyards. The rest will be built by contract.

The total Vote proposed for New Construction is £9,003,256, of which £8,465,406 will be devoted to pushing forward the ships already in hand to the utmost of our power and to work on the submarine boats, and £537,850 to starting work on the additional ships to be commenced. The object aimed at in this distribution of the money is to advance the work on the many ships now under construction as far as possible towards completion, and to place the ships to be newly commenced into such a position that the utmost possible amount of work can be put into them in 1902-3.

The arrears in the delivery of hulls, armour-plates, guns, gun-mountings, and machinery has been a continual source of anxiety equally to the last and the present Board. The financial position of

Messrs. Maudslay and of Messrs. Earle greatly contributed to the difficulties experienced in the deliveries of machinery. A Committee has been appointed to thoroughly investigate the causes of the arrears in every case, and to advise how a recurrence of the evil can best be obviated. The Committee consists of Mr. H. O. Arnold Forster, M.P., Rear-Admiral A. K. Wilson, C.B., V.C., Sir Thomas Sutherland, G.C.M.G., and Sir Francis Evans, K.C.M.G.

NAVAL ORDNANCE.

The amount required under the Naval Ordnance Vote is larger than the original Vote for 1900-1901 by £915,000. An additional Estimate of £753,200, was, however, taken under this Vote during the year, so the net increase over 1900-1901 is £161,800.

A sum of £420,000 is included in the Estimate in practical completion of the policy of increasing the reserves of guns and ammunition.

Provision is also included for the continuation of the issue of armour-piercing shell to the Fleet.

Deliveries of the new design of 12-in. B.L. wire gun have been made, and these guns are now mounted in the battleships of the Formidable class.

Some delay has occurred in the completion of the new 9·2-in. B.L. guns, as the trial of the first gun showed that a slight modification of design was necessary. Deliveries are, however, now being made, the first two guns having been mounted in H.M.S. Cressy, and it is hoped that the guns for succeeding ships will be ready by the time they are required.

A new gun of 7·5-in. calibre has been tried satisfactorily, and has been approved.

A 5-in. B.L. gun has been converted to take the Welin breech screw, and the design has been approved.

Progress is being made each year with the re-armament of the Fleet with ·303-in. Maxims in lieu of the older patterns of machine guns.

Telescopic sights have been adopted for Q.F. guns, and the supply is proceeding.

A new design of mounting for the 9·2-in. gun has been tried during the past year with very satisfactory results.

As the result of experience gained in South Africa and China some modifications and additions are being made to the seamen's equipment for service on shore.

Wireless telegraph apparatus has been obtained and supplied to a certain number of ships at home and abroad.

NEW WORKS.

WORKS PROVIDED IN ESTIMATES.

Chatham.—Good progress has been made with the new building slip, shops, &c. The New Foundry will be completed early in next financial year.

Portsmouth.—Very satisfactory progress has been made with the new smithery connected with it, and it is expected the work will be completed during next financial year.

Devonport.—Good progress has been made with the new building slip; the shops will be commenced shortly.

Pembroke.—A contract has been made for the new smithery, and considerable progress has been made. It is expected that the work will be completed in 1901–1902.

Bermuda.—A contract has been made for the supply of the iron-work to be sent from England for the bridge between Somerset and Watford Islands. The excavation of a berth for the floating dock at Bermuda will probably not be completed till 1902.

Dredging.—The deepening of French Creek at Malta has been progressing, and a considerable amount of dredging has been done at Wei-hai-Wei.

Coaling Depots.—A new subhead has been introduced into Vote 10 in connexion with coaling arrangements generally at home and abroad. Good progress is being made with the works already started at Chatham.

Hospitals.—Progress continues to be made with the work of providing additional and improved hospital accommodation at home and abroad.

Naval Armaments.—The torpedo range at Portland is expected to be practically finished by the end of next financial year; the contract for the pier is nearly completed, and one for the superstructure has recently been made.

PROGRESS UNDER NAVAL WORKS LOAN ACTS.

Chatham.—Dock. A contract has been made, and the work is well in hand.

Colombo.—The new dock at this station is in hand, being built by the Colonial Government.

Malta.—Dockyard extension. A contract has been made for the new docks. Much subsidiary and preliminary work has also been carried out.

Bermuda.—Dockyard extension. Tenders for this contract are under consideration. Dredging on sites of wharf and breakwater preparatory to their construction has been in progress for some time.

Dartmouth.—Britannia Royal Naval College. A contract for the main building and sick quarters has been made. Much work has been done in making roads, &c.

Magazines.—Work is progressing satisfactorily; that at Portsmouth in particular being in an advanced condition. The scheme at Chatham comprises an entirely new establishment.

Hospitals.—The Infectious Hospital at Haulbowline is completed, and Haslar Hospital will be completed in 1901–1902.

Inclosure and Defence of Harbours.

Gibraltar.—The Admiralty Mole Extension was brought up to water-level throughout its whole length by 30th September, 1898. The quay wall on the harbour side of the Mole has been brought up to coping level for a distance of 2,358 feet. New coal sheds 750 feet in length have been completed on the Mole. The Detached Mole has been completed except portions of the upper structure and the round heads at the north and south extremities. On the Commercial Mole the reclamation and wharf wall are finished, and a portion of the new wharf has been opened for traffic. The northern arm is well advanced, and the viaduct and western arm are well in hand.

Portland.—The whole of the new breakwater was brought up to water-level on the 17th April, 1899, and the work is being increased to the full section. The facing of a portion of the breakwater has been commenced.

Dover.—Admiralty Pier Extension.—The excavation for the foundation has been executed for about 450 feet, and block setting is in progress. The foundation course has been laid for a length of 440 feet, and the blockwork has been completed for a length of 260 feet at low-water level. The work at the junction with the existing pier head has been carried up to within two courses of low water.

East Reclamation.—The wall is now practically complete to cope level for a length of about 1,250 feet. Considerable progress has been made with the filling at the back of the wall, and the eastern half of the blockyard is now being laid out.

East Arm and Root Wall.—Ten bays of the East Arm temporary staging have now been completed. Two goliaths, one 60 tons and one of 40 tons, are in use on this staging, and a second machine for 40 ton loads is in course of erection. About 400 feet of the

foundations have been completed in the Root Wall, and about 100 feet of the East Arm above low-water level; a considerable quantity of concrete-in-mass has been deposited, and some of the Root Wall blocks have been set.

Adapting Naval Ports to Present Needs of Fleet.

Deepening Harbours and Approaches.—The dredging is finished at Chatham and Haulbowline. The dredging of Portsmouth Harbour is still in progress. The removal of the Vanguard, Rubble Bank, and Cremyll Shoals at Devonport is completed. The dredging above Saltash Bridge is in hand.

Keyham Dockyard Extension.—Graving Dock No. 4. Side and end walls are complete. Excavation between the side walls is practically completed. Concreting under the floor is completed for a length of 375 feet.

Graving Dock, No. 5.—Excavation of rock is nearly completed, and setting of granite floor stones has been commenced.

Graving Dock, No. 6.—Good progress is being made in the excavation of the rock.

Entrance Lock.—The west wall is built to underside of coping for a length of 300 feet, and for the remaining length to level of 8 feet below coping. On site of floor and east wall the mud is being removed.

Closed Basin.—The North Wall is nearly completed, East Wall is completed. A length of 640 feet of West Wall has been constructed up to levels varying from 38 feet to 15 feet below coping. Excavation for Caisson Camber at entrance is in progress. Excavation of mud on site of basin has been continued.

Tidal Basin.—East and South Walls, also South Arm at entrances are completed.

Outer Wall.—The wall is in progress and has been built to level of 3 feet below coping for a length of 160 feet at South end.

Gibraltar Dockyard Extension.—The Reclamation is in progress; pile foundations are being driven, and the superstructures of the Chief Constructor's and Chief Engineer's shops are in hand. The excavation of the New Mole Parade and the retaining walls have been completed. The excavation of No. 1 Dock is in progress. The dam for No. 3 Dock is finished; the enclosed area is pumped dry and the excavation is in progress.

Hong Kong.—The contractors have commenced the work of constructing the dock, reclaiming land, providing wharf walls and a basin, and erecting additional shops.

Simon's Bay Dockyard Extension.—A tender has been accepted for this work. The necessary land has been acquired, and the houses on the property are being converted into quarters.

Naval Barracks, &c.

Chatham Naval Barracks.—The West Block of the Seamen's Quarters is nearly completed, and the two remaining blocks are well in hand. The Officers' Mess and the North and South Blocks of Officers' Quarters are approaching completion.

Sheerness Naval Barracks.—The proposal to build new barracks for the Gunnery School at Sheerness has been abandoned, as the only available site was found on examination to be unsuitable on sanitary grounds. Negotiations for a site at Chatham are in progress.

Portsmouth Naval Barracks.—The War Office have transferred the Anglesea Barracks and have arranged for the transfer of further land required on the site of the Military Hospital. One block of Seamen's Quarters is up to roof level; the second block is up to second-floor level, and the third block has been commenced.

Keyham Naval Barracks.—The eastern block of Seamen's Quarters is practically finished; the western block is nearly finished. The Officers' Mess and Quarters are roofed in.

Chatham Naval Hospital.—The work is in hand, and some of the buildings are up to first-floor level.

A Naval Works Loan Bill to provide during the next two years for certain new works and for the expenditure on works already authorised will shortly be introduced.

SELBORNE.

1st March, 1901.

Abstract of Navy

| Votes. | | Estimates, | |
|--------|---|-----------------|------------------------|
| | | Gross Estimate. | Appropriations in Aid. |
| | I.—NUMBERS. | | |
| A. | Total Number of Officers, Seamen, Boys, Coast Guard, and Royal Marines | 118,625 | ... |
| | II.—EFFECTIVE SERVICES. | £ | £ |
| 1 | Wages, &c., of Officers, Seamen and Boys, Coast Guard, and Royal Marines | 5,877,308 | 117,308 |
| 2 | Victualling and Clothing for the Navy | 2,389,539 | 497,239 |
| 3 | Medical Establishments and Services | 239,913 | 20,913 |
| 4 | Martial Law | 16,281 | 81 |
| 5 | Educational Services | 129,479 | 28,879 |
| 6 | Scientific Services | 86,259 | 20,459 |
| 7 | Royal Naval Reserves | 292,236 | 136 |
| 8 | Shipbuilding, Repairs, Maintenance, &c. : | | |
| | Section I.—Personnel | 2,696,815 | 12,815 |
| | Section II.—Matériel | 5,481,500 | 175,000 |
| | Section III.—Contract Work | 6,757,920 | 72,420 |
| 9 | Naval Armaments | 3,984,255 | 64,555 |
| 10 | Works, Buildings, and Repairs at Home and Abroad | 1,043,100 | 20,000 |
| 11 | Miscellaneous Effective Services | 375,604 | 16,104 |
| 12 | Admiralty Office | 288,600 | 9,000 |
| | Total Effective Services | £ 29,658,809 | 1,054,909 |
| | III.—NON-EFFECTIVE SERVICES. | | |
| 13 | Half-Pay, Reserved, and Retired Pay. | 803,154 | 12,254 |
| 14 | Naval and Marine Pensions, Gratuities, and Compassionate Allowances | 1,162,009 | 21,909 |
| 15 | Civil Pensions and Gratuities | 341,001 | 401 |
| | Total Non-Effective Services | £ 2,306,164 | 34,564 |
| | IV.—EXTRA ESTIMATE FOR SERVICES IN CONNECTION WITH THE COLONIES. | | |
| 16 | Additional Naval Force for Service in Australasian Waters—Annuity payable under | .. | .. |
| | GRAND TOTAL | £ 31,964,973 | 1,089,473 |

Note.—Under an Act of the Cape of Good Hope Legislature, entitled, “The Navy Contribution towards the annual expenditure by the Imperial Government in connection with A gift of 12,000 tons of coal for the use of His Majesty’s Ships, etc., is made annually by the

Estimates for 1901-1902.

| 1901-1902. | Estimates, 1900-1901. | | | Difference on Net Estimates. | | Votes. |
|----------------|-----------------------------|------------------------|-------------------------|------------------------------|-----------|-----------|
| Net Estimate. | Gross Estimate. | Appropriations in Aid. | Net Estimate. | Increase. | Decrease. | |
| Total Numbers. | | | Total Numbers. | Numbers. | Numbers. | A. |
| 118,625 | 114,880 | | 114,880 | 3,745 | | |
| £ | £ | £ | £ | £ | £ | |
| 5,760,000 | 5,643,016 | 116,016 | 5,527,000 | 233,000 | | 1 |
| 1,892,300 | 2,186,175 | 470,875 | 1,715,300 | 177,000 | | 2 |
| 219,000 | 230,175 | 21,375 | 208,800 | 10,200 | | 3 |
| 16,200 | 18,320 | 20 | 13,300 | 2,900 | | 4 |
| 100,600 | 120,744 | 28,444 | 92,300 | 8,300 | | 5 |
| 65,800 | 81,185 | 14,285 | 66,900 | | 1,100 | 6 |
| 292,100 | 271,213 | 113 | 271,100 | 21,000 | | 7 |
| | | | | | | 8 |
| 2,684,000 | { 2,524,815 (a) 11,000 | 12,815 | { 2,512,000 11,000 | 161,000 | | Sec. I. |
| 5,306,500 | { 4,248,000 (a) 55,100 | 164,000 | { 4,084,000 55,100 | 1,167,400 | | Sec. II. |
| 6,685,500 | { 6,367,055 (a) 410,000 | 38,055 | { 6,329,000 410,000 | | 53,500 | Sec. III. |
| 3,919,700 | { 3,060,008 (a) 753,200 | 55,308 | { 3,004,700 753,200 | 161,800 | | 9 |
| 1,023,100 | { 865,800 (a) 40,000 | 20,000 | { 845,800 40,000 | 137,300 | | 10 |
| 359,500 | 281,912 | 10,712 | 271,200 | 88,300 | | 11 |
| 279,600 | 276,100 | 9,000 | 267,100 | 12,500 | | 12 |
| 28,603,900 | 26,169,518 (a) 1,269,300 | 961,018 | 25,208,500 1,269,300 | 2,180,700 | 54,600 | |
| 790,900 | 798,972 | 12,272 | 786,700 | 4,200 | | 13 |
| 1,140,100 | 1,145,550 | 21,950 | 1,123,600 | 16,500 | | 14 |
| 340,600 | 343,882 | 382 | 343,500 | | 2,900 | 15 |
| 2,271,600 | 2,288,404 | 34,604 | 2,253,800 | 20,700 | 2,900 | |
| ... | 95,300 | 35,000 | 60,300 | | 60,300 | 16 |
| 30,875,500 | 28,558,222 (a) 1,269,300 | 1,080,622 | 27,522,600 1,269,300 | 2,201,400 | 57,500 | |

Net Increase £2,083,600.

(a) Additional Estimate, 13th July 1900 (Parliamentary Paper, No. 270).

tion Act, 1898," a sum of £30,000 is paid annually out of the public revenue of that Colony as a His Majesty's Naval Service.

Natal Government.

STATEMENT showing the Actual and Estimated EXPENDITURE for
NAVAL SERVICES for the Three Years ending the 31st March,
1902.

| | | £ | s. | d. |
|------------|---|-------------|----|----|
| 1899-1900. | { Estimated Expenditure (after deducting Appropriations in Aid). | £26,594,500 | 0 | 0 |
| | { Net Expenditure, as per Final Account | 25,731,220 | 9 | 6 |
| | (Expenditure less than Estimate) | £863,279 | 10 | 6 |
| 1900-1901. | { Estimated Expenditure (after deducting Appropriations in Aid) | £27,522,600 | 0 | 0 |
| | { Additional Estimate (13th July, 1900) | £1,269,300 | 0 | 0 |
| | | £28,791,900 | 0 | 0 |
| 1901-1902. | { Estimated Expenditure (after deducting Appropriations in Aid) | £30,875,500 | 0 | 0 |

STATEMENT of the Principal Points of DIFFERENCE between the
ESTIMATES of 1900-1901 and those for 1901-1902.

| INCREASES. | | £ |
|---|--|-------------|
| Wages, &c., of Officers, Seamen, and Marines | | 233,000 |
| Victualling and Clothing | | 177,000 |
| Medical Establishments and Services | | 10,200 |
| Martial Law | | 2,900 |
| Educational Services | | 8,300 |
| Royal Naval Reserves | | 21,000 |
| Wages, &c., of Men in Dockyards | | 191,983 |
| Naval Stores | | 1,014,900 |
| Propelling and Auxiliary Machinery for His Majesty's Ships and Vessels } (Contract) | | 187,155 |
| Purchase of Ships and Vessels | | 29,000 |
| Repairs and Alterations by Contract of Ships, &c. | | 22,468 |
| Inspection of Contract Work | | 8,000 |
| Machinery for Shore Establishments (Contract) | | 115,000 |
| Wages of Artificers and Crews of Vessels (Naval Ordnance Establishments) | | 27,547 |
| Projectiles and Ammunition | | 140,050 |
| Small Arms and Miscellaneous Naval Ordnance Stores, &c. | | 48,300 |
| Inspection, Proof, Experiments, and Freight (Naval Ordnance Stores) | | 29,000 |
| Works, Buildings, and Repairs | | 137,300 |
| Miscellaneous Effective Services (Passage Money, &c.) | | 88,300 |
| Non-Effective Services | | 17,800 |
| Miscellaneous Items | | 32,655 |
| | | 2,541,858 |
| DECREASES. | | £ |
| Scientific Services | | 1,100 |
| Hulls of Ships (Contract) | | 190,201 |
| Gun Mountings (Contract) | | 39,670 |
| Royal Reserve of Merchant Cruisers | | 55,887 |
| Guns | | 76,100 |
| Cessation of Annuity payable under the Australasian } Agreement (Imperial Defence Act, 1888) | | 95,300 |
| | | 458,258 |
| Net Increase | | £ 2,083,600 |

STATEMENT showing the Total Estimated EXPENDITURE for the NAVAL SERVICE, including Amounts provided in the NAVY ESTIMATES, as well as in the CIVIL SERVICE and other ESTIMATES, for the following Services:—

| | 1901-1902. | 1900-1901. |
|--|--------------|------------|
| NAVY ESTIMATES: | £ | £ |
| Estimated Expenditure (after deducting Appropriations in Aid) | 30,875,500 | 27,522,800 |
| CIVIL SERVICE ESTIMATES: | | 1,269,300 |
| Estimated Expenditure under— | | (a) |
| Class I. Vote 8.—Public Buildings, Great Britain: | | |
| Maintenance and Repairs, including } £ | | |
| New Works, Alterations, &c. } | 4,460 | |
| Rents, Insurance, Tithes, &c. | 8,000 | |
| Fuel, Light, Water, &c. | 4,400 | |
| Furniture | 2,400 | |
| Removal into and furnishing New Block } £ | 2,500 | |
| of Admiralty Extension } | (b) | |
| | 21,760 | 29,900 |
| Class I. Vote 9.—Surveys of the United Kingdom | 200 | 200 |
| " I. " 12.—Rates on Government Property | 98,800 | 88,800 |
| " I. " 13.—Public Works and Buildings, Ireland: | | |
| Coast Guard, viz.: | £ | |
| Purchase of Sites | 625 | |
| New Works and Alterations, including } £ | 10,518 | |
| Naval Reserve Stations } | 5,342 | |
| Maintenance and Supplies | 5,342 | |
| | £16,485 | |
| Naval Reserve, viz.: | | |
| Maintenance and Supplies | 155 | |
| | 16,640 | 10,470 |
| Class II. Vote 8.—Board of Trade: | | |
| Staff and Incidental Expenses in connection with | | |
| the Royal Naval Reserve Force | 3,466 | 3,880 |
| " II. " 9.—Mercantile Marine Services: | | |
| Staff and Incidental Expenses in connection with | | |
| the Royal Naval Reserve Force | 2,450 | 2,450 |
| " II. " 14.—Exchequer and Audit Department (Cost of | | |
| Audit): | £ | |
| Navy Cash Accounts | 7,865 | |
| Expense and Manufacturing Ac- } £ | 4,932 | |
| counts } | 5,539 | |
| Store Accounts | 5,539 | |
| | 18,336 | 17,506 |
| Class II. Vote 23.—Stationery and Printing | 74,000 | 71,000 |
| " III. " 1.—Law Charges, England | 5,380 | 3,080 |
| Maintenance of Naval Prisoners: | | |
| " III. " 7.—Prisons, England and the Colonies | 5,980 | 4,928 |
| " III. " 13.—Prisons, Scotland | 105 | 100 |
| " III. " 20.—Prisons, Ireland | 100 | 59 |
| REVENUE DEPARTMENT ESTIMATES: | | |
| Vote 1.—Customs.—Percentage for provision of funds for District Pay- | | |
| masters of the Coast Guard | 122 | 142 |
| Vote 1.—Customs.—Staff and Incidental Expenses in connection with | | |
| the Royal Naval Reserve Force | 3,261 | 3,261 |
| Vote 2.—Inland Revenue.—Analysis of Food, &c. | 120 | 100 |
| Vote 3.—Post Office.—Postage of Official Correspondence (in- | | |
| cluding Parcels) | £ | |
| 15,504 | | |
| Vote 5.—Post Office Telegraphs.—Official Telegrams and Ex- | | |
| penses in connection with Telegraphs (Admiralty | | |
| Wires, and Services of Clerks) } | 18,263 | |
| | 33,767 | 29,744 |
| Total | £ 31,159,987 | 27,787,720 |
| | | 1,269,300 |
| | | (a) |

Note.—In addition to the Services shown above, an annuity of £16,243 13s. is payable to the Commissioners of Woods, &c., from the Consolidated Fund, under the Public Offices Sites Act of 1882 (45 & 46 Vict. c. 32).

(a) Additional Estimate, 13th July, 1900.

(b) Part re-vote.

VOTE (A.)

NUMBERS of OFFICERS, SEAMEN, BOYS, and ROYAL MARINES,
Borne on the Books of His Majesty's Ships, and at the ROYAL
MARINE DIVISIONS.

One Hundred and Eighteen Thousand Six Hundred and Twenty-five.

I.—SEA SERVICE.

| Under which Vote Provided. | RANKS, &c. | NUMBERS, ALL RANKS. | | Num- bers of all Ranks borne on 1st January, 1901. |
|-------------------------------------|---|---------------------|------------|---|
| | | 1901-1902. | 1900-1901. | |
| Vote 1 | FOR HIS MAJESTY'S FLEET | | | |
| | Flag Officers | 15 | 15 | |
| | Commissioned Officers | 3,754 | 3,628 | |
| | Subordinate Officers | 852 | 806 | |
| | Warrant Officers | 1,501 | 1,413 | |
| | Petty Officers and Seamen . . . | 75,501 | 73,259 | |
| | Boys (Service) | 3,700 | 3,700 | |
| | | 85,823 | 82,821 | 81,179 |
| | COAST GUARD. | | | |
| | Commissioned Officers | 89 | 89 | |
| | Chief Officers of Stations . . . | 238 | 237 | |
| | Petty Officers and Seamen . . . | 3,873 | 3,874 | |
| | | 4,200 | 4,200 | 4,107 |
| | ROYAL MARINES (for Service Afloat and on Shore). | | | |
| | Commissioned Officers | 471 | 444 | |
| | Warrant Officers | 33 | 32 | |
| | Staff Sergeants and Sergeants . | 1,417 | 1,361 | |
| | Buglers and Musicians | 647 | 620 | |
| | Rank and File | 17,022 | 16,133 | |
| | | 19,590 | 18,590 | 18,368 |
| | Total | 109,113 | 105,611 | 103,654 |
| Net Increase | | 3,502 | | |

II.—OTHER SERVICES.

| | | | | |
|-------------------------------------|---|---------|---------|-------|
| Vote 1 | Naval Cadets | 260 | 260 | |
| | Engineer Students | 180 | 178 | |
| | Pensioners in Home Ships and in the Reserves | 1,048 | 987 | |
| | Boys under Training | 6,200 | 6,200 | |
| Other Votes | | 7,688 | 7,625 | 7,015 |
| | Various Services | 1,824 | 1,644 | 1,586 |
| | Total | 9,512 | 9,269 | 8,601 |
| Net Increase | | 243 | | |
| Total, Sea Service | | 109,113 | 105,611 | |
| " other Services | | 9,512 | 9,269 | |
| | | 118,625 | 114,880 | |
| Net Increase | | 3,745 | | |
| Including Officers and Seamen . . . | | 1,621 | — | 1,531 |
| " Pensioners (Vote 1) | | 1,041 | — | 987 |
| " Pensioners (other Votes) | | 15 | — | 16 |
| " Boys (Training, Seaman Class) . . | | 6,200 | — | 6,200 |
| " Boys (Training, Artisans) | | 420 | — | 320 |
| " Royal Marines | | 215 | — | 215 |
| | | 9,512 | — | 9,269 |

VOTE 8. **SHIPBUILDING, REPAIRS, MAINTENANCE, &c.**

I.—ESTIMATE of the SUM which will be required, in the YEAR ending 31st March, 1902, to defray the EXPENSES of SHIPBUILDING, REPAIRS, MAINTENANCE, &c., including the COST of ESTABLISHMENTS of DOCKYARDS and NAVAL YARDS at HOME and ABROAD.

DOCKYARD WORK.

SECTION I.—PERSONNEL.—Two Million Six Hundred and Eighty-Four Thousand Pounds.

(£2,684,000.)

SECTION II.—MATÉRIEL.—Five Million Three Hundred and Six Thousand Five Hundred Pounds.

(£5,306,500.)

CONTRACT WORK.

SECTION III.—CONTRACT WORK.—Six Million Six Hundred and Eighty-five Thousand Five Hundred Pounds.

(£6,685,500.)

I.—SUB-HEADS under which SECTION I., PERSONNEL, of this VOTE will be accounted for.

| | ESTIMATES. | | Increase. | Decrease. |
|--|-------------|------------|--------------|-----------|
| | 1901-1902. | 1900-1901. | | |
| | £ | £ | £ | £ |
| DOCKYARD WORK. | | | | |
| SECTION I.—PERSONNEL. | | | | |
| <i>Dockyards at Home.</i> | | | | |
| A.—Salaries and Allowances | (a) 185,751 | 178,562 | 7,189 | .. |
| B.—Wages, &c., of Men, and hire of Teams | 2,096,520 | 1,945,392 | 140,128 | .. |
| | | (b) 11,000 | | |
| C.—Wages, &c., of Police Force | 43,786 | 41,040 | 2,746 | .. |
| D.—Contingencies | 7,000 | 6,600 | 400 | .. |
| <i>Naval Yards Abroad.</i> | | | | |
| E.—Salaries and Allowances | (a) 80,255 | 66,442 | 13,813 | .. |
| | | (c) 3,197 | | |
| F.—Wages, &c., of Men, and hire of Teams | 268,522 | 267,970 | .. | 2,645 |
| | | (d) 3,197 | | |
| G.—Wages, &c., of Police Force | 13,681 | 14,412 | .. | 731 |
| H.—Contingencies | 1,300 | 1,200 | 100 | .. |
| | £ 2,696,815 | 2,524,815 | 164,376 | 3,376 |
| | | (b) 11,000 | | |
| <i>Deduct,—</i> | | | | |
| I.—Appropriations in Aid | 12,815 | 12,815 | .. | .. |
| | £ 2,684,000 | 2,512,000 | 164,376 | 3,376 |
| | | (b) 11,000 | | |
| Net Increase | | | £161,000 (e) | |

(a) These amounts include the sums of £27,580 and £8,554 for pay of Inspectors of Trades at Home and Inspectors of Shipwrights Abroad respectively, which is charged direct to the cost of shipbuilding.

(b) Additional Estimate, 13th July 1900.

(c) Provided under Sub-head F. in 1900-1901.

(d) Transferred to Sub-head E. in 1901-1902.

(e) This Vote is decreased by a transfer of £50,000 to Vote 8, Section II. The real increase is therefore £211,000.

Note.—Provision has been made for New Construction in the above Vote to the extent of—

| | |
|---------------------|------------|
| Section 1 | £1,005,700 |
| „ 2 | 1,907,720 |
| „ 3 | 6,089,836 |

£9,003,256

2 K 2

VOTE 8.—SHIPBUILDING, REPAIRS, MAINTENANCE, &c.—*continued.*

II.—SUB-HEADS under which SECTION II., MATÉRIEL, of this VOTE will be accounted for.

| | ESTIMATES. | | Increase. | Decrease. |
|--|--------------|-------------------------|----------------|-----------|
| | 1901-1902. | 1900-1901. | | |
| | £ | £ | £ | £ |
| DOCKYARD WORK— <i>continued.</i> | | | | |
| SECTION II.—MATÉRIEL. | | | | |
| Naval Stores. | | | | |
| A.—Timber, Masts, Deals, &c. | 145,000 | 136,000 | 9,000 | .. |
| B.—Metals and Metal Articles | 2,426,000 | 2,043,000 (a) 39,000 | 344,000 | .. |
| C.—Coals for Yard purposes | 126,000 | 79,500 | 46,500 | .. |
| D.—Hemp, Canvas, &c. | 225,000 | 191,500 | 33,500 | .. |
| E.—Paint Materials, Oils, Pitch, Tar, Tallow, Boats, Furniture, and other Miscellaneous Articles | 584,500 | 500,000 (a) 2,000 | 82,500 | .. |
| F.—Electrical, Torpedo, and other Ap- paratus | 235,000 | 190,000 (a) 14,100 | 30,900 | .. |
| G.—Freight | 69,000 | 60,000 | 9,000 | .. |
| H.—Rents, Water, &c., Dockyards at Home, and Naval Yards Abroad | 35,785 | 33,900 | 1,885 | .. |
| I.—Gas, &c., Dockyards at Home, and Naval Yards Abroad. | 15,215 | 14,100 | 1,115 | .. |
| Coals for the Fleet. | | | | |
| K.—Coals, &c., for the Fleet | 1,620,000 | 1,000,000 | 620,000 | .. |
| | £ 5,481,500 | 4,248,000 (a) 55,100 | 1,178,400 | .. |
| Deduct,— | | | | |
| L.—Appropriations in Aid | 175,000 | 164,000 | 11,000 | .. |
| | £ 5,306,500 | 4,084,000 (a) 55,100 | 1,167,400 | .. |
| | Net Increase | | £1,167,400 (b) | |

(a) Additional Estimate, 13th July 1900.

(b) This Vote is increased by a transfer of £50,000 from Vote 8, Section I., and £42,000 from Vote 8, Section III. The real increase is therefore £1,075,400.

VOTE 8.—SHIPBUILDING, REPAIRS, MAINTENANCE, &c.—*continued*.

II.—SUB-HEADS under which SECTION III., CONTRACT WORK, of this VOTE will be accounted for.

| | ESTIMATES. | | Increase. | Decrease. |
|--|------------------------|--------------------------|-------------|-----------|
| | 1901-1902. | 1900-1901. | | |
| | £ | £ | £ | £ |
| SECTION III.—CONTRACT WORK. | | | | |
| A.—Propelling Machinery for His Majesty's Ships and Vessels | 2,367,236 | 1,999,130 (a) 201,460 | 166,646 | .. |
| B.—Auxiliary Machinery for His Majesty's Ships and Vessels | 89,568 | 69,059 | 20,509 | .. |
| C.—Hulls of Ships, &c., Building by Contract | 3,187,230 | 3,381,961 (a) 90,470 | .. | 285,201 |
| D.—Purchase of Ships, Vessels, &c. | 109,000 | .. (a) 80,000 | 29,000 | .. |
| E.—Repairs and Alterations by Contract of Ships, &c., and their Machinery and Stores | 115,523 | 93,055 | 22,468 | .. |
| F.—Inspection of Contract Work | 56,000 | 48,000 | 8,000 | .. |
| G.—Gun Mountings and Air-Compressing Machinery | 611,050 | 612,650 (a) 38,070 | .. | 39,670 |
| H.—Machinery for His Majesty's Shore Establishments at Home and Abroad | 215,000 | 100,000 | 115,000 | .. |
| I.—Royal Reserve of Merchant Cruisers | 7,313 | 63,200 | .. | 55,887 |
| | £ 6,757,920 | 6,367,055 (a) 410,000 | 361,623 | 380,758 |
| <i>Deduct,—</i> | | | | |
| K.—Appropriations in Aid | 72,420 | 38,055 (b) 35,000 | 34,365 | .. |
| | £ 6,685,500 | 6,329,000 (a) 410,000 | 327,258 | 380,758 |
| | Net Decrease | | £53,500 (c) | |

(a) Additional Estimate, 13th July 1900.

(b) Provided under Vote 16 in 1900-1901.

(c) This Vote is decreased by a transfer of £42,000 to Vote 8, Section II., and £35,000 (Appropriation in Aid) from Vote 16. There is, therefore, a real increase of £23,500.

PROGRAMME of the ESTIMATED EXPENDITURE in CASH, and in NET REPAIRS, MAINTENANCE, &c.,
SUB-HEADS under which this ESTIMATED EXPENDITURE will be provisions of Sec. 1 (2), ARMY

| | ESTIMATED EXPENDITURE IN | | | |
|--|--------------------------|--------------------|--------------------------|-------------------------------|
| | Direct Expenditure. | | | |
| | Dockyard Work. | | Contract Work, Sec. III. | Total Direct Expenditure. (A) |
| | Personnel, Sec. I. | Matériel, Sec. II. | | |
| | £ | £ | £ | £ |
| NEW CONSTRUCTION: | | | | |
| A.—DOCKYARD-BUILT SHIPS— | | | | |
| Hulls, &c. (c) | 832,310 | (g) 1,787,590 | 256,740 | 2,876,640 1 |
| Machinery | 40,700 | 27,020 | 848,141 | 915,861 2 |
| | 873,010 | 1,814,610 | 1,104,881 | 3,792,501 3 |
| B.—CONTRACT-BUILT SHIPS— | | | | |
| Hulls, &c. (c) | 125,640 | 88,860 | (h) 3,511,166 | 3,725,666 4 |
| Machinery | .. | .. | 1,383,130 | 1,383,130 5 |
| | 125,640 | 88,860 | 4,894,296 | 5,108,796 6 |
| C.—SMALL VESSELS (d) | 7,050 | 4,250 | 90,659 | 101,959 7 |
| TOTAL NEW CONSTRUCTION | 1,005,700 | 1,907,720 | 6,089,836 | 9,003,256 8 (f) |
| D.—RE-CONSTRUCTION, REPAIRS, ALTERATIONS, &c. | 892,776 | 512,530 | 304,602 | 1,709,908 9 |
| E.—SEA STORES, COALS, &c. | .. | 807,000 | 18,391 | 825,391 10 |
| F.—ESTABLISHMENT, INCIDENTAL, AND MISCELLANEOUS CHARGES, UNAPPROPRIATED | .. | .. | .. | .. 11 |
| TOTAL | 1,898,476 | 3,227,250 | 6,412,829 | 11,538,555 12 |

(c) Including Hydraulic and Transferable Gun Mountings, &c.

(d) Including Harbour Craft, and excluding Torpedo Boats, &c., the value of which is included under other Sub-Heads.

(f) Exclusive of £37,300 provided under Vote 2 for new Tank Vessels and Lighters for Victualling Yard Service; also £22,433 provided under Vote 9 for new Vessels for Naval Ordnance Store Service, and £80,000 for Coaling Craft, Vote 8, Section 2, Sub-Head K.

(g) Including £1,224,000 for Armour.

(h) Including £1,018,000 for Armour.

VALUES OF STORES issued for SHIPBUILDING, RE-CONSTRUCTION, in the Year 1901-1902.

accounted for in the NAVY EXPENSE ACCOUNTS, under the AND NAVY AUDIT ACT, 1889.

| 1901-1902. | | EXPENDITURE AS ESTIMATED IN NAVY ESTIMATES, 1900-1901. | | | Difference between Direct Expenditure, 1900-1901 (B) and 1901-1902 (A). | |
|---|-----------------------|--|---|-----------------------|---|-----------|
| Establishment, &c., Charges, apportioned. | Aggregate, 1901-1902. | Direct Expenditure. (B) | Establishment, &c., Charges, apportioned. | Aggregate, 1900-1901. | Increase. | Decrease. |
| £ | £ | £ | £ | £ | £ | £ |
| 300,289 | 3,176,929 | (i) 2,678,822 | 269,791 | 2,948,613 | 197,818 | .. |
| 25,856 | 941,717 | 743,573 | 22,320 | 765,893 | 172,288 | .. |
| 328,145 | 4,118,646 | 3,422,395 | 292,111 | 3,714,506 | 370,106 | .. |
| 92,916 | 3,818,582 | (k) 3,768,455 (e) 103,690 | 78,829 | 3,950,974 | .. | 146,479 |
| 22,113 | 1,405,243 | (l) 1,168,803 (e) 201,460 | 17,529 | 1,387,792 | 12,867 | .. |
| 115,029 | 5,223,825 | 5,242,408 | 96,358 | 5,338,766 | .. | 133,612 |
| 1,741 | 103,700 | (m) 100,493 (e) 80,000 | 1,786 | 182,229 | .. | 78,534 |
| 442,915 | 9,446,171 | (n) 8,460,146 (e) 385,150 | 890,205 | 9,235,501 | 157,960 | .. |
| 203,588 | 1,918,496 | (o) 1,617,811 (e) 1,850 | 182,879 | 1,802,540 | 90,247 | .. |
| 42,912 | 868,303 | (p) 671,628 (e) 18,100 (q) 949,000 | 39,765 12,345 | 729,493 961,345 | .. | 813,337 |
| 1,574,194 | 1,574,194 | .. | (r) 1,318,361 (e) 30,000 | 1,348,361 | .. | .. |
| 2,263,609 | 13,802,164 | 12,103,685 | 1,973,555 | 14,077,240 | .. | .. |

NET DECREASE ON DIRECT EXPENDITURE

£565,130.

Estimated value of Coals to be issued to Ships in 1900-1901, provision for which service is excluded from the Programme for 1901-1902

949,000.

ACTUAL INCREASE

£383,870.

(e) Additional estimate (Parliamentary paper dated 12th July 1900, No. 270).

(f) Including £1,003,506 for Armour.


(g) Including £1,211,274 for Armour.

(h) Value of coals for steaming purposes.

RECAPITULATION OF ESTIMATED EXPENDITURE.

| ESTIMATED EXPENDITURE. | | ESTIMATED DISTRIBUTION OF THE DIRECT AND INCIDENTAL EXPENDITURE. | | | | | | | | | | |
|---|--|--|---------------------|--|-----------|----------------------------------|-------------------------------------|----------------------------------|-----------------------|---|--|--|
| | Charged direct and incidental as incurred. | Establishment and incidental Charges Appropriated. | Naval Construction. | | | | | | Stores for Ships, &c. | Establishment and incidental Charges Unappropriated to Ships, &c. | | Total Amount of Estimated Expenditure. |
| | | | New Construction. | Re-construction, Repairs, Alterations, and Refits. | | Ships in Commission and Reserve. | Ships for Relief, or Re-commission. | Ships in Commission and Reserve. | | Fleet, Port, National, and Unappropriated Charges. | Unappropriated Charges (Haulbowline, West India Docks and Naval Yards Abroad). | |
| | | | | (a.) | (b.) | | | | | | | |
| SUB-HEADS OF EXPENDITURE. | | | A, B, and C. | | D. | | E. | | F. | | | |
| SECTION I.—DOCKYARD | £ | £ | £ | £ | £ | £ | £ | £ | £ | £ | £ | |
| PERSONNEL | 1,898,476 | 970,097 | 1,186,742 | .. | 420,566 | 571,373 | 27,089 | 222,390 | 222,390 | 2,868,573 | | |
| SECTION II.—WORK | 3,227,250 | 969,827 | 2,072,231 | .. | 222,229 | 390,716 | 822,873 | 403,937 | 403,937 | 4,197,077 | | |
| MATÉRIEL | 6,412,829 | 323,685 | 6,187,198 | .. | 133,552 | 175,060 | 18,391 | 19,578 | .. | 6,736,514 | | |
| SECTION III.—CONTRACT WORK | 11,538,555 | 2,263,609 | 9,446,171 | .. | 776,347 | 1,137,149 | 868,303 | 626,327 | 626,327 | 13,802,164 | | |
| TOTAL ESTIMATED EXPENDITURE for 1901-1902 | £ 13,802,164 | | 9,446,171 | | 1,913,496 | | 868,303 | 1,574,194 | | 13,802,164 | | |
| TOTALS OF SUB-HEADS | £ | | 9,446,171 | | 1,913,496 | | 868,303 | 1,574,194 | | 13,802,164 | | |

DIAGRAM SHEWING THE ACTUAL EXPENDITURE UPON THE CONSTRUCTION OF NEW SHIPS DURING THE 30 YEARS BETWEEN 1872-73 & 1901-2.



(a) Includes £1,523,000 for purchase of Ships under the Vote of Credit.
 (b) Includes Expenditure under Lord Northbrook's Special Programme.
 (c) Includes Expenditure under the Defence Acts of 1888 and 1889.

Handwritten: 1888

LIST of NEW SHIPS and VESSELS Estimated to be Passed into the
FLEET RESERVE during the Years 1901-1902 and 1900-1901.

| 1901-1902. | | | | 1900-1901. | | | |
|---|----------------------------|------------------------|-----------------|---|----------------------------|------------------------|-----------------|
| NAME OF SHIP. | Load Displacement in Tons. | Indicated Horse Power. | Number of Guns. | NAME OF SHIP. | Load Displacement in Tons. | Indicated Horse Power. | Number of Guns. |
| ARMoured SHIPS. | | | | ARMoured SHIPS. | | | |
| Formidable | 15,000 | 15,000 | 16 | Albion | 12,950 | 13,500 | 16 |
| Implacable | 15,000 | 15,000 | 16 | Glory | 12,950 | 13,500 | 16 |
| Irresistible | 15,000 | 15,000 | 16 | | | | |
| Bulwark | 15,000 | 15,000 | 16 | | | | |
| Vengeance | 12,950 | 13,500 | 16 | | | | |
| Aboukir | 12,000 | 21,000 | 14 | | | | |
| Cressy | 12,000 | 21,000 | 14 | | | | |
| Bacchante | 12,000 | 21,000 | 14 | | | | |
| Hogue | 12,000 | 21,000 | 14 | | | | |
| Sutlej | 12,000 | 21,000 | 14 | | | | |
| PROTECTED SHIPS. | | | | PROTECTED SHIPS. | | | |
| Spartiate | 11,000 | 18,000 | 16 | Pandora | 2,200 | *7,000 | — |
| UNPROTECTED SHIPS. | | | | UNPROTECTED SHIPS. | | | |
| Victoria and Albert . | 4,700 | 11,000 | — | Shearwater | 980 | 1,400 | 6 |
| Assistance | 9,600 | *4,200 (Howden's) | — | Vestal | 980 | 1,400 | 6 |
| Espiegle | 1,070 | 1,400 | 6 | Mutine | 980 | 1,400 | 6 |
| Fantome | 1,070 | 1,400 | 6 | | | | |
| Rinaldo | 980 | 1,400 | 6 | | | | |
| Teal | 180 | *800 | — | | | | |
| Moorhen | 180 | *800 | — | | | | |
| TORPEDO-BOAT { 18 } DESTROYERS { No. } | various | | | TORPEDO-BOAT { 15 } DESTROYERS { No. } | various | | — |
| TORPEDO-BOATS { 4 } { No. } | — | — | — | | | | |

* Forced draught.

French Navy Estimates, 1901.

| Cap. in French Esti- mates. | Heads of Expenditure. | Credits voted for 1901. | Credits voted for 1900. |
|--------------------------------------|---|----------------------------|----------------------------|
| | PERSONNEL. | £ | £ |
| 1, 2 | Admiralty Office | 139,380 | 132,986 |
| 3, 4 | Navy Pay | 1,951,348 | 1,878,220 |
| 5 | Marines. | 645,922 | 622,420 |
| 6 | Gendarmerie Maritime | 30,792 | 30,792 |
| 7 | Inspection of Administrative Services | 10,389 | 10,368 |
| 8 | Construction Staff | 231,336 | 195,440 |
| 9, 10, 11 | Administrative Staff, Commissariat, etc. | 273,440 | 268,491 |
| 12 | Medical and Religious Staff | 86,592 | 87,357 |
| 13 | Fisheries and Navigation | 28,052 | 26,872 |
| | LABOUR. | | |
| | Wages— | | |
| 14 | { Shipbuilding; new construction; fitting } for sea | 469,646 | 539,360 |
| 15 | Shipbuilding; repairs | 214,620 | 295,137 |
| 17 | Armaments; construction of new guns | 125,354 | 111,806 |
| 18 | Armaments; repairs | 67,600 | 26,582 |
| 19 | Works | 27,131 | 30,758 |
| 20 | Victualling | 33,969 | 33,545 |
| 16 | { Master-attendants' and Storekeepers' } Departments | 258,545 | 211,883 |
| 21 | Hospitals and Miscellaneous | 14,207 | 14,597 |
| | MATÉRIEL. | | |
| | Stores and Supplies— | | |
| 22 | Admiralty | 10,136 | 10,100 |
| 24 | Shipbuilding in Dockyards | 1,539,824 | 1,600,000 |
| 25, 26 | Shipbuilding by contract | 1,397,181 | 1,339,000 |
| 27, 28 | Fitting for sea; maintenance; repairs | 746,994 | 502,000 |
| | Carried forward | £8,302,458 | £7,967,714 |

| Cap. in French Estimates. | Heads of Expenditure. | Credits voted for 1901. | Credits voted for 1900. |
|---------------------------|---|-------------------------|-------------------------|
| | Brought forward - - | £ 8,302,458 | £ 7,967,714 |
| | <i>MATÉRIEL—continued.</i> | | |
| | <i>Stores and Supplies—continued.</i> | | |
| 23 | Hydrographic Service. | 20,944 | 22,544 |
| 29, 30 | { Repairs, conversions, etc., in dockyards and by contract } | 592,202 | 445,260 |
| 31, 32 | { Armaments; new guns and conversions; Powder, ammunition, repairs, tools, etc. } | 1,109,240 | 1,068,080 |
| 33, 34 | Torpedoes | 178,056 | 128,720 |
| 35 | Works; new and large alterations. . | 589,711 | 434,972 |
| 36 | Ditto; deepening of the Charente . | 19,966 | .. |
| 37 | { Ditto, supplementary for defence of military ports } | 35,950 | 36,872 |
| 38, 39 | Works; repairs | 70,045 | 60,920 |
| 40 | Clothing | 220,140 | 212,160 |
| 41 | Barracks | 30,625 | 34,081 |
| 42, 43 | Victualling. | 1,015,536 | 960,117 |
| 44 | Hospitals, etc. | 107,959 | 107,959 |
| * | Machinery, tools, etc. | .. | 212,732 |
| 45, 46 | { Fuel, lighting, office furniture, printing, etc. } | 55,145 | 55,216 |
| | <i>MISCELLANEOUS.</i> | | |
| 47, 48 | { Travelling expenses, freight, allowance for lodgings, etc. } | 234,200 | 244,200 |
| 49 | Charitable and subscriptions | 41,232 | 40,934 |
| 50 | { Fisheries and Commerce (materials for protection, etc.) } | 13,460 | 12,948 |
| 51 | Pensions | 466,828 | 453,788 |
| 52 | Secret Service | 4,000 | 4,000 |
| 53, 54, 55 } | Miscellaneous | .. | 4,444 |
| | Total | £13,107,697 | £12,507,661 |

* Charges for machinery and tools are distributed among the various heads of expenditure in 1901 Estimates.

PROGRAMME OF NEW CONSTRUCTION, TO BE CONTINUED OR UNDERTAKEN
IN 1901.—BUILDING IN DOCKYARDS.

| Class. | Names of Ships. | Where Building. | Date of Commencement. | Proposed Date of Completion. | Estimated Cost. | Expenditure proposed for 1901. |
|---|--------------------------|-----------------|-----------------------|------------------------------|-----------------|--------------------------------|
| | | | | | £ | £ |
| Battleships. | Henri IV. . . . | Cherbourg | 1897 | 1901 | 801,248 | 55,618 |
| | Iéna | Brest . . | 1898 | 1900 | 1,111,340 | 40,760 |
| | Suffren | " . . | 1899 | 1901 | 1,195,564 | 292,935 |
| | A. 8. | " . . | .. | 1905 | 1,421,708 | 68,035 |
| Armoured Cruisers, First-class . . . | Jeanne d'Arc . . | Toulon . . | 1896 | 1901 | 875,847 | 66,729 |
| | Dupetit-Thouars | " . . | 1899 | 1902 | 831,839 | 157,060 |
| | Gueydon | Lorient . . | 1898 | 1902 | 817,944 | 135,572 |
| | Condé | " . . | .. | 1903 | 868,799 | 221,248 |
| | Gloire | " . . | 1899 | 1902 | 883,269 | 254,347 |
| | La Marseillaise . | Brest . . | 1900 | 1902 | 881,270 | 288,500 |
| | Jules Ferry (ex C. 11) | Cherbourg | .. | 1904 | 1,169,940 | 232,841 |
| | Léon Gambetta (ex C. 12) | Brest . . | .. | 1903 | 1,169,940 | 252,536 |
| | C 13 (Victor Hugo) | Toulon . . | .. | 1905 | 1,169,940 | 30,695 |
| | Dupleix | Rochefort | 1899 | 1902 | 652,354 | 80,972 |
| | Jurien de la Gravière | Lorient . . | 1897 | 1901 | 457,979 | 28,130 |
| | Pertuisane . . . | Rochefort | .. | 1901 | 68,907 | 42,589 |
| | Escopette . . . | " . . | .. | " | 68,907 | 43,591 |
| Torpedo-gunboats and Destroyers . | Flamberge . . . | " . . | .. | " | 68,907 | 27,822 |
| | Rapière | " . . | .. | 1902 | 68,907 | 27,613 |
| | Carabine (ex M. 12) | " . . | .. | " | 68,907 | 20,630 |
| | Sarbacane (ex M. 13) | " . . | .. | " | 68,907 | 20,609 |
| | M. 22 | " . . | .. | 1903 | 68,907 | 10,900 |
| | M. 23 | " . . | .. | " | 68,907 | 10,900 |
| | | | | | | |
| Aviso-transport . | Vaucluse | " . . | 1886 | 1901 | 81,256 | 18,386 |
| Submarines . . . | Algérien | Cherbourg | 1899 | 1900 | 30,404 | 2,800 |
| | Sirène | " . . | 1900 | 1901 | 24,700 | 16,123 |
| | Triton | " . . | " | " | 24,700 | 15,723 |
| Carried Forward | | | | | £ 15,016,297 | 2,458,659 |

PROGRAMME OF NEW CONSTRUCTION, TO BE CONTINUED OR UNDERTAKEN
IN 1901.—BUILDING IN DOCKYARDS—*continued.*

| Class. | Names of Ships. | Where Building. | Date of Commencement. | Proposed Date of Completion. | Estimated Cost. | Expenditure proposed for 1901. |
|--------------------------------------|---|-----------------|-----------------------|------------------------------|-----------------|--------------------------------|
| | | | Brought forward | | £ 15,016,297 | £ 2,458,659 |
| Submarines continued | Farfadet . . . | Rocheport | 1900 | 1900 | 32,006 | 3,738 |
| | Korrigan . . . | „ | 1900 | 1901 | 32,006 | 4,098 |
| | Gnome . . . | „ | .. | 1901 | 32,006 | 4,546 |
| | Lutin . . . | „ | .. | 1901 | 32,006 | 6,226 |
| | Silure (ex Q. 13) | Cherbourg | .. | 1902 | 24,700 | 19,001 |
| | Espadon (ex Q. 14) | „ | .. | 1902 | 24,700 | 18,681 |
| | (Q. 15 to Q. 22) (eight boats* . . .) | Various . | .. | 1902-3 | 197,600 | 50,963 |
| First-class Torpedo-boats | (Six First - class Torpedo - boats Nos. 223, 224, 225, 226, 244 and P. 96) | Various . | .. | 1901-3 | 114,966 | 27,236 |
| Total Building in Dockyards in 1901. | | | | | £ 15,506,287 | £ 2,593,148 |

* It has been decided to put in hand 20 submarine boats in 1901.—Ed.

PROGRAMME OF NEW CONSTRUCTION, TO BE CONTINUED OR UNDERTAKEN
IN 1901.—BUILDING BY CONTRACT.

| Class. | Names of Ships. | Places of Building and Completion. | Date of Contract. | Date of Completion. | Total Estimated Cost. | Expenditure proposed for 1901. |
|-------------------------------|---------------------------------|--|-------------------|---|-----------------------|--------------------------------|
| | | | | | £ | £ |
| Battleship . . . | A. 10. | .. | .. | 1905 | 1,416,564 | 56,432 |
| First-class Armoured Cruisers | Montcalm . . . | La Seyne—Toulon . | 1897 | 1901 | 902,809 | 139,164 |
| | Sully | " " | 1899 | 1903 | 954,536 | 223,558 |
| | Amiral Aube . . | St. Nazaire—Brest . | " | " | 973,440 | 298,850 |
| | Desaix | " " | 1897 | 1902 | 762,759 | 105,617 |
| | Kléber | Bordeaux—Rochefort | " | " | 770,320 | 121,090 |
| Destroyers . . . | Arquebuse . . . | Le Havre—Cherbourg | 1900 | 1903 | 73,108 | 36,731 |
| | Arbalète | " " | " | " | 73,103 | 36,414 |
| | Mousquet | " " | " | " | 67,463 | 36,414 |
| | Javeline | " " | " | " | 67,463 | 36,414 |
| | Sagaie | " " | " | " | 67,463 | 36,414 |
| | Epieu | " " | " | " | 67,463 | 36,730 |
| | Harpon | " " | " | " | 67,463 | 36,730 |
| | Fronde | " " | " | " | 67,463 | 36,730 |
| | M. 24 to M. 31 eight boats } | " " | .. | 1903-4 | 539,704 | 38,400 |
| Sea-going Torpedo Boats . | Siroco | Le Havre—Cherbourg | 1898 | 1900 | 42,598 | 3,960 |
| | Mistral | " " | " | 1901 | 42,598 | 4,080 |
| | Simoun | " " | " | " | 40,957 | 2,120 |
| | Typhon | " " | " | " | 40,957 | 5,380 |
| | Trombe | Nantes—Lorient . | " | 1900 | 41,108 | 3,460 |
| | Audacieux | " " | " | " | 41,108 | 5,500 |
| | Bourrasque . . . | Le Havre—Cherbourg | 1899 | 1901 | 40,317 | 19,332 |
| | Rafale | " " | " | " | 40,317 | 24,012 |
| | Borée | Bordeaux—Rochefort | " | " | 39,636 | 19,006 |
| | Tramontane . . . | " " | " | " | 39,636 | 15,807 |
| First-class Torpedo Boats . | 31 First-class Torpedo Boats | { Le Havre—Cher. : 6 Chalon—Toulon : 9 Bord.—Rochf. : 5 .. 11 | Various | { 5 in 1900 8 in 1901 14 in 1902 4 in 1903 | 567,807 | 177,562 |
| Torpedo Scout . | Libellule | Cherbourg | 1899 | 1900 | 13,754 | 1,218 |

Total Building by Contract in 1901 £7,861,909 1,552,125

German Navy Estimates, 1901.

(Converted at £1 = 20·43 marks.)

ORDINARY PERMANENT ESTIMATES.

| | Proposed for the financial year 1901. | Granted for the financial year 1900. |
|--|---|--|
| | £ | £ |
| Imperial Naval Office | 72,590 | 63,743 |
| Observatories | 15,614 | 15,651 |
| Accounts | 17,553 | 16,222 |
| Martial Law | 5,266 | 3,486 |
| Divine Service and Schools | 4,121 | 3,909 |
| Military Personnel | 878,132 | 808,986 |
| Maintenance of the Fleet | 935,553 | 845,462 |
| Victualling | 57,450 | 54,932 |
| Clothing | 15,653 | 15,144 |
| Barrack Administration, Cashiers and Accountants | 121,920 | 114,602 |
| Lodging Allowance | 66,525 | 62,024 |
| Medical | 65,416 | 58,571 |
| Travelling Expenses, Freight Charges, &c. | 121,644 | 121,644 |
| Training Establishments | 15,486 | 14,515 |
| Dockyard Expenses | 1,058,343 | 1,000,249 |
| Ordnance and Fortification | 355,776 | 324,702 |
| Accountant-General's Department | 27,086 | 24,563 |
| Pilotage and Surveying Services | 25,696 | 25,257 |
| Miscellaneous Expenses | 43,562 | 41,745 |
| Administration of Kiau-chau Protectorate | 2,355 | 1,898 |
| Total | £ 3,910,746 | 3,617,805 |

SPECIAL ORDINARY ESTIMATES.

*Shipbuilding Programme for the Financial Year, 1901.**For the Construction of—*

| | £ |
|--|-------------------|
| Battleship Kaiser Barbarossa (A), 4th and final instalment | 134,606 |
| „ Kaiser Karl der Grosse (B), 4th and final instalment | 100,734 |
| Large cruiser Prinz Heinrich (A), 4th and final instalment | 165,198 |
| Battleship Wittelsbach (C), 3rd instalment | 176,211 |
| „ D, 3rd instalment | 293,685 |
| „ E, „ | 293,685 |
| Small cruiser Thetis (C), 3rd and final instalment | 55,800 |
| „ Ariadne (D), „ | 55,800 |
| Battleship F, 2nd instalment | 318,160 |
| „ G, „ | 318,160 |
| Large cruiser B, „ | 293,685 |
| Small cruiser E, 2nd and final instalment | 129,222 |
| „ Amazone (F), 2nd and final instalment | 129,222 |
| Gunboat A, 2nd and final instalment | 48,946 |
| Battleship H, 1st instalment | 146,842 |
| „ J, „ | 146,842 |
| Large cruiser Ersatz König Wilhelm, 1st instalment | 166,422 |
| Small cruiser G, 1st instalment | 63,632 |
| „ H, „ | 63,632 |
| „ J, „ | 63,632 |
| Alteration of vessels of Siegfried class, 1st instalment | 220,264 |
| One Torpedo-boat Division, 2nd and final instalment | 168,380 |
| „ „ 1st instalment | 117,474 |
| Total | <u>£3,670,234</u> |

SUMMARY.

| | Proposed for the financial year 1901. | Granted for the financial year 1900. |
|--|---|--|
| | £ | £ |
| Ordinary Permanent Estimates | 3,910,746 | 3,617,305 |
| Shipbuilding | 3,670,234 | 2,395,203 |
| Armaments and Torpedo Equipments | 1,253,206 | 1,008,370 |
| Other Items | 306,008 | 185,218 |
| Extraordinary Expenditure | 489,476 | 270,191 |
| Total | £ 9,629,670 | 7,476,287 |

Italian Navy Estimates, 1901-1902.

FINANCIAL YEAR, 1ST JULY, 1901, TO 30TH JUNE, 1902.

Converted at £1 = 27 lire.

| | Proposed for 1901-1902. | Revised Estimates 1900-1901. |
|---|----------------------------|------------------------------------|
| ORDINARY EXPENDITURE—GENERAL EXPENSES. | | |
| | £ | £ |
| Admiralty | 48,883 | 49,338 |
| Pensions. | 200,926 | 190,963 |
| Expenditure on various services connected with the Mer- cantile Marine | 427,431 | 527,250 |
| Total | £ 677,240 | 767,551 |
| EXPENDITURE FOR NAVAL SERVICES. | | |
| Ships fitting out | 225,148 | 220,670 |
| General Staff of the Navy | 127,111 | 120,119 |
| Corps of Constructors | 49,629 | 49,074 |
| Commissariat Service | 83,259 | 33,333 |
| Medical Service | 24,867 | 24,867 |
| Wages—Men | 462,963 | 444,444 |
| Gratuities | 62,618 | 55,619 |
| Assistants to Constructors and others | 53,681 | 53,348 |
| Accountants, &c. | 53,520 | 53,518 |
| Police | 11,326 | 11,326 |
| Telegraph Service | 9,259 | 6,666 |
| Telegraph Materials | 5,925 | 8,518 |
| Forts— <i>Personnel</i> | 12,037 | 11,111 |
| Victualling | 300,000 | 290,370 |
| Lighting | 7,704 | 7,333 |
| Hospital Services | 17,828 | 17,828 |
| Honorary Distinctions | 444 | 444 |
| Fuel and Stores | 266,666 | 205,255 |
| Salaries and Wages—Workshops and Fortifications | 4,130 | 4,130 |
| Training Establishments | 15,111 | 15,555 |
| Naval Academy | 5,536 | 5,431 |
| Scientific Services— <i>Personnel</i> | 1,374 | 1,419 |
| „ „ <i>Materiel</i> | 9,444 | 9,259 |
| Law Charges | 1,185 | 1,185 |
| Travelling Expenses. | 18,518 | 18,518 |
| Transport of Materials | 4,629 | 4,629 |
| Carried forward | £ 1,783,912 | 1,673,969 |

| | Proposed for 1901-1902. | Revised Estimates. 1900-1901. |
|---|----------------------------|----------------------------------|
| | £ | £ |
| Brought forward | 1,783,912 | 1,673,969 |
| Materials and Labour for repairs of Ships | 487,034 | 668,518 |
| Guns, Torpedoes and Small Arms | 262,963 | 81,481 |
| Labour for construction and repairs of Armaments | 82,334 | 82,334 |
| Works Department—Repairs | 87,171 | 87,171 |
| Construction and Completion of the following Vessels, viz. : | | |
| 1st Class Battleships: Benedetto Brin, at Castellamare; Regina Margherita, at Spezia | | |
| Armoured Cruiser: Francesco Ferruccio, at Venice | | |
| Torpedo-boat Destroyers | 888,888 | 888,888 |
| Small Craft | | |
| Laying down of a 1st class Battleship | | |
| Alteration of the Italia | | |
| Total | £ 3,592,302 | 3,482,361 |

EXTRAORDINARY EXPENDITURE.

| | | |
|--|----------|--------|
| | £ | £ |
| General Expenses and Half Pay | 2,760 | 2,832 |
| Shipbuilding | 14,814 | 18,518 |
| Coast Defence and Fortifications | 14,814 | 14,812 |
| Torpedoes | 18,518 | 18,518 |
| Total | £ 50,906 | 54,680 |

SUMMARY.

| | | |
|---|-------------|-----------|
| | £ | £ |
| Ordinary Expenditure—General Expenses | 677,240 | 767,551 |
| Expenditure for Naval Services | 3,592,302 | 3,482,361 |
| Extraordinary Expenditure | 50,906 | 54,680 |
| Depreciation of Ships in Commission | 129,629 | 129,629 |
| Rent of Lands occupied by Government | 98,671 | 98,532 |
| Grand Total | £ 4,548,748 | 4,532,753 |

Russian Navy Estimates, 1901.

(Converted at £1 = 9·6 Roubles)

| Heads of Expenditure. | 1901. | 1900. |
|--|--------------|-----------|
| | £ | £ |
| Central and Ports Administration | 244,690 | 237,014 |
| Salaries and Assistance | 56,800 | 52,744 |
| Educational | 118,000 | 102,469 |
| Medical Establishments and Services | 125,393 | 108,885 |
| Pay of Officers, Seamen, etc. | 561,723 | 494,941 |
| Victualling | 196,955 | 183,441 |
| Clothing | 300,195 | 246,631 |
| Expenses of Ships in Commission | 2,116,542 | 1,489,351 |
| Hydrographic Department | 104,959 | 83,867 |
| Hydrographic Survey of the Mouths of the Yenesei and Obi | 5,698 | 5,698 |
| Naval Armaments and Electric Lighting | 1,246,365 | 905,837 |
| New Construction | 1,854,733 | 2,402,128 |
| Repairs and Refits | 812,258 | 652,801 |
| Admiralty Yards and Workshops | 606,528 | 488,463 |
| Buildings, Rent and Repairs | 589,000 | 421,825 |
| Building and Maintenance of Lighthouses | 31,250 | 28,646 |
| Various Expenses | 258,087 | 231,878 |
| Works of Port Alexander III. | 333,333 | 333,333 |
| Improvement of Vladivostock | 208,333 | 312,500 |
| Improvement and Fortification of Port Arthur | 312,500 | 312,500 |
| Expenditure on account of Next Year's Estimates | 31,006 | 26,369 |
| Total | £ 10,114,348 | 9,121,321 |

United States Navy Estimates, 1901 and 1902.

(Converted at £1 = \$4·8665, Par, as adopted by Congress).

| Detailed objects of Expenditure and Appropriation. | Estimates, 1901. | Appropriations, 1901. | Estimates, 1902. |
|---|------------------|-----------------------|------------------|
| | £ | £ | £ |
| Pay of the Navy | 2,631,315 | 2,632,466 | 3,108,122 |
| Pay, Miscellaneous | 102,743 | 102,743 | 123,292 |
| Contingent, Navy | 2,055 | 4,109 | 2,055 |
| Emergency Fund | .. | 61,646 | 102,748 |
| Bureau of Navigation . . . | 93,366 | 117,378 | 144,194 |
| „ Ordnance | 514,357 | 490,727 | 534,563 |
| „ Equipment. . . . | 666,285 | 711,816 | 917,456 |
| „ Yards and Docks . . | 109,590 | 125,026 | 135,994 |
| Public Works— | | | |
| Yards and Docks . . . | 2,829,233 | 1,665,646 | 2,528,005 |
| Naval Observatory . . . | 6,267 | 2,569 | 5,754 |
| Bureau of Navigation, including Naval Academy Buildings | 415,288 | 71,920 | 640,382 |
| Bureau of Ordnance . . . | .. | .. | 175,978 |
| Bureau of Medicine and Surgery . | 36,987 | 45,207 | 42,124 |
| „ Supplies and Accounts | 661,755 | 561,230 | 921,370 |
| „ Construction and Repairs | 1,293,706 | 1,281,377 | 1,658,445 |
| „ Steam Engineering . . | 570,000 | 570,081 | 775,280 |
| Naval Academy | 42,703 | 40,045 | 45,119 |
| Marine Corps | 554,890 | 557,458 | 599,717 |
| Increase of Navy | 4,722,718 | 4,344,128 | 5,378,180 |
| Total | £15,253,318 | £13,385,572 | £17,838,773 |

INDEX.

A.

- A (Swedish coast defence ship), 69, 358, plate 77.
 A 8 (French battleship), 42, 80, 308
 A 10 (French battleship), 42, 80, 308
 Aboukir, 20, 83, 272, plate 7
 Abrek, 72, 88, 350
 Abyssinia, 76, 87, 279
 Achéron, 75, 87, 308
 Adder, 60, 387, plate 88
 Admiral Boutakoff, 52, 87, 346
 Admiral Korniloff, 75, 84, 350
 Admiral Nakimoff, 54, 75, 83, 346, plate 65
 Admiral Oushakoff, 87, 346
 Admiral Senjavin, 87, 346
 Aegir, 87, 320, plate 48
 Æolus, 84, 280, plate 1
 Agamemnon, 87, 272
 Agordat, 88, 331
 Ajax, 87, 272
 Akashi, 86, 336
 Akitsushima, 86, 336
 Alabama, 57, 76, 80, 362, plate 78
 Alacrity, 75, 86, 280
 Alarm, 88, 280
 Albany, 75, 84, 365
 Albemarle, 18, 80, 260, 272, plate 9
 Albion, 15, 80, 259, 272, plate 5
 Alexander II., 72, 81, 346, plate 65
 Alexander III., 52, 80, 346
 Alexandra, 72, 82, 272
 Alger, 813, plate 42
 Almirante O'Higgins, 304, 27, plate 27
 Almirante Simpson, 304
 Almirante Tamandare, 303
 Amazona, 46, 86, 323
 Amiral Aube, 42, 83, 308
 Amiral Baudin, 72, 81, 308, plate 30
 Amiral Duperré, 40, 81, 308, plate 30
 Amiral Tréhouart, 72, 82, 308, plate 31
 Ammiraglio di St. Bon, 80, 329, plate 54
 Amphion, 84, 280
 Amphitrite (British), 83, 281, plate 6
 Amphitrite (United States), 87, 362
 Andrada, 303
 Andrea Doria, 73, 81, 329, plate 50
 Andromache, 84, 280, plate 1
 Andromeda, 72, 83, 280, plate 6
 Anson, 81, 272, plate 3
 Antelope, 88, 280
 Apollo, 84, 280, plate 1
 Archer, 86, 280
 Arethusa, 75, 77, 84, 281
 Aretusa, 88, 331
 Argonaut, 75, 83, 281, plate 6
 Ariadne (British), 83, 281, plate 6
 Ariadne (German), 46, 86, 323
 Arkansas, 58, 87, 362, plate 79
 Armour, 391-421
 " compound and ordinary, 392
 " effect of cap projectiles, 407, 411
 " for protection of secondary armament, 403
 " guns *versus* armour plates, 393, 396, 411
 " Harveyed plates, 393, 394
 " Krupp plates, 395, 408-411
 " progress in, 392, 394
 " resisting power of armour plates of battleships, 397-402
 " Terni plates, 404-407
 " the "Belleisle" experiments, 412-421
 Armoured cruisers, 19-23
 Armoured ships, Argentine, list of, 297
 " Austria-Hungary, list of, 299
 " Brazil, list of, 302
 " British, list of, 272-279
 " Chili, list of, 304
 " Denmark, list of, 306
 " France, list of, 308-312
 " Germany, list of, 320-322

- Armoured ships, Greece, list of, 327
 " Italy, list of, 329, 330
 " Japan, list of, 335
 " Netherlands, list of, 338, 339
 " Norway, list of, 343
 " Portugal, list of, 344
 " Russia, list of, 346-349
 " Spain, list of, 354
 " Sweden, list of, 358
 " Turkey, list of, 360
 " United States, list of, 362-364
 Arrogant, 72, 85, 281, plate 2
 Asahi, 63, 80, 335
 Asama, 83, 335, plate 56
 Askold, 51, 83, 350
 Aspern, 65, 300
 Astræa, 75, 84, 281, plate 1
 Atalanta, 76, 86, 365
 Aurora (British), 75, 84, 272, plate 2
 Aurora (Russian), 51, 83, 350
 Australia, 72, 84, 272, plate 2
 Austria-Hungary, increase in *personnel* of Navy, 66
 Austria-Hungary, Naval programme, 65
 Automatic Stoker, 140
 Auxiliary Cruisers, British, list of, 295
 " " France, list of, 319
 " " Germany, list of, 326
 " " Italy, list of, 334
 " " Russia, list of, 353
 " " United States, list of, 368, 369
 Azuma, 83, 335
- B.
- B (German cruiser), 83, 320
 B (Swedish coast-defence ship), 69, 358, plate 77
 Bacchante, 20, 83, 272, plate 7
 Baden, 82, 320
 Baltimore, 84, 365
 Barfleur, 75, 81, 272, plate 5
 Barham, 86, 281
 Barracouta, 76, 86, 281
 Barrosa, 76, 86, 281
 Barroso, 303
 Battleships, British, 7, 15-19, 80-82
 " British and Foreign compared, 80-82
 " French, 8, 80-82
 " German, 46, 80-82
 " Italian, 80-82
 " Japanese, 80-82
 " Russian, 80-82
 " United States, 8, 80-82
 Bayan, 51, 53, 83, 346, plate 67
 Bayern, 83, 320
 Bedford, 21, 83, 272, plate 13
 Belgium, ships belonging to, 370
 Bellerophon, 87, 272
 Bellona, 86, 281
 Benbow, 72, 81, 273, plate 3
 Benedetto Brin, 56, 80, 329, plate 51
 Benjamin Constant, 303
 Beowulf, 87, 320, plate 48
 Berwick, 22, 83, 273
 Blake, 83, 281, plate 4
 Blanche, 86, 281
 Blanco Encalada, 304, plate 25
 Blenheim, 75, 83, 281, plate 4
 Blitz, 86, 323
 Blonde, 86, 281
 Bogatyr, 51, 53, 83, 350
 Bombe, 88, 313
 Bonaventure, 75, 84, 282, plate 1
 Boomerang, 88, 282
 Borodino, 52, 80, 346
 Boston, 86, 365
 Bouvet, 72, 80, 308
 Bouvines, 72, 82, 308, plate 31
 Boyarin, 51, 54, 86, 350
 Brandenburg, 46, 75, 80, 320, plate 48
 Brennus, 72, 80, 309, plate 31
 Brilliant, 84, 282, plate 1
 Brisk, 75, 86, 282
 British Navy—American Squadron, 76
 " Australian Squadron, 77
 " Cape of Good Hope Squadron, 76
 " Channel Squadron, 72
 " China Squadron, 75
 " East Indian Squadron, 76
 " increase of *personnel*, 3, 31
 " Mediterranean Squadron, 72
 " Pacific Squadron, 77
 " Reserve Squadron, 72
 " the Fleet's appendages, 30, 161-166
 Brooklyn, 75, 83, 362, plate 78
 Bruix, 72, 84, 309, plate 32
 Budapest, 299, plate 21
 Buenos Aires, 298, plate 18
 Bugeaud, 75, 84, 313, plate 34
 Bulgaria, ships belonging to, 370
 Bulwark, 16, 80, 260, 273, plate 7
 Bussard, 75, 86, 323
- C.
- C (Swedish coast-defence ship), 69, 358, plate 77
 Cæsar, 72, 83, 258, 273, plate 14
 Caiman, 82, 309, plate 32
 Calabria, 77, 86, 331
 Calatafini, 88, 331
 California, 62, 83, 362, plate 80

Cambrian, 84, 282, plate 1
 Camperdown, 71, 72, 81, 273, plate 3
 Canopus, 15, 72, 80, 259, 273, plate 5
 Capitan Prat, 304, plate 25
 Caprera, 331
 Captain Sacken, 88, 350
 Carumuru, 303
 Cardenal Cisneros, 354, plate 75
 Carlo Alberto, 83, 329, plate 54
 Carnot, 72, 80, 309, plate 33
 Casabianca, 72, 88, 313
 Cassard, 72, 84, 313
 Cassini, 72, 88, 313
 Cataluña, 68, 354, plate 75
 Catherine II., 81, 346, plate 66
 Catinat, 76, 84, 313
 Cécille, 76, 84, 313
 Centurion, 75, 81, 273, plate 5
 Challenger, 85, 282
 Chanzy, 72, 84, 309, plate 32
 Charlemagne, 72, 80, 309, plate 33
 Charles Martel, 72, 80, 309
 Charleston, 62, 83, 362, plate 86
 Charner, 75, 84, 308, plate 32
 Charybdis, 76, 84, 283, plate 1
 Chasseloup-Laubat, 75, 84, 313, plate 34
 Châteaurenault, 35, 72, 83, 313, plate 37
 Chattanooga, 84, 365
 Chicago, 76, 84, 365
 Chihaya, 64, 88, 336
 China, loss of four destroyers, 66
 Chin-Yuen, 82, 335, plate 57
 Chitose, 84, 336
 Chiyoda, 335
 Cincinnati, 84, 365
 Circe, 88, 283
 Cleveland, 84, 365
 Coastguard and Harbour defence ships,
 87
 Coatit, 88, 331
 Coccyte, 72, 87, 309
 Coëtlogon, 86, 314
 Collingwood, 72, 81, 273, plate 3
 Colorado, 62, 83, 362, plate 80
 Colossus, 72, 82, 273
 Columbia, 83, 365, plate 80
 Comparative Tables, British and Foreign
 Battleships, 80-82
 Comparative Tables, British and Foreign
 Coastguard and Harbour defence ships,
 87
 Comparative Tables, British and Foreign
 Cruisers, 83-86
 Comparative Tables, British and Foreign
 Gunboats, 88
 Condé, 42, 83, 309, plate 38
 Condor (British), 25, 283
 Condor (French), 72, 88, 314
 Confianza, 88, 331
 Conqueror, 87, 273
 Cornwall, 21, 83, 260, 273

Cornwallis, 16, 80, 260, 273, plate 9
 Cosmao, 86, 314
 Cossack, 76, 86, 283
 Couleuvrine, 88, 314
 Courbet, 72, 81, 309, plate 34
 Crescent, 24, 76, 83, 283, plate 4
 Cressy, 19, 83, 255, 273, plate 7
 Cruisers, British, 10, 83-86
 „ British and foreign compared,
 83-86
 „ French, 10, 83-86
 „ German, 83-86
 „ Italian, 83-86
 „ Japanese, 83-86
 „ Russian, 10, 83-86
 „ United States, 10, 83-86
 Cruising ships, Argentine, list of, 298
 „ Austria-Hungary, list of,
 300, 301
 „ Brazil, list of, 303
 „ British, list of, 280-294
 „ British Colonial, list of,
 296
 „ Chili, list of, 304
 „ China, list of, 305
 „ Denmark, list of, 307
 „ France, list of, 313-318
 „ Germany, list of, 323-325
 „ Greece, list of, 328
 „ Italy, list of, 331-334
 „ Japan, list of, 336, 337
 „ Netherlands, list of, 340-
 342
 „ Norway, list of, 343
 „ Portugal, list of, 344, 345
 „ Russia, list of, 350-352
 „ Spain, list of, 356, 357
 „ Sweden, list of, 359
 „ Turkey, list of, 361
 „ United States, list of,
 365-367
 Cumberland, 22, 83, 273
 Cyclops, 87, 273

D.

D (German battleship), 46, 80, 321
 Dague, 72, 68, 314
 Dandolo, 73, 82, 329, plate 50
 D'Assas, 72, 84, 314
 Davout, 42, 86, 314
 Décidée, 35, 314
 Denmark, Naval progress, 66
 Denver, 84, 366
 D'Entrecasteaux, 72, 83, 314, plate 36
 De Ruyter, 67, 338
 Desaix, 42, 83, 309, plate 37
 Descartes, 75, 84, 314, plate 35
 Des Moines, 84, 366

D'Estrées, 35, 86, 314, plate 35
 Detroit, 86, 365
 Deutschland, 82, 320
 Devastation, 72, 82, 274
 Dévastation, 42, 81, 309, plate 34
 Diadem, 72, 83, 283, plate 6
 Diana (British), 72, 85, 283, plate 10
 Diana (Russian), 83, 350
 Dido, 75, 85, 283, plate 10
 D'Iberville, 88, 314
 Dimitri Donskoi, 75, 84, 347
 Dogali, 86, 332
 Donegal, 22, 83, 274
 Doris, 76, 85, 283, plate 10
 Dragonne, 88, 314
 Drake, 19, 21, 83, 274, plate 6
 Dreadnought, 82, 274, plate 8
 Dristigheten, 69, 358
 Dryad, 72, 283
 Dubourdieu, 314
 Du Chayla, 72, 84, 314
 Duguesclin, 309
 Duilio, 82, 329, plate 50
 Duncan, 16, 80, 260, 274, plate 9
 Dunois, 72, 88, 315
 Dupetit-Thouars, 42, 83, 309, plate 38
 Dupleix, 36, 42, 83, 310, plate 37
 Dupuy-de-Lôme, 72, 83, 310, plate 36
 Dvenadzat Apostoloff, 81, 347

E.

E (Austrian cruiser), 65, 299
 E (German battleship), 46, 80, 321
 Eclipse, 85, 284, plate 10
 Ecuador, ships belonging to, 370
 Edgar, 24, 83, 284, plate 4
 Edinburgh, 82, 274
 Effective fighting ships built and building, 89
 Eidsvold, 67, 343, plate 64
 Elba, 77, 86, 332
 Emanuele Filiberto, 80, 329, plate 54
 Emperador Carlos V., 354, plate 74
 Empress of India, 72, 80, 274, plate 15
 Encounter, 24, 85, 284
 Endymion, 75, 83, 284, plate 4
 Engine room staff, training of, 9
 Epervier, 88, 315
 Esmeralda, 304, plate 26
 Espiègle, 26, 284
 Espora, 298
 Essex, 21, 83, 255, 274, plate 13
 Estremadura, 68, 355
 Etna, 84, 332
 Etruria, 86, 332
 Euridice, 88, 332
 Europa, 83, 284, plate 6

Euryalus, 20, 83, 274, plate 7
 Evertsen, 67, 338, plate 62
 Exmouth, 16, 80, 260, 274, plate 9

F.

F (German battleship), 46, 80, 321
 Fantôme, 26, 284
 Faucon, 88, 315
 Fearless, 86, 284
 Fiermosca, 77, 84, 332
 Flamme, 87, 310
 Flèche, 72, 88, 315
 Fleet Auxiliaries, 161-166
 " Ammunition ships, 163
 " classes and essentials of, 161
 " colliers, 161
 " condensing ships, 164
 " engineers' store ships, 163
 " hospital ships, 163
 " manning of, 165
 " repairing ships, 164
 " provision and store ships, 163
 Fleurus, 88, 315
 Flora, 76, 84, 284, plate 1
 Florida, 87, 362
 Forbin, 86, 315
 Formidable (British), 16, 80, 260, 274, plate 7
 Formidable (French), 72, 81, 310, plate 30
 Forte, 76, 84, 284, plate 1
 Forth, 84, 284
 Foudre, 72, 315
 Fox, 84, 284, plate 1
 France, Atlantic Squadron, 76
 " China Squadron, 75
 " Mediterranean Squadron, 72
 " Naval bases, 42
 " Northern Squadron, 72
 " Reserve Squadron, 72
 " shipbuilding programme, 33
 " vessels completed in 1900, 35
 " vessels launched in 1900, 36
 Francesco Ferruccio, 83, 329, plate 52
 Francesco Morosini, 73, 81, 329, plate 50
 Freya, 84, 323, plate 44
 Friant, 75, 84, 315, plate 34
 Friedland, 82, 310
 Frithjof, 87, 321, plate 48
 Fuji, 80, 335, plate 58
 Furieux, 41, 87, 310
 Furious, 72, 85, 285, plate 2
 Fürst Bismarck, 75, 83, 321, plate 45
 Fusée, 87, 310

G.

- G (German battleship), 46, 80, 321
 G (German cruiser), 47, 86, 323
 Gaidamak, 88, 351
 Galatea, 72, 84, 274, plate 2
 Galilée, 72, 86, 315
 Galveston, 84, 366
 Garibaldi, 297, plate 19
 Gaulois, 72, 80, 310, plate 33
 Gazelle, 47, 86, 323
 Gefion, 75, 84, 323, plate 46
 Geier, 75, 86, 323
 Geiser, 307
 Gelderland, 67, 341
 General Admiral, 84, 347
 General Admiral Apraxine, 87, 347
 General Belgrano, 297, plate 19
 General San Martin, 297, plate 19
 Georgia, 61, 80, 362, plate 86
 Georgi Pobiedonosetz, 81, 347
 Germany, China Squadron, 75
 " Navy Act of 1900, 45
 " Navy League, 48
 " new docks, 48
 " types of new battleships, 46
 Gertzog Edinburgski, 84, 347
 Gibraltar, 76, 83, 285, plate 4
 Giovanni Bausan, 86, 333
 Giuseppe Garibaldi, 56, 83, 329, plate 52
 Gladiator, 72, 85, 285, plate 2
 Glatton, 87, 274
 Gleaner, 88, 285
 Gloire, 36, 42, 83, 310, plate 38
 Glory, 15, 75, 80, 259, 275, plate 5
 Goito, 88, 333
 Goliath, 15, 75, 80, 259, 275, plate 5
 Good Hope, 21, 53, 275, plate 6
 Gorgon, 87, 275
 Gossamer, 88, 285
 Grafton, 83, 285, plate 4
 Grampus, 60, 387, plate 88
 Grasshopper, 88, 285
 Greif, 86, 323
 Gremiastchy, 75, 87, 347
 Grenade, 87, 310
 Griden, 88, 351
 Gromoboi, 75, 83, 347, plate 68
 Gueydon, 42, 83, 308, plate 38
 Guichen, 35, 75, 83, 315
 Gunboats, British and Foreign, compared,
 88

H.

- H (German battleship), 46, 80, 321
 H (German cruiser), 323
 Habsburg, 65, 299, plate 23
 Hagen, 47, 87, 321, plate 48
 Halcyon, 72, 88, 285

- Hannibal, 72, 80, 258, 275, plate 14
 Hansa, 75, 84, 323, plate 44
 Harrier, 88, 285
 Hashidate, 84, 336, plate 57
 Hatsuse, 63, 80, 335, plate 59
 Hawke, 83, 285, plate 4
 Hayti, ships belonging to, 370
 Hazard, 88, 285
 Hebe, 88, 285
 Hecate, 87, 275
 Hecla, 30, 285
 Heimdall, 87, 321, plate 48
 Hela, 75, 86, 324
 Helgoland, 306, plate 28
 Henri IV., 41, 81, 310, plate 39
 Hercules, 87, 275
 Herluf Trolle, 306, plate 29
 Hermes, 24, 85, 285, plate 10
 Hermione, 75, 84, 285, plate 1
 Hero, 87, 275
 Hertha, 75, 84, 324, plate 44
 Highflyer, 25, 76, 85, 285, plate 10
 Hildebrande, 87, 321, plate 48
 Hoche, 35, 40, 72, 81, 310, plate 40
 Hogue, 30, 83, 275, plate 7
 Holland, 341, plate 63
 Hood, 71, 72, 80, 275, plate 16
 Hotspur, 76, 87, 275
 Howe, 72, 81, 275, plate 3
 Hummel, 87, 321
 Hussar, 72, 88, 286
 Hyacinth, 85, 285, plate 10
 Hydra, 66, 327, plate 49

I.

- Idzumi, 86, 336
 Idzumo, 64, 83, 335, plate 60
 Iéna, 35, 72, 80, 310
 Illinois, 80, 362, plate 78
 Illustrious, 72, 80, 258, 275, plate 14
 Immortalité, 84, 275, plate 2
 Impérieuse, 83, 275, plate 10
 Implacable, 16, 80, 260, 276, plate 7
 Indefatigable, 76, 84, 286, plate 1
 Independencia, 297, plate 19
 Indiana, 80, 362, plate 84
 Indomptable, 82, 311, plate 32
 Infernet, 35, 76, 86, 316
 Inflexible, 82, 275, plate 8
 Intrepid, 85, 286, plate 1
 Iowa, 77, 80, 363, plate 81
 Iphigenia, 85, 286, plate 1
 Irene, 75, 84, 324
 Iridé, 88, 333
 Iris, 86, 286
 Irresistible, 16, 80, 260, 276, plate 7
 Isis, 75, 85, 286, plate 10
 Isly, 76, 84, 316, plate 42

Italia, 81, 330, plate 53
 Italy, China Squadron, 77
 „ Mediterranean Squadron, 73
 „ Naval programme, 55
 „ new battleships, 55
 Itsukushima, 84, 336, plate 57
 Iver Hvitfeldt, 306, plate 28
 Iwate, 64, 83, 335

J.

J (German battleship), 46, 80, 321
 J (German cruiser), 323
 Jagd, 88, 324
 Jaseur, 88, 286
 Jason, 88, 286
 Jauréguiberry, 72, 80, 311, plate 41
 Jean Bart, 84, 316, plate 42
 Jeanne d'Arc, 42, 83, 311, plate 40
 Jemmapes, 72, 82, 311, plate 31
 Jules Ferry, 36, 83, 311
 Juno, 85, 286, plate 10
 Jupiter, 72, 80, 276, plate 4
 Jurien de la Gravière, 42, 84, 316

K.

Kaiser, 46, 82, 321
 Kaiser Barbarossa, 46, 80, 321
 Kaiser Franz Joseph, 300, plate 22
 Kaiser Friedrich III., 46, 80, 321, plate 47
 Kaiser Karl der Grosse, 46, 80, 321, plate 47
 Kaiser Karl VI., 65, 299, plate 20
 Kaiser Wilhelm der Grosse, 46, 80, 321, plate 47
 Kaiser Wilhelm II., 46, 80, 321, plate 47
 Kaiserin Augusta, 75, 83, 324, plate 46
 Kaiserin Elizabeth, 300, plate 22
 Kaiserin Maria Teresa, 299, plate 21
 Karrakatta, 88, 286
 Kasagi, 84, 336, plate 61
 Katoomba, 77, 86, 287, plate 12
 Kazarsky, 88, 351
 Kearsarge, 57, 60, 76, 80, 363, plate 82
 Kent, 19, 21, 83, 276, plate 13
 Kentucky, 60, 75, 80, 363, plate 82
 Khrabry, 72, 87, 347
 King Alfred, 21, 83, 276, plate 6
 Kléber, 42, 83, 311, plate 37
 Kniaz Potemkine Tavritchesky, 51, 80, 347
 Kniaz Souvaroff, 52, 80, 347
 Komet, 88, 324
 Kondor, 86, 324
 König Wilhelm, 83, 321

Koningin Regente, 67, 338
 Koningin Wilhelmina der Nederlanden, 338, plate 62
 Kormoran, 86, 324
 Kortenaer, 338, plate 62
 Kronprinzessin Stefanie, 299, plate 22
 Kronprinz Rudolph, 299, plate 23
 Kurfürst Friedrich Wilhelm, 75, 80, 321, plate 48

L.

La Hire, 72, 88, 316
 Lalande, 86, 316
 Lancaster, 21, 83, 276
 Lance, 88, 316
 Latona, 85, 287, plate 1
 Latouche-Tréville, 72, 84, 311, plate 32
 Laudon, 66, 299
 Lavoisier, 72, 86, 316
 Leander, 77, 84, 287
 Leda, 88, 287
 Léger, 88, 316
 Leon Gambetta, 36, 83, 311
 Lepanto, 73, 81, 330, plate 53
 Leviathan, 21, 83, 276, plate 6
 Lévrier, 72, 88, 316
 Libertad, 297, plate 19
 Lieutenant Ilyn, 88, 351
 Liguria, 86, 333
 Linois, 72, 86, 317
 Lombardia, 86, 333
 London, 16, 80, 260, 276, plate 7

M.

Magdala, 76, 87, 279
 Magenta, 72, 81, 311, plate 42
 Magicienne, 76, 86, 287
 Magnificent, 72, 80, 254, 276, plate 14
 Maine, 80, 363, plate 79
 Majestic, 72, 80, 254, 276, plate 14
 Manning of the Navy and mercantile marine, 153-160
 Marathon, 76, 86, 287
 Marblehead, 77, 86, 366
 Marceau, 42, 81, 311, plate 42
 Marco Polo, 84, 330, plate 53
 Marine engineering, 119-152
 „ Admiralty boiler committee, 119, 147
 „ Admiralty memorandum on water-tube boilers, 119
 „ Babcock and Wilcox boiler, 123-126

- Marine engineering, Belleville boiler, 122, 150
 " heat-catching devices, 144
 " interim report of boiler committee, 146-152
 " mechanical stoking, 140
 " Niclausse boiler, 126, 150
 " Parsons steam turbine, 146
 " small tube boilers, 119
 " Thornycroft - Marshall boiler, 127, 150
 " trials with different types of boilers, 128-140
 Mars, 72, 80, 276, plate 14
 Marseillaise, 36, 83, 311
 Marshal Deodoro, 302, plate 24
 Marshal Floriano, 302, plate 24
 Maryland, 62, 83, 363, plate 80
 Massachusetts, 76, 80, 363, plate 84
 Masséna, 80, 311
 Matsushima, 84, 336
 Medea, 86, 287
 Medusa (British), 46, 86, 287
 Medusa (German), 86, 324
 Melampus, 72, 85, 287, plate 1
 Melpomene, 86, 287
 Mercantile Auxiliaries, 12
 Mercury, 86, 287
 Merlin, 25, 287
 Mersey, 84, 288
 Messoudieh, 69, 360
 Meteor, 88, 324
 Mexico, Naval programme, 67
 " ships belonging to, 370
 Mikasa, 63, 80, 335, plate 58
 Milan, 86, 317
 Mildura, 77, 86, 288, plate 12
 Milwaukee, 62, 83, 363, plate 86
 Minerva (British), 85, 288, plate 10
 Minerva (Italian), 88, 333
 Minin, 84, 347
 Ministro Zentino, 304, plate 27
 Minneapolis, 83, 366, plate 80
 Missouri, 80, 363, plate 79
 Mitraille, 87, 311
 Miyako, 86, 336
 Moccasin, 60, 387, plate 88
 Mohawk, 77, 86, 288
 Monadnock, 75, 87, 363
 Monarch (Austrian), 65, 299, plate 21
 Monarch (British), 76, 87, 276
 Monmouth, 21, 83, 276, plate 13
 Montabello, 88, 333
 Montagu, 18, 80, 260, 276, plate 9
 Montcalm, 36, 42, 83, 311, plate 38
 Monterey, 75, 87, 363, plate 83
 Montgomery, 86, 366
 Monzambano, 88, 333
 Morocco, ships belonging to, 370
 Mutine, 26, 288
- N.
- Naiad, 85, 288, plate 1
 Naniwa, 84, 337
 Narcissus, 84, 277, plate 2
 Natter, 87, 322
 Naval Administration, 14
 Naval Brigade in China, 204-217
 " in South Africa, 188-204
 Naval Estimates, British, 1, 482-493
 " British, First Lord's explanatory statement, 461-481
 " French, 1, 494-498
 " German, 499, 500
 " Italian, 501, 502
 " Russian, 1, 503
 " United States, 504
 Naval manœuvres, British, 90-118
 " French, 43-45
 " German, 49
 Naval policy, 1
 Naval strategy, 233-252
 " advantages and disadvantages of physical conditions, 248
 " coal strategy, 246
 " defensive strategy, 237, 240
 " definitions, 238
 " identity of naval and military strategical principles, 241
 " importance of coal question, 246
 " lines of communication, 239
 " naval mobility, 245
 " new conditions in strategy, 251
 " offensive strategy, 237
 Naval strength in China, 73-78
 Naval training, officers, 4, 32
 " seamen, 5
 Navarin, 75, 81, 347
 Nebraska, 61, 80, 363, plate 86
 Neptune, 42, 81, 311, plate 42
 Netherlands, Naval programme, 67
 Nevada, 58, 87, 363
 Newark, 75, 84, 366
 New Jersey, 61, 80, 364, plate 86

New Orleans, 75, 84, 367
 New ship (Norwegian coast defence), 343
 New York, 83, 364, plate 85
 Nicolai I., 54, 81, 348, plate 69
 Nielly, 76, 317
 Niger, 88, 288
 Nile, 72, 81, 277, plate 17
 Niobe (British), 71, 72, 83, 288, plate 6
 Niobe (German), 47, 86 324
 Noord Brabant, 341
 Norge, 343, plate 64
 Novgorod, 87, 348
 Novik, 51, 86, 351
 Nueve de Julio, 298, plate 18
 Nympe 86, 324

O.

Ocean, 15, 71, 75, 80, 259, 277, plate 5
 Odin (British), 25, 288
 Odin (Denmark), 306
 Odin (German), 87, 322, plate 48
 Ohio, 80, 364, plate 79
 Oldenburg, 82, 322
 Olympia, 84, 367
 Onyx, 88, 288
 Ordnance, 424-458
 „ Accuracy and rapidity of fire,
 424, 429
 „ Austrian Naval, 441
 „ British rifled, 438, 440
 „ Cordite *versus* nitro-cellulose
 powders, 435
 „ Danish Naval, 442
 „ Dutch Naval, 443
 „ Elswick Q.-F. guns, 452
 „ French Naval, 444, 445
 „ German Naval, 446
 „ Improvement in gun-mount-
 ings, 424-429
 „ Italian Naval, 447
 „ Krupp Q.-F. guns, 455, 456
 „ Prize-firing of H.M.S. Terrible,
 433
 „ Russian Naval, 448
 „ Schneider-Canet Q.-F. guns,
 454
 „ Spanish, 449
 „ Sweden and Norway Naval,
 450
 „ Tables relating to conversion
 of measures, 457, 458
 „ United States Naval, 451
 „ Vickers Q.-F. guns, 453
 Oregon, 75, 80, 364, plate 84
 Orel, 52, 80, 348
 Orion, 72, 87, 277
 Orlando, 75, 84, 277, plate 2
 Orslayba, 80, 348, plate 68
 Otavazny, 75, 87, 348

P.

Pactolus, 25, 72, 86, 289, plate 12
 Pallada, 83, 351, plate 70
 Pallas, 76, 86, 288 plate 12
 Pamyat Azova, 83, 348, plate 69
 Pamyat Merkuria, 86, 351
 Pandora, 25, 86, 289, plate 12
 Partenope, 73, 88, 333
 Pascal, 75, 84, 317
 Patria, 298
 Pearl, 86, 288, plate 12
 Pegasus, 25, 86, 289, plate 12
 Pelayo, 354, plate 76
 Pelikan, 325
 Pelorus, 25, 72, 86, 289, plate 12
 Pennsylvania, 62, 83, 364, plate 80
 Peresviet, 80, 348, plate 68
 Perseus, 25, 86, 289, plate 12
 Persia, ships belonging to, 371
 Peru, ships belonging to, 371
 Peter Veliky, 82, 348
 Petropavlovsk, 75, 80, 348, plate 70
 Pfeil, 86, 325
 Phaeton, 77, 84, 289
 Philadelphia, 77, 84, 367
 Philomel, 76, 86, 289, plate 12
 Phlégéton, 87, 311
 Phœbe, 86, 289, plate 12
 Piemonte, 86, 333
 Piet-Hein, 339, plate 62
 Pike, 60, 387, plate 88
 Pioneer, 25, 86, 289, plate 12
 Pique, 75, 85, 289, plate 1
 Pobieda, 51, 80, 348
 Poltava, 75, 80, 348, plate 70
 Polyphemus, 88, 289
 Pomone, 25, 76, 86, 289, plate 12
 Porpoise (British), 77, 86, 290
 Porpoise (United States), 60, 387, plate
 88
 Posadnik, 88, 351
 Pothuau, 72, 84, 308, plate 43
 Powerful, 83, 290, plate 11
 Presidente Errázuriz, 304
 Presidente Pinto, 304
 Prince George, 72, 80, 277, plate 14
 Prince of Wales, 18, 80, 260, 277
 Princesa de Asturias, 354, plate 75
 Prinzess Wilhelm, 84, 325
 Prinz Heinrich, 46, 47, 83, 322, plate 47
 Protet, 84, 317
 Prometheus, 25, 86, 289, plate 12
 Proserpine, 25, 76, 86, 289, plate 12
 Psara, 66, 327, plate 49
 Psilander, 69, 359
 Psyche, 25, 76, 86, 289, plate 12
 Pueyrredon, 297, plate 19
 Puglia, 56, 86, 333
 Pylades, 77, 290
 Pyramus, 25, 86, 289, plate 12

Q.

Queen, 18, 80, 260, 277
 Quinze de Novembro, 303

R.

Raccoon, 76, 86, 290
 Rainbow, 85, 290, plate 1
 Rainha Amelia, 68, 345
 Raleigh, 84, 367
 Ramillies, 72, 80, 277, plate 15
 Rattlesnake, 88, 290
 Razboynik, 75, 351
 Reconstruction of ships, 10
 Redoutable, 75, 82, 311, plate 34
 Regina Elena, 55, 80, 330, plate 51
 Regina Margherita, 55, 80, 330, plate 51
 Reinier Claeszen, 339, plate 63
 Relative strength of navies, 78, 79
 Renard, 88, 291
 Renown, 72, 80, 277, plate 11
 Repulse, 72, 80, 277, plate 15
 Requin, 41, 82, 312, plate 32
 Reserves : Colonial, 32
 " Royal Fleet, 31
 " Royal Marines, 32
 " Royal Naval, 31
 " Volunteer, 3
 Resolution, 72, 80, 277, plate 15
 Retribution, 85, 291, plate 1
 Retwisan, 51, 80, 349, plate 71
 Re Umberto, 80, 330, plate 55
 Revenge, 80, 278, plate 15
 Rhode Island, 61, 80, 364, plate 86
 Riachuelo, 302, plate 24
 Rinaldo, 26, 291, plate 12
 Ringarooma, 77, 86, 291, plate 12
 Rodney, 72, 81, 278, plate 3
 Rosario, 25, 291
 Rossia, 75, 83, 349, plate 71
 Rostislav, 81, 349
 Roumania, ships belonging to, 371
 Royal Arthur, 77, 83, 291, plate 4
 Royal Oak, 72, 80, 278, plate 15
 Royal Sovereign, 72, 80, 254, 278, plate 15
 Ruggiero di Lauria, 81, 330, plate 50
 Rupert, 72, 87, 278
 Rurik, 75, 83, 349, plate 71
 Russell, 16, 80, 260, 278, plate 9
 Russia, China Squadron, 75
 " Mediterranean Squadron, 72
 " Naval progress, 51
 Rynda, 86, 352

S.

Sachsen, 82, 322
 Saetta, 88, 333
 St. Barbe, 72, 88, 317

Saint Domingo, ships belonging to, 371
 St. George, 83, 291, plate 4
 St. Louis (French), 35, 72, 80, 312, plate 33
 St. Louis (United States), 62, 83, 364, plate 86
 Salamander, 72, 88, 291
 Salve, 88, 317
 Sandfly, 72, 88, 291
 San Francisco, 84, 367
 Sans-Pareil, 72, 81, 278, plate 17
 Sappho, 76, 85, 292, plate 1
 Sarawak, ships belonging to, 371
 Sardegna, 78, 80, 330, plate 55
 Schwalbe, 75, 325
 Scout, 86, 292
 Scylla, 85, 292, plate 1
 Seagull, 88, 292
 See-Adler, 75, 325
 Severn, 72, 84, 292
 Sevastopol, 54, 75, 80, 349, plate 70
 Shark, 60, 387, plate 88
 Sharpshooter, 88, 292
 Shearwater, 25, 292
 Sheldrake, 88, 292
 Shikishima, 80, 335, plate 59
 Siam, ships belonging to, 371
 Sicilia, 78, 80, 330, plate 55
 Siegfried, 87, 322, plate 48
 Sinope, 81, 349, plate 66
 Sirius, 85, 293, plate 1
 Sissoi Veliky, 75, 81, 349, plate 72
 Skipjack, 88, 292
 Skjold, 306
 South Dakota, 62, 83, 364, plate 80
 Spain, Navy League, 68
 Spanker, 88, 292
 Spartan, 85, 293, plate 1
 Spartiate, 24, 83, 292, plate 6
 Speedwell, 88, 292
 Speedy, 72, 88, 293
 Spetsai, 66, 327, plate 49
 Spider, 88, 293
 Stromboli, 77, 84, 334
 Styx, 75, 87, 312
 Submarine boats, 12, 29, 37-40, 59
 Suchet, 76, 318
 Suffolk, 21, 83, 278
 Suffren, 41, 80, 312, plate 43
 Sully, 42, 83, 312, plate 38
 Sultan, 82, 278
 Suma, 86, 337
 Superb, 82, 278
 Surcouf, 72, 86, 318
 Surprise, 86, 293
 Sutlej, 19, 83, 278
 Svetlana, 84, 352
 Sweden, Naval programme, 69
 Sybille, 80, 85, plate 1
 Szigetvár, 65, 301

T.

- Tacoma, 84, 367
 Tago, 72, 84, 318
 Takachiho, 84, 337
 Takasago, 84, 337, plate 56
 Talbot, 85, 293, plate 10
 Tamoyo, 303
 Tartar, 76, 86, 293
 Tatsuta, 88, 337
 Tauranga, 77, 86, 293, plate 12
 Tcheshmé, 81, 349, plate 66
 Temeraire, 82, 279
 Tempête, 72, 87, 312
 Terpsichore, 76, 85, 293, plate 1
 Terrible (British), 75, 83, 293, plate 11
 Terrible (French), 72, 82, 312, plate 32
 Texas, 82, 364, plate 87
 Thames, 84, 293
 Theseus, 72, 83, 293, plate 4
 Thetis (British), 76, 85, 293, plate 1
 Thetis (German), 46, 86, 325
 Thordon, 69, 358
 Thule, 69, 358
 Thunderer, 82, 279
 Timbira, 303
 Tirfing, 69, 358
 Tokiwa, 83, 335, plate 56
 Tonnant, 87, 312
 Torkenskjold, 343
 Tourville, 818
 Torpedo-boat destroyers, trials of, 27
 Torpedo-boat flotilla, Argentine, list of, 375
 " Austria - Hungary, list of, 375
 " Brazil, list of, 376
 " British, list of, 372-374
 " British Colonial, list of, 374
 " Chili, list of, 376
 " China, list of, 377
 " Costa Rica, list of, 377
 " Denmark, list of, 377
 " France, list of, 378, 379
 " Germany, list of, 380
 " Greece, list of, 380
 " Italy, list of, 381
 " Japan, list of, 382
 " Mexico, list of, 382
 " Netherlands, list of, 382
 " Norway, list of, 383
 " Portugal, list of, 383
 " Roumania, list of, 383
 " Russia, list of, 384, 385
 " Spain, list of, 385

- Torpedo-boat flotilla, Sweden, list of, 386
 " Turkey, list of, 386
 " United States, list of, 387
 Trafalgar, 72, 81, 279, plate 17
 Training of Mercantile Marine officers, 155
 " " seamen, 157
 Transport Operations to South Africa, 167-186
 " conditions and magnitude of the work, 167-169
 " horse transport, 174-183
 " mishaps, 177
 " naval and military co-operation, 180
 " resources of mercantile marine not exhausted, 170
 " transport and freight vessels employed, 169
 " Transport Staff at British ports, 172
 " Transport Staff at S. African ports, 178
 " Victualling the troops, 175
 " Work at British ports, 176
 " Work at S. African ports, 178, 185
 Tria Sviatitelia, 80, 349, plate 73
 Tribune, 76, 85, 293, plate 1
 Tripoli, 88, 334
 Troude, 86, 318
 Tsarevitch, 51, 80, 346, plate 67

U.

- Umbria, 86, 334
 Undaunted, 73, 84, 279, plate 2
 Unnamed ships, II. (Austrian battleship), 65, 299
 " III. (Austrian battleship), 65, 299
 " IV. (Austrian battleship), 66, 299
 " (Chinese cruiser), 305
 " (Danish Coast defence ship), 306
 " (Japanese cruiser), 337
 " (Russian cruiser), 350
 United States, Atlantic Squadron, 76
 " China Squadron, 76

United States, Naval programme, 62
 " new battleships, 60
 Urania, 73, 88, 334
 Uruguay, ships belonging to, 371
 Utrecht, 342

V.

Valkyrien, 307
 Valmy, 82, 312, plate 31
 Varese, 56, 83, 330, plate 52
 Varyag, 54, 352
 Vasco da Gama, 68, 344
 Vauban, 75, 82, 312
 Vautour, 72, 88, 318
 Venerable, 16, 80, 260, 279, plate 7
 Venezuela, ships belonging to, 371
 Vengeance, 15, 80, 259, 279, plate 5
 Venus, 85, 294, plate 10
 Vestal, 25, 294
 Vesuvio, 77, 84, 334
 Vettor Pisani, 77, 83, 330, plate 54
 Victor Hugo, 42, 83, 312
 Victoria Luise, 84, 325, plate 44
 Victorious, 72, 80, 279, plate 14
 Vindictive, 72, 85, 294, plate 2
 Vineta, 84, 325, plate 44
 Virginia, 61, 80, 364, plate 86
 Vittorio Emanuele III., 55, 80, 330,
 plate 51
 Vladimir Monomach, 75, 84, 349
 Voevada, 88, 352
 Vulcan, 30, 72, 294
 Vzdunik, 88, 352

W.

Wacht, 88, 325
 Wallaroo, 75, 77, 86, 294, plate 12
 War and its chief lesson, 218-232
 " causes of failure, 226
 " disasters awaiting self-
 efficiency, 220
 " failures of supposed effici-
 ency, 223-226
 " formalism of peace training,
 227
 " lessons of land warfare, 219
 " peace training and war, 219
 " professional self-satisfac-
 tion, 227

War and the "canker" of a long peace,
 228

" its vital questions, 231
 Warship-building (British) during past
 5 years, 253-267
 " causes of under-ex-
 penditure, 256
 " committee on delays,
 266
 " contractors' com-
 plaints, 257
 " effect of engineering
 disputes, 258
 " magnitude of the
 work, 253
 " ship-building pro-
 gramme, 254, 260
 " slip *versus* dock-
 building, 264
 " sums underspent, 256
 " time-standard for
 completion, 263
 " variation in cost of
 building, 265

Warspite, 77, 83, 279, plate 10
 Waryag, 83, 352, plate 72
 Water-tube boilers, 9, 128-140
 Wattignies, 88, 318
 Weissenburg, 75, 80, 322, plate 48
 West Virginia, 62, 83, 364, plate 80
 Wien, 299, plate 21
 Wisconsin, 57, 80, 364, plate 78
 Wittelsbach, 46, 80, 322
 Würth, 75, 80, 322, plate 48
 Württemberg, 82, 322
 Wyoming, 58, 87, 364

Y.

Yakumo, 83, 335
 Yashima, 80, 335, plate 58
 Yayeyama, 86, 337
 Yoshino, 84, 337, plate 61

Z.

Zabiaka, 75, 352
 Zeeland, 342
 Zélée, 35, 318
 Zenta, 301, plate 20

CASINO GADITANO

12
4-7

ANNUAL

1901

J. GRIFFIN & Co.
PORTSMOUTH

THE NAVAL ANNUAL



THIRTIETH YEAR OF PUBLICATION

J. GRIFFIN & Co. PORTSMOUTH